To request translation or disability-related accommodations, please contact us at **DTDcompliance@clackamas.us** | **503-742-4400**.

Si quiere solicitar servicios de traducción o adaptaciones para la discapacidad, contáctenos en/al **DTDcompliance@clackamas.us** | **503-742-4400**.

Чтобы запросить перевод или приспособления, связанные с инвалидностью, пожалуйста, свяжитесь с нами по:
DTDcompliance@clackamas.us | **503-742-4400**.

Щоб попросити переклад або спеціальні послуги для осіб з особливими потребами, зверніться до нас, скориставшись такими контактними даними:
DTDcompliance@clackamas.us | **503-742-4400**.

如需翻译服务或残障相关的协助，请与我们联系：
DTDcompliance@clackamas.us | **503-742-4400**。

Để yêu cầu dịch vụ dịch thuật hoặc điều chỉnh liên quan đến tình trạng khuyết tật, vui lòng liên hệ với chúng tôi qua **DTDcompliance@clackamas.us** | **503-742-4400.**

Clackamas County
www.clackamas.us

GENERAL NOTES

1. BACKFILL MATERIAL WITHIN THE PIPE ZONE SHALL BE SAND FOR GAS LINES, AND 3/4"–0" AGGREGATE FOR ALL OTHER UTILITIES.

2. IF CORE POTHOLE EXCAVATION OCCURS ON THE SHOULDER, 3/4"–0" BACK FILL (MEETING COUNTY SPEC.) IS REQUIRED.

3. ROAD SHOULDERS AND RIGHT–OF–WAY MUST BE RESTORED TO AS GOOD OR BETTER CONDITION WITH COUNTY APPROVED MATERIALS.

ASPHALT NOTES

4. POTHOLE EXCAVATIONS WITHIN ACP ROAD SURFACES SHALL BE FILLED ABOVE THE PIPE ZONE WITH 100 TO 200 PSI CDF AND BEFORE POTHOLE SHALL BE CAPPED WITH A TWO INCH GRIND, 12" ON ALL SIDES OF THE POTHOLE. HOT MIX ACP TO MATCH THE THICKNESS OF THE EXISTING ACP AND SEALED WITH HOT EMULSION AND SAND.

CONCRETE NOTES

5. IF A POTHOLE IS DONE WITHIN THE SIDEWALK PANEL, A FULL PANEL REPLACEMENT AT JOINTS IS REQUIRED. FORMS INSPECTION IS REQUIRED BEFORE POUR.

6. POTHOLE EXCAVATIONS WITHIN A CONCRETE ROAD PANEL SHALL BE FILLED ABOVE THE PIPE ZONE WITH 100 TO 200 PSI CDF WITH 24 HOURS OF CURE TIME. POTHOLE SHALL BE CAPPED 12" DEEP (TWO INCHES DEEPER THAN PANEL) WITH A 4000 PSI QUICK SET CONCRETE MIXTURE, SEALED WITH HOT EMULSION AND SAND SEALED.

REVISION	DATE	BY
REVISED	12/19	BP
REVISED	3/20	RM

DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT

150 BEAVERCREEK ROAD
OREGON CITY, OR 97045

CLACKAMAS COUNTY

APPROVAL DATE: 6/1/2020 SCALE: N.T.S.

NOTES FOR
U295A

STANDARD DRAWING

U295B