

INVITATION TO BID #2018-07 Feyrer Park Paving Project ADDENDUM NUMBER 3 February 26, 2018

On January 30, 2018, Clackamas County ("County") published Invitation to Bid #2018-07 ("BID") and amended with Amendment #1 on February 14, 2018, and Amendment #2 on February 15, 2018. The County has found that it is in its interest to amend the BID through the issuance of this Addendum #3. Except as expressly amended below, all other terms and conditions of the original BID and subsequent Addenda shall remain unchanged.

1. Remove and replace the bid schedule with the attached bid schedule titled Feyrer Park Paving Package, Addendum #3, dated spring 2018.

Attachments: Bid Schedule, Feyrer Park Paving Package, Spring 2018, Addendum #3.

End of Addendum #3

| Feyrer | Feyrer Park Package | | Spring 2018 | | Addendum #3 | page 1 of 5 |
|--------|---------------------|---|-------------|----------|-------------|-------------|
| | | FEYRER PARK PAVING PACKAGE | | | | |
| Item # | Spec # | Item Description | Unit | Quantity | Unit Price | Amount |
| TEMPO | | TURES AND APPURTENANCES FOR PAVING PACKAGE | | | | |
| 10 | 00210 | MOBILIZATION | LS | 1 | | |
| 20 | 00290 | POLLUTION CONTROL PLAN | LS | 1 | | |
| TEMPOF | ARY FEAT | TURES AND APPURTENANCES FOR PAVING PACKAGE-SUBTOTAL | | | | |

| | | Worksite #1 - Feyrer Park Road (BCM to ECM) | | | | |
|----------|-----------|---|------|----------|------------|--------|
| ltem # | Spec # | Item Description | Unit | Quantity | Unit Price | Amount |
| TEMPOF | RARY FEA | TURES AND APPURTENANCES | | | | |
| 101 | 00225 | TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE | LS | 1 | | |
| 102 | 00225 | TEMPORARY FLEXIBLE PAVEMENT MARKERS | FOOT | 10060 | | |
| 103 | 00225 | TEMPORARY STRIPING | EACH | 9260 | | |
| TEMPOR | RARY FEAT | TURES AND APPURTENANCES-SUBTOTAL | - | | | |
| | | | | | | |
| ROADW | ORK | | | | | |
| 104 | 00310 | ASPHALT PAVEMENT SAW CUTTING | FOOT | 500 | | |
| ROADW | ORK-SUBT | ΓΟΤΑL | | | | |
| | | | | | | |
| DRAINA | GE AND S | EWERS | | | | |
| 105 | 480 | DRAINAGE CURBS, STANDARD | FOOT | 150 | | |
| DRAINA | GE AND S | EWERS - SUBTOTAL | | | | |
| | | | | | | |
| BASES | | | | | | |
| 106 | 00620 | COLD PLANE PAVEMENT REMOVAL, 0 - 4 INCH DEPTH | SQYD | 4505 | | |
| 107 | 00620 | COLD PLANE PAVEMENT REMOVAL, 4 INCH DEEP | SQYD | 2790 | | |
| 108 | 00641 | SHOULDER ROCK IN PLACE | TON | 4140 | | |
| 109 | 00641 | 4"-0 AGGREGATE BASE | TON | 350 | | |
| BASE - S | UBTOTAL | | | | | |
| | | | | | | |
| WEARIN | IG SURFA | CES | | | | |
| 110 | 00745 | LEVEL 3, 1/2 INCH ACP | TON | 7045 | | |
| 111 | 00749 | EXTRA FOR ASPHALT APPROACHES | EACH | 12 | | |
| WEARIN | G SURFA | CES - SUBTOTAL | | | | |

| Feyrer Park Package | | ckage | Spring | 2018 | Addendum #3 | page 2 of 5 |
|---------------------|-----------|---|--------|------------|-------------|-------------|
| | | Worksite #1 - Feyrer Park Road (BCM to ECM) | | | | |
| ltem # | Spec # | Item Description | Unit | Quantity | Unit Price | Amount |
| PERMA | NENT TRA | FFIC CONTROL | | | | |
| 112 | 00855 | BI-DIRECTIONAL YELLOW TYPE 1AR MARKERS, RECESSED | EACH | 292 | | |
| 113 | 00866 | HI-BUILD PAINT, 25 MIL, SPRAYED | FOOT | 45600 | | |
| 114 | 00867 | PAVEMENT BAR, TYPE B-HS | SQFT | 70 | | |
| PERMAN | IENT TRA | FFIC CONTROL-SUBTOTAL | - | - | | |
| WORK. | SITE #1 | - FEYRER PARK ROAD PAVING PROJECT (BCM TO ECM) TOTAL | | | | |
| | | | | | | |
| | | Worksite #2 - Mathias Road Paving Project (BCM to ECM |) | | | |
| ltem # | Spec # | Item Description | Unit | Quantity | Unit Price | Amount |
| TEMPOR | RARY FEA | TURES AND APPURTENANCES | | | | |
| 201 | 00225 | TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE | LS | 1 | | |
| 202 | 00225 | TEMPORARY FLEXIBLE PAVEMENT MARKERS | EACH | 800 | | |
| TEMPOF | RARY FEAT | URES AND APPURTENANCES-SUBTOTAL | | | | |
| ROADW | ORK | | | | | |
| 203 | | ASPHALT PAVEMENT SAW CUTTING | FOOT | 75 | | |
| ROADW | ORK-SUB1 | TOTAL | | L 1 | | |
| | | | | | | |
| DRAINA | GE AND S | EWERS | | | | |
| 204 | 480 | DRAINAGE CURBS, STANDARD | FOOT | 150 | | |
| DRAINA | GE AND S | EWERS - SUBTOTAL | | | | |
| | | | | | | |
| BASES | | | | <u> </u> | | |
| 205 | | COLD PLANE PAVEMENT REMOVAL, 0 - 4 INCH DEPTH | SQYD | 1630 | | |
| 206 | 00641 | SHOULDER ROCK IN PLACE | TON | 1180 | | |
| BASE - S | UBTOTAL | | | | | |
| WEARIN | G SURFA | CES | | . <u> </u> | | |
| 207 | 00745 | LEVEL 3, 1/2 INCH ACP | TON | 2250 | | |
| 208 | 00749 | EXTRA FOR ASPHALT APPROACHES | EACH | 20 | | |
| NEARIN | G SURFAC | CES - SUBTOTAL | | | _ | |

| Feyrer Park Package | | Spring 2018 | | Addendum #3 | page 3 of 5 | |
|---------------------|-----------|--|------|-------------|-------------|--------|
| | | Worksite #2 - Mathias Road Paving Project (BCM to ECM) | | | | |
| ltem # | Spec # | Item Description | Unit | Quantity | Unit Price | Amount |
| PERMAN | NENT TRA | FFIC CONTROL | | | | |
| 209 | 00855 | BI-DIRECTIONAL YELLOW TYPE 1AR MARKERS, RECESSED | EACH | 105 | | |
| 210 | 00866 | HI-BUILD PAINT, 25 MIL, SPRAYED | FOOT | 4105 | | |
| 211 | 00867 | PAVEMENT BAR, TYPE B-HS | SQFT | 15 | | |
| PERMAN | IENT TRA | FFIC CONTROL-SUBTOTAL | | | | |
| WORKS | SITE #2 | - MATHIAS ROAD PAVING PROJECT (BCM TO ECM) TOTAL | | | | |
| | | | | | | |
| | | Worksite #3 - Molalla Avenue (BCM to Wilhoit) | | | | |
| ltem # | Spec # | Item Description | Unit | Quantity | Unit Price | Amount |
| TEMPOF | RARY FEA | TURES AND APPURTENANCES | | | | |
| 301 | 00225 | TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE | LS | 1 | | |
| 302 | 00225 | TEMPORARY FLEXIBLE PAVEMENT MARKERS | EACH | 6164 | | |
| TEMPOR | RARY FEAT | TURES AND APPURTENANCES-SUBTOTAL | | | | |
| | | | | | | |
| ROADW | ORK | | | | | |
| 303 | 00310 | ASPHALT PAVEMENT SAW CUTTING | FOOT | 91 | | |
| ROADW | ORK-SUB | ΤΟΤΑΙ | | | | |
| | | | | | | |
| DRAINA | GE AND S | EWERS | | | | |
| 304 | 480 | DRAINAGE CURBS, STANDARD | FOOT | 150 | | |
| DRAINA | GE AND S | EWERS - SUBTOTAL | | | | |
| | | | | | | |
| BASES | | r | | | | |
| 305 | 00620 | COLD PLANE PAVEMENT REMOVAL, 0 - 4 INCH DEPTH | SQYD | 3015 | | |
| 306 | 00641 | SHOULDER ROCK IN PLACE | TON | 1500 | | |
| BASES - S | SUBTOTA | L | | | | |
| | | | | | | |
| | IG SURFA | | | | | |
| 307 | | LEVEL 2, 1/2 INCH ACP | TON | 2855 | | |
| 308 | | EXTRA FOR ASPHALT APPROACHES | EACH | 28 | | |
| WEARIN | G SURFA | CES - SUBTOTAL | | | | |

| Feyrer | Feyrer Park Package | | | 2018 | Addendum #3 | page 4 of 5 |
|--------|---------------------|--|------|-------|-------------|-------------|
| | | Worksite #3 - Molalla Avenue (BCM to Wilhoit) | | | | |
| PERMA | NENT TRA | FFIC CONTROL | | | | |
| 309 | 00855 | BI-DIRECTIONAL YELLOW TYPE 1AR MARKERS, RECESSED | EACH | 120 | | |
| 310 | 00866 | HI-BUILD PAINT, 25 MIL, SPRAYED | FOOT | 16100 | | |
| 311 | 00867 | PAVEMENT BAR, TYPE B-HS | SQFT | 32 | | |
| PERMAI | VENT TRA | FFIC CONTROL-SUBTOTAL | | | | |
| WORK | SITE #3 | - MOLALLA AVENUE (WILHOIT TO ECM) TOTAL | | | | |

| | | Worksite #4 - Ona Way (HWY 211 to ECM) | | | | |
|-----------|-----------|--|------|----------|------------|--------|
| ltem # | Spec # | Item Description | Unit | Quantity | Unit Price | Amount |
| TEMPOR | ARY FEAT | TURES AND APPURTENANCES | | | | |
| 401 | 00225 | TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE | LS | 1 | | |
| 402 | 00225 | TEMPORARY FLEXIBLE PAVEMENT MARKERS | EACH | 2420 | | |
| 403 | 00280 | COMPOST FILTER BERM | FOOT | 7120 | | |
| 404 | 00280 | INLET PROTECTION | EA | 1 | | |
| TEMPOR | ARY FEAT | URES AND APPURTENANCES-SUBTOTAL | | | | |
| | | | | | | |
| ROADW | ORK | | | | | |
| 405 | 00310 | ASPHALT PAVEMENT SAW CUTTING | FOOT | 78 | | |
| ROADWO | ORK-SUBT | TOTAL | | | | |
| | | | | | | |
| DRAINA | GE AND S | EWERS | | | | |
| 406 | 480 | DRAINAGE CURBS, STANDARD | FOOT | 150 | | |
| DRAINAC | GE AND SI | EWERS - SUBTOTAL | | | | |
| | | | | | | |
| BASES | | | | | | |
| 407 | 00641 | SHOULDER ROCK IN PLACE | TON | 1340 | | |
| 408 | 00644 | FDR/CTB: TREATED BASE/SOIL, 12-INCHES THICK | SQYD | 9170 | | |
| 409 | 00644 | PORTLAND CEMENT (8% NOMINAL) | TON | 450 | | |
| 410 | 00644 | EXCESSIVE MATERIAL REMOVAL/DISPOSAL-AS NEEDED/DIRECTED BY ENGINEER | CY | 120 | | |
| 411 | 00644 | SUPPLEMENTARY AGGREGATE (BASE AGGREGATE) | TON | 100 | | |
| BASES - S | SUBTOTAL | L | | | | |
| | | | | | | |

| Feyrer | Feyrer Park Package | | Spring 2018 | | Addendum #3 | page 5 of 5 |
|--------|---------------------|---|-------------|------|-------------|-------------|
| | | Worksite #4 - Ona Way (HWY 211 to ECM) | | | | |
| WEARIN | NG SURFA | CES | | | | |
| 412 | 00710 | SINGLE APPLICATION EMULSIFIED ASPHALT SURFACE TREATMENT | SQYD | 9170 | | |
| 413 | 00745 | LEVEL 3, 1/2 INCH ACP | TON | 2400 | | |
| 414 | 00749 | EXTRA FOR ASPHALT APPROACHES | EACH | 37 | | |
| WEARIN | IG SURFAC | CES - SUBTOTAL | | | | |
| | | | | | | |
| PERMA | NENT TRA | FFIC CONTROL | | | | |
| 415 | 00867 | PAVEMENT BAR, TYPE B-HS / SQFT | SQFT | 15 | | |
| PERMA | NENT TRA | FFIC CONTROL-SUBTOTAL | | | | |
| WORK | SITE #4 | - ONA WAY (HWY 211 TO ECM) TOTAL | | | | |

WORKSITE TOTALS

TEMPORARY FEATURES AND APPURTENANCES FOR PAVING PACKAGE TOTAL

WORKSITE #1 - FEYRER PARK ROAD (BCM TO ECM) TOTAL

WORKSITE #2 - MATHIAS ROAD PAVING (BCM TO ECM) TOTAL

WORKSITE #3 - MOLALLA AVE (BCM TO WILHOIT) TOTAL

WORKSITE #4 - ONA WAY (HWY 211 TO ECM) TOTAL

PAVING PACKAGE TOTAL

| Total Price | Dollars and |
|--------------|-------------|
| - | Cents |
| Name of Firm | |
| Name (Print) | |
| Signature | |