To request translation or disability-related accommodations, please contact us at **DTDcompliance@clackamas.us** | **503-742-4400**.

Si quiere solicitar servicios de traducción o adaptaciones para la discapacidad, contáctenos en/al **DTDcompliance@clackamas.us** | **503-742-4400**.

Чтобы запросить перевод или приспособления, связанные с инвалидностью, пожалуйста, свяжитесь с нами по:
DTDcompliance@clackamas.us | **503-742-4400**.

Щоб попросити переклад або спеціальні послуги для осіб з особливими потребами, зверніться до нас, скориставшись такими контактними даними:
DTDcompliance@clackamas.us | **503-742-4400**.

如需翻译服务或残障相关的协助，请与我们联系：
DTDcompliance@clackamas.us | **503-742-4400**。

Để yêu cầu dịch vụ dịch thuật hoặc điều chỉnh liên quan đến tình trạng khuyết tật, vui lòng liên hệ với chúng tôi qua **DTDcompliance@clackamas.us** | **503-742-4400.**

Clackamas County
www.clackamas.us

Table 5-3d Regional Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description	Priority
4000	County-wide	TSP Refinement	State facility locations applicable where mobility target is not met in 2035	TSP Refinement to develop alternative mobility targets for state facilities consistent with Oregon Highway Plan (OHP) 1F3.	High
4001	5-11a	I-205 / Sunnyside Road interchange	I-205 / Sunnyside Road interchange	Add dual northbound right-turns; install bike signal; construct sidewalk extension / bulb to accommodate pedestrians and bicyclists around signal pole.	High
4002	5-11a	OR 212	OR 212 / 172nd Ave intersection	Add second eastbound left-turn lane	High
4003	5-11a	OR 212	SE 162nd to Anderson Rd	Add bikeways, pedestrian facilities ways, and landscape pedestrian facilities buffer; widen to 6 lanes within Happy Valley; add center turn lane within Damascus	High
4004	5-11a	OR 213	Sunnybrook Blvd to Portland City Limits	Extend fiberoptic communications, CCTV at key intersections and adaptive signal timing	High
4005	5-11a	OR 224	OR 224 / Lake Rd / Webster Rd intersection	Add turn-lanes, including second left-turn lane on westbound OR 224, second left-turn lane and right-turn lane on northbound SE Webster Rd, and second left-turn lane on southbound SE Lake Rd	High
4006	5-11a	OR 224	OR 224 / Johnson Rd intersection	Add second left-turn lane on westbound OR 224	High
4007	5-11a	OR 224	OR 224 / Hubbard Rd / 135th Ave intersection	Add intersection improvements, including right-turn lanes	High
4008	5-11a	OR 224	Springwater Rd / OR 224 intersection	Add signal and turn lanes on all approaches	High
4009	5-11a	OR 224	Rock Creek Junction to Midway St	Widen to four lanes; add bikeways.	High
4010	5-11a	Sunrise Project - Preliminary Engineering	Webster Rd/ OR 224 to 172nd Ave / OR 212	Preliminary engineering from Webster Rd to 172nd Ave	High
4011	5-11a	Sunrise Project - Right-of-Way	Webster Rd/ OR 224 to 172nd Ave / OR 212	Acquire right-of-way to accommodate 6 lane expressway plus auxiliary lanes	High
4012	5-11a	SunriseProject - Multi-use Path	122nd to Rock Creek Junction	Construct multi-use path from 122nd to Rock Creek Junction parallel to the Sunrise project consistent with FEIS.	High
4013	5-11b	OR 224	OR 224 /232nd Ave intersection	Install traffic signal or roundabout	High
4014	5-11b	OR 224	Eaglecreek Rd / OR 224 intersection	Install signal	High
4015	5-11c	OR 99E	Milwaukie city limit to Gladstone city limit	Add bikeways, pedestrian facilities ways, median enhancements, crosswalks and pedestrian facilities refuges	High
4016	5-11d	I-205	Stafford Rd to OR 99E	Work with ODOT, Metro, Oregon City, West Linn and any other effected jurisdictions to analyze and develop a solution to the transportation bottle neck on I-205 between Oregon City and I-205 / Stafford Road Interchange. Possible solutions include widening to 3-lanes in each direction.	High
4017	5-11e	I-205	Willamette River to West Linn city limit	Add southbound truck climbing lane	High
4018	5-11e	I-205	I-205 Corridor	Corridor-wide operational improvements	High
4019	5-11e	OR 211	Beavercreek Rd, Union Hall Rd to Dhooghe Rd	Widen to include shoulders, bikeways, add passing lanes where needed and turn lanes at major intersections	High
4020	5-11e	OR 213	OR 213 / Spangler Rd intersection	Install traffic signal to replace existing two-way stop	High

Table 5-3d Regional Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description	Priority
4021	5-11e	OR 213	OR 213 / Henrici Rd intersection	Install traffic signal or roundabout and additional intersection improvements as needed	High
4022	5-11e	OR 213	OR 213 / Leland Rd intersection	Add northbound through auxiliary lane	High
4023	5-11e	OR 213	Leland Rd / Union Hall Rd intersection	Add southbound auxiliary lane	High
4024	5-11e	OR 213	Mulino to Molalla	Perform road safety audit or transportation safety review to identify appropriate safety improvements	High
4025	5-11e	OR 99E	OR 99E / Barlow Rd intersection	Add left-turn lane on southbound Barlow Rd - To widen Barlow Rd to add a southbound left turn lane on the north approach would need to modify the existing railroad crossing warning system	High
4026	5-11a	I-205 / Johnson Creek Blvd interchange	I-205 / Johnson Creek Blvd interchange	Add loop ramp and northbound on-ramp; realign southbound off-ramp and install dual right-turn lanes	Medium
4027	5-11a	I-205 / OR 212/224 Interchange	In vicinity of Roots Rd and McKinley Ave	Connect bikeways in accordance with the Active Transportation Plan	Medium
4028	5-11a	OR 212	Rock Creek Junction to 172nd	Construct climbing lane	Medium
4029	5-11a	OR 212	OR 212 / SE 162nd Ave intersection	Add left-turn pockets and traffic signal	Medium
4030	5-11a	OR 213	Sunnyside Rd to Sunnybrook Rd	Widen to 7 lanes with boulevard treatments	Medium
4031	5-11a	OR 213	OR 213 / Harmony Rd / Sunnyside Rd intersection	Add bikeways, pedestrian facilities ways, dual northbound and southbound left-turn lanes, and lighting; convert driveways north of intersection to right-in / right-out	Medium
4032	5-11a	OR 224	OR 224 / Rusk Rd off-ramp	Extend right-turn lane on OR 224	Medium
4033	5-11a	OR 224	Milwaukie city limits to I-205	Construct multi-use path as parallel route to OR 224	Medium
4034	5-11a	OR 224	Lake Rd / Johnson Rd / Pheasant Ct	Realign Lake Rd / Johnson Rd to provide southern OR 224 access via Pheasant Ct; add turn lanes at OR 224 / Pheasant Ct intersection; close access at Lake / Webster south of OR 224	Medium
4035	5-11a	OR 99E	OR 99E / Jennings Ave intersection	Determine safe connection of Trolley Trail at OR 99E / Jennings Ave intersection	Medium
4036	5-11a	Sunrise Project	I-205 to 172nd Ave	Construct improvements to 172nd	Medium
4037	5-11b	OR 211	Hayden Rd to OR 224	Widen to rural arterial standard with shoulders, bikeways in accordance with the Active Transportation Plan and turn lanes at major intersections	Medium
4038	5-11b	US 26	Govt. Camp Loop W to OR 35	Implement Finding of Mt Hood Multimodal Study including phased safety improvements	Medium
4039	5-11b	US 26	OR 35 Junction to Wasco County line	Widen roadway to include bikeways /shoulders, add passing lanes where needed and turn lanes at major intersections	Medium
4040	5-11e	OR 211	OR 170 (Canby-Marquam Hwy) / OR 211 intersection	Install eastbound and westbound left-turn lanes, and eastbound right-turn lane; remove or decrease horizontal curve	Medium
4041	5-11e	OR 211	Marion County line to OR 170 (Canby-Marquam Hwy)	Widen to include shoulders, bikeways, add passing lanes where needed and turn lanes at major intersections	Medium
4042	5-11e	OR 99E	Barlow Rd to Marion County line	Four lane widening with median, left-turn lanes from mile post 24.05	Medium
4043	5-11e/f	OR 213	Oregon City boundary to Marion County line	Add shoulders and bikeways	Medium

Table 5-3d Regional Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description	Priority
4044	5-11a	OR 212	I-205 to OR 224	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4045	5-11a	OR 212	Within the Damascus City Limits (Armstrong Cr to 257th)	Obtain right-of-way for future 4 lane facility with planted median and 5 lanes at major intersections; build as major development occurs and apply access management to reduce number of driveways.	Low
4046	5-11a	OR 213	Clatsop St to Sunnyside Rd	OR 213/82nd Avenue Boulevard Design Improvements - Widen to add sidewalks, lighting, central median, planting strips and landscaping; fill gaps in the bike and pedestrian facilities network. Add pedestrian crossings in the vicinity of Luther Rd, Glencoe Rd and south of Boyer Dr. Install access management median Hinkley Ave to Lindy St and Monterey Ave to Harmony Rd. Install advanced street name signs from Sunnyside Rd to Sunnyside Dr. Remove signal at north entrance of Clackamas Town Center and evaluate traffic diversion. 2014 ODOT OR 213 paving project programmed King to OR 224.	Low
4047	5-11a	OR 213 (82nd Ave)	Luther Road to Sunnybrook Blvd	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4048	5-11a	OR 224	Webster Rd and 82nd Ave	Provide frontage connection on the north side of OR 244	Low
4049	5-11a	OR 224	Springwater Rd to 232nd Dr	Shoulder widening, horizontal realignment, realignment of roadway to bluff	Low
4050	5-11b	OR 211	OR 224 to eastbound US 26	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4051	5-11b	OR 211	OR 224 to Hillcockburn Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4052	5-11b	OR 211	Tickle Creek Rd/OR 211 intersection	Remove or decrease horizontal curve, relocate intersection	Low
4053	5-11b	OR 211	362nd Dr / OR 211 intersection	Remove or decrease vertical curve and remove vegetation	Low
4054	5-11b	OR 211	Eagle Creek Rd to Tickle Creek Rd	Widen to include bikeways /shoulders and add passing /climbing lanes where needed	Low
4055	5-11b	OR 211	0.14 miles east of Coop Rd to Jacknife Rd	Widen to add shoulder / bikeways; realign to remove horizontal and vertical curves	Low
4056	5-11b	OR 211	Tickle Creek Rd to 362nd Dr	Widen to include bikeways /shoulders and add passing /climbing lanes where needed	Low
4057	5-11b	OR 211	Bornstedt Rd to City of Sandy	Add shoulders and bikeways	Low
4058	5-11b	OR 224	232nd Ave to OR 211	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4059	5-11b	OR 224	Fish Creek Rd to National Forest Rd 46	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4060	5-11b	OR 224	Bakers Ferry Rd / OR 224 intersection	Add eastbound right-turn lane	Low
4061	5-11b	OR 224	Amisigger Rd / OR 224 intersection	Install traffic signal; add southbound and eastbound left-turn lanes and westbound right-turn lane	Low
4062	5-11b	OR 224	Heiple Rd / OR 224 intersection	Add southbound right-turn lane	Low
4063	5-11b	OR 224	OR 212 to Estacada city limits	Widen to include shoulders and bikeways; add passing lanes where needed	Low
4065	5-11b	US 26	US 26 / Haley Rd intersection	Develop a plan to address to address access and safety issues on US 26 at this intersection and implement that plan	Low

Table 5-3d Regional Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description	Priority
4066	5-11b	US 26	Kelso Rd to Duncan Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4067	5-11b	US 26	Duncan Rd to Langensand Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4068	5-11b	US 26	Firwood Rd to Sleepy Hollow Dr	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4069	5-11b	US 26	Rhododendron to OR 35	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4070	5-11b	US 26	US 26 / Firwood Rd intersection	Add eastbound right-turn lane	Low
4071	5-11b	US 26	US 26 / Brightwood Loop W	Add westbound right-turn lane	Low
4072	5-11b	US 26	US 26 / Brightwood Loop E	Add westbound right-turn lane	Low
4073	5-11b	US 26	Lolo Pass Rd to Govt. Camp Loop Rd. W	Implement Finding of Mt Hood Multimodal Study including ITS approach with variable speed signage; construct multi-use path between Lolo Pass Rd and John Lake Rd; add enhanced pedestrian crossing, sidewalks, curbs, gutters, pedestrian refuge island, pedestrian illumination and access management in Rhododendron; construct multi-use path connecting Mt. Hood Express transit stop and Pioneer Bridle Trailhead	High
4074	5-11c	OR 99E	Park Ave to Gladstone city limits	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4075	5-11d	OR 43	Lake Oswego to Portland	Develop active transportation connection in accordance with the Active Transportation Plan.	Low
4076	5-11e	OR 211	Dhooghe Rd / OR 211 intersection	Remove or decrease horizontal curve, relocate intersection	Low
4077	5-11e	OR 211	OR 170 (Canby-Marquam Hwy) to City of Molalla	Add shoulders and bikeways	Low
4078	5-11e	OR 211	Needy Rd to 0.6 miles west of Needy Rd	Remove or decrease vertical curve to allow passing zone, add passing lane in one or both directions, possible relocation of intersection	Low
4079	5-11e	OR 211	Molalla city limits to Hayden Rd	Widen to rural arterial standard (2 lanes) with shoulders and bikeways	Low
4080	5-11e	OR 211	Beavercreek Rd to Upper Highland Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4081	5-11e	OR 213	OR 213 / Carus Rd intersection	Install traffic signal to replace existing two-way stop See U339	Low
4082	5-11e	OR 213	OR 213 / Beavercreek Rd intersection	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4083	5-11e	OR 213	Carus Rd / OR 213 intersection	Install southbound left-turn and right-turn lanes	Low
4085	5-11e	OR 99E	Oregon City to Canby	Add shoulders and bikeways	Low
4086	5-11e	OR 99E	Sequoia Parkway to Lone Elder Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4087	5-11e	OR 99E	Territorial Rd to Metro boundary	Perform road safety audit or transportation safety review to identify appropriate safety improvements	Low
4088	5-11b	Government Camp Loop Rd	US 26 to US 26	Add bikeways through Government Camp in accordance with the Active Transportation Plan	High
4089	5-11a	OR 213	Causey Ave to King Rd	Work with TriMet and ODOT to evaluate the Business Access Transit lane and identify projects / approaches to improve safety and enhance transit operation.	High

Table 5-3d Regional Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description	Priority
4090	5-11a	I-205 MUP	I-205 SB Ramp / Sunnyside Rd	Travelling south on the I-205 multi-use path, install a pedestrian signal to cross the I-205 southbound / Sunnyside right turn lane. Perform traffic analysis to evaluate impacts to vehicle queuing. Modification subject to ODOT approval.	High
4091	5-11a	I-205 MUP	Monterey Ave	Install parabolic mirror and/or signage to resolve limited sight distance issues at the intersection of the I-205 MUP and the path extension at Monterey Ave.	High
4092	5-11b	US 26	Arrah Wanna Blvd to Welches Rd	Add multi-use path on north side of US 26	High
4093	5-11b	US 26	Main Park Rd to Salmon River Rd	Add multi-use path on south side of US 26	High
4094	5-11b	US 26 / Welches Rd	US 26 / Welches Rd	Pedestrian and ADA improvments at signal, including crossing improvments on the north side of the intersection.	Medium
4095	5-11b	US 26 / Arrah Wanna Blvd	US 26 / Arrah Wanna Blvd	Install a continental style crosswalk, accompanied by roadway and streetscape improvements	Medium
4096	5-11b	US 26 / Salmon River Rd	US 26 / Salmon River Rd	Install an enhanced pedestrian crossing	High
4097	5-11a	OR 212	OR 212/SE 222nd Drive intersection	Install traffic signal and separate southbound right- and left-turn lanes.	High
4098	5-11a	OR 212	OR 212/SE 242nd Drive intersection	Install separate southbound left-turn.	Low
4099	5-11a	OR 212	OR 212/SE Sunnyside Road-Anderson Road and OR 212/SE Foster Road	Convert OR 212/SE Sunnyside Road intersection to right-in/right-out/left in; add eastbound through and southbound left-turn lane at OR 212/SE Foster Road intersection, provide pedestrian and bicycle facilities.	High
4100	5-11a	OR 212	OR 212/SE Tong Road/SE 187th Avenue Intersection	Signalize intersection.	Medium
4101	5-11a	OR 212 Corridor Plan	SE 172nd Avenue to US 26	Planning effort to establish the long-term vision, conceptual alignment, cross-section, and access locations for OR 212 between SE 172nd Avenue and US 26.	Medium
4102	5-11a	OR 212 Alternative Mobility and Fee in Lieu Strategy	Rock Creek Junction to SE Foster Road	Planning effort to establish alternative mobility standard, acceptable traffic operations levels, improvements, and cost estimates for over-capacity intersections.	High
4103	5-11a	OR 224	OR 224/SE 232nd Drive Intersection	Study to assess need for and feasibility of improvements, such as a signal or roundabout (does not include improvement design or construction).	High