



INVITATION TO BID #2018-29
Detention Pond Rehabilitation and Repair
ADDENDUM NUMBER 1
April 10, 2018

On March 22, 2018, Clackamas County ("County") on behalf of Clackamas County Service District No. 1 ("CCSD#1") and Water Environment Services published Invitation to Bid #2018-29. The County has found that it is in its interest to amend the BID through the issuance of this Addendum #1. Except as expressly amended below, all other terms and conditions of the original BID shall remain unchanged.

- 1. Remove and replace the Detention Pond Rehabilitation and Repair Bid Schedule with Detention Pond Rehabilitation and Repair Bid Schedule Addendum #1 dated 4/10/18, hereby attached and incorporated by reference.**

*note the addition of the following bid items:

Line item: #3 – Traffic Control

#4 – Dewatering

#14 - Outlet rip rap- Class 200 rip rap**

#26 – Sidewalk Repair

#32 – Sidewalk Repair

Attachments:

- Bid #2018-29 Detention Pond Rehabilitation and Repair
Bid Schedule- Addendum #1 4/10/18

End of Addendum #1

Item No.	Item Description	Qty	Unit	Unit Cost	Total Cost
1	Mobilization	1	L.S.		
2	Erosion Control	1	L.S.		
3	Traffic Control	1	L.S.		
4	Dewatering	1	L.S.		
Bid Items Per Pond:					
Pond 1: Engert Ridge		Qty	Unit	Unit Cost	Total Cost
5	Clearing/Grubbing/Vegetation Removal	1.00	LS		
6	Haul and Disposal - Organic Material (Approx 1.5ft material)	484	C.Y.		
7	Class 100 rip rap **	5.0	C.Y.		
8	Jute Matting - Pond 1 (6 ft x 125 ft)	750.0	SF		
9	Hydroseeding - Wetland Mix/Pond Bottom	4,356	SF		
10	Hydroseeding - Upland Mix/Pond Side Slopes	4,356	SF		
Pond 2: Orchard View Lane		Qty	Unit	Unit Cost	Total Cost
11	Clearing/Grubbing/Vegetation Removal	1.00	LS		
12	Haul and Disposal - Organic Material (Approx 1.5ft material)	278	C.Y.		
13	Class 100 rip rap **	5.0	C.Y.		
14	Outlet rip rap - Class 200 rip rap **	5.0	C.Y.		
15	Hydroseeding - Wetland Mix/Pond Bottom	5,000	SF		
16	Hydroseeding - Upland Mix/Pond Side Slopes	5,300	SF		
Pond 3: 129th & Scott Creek		Qty	Unit	Unit Cost	Total Cost
17	Clearing/Grubbing/Vegetation Removal	1.00	LS		
18	Haul and Disposal - Organic Material (Approx 1 ft material)	129	C.Y.		
19	Class 100 rip rap **	6.8	C.Y.		
20	Class 200 rip rap **	18.0	C.Y.		
21	Hydroseeding - Wetland Mix/Pond Bottom	1,742	SF		
22	Hydroseeding - Upland Mix/Pond Side Slopes	1,742	SF		
Pond 4: Liberty View (129th & Mt. Gate)		Qty	Unit	Unit Cost	Total Cost
23	Clearing/Grubbing/Vegetation Removal	1.00	LS		
24	Haul and Disposal - Organic Material (Approx 1.5ft material)	184	C.Y.		
25	Class 100 rip rap **	5.0	C.Y.		
26	Sidewalk Repair	1.0	L.S.		
27	Hydroseeding - Wetland Mix/Pond Bottom	4,356	SF		
28	Hydroseeding - Upland Mix/Pond Side Slopes	4,356	SF		
Pond 5: Kensington Bluff Pond 1		Qty	Unit	Unit Cost	Total Cost
29	Clearing/Grubbing/Vegetation Removal	1.00	LS		
30	Haul and Disposal - Organic Material	100	C.Y.		
31	Class 200 rip rap **	5.0	C.Y.		
32	Sidewalk Repair	1.0	L.S.		
33	Hydroseeding - Wetland Mix/Pond Bottom	2,178	SF		
34	Hydroseeding - Upland Mix/Pond Side Slopes	2,178	SF		
Pond 6: Kensington Bluff Pond 2		Qty	Unit	Unit Cost	Total Cost
35	Clearing/Grubbing/Vegetation Removal	1.00	LS		
36	Haul and Disposal - Organic Material	100	C.Y.		
37	Class 200 rip rap **	5.0	C.Y.		
38	Hydroseeding - Wetland Mix/Pond Bottom	4,356	SF		
39	Hydroseeding - Upland Mix/Pond Side Slopes	4,356	SF		

** Rip Rap bid items will only be used if the existing material cannot be found and/or needs to be replaced

Firm Name_____

Authorized Signature_____

Date_____