

## NOTES:

1. ALL PATCH JOINTS SHALL BE CLEANED (SWEPT/BLOWN OUT) AND TACKED BEFORE PAVING.

(SEE DWG U200, U250 & U270 FOR BACKFILL AND TRENCH PATCH REQUIREMENTS)

- 2. ALL CUTS ARE TO BE PARALLEL AND PERPENDICULAR TO DIRECTION OF TRAFFIC.
- 3. GRIND AREA WILL BE CLEANED (SWEPT/BLOWN OUT) AND TACKED WITH HOT ASPHALT TACK COAT BEFORE INLAY IS COMPLETED.

SECTION A-A

- 4. AFTER PAVING HOT LIQUID ASPHALT WILL BE USED TO SAND SEAL ALL SEAMS.
- 5. SEE STD. DWG U290 TO ADDRESS MULTIPLE AND PROPOSED TRENCHES WITHIN 5 FEET OF EXISTING TRENCH REPAIRS.
- 6. THE ROAD RIGHT-OF-WAY WILL BE LEFT IN AS GOOD AS OR BETTER CONDITION THAN WHEN THE PROJECT BEGAN.
- 7. IF THE OUTSIDE SAW CUT IS LESS THAN THREE (3) FEET FROM THE E/PT OR CURB, THE EXISTING OUTSIDE ASPHALT TO THE E/P OR CURB MUST BE REMOVED AND REPLACED AS PART OF THE GRIND & INLAY LIMITS.
- 8. TRENCH LIMITS LESS THAN ONE FOOT FROM CENTERLINE OR LANE LINE SHALL EXTEND GRIND & INLAY LIMITS.
- 9. GRIND AND INLAY ADJACENT TO CURB RAMPS MAY REQUIRE ADA IMPROVEMENTS.
- 10. THE COUNTY MAY INCREASE OR DECREASE THESE REQUIREMENTS BASED ON LOCAL CONDITIONS.
- 11. COMPLY WITH SMOOTHNESS REQUIREMENTS OF OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION SECTION 00744.70

REVISION	DATE			_	APPROVAL DATE: 6/1/2020	SCALE: N.T.S.	STANDARD
REVISED	05/18	RN	DEPARTMENT OF TRANSPORTATION				DRAWING
REVISED	09/18	RM	AND DEVELOPMENT		PAVEMENT CUT ST	VNDVDD	
REVISED	12/19	AAR	150 BEAVERCREEK ROAD		FAVEIVILINI COI STAINDAIND		11275
			OREGON CITY, OR 97045	CLACKAMAS	ARTERIAL/COLLECT	OR ROADS	0273
			CRESON CITT, OR 37040	COUNTY	, t. = , o o = = = o .		