



#### DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT

DEVELOPMENT SERVICES BUILDING

150 BEAVERCREEK ROAD OREGON CITY, OR 97045

BCC Agenda Date/Item:_	
------------------------	--

**Board of County Commissioners** 

Approval of a Public Improvement Contract with Emery & Sons Construction Company Group, LLC for the Jennings Ave: OR99E to Oatfield Rd Project. Total contract value is \$5,253,884.75. Funding is through Federal Surface Transportation Program, America Rescue Plan Act Funds, and County Road Funds. No County General Funds are involved.

Previous Board	2/20/24: Request for cons	sent.		
Action/Review	4/20/2023: BCC Approval Agreement No. 31035 wire 06/24/21: BCC Approval Agreement No. 31035 wire 01/21/21: BCC Approval Inc. 10/17/19: BCC Approval 10/11/18: BCC Approval Right-of-Way Services wire 06/29/17: BCC Approval with Oregon Department 01/01/17: BCC Approval	I of Amendment # 2 of Suth the Oregon Department of Amendment #1 of Support Oregon Department of Amendment #1 to Confer a Contract with Murrays of Intergovernmental Agreement Oregon Department of Supplemental Project A of Transportation.	t of Transportation olemental Project Transportation. tract with Murraysmith, smith, Inc. eement No. 32338 for Transportation. Agreement No. 31035 reement No. 30923 for	
Performance	The project will build a strong infrastructure.			
Clackamas				
Counsel Review	Yes – Andrew Naylor	Procurement Review	Yes	
Contact Person	Stan Monte	Contact Phone	503-742-4678	

**EXECUTIVE SUMMARY**: This is a request for a contract with Emery and Sons Construction Group, LLC for the construction of the Jennings Ave: OR99E to Oatfield Rd Project. The improvements include constructing a curb-tight sidewalk on the north side of the roadway and constructing bike lanes on both sides of the roadway for enhanced bicycle and pedestrian connectivity. The total length of the project is approximately 3/4 of a mile.

For Filing Use Only	

Funding for this contract is from Federal Surface Transportation Program (\$3,551,186.79) funds, American Rescue Plan (\$1,163,124.00) funds and County Road Fund (\$539,573.96). Construction is expected to take eight months with the project completed by October 31, 2024.

#### **PROCUREMENT PROCESS:**

This project was advertised in accordance with ORS and LCRB Rules on October 19, 2023 through Invitation to Bid 2023-90. Bid proposals were publically opened December 6, 2023 and the County received ten (10) ten bids in response ranging from \$5,253,884.75 to \$7,001,103.00. After review of the Bid Proposals, contracting with Emery & Sons Construction Group, LLC was determined to be in the best interest of the county based upon the evaluation of the bids.

**RECOMMENDATION:** Staff respectfully recommends the Board approve and sign this contract with Emery & Sons Construction Group, LLC. for the Jennings Ave: OR99E to Oatfield Rd Project.

Respectfully submitted,

Dan Johnson

Dan Johnson
Director of Transportation & Development



# CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT

#### AGREEMENT FORM

#### Contract #9037

This Public Improvement Contract for the Jennings Ave: OR99E to Oatfield Rd Project (the "Contract"), is made by and between the Clackamas County, a political subdivision of the State of Oregon, hereinafter called "County," and Emery & Sons Construction Group, LLC, hereinafter called the "Contractor" (collectively the "Parties"), shall become effective on the date this Contract has been signed by all the Parties and all County approvals have been obtained, whichever is later.

Project Name: #2023-90 Jennings Ave: OR99E to Oatfield Rd Project

#### 1. Contract Price, Contract Documents and Work.

The Contractor, in consideration of the sum of Five Million Two Hundred Fifty Three Thousand Eight Hundred Eighty Four Dollars and Seventy-Five Cents (5,253,884.75) (the "Contract Price"), to be paid to the Contractor by County in the manner and at the time hereinafter provided, and subject to the terms and conditions provided for in the Instructions to Bidders and other Contract Documents as defined in Section 12, General Conditions for Construction for (Certified LPA) Clackamas County, all of which are incorporated herein by reference, hereby agrees to perform all Work described and reasonably inferred from the Contract Documents. The Contract Price are the prices fixed in the Contractor's Bid Proposal for said work as set forth herein under the Schedule of Bid Prices.

Also, the following documents are incorporated by reference in this Contract and made a part hereof:

- Notice of Public Improvement Contract Opportunity
- Instructions to Bidders
- Supplemental Instructions to Bidders
- Bid Bond
- Bid Proposal and Schedule of Prices
- Public Improvement Contract Form
- Affidavit of Non Collusion
- First-Tier Subcontractor Disclosure Form

- Certificate Regarding Ineligible Contractors
- Performance Bond and Payment Bond
- Prevailing Wage Rates
- Plans, Special Provisions and Drawings
- General Conditions for Construction for (Certified LPA) Clackamas County
- DBE, FHWA and ODOT Forms in Section 13 of the Bid Proposal

#### 2. Representatives.

Contractor has named Vince Makinson as its Authorized Representative to act on its behalf.

The County designates <u>Stan Monte</u> as its Authorized Representative in the administration of this Contract. The above-named individual shall be the initial point of contact for matters related to Contract performance, payment, authorization, and to carry out the responsibilities of the County.

#### 3. Key Persons.

The Contractor's personnel identified below shall be considered Key Persons and shall not be replaced during the project without the prior written permission of County, which shall not be unreasonably withheld. If the Contractor intends to substitute personnel, a request must be given to County at least 30 days prior to the intended time of substitution. When replacements have been approved by County, the Contractor shall provide a transition period of at least 10 working days during which the original and replacement personnel shall be working on the project concurrently. Once a replacement for any of these staff members is authorized, further replacement shall not occur without the prior written permission of County. The Contractor's project staff shall consist of the following personnel:

**Project Executive:** <u>Vince Makinson</u> shall be the Contractor's project executive, and will provide oversight and guidance throughout the project term.

**Project Manager**: <u>Aaron Slowik</u> shall be the Contractor's project manager and will participate in all meetings throughout the project term.

#### 4. Contract Dates.

COMMENCEMENT DATE: Upon Issuance of Notice to Proceed ("NTP")

CONTRACT COMPLETION DATE(S): October 31, 2024, as specified in the Special Provisions that accompany the General Conditions for Construction for Clackamas County Section 00180.50(h), Contract Time.

CONTRACT EXPIRATION DATE: December 31, 2025

Time is of the essence for this Contract. It is imperative that the Work in this Contract reach Third Notification by the above specified dates.

#### 5. Insurance Certificates.

In accordance with Section 00170.70 of Section 12 of the Bid Proposal, General Conditions for Construction for (Certified LPA) Clackamas County, Contractor shall furnish proof of the required insurance naming Clackamas County and the State of Oregon and the Oregon Department of Transportation as an additional insured. Insurance certificates may be returned with the signed Contract.

#### 6. Tax Compliance.

Contractor must, throughout the duration of this Contract and any extensions, comply with all tax laws of this state and all applicable tax laws of any political subdivision of this state. Any violation of this section shall constitute a material breach of this Contract. Further, any violation of Contractor's warranty in this Contract that Contractor has complied with the tax laws of this state and the applicable tax laws of any political subdivision of this state also shall constitute a material breach of this Contract. Any violation shall entitle County to terminate this Contract, to pursue and recover any and all damages that arise from the breach and the termination of this Contract, and to pursue any or all of the remedies available under this Contract, at law, or in equity, including but not limited to: (A) Termination of this Contract, in whole or in part; (B) Exercise of the right of setoff, and withholding of amounts otherwise due and owing to Contractor, in an amount equal to County's setoff right, without penalty; and (C) Initiation of an action or proceeding for damages, specific performance, declaratory or injunctive relief. County shall be entitled to recover any and all damages suffered as the result of Contractor's breach of this Contract, including but not limited to direct, indirect, incidental and consequential damages, costs of cure, and costs incurred in securing replacement performance. These remedies are cumulative to the extent the remedies are not inconsistent, and County may pursue any remedy or remedies singly, collectively, successively, or in any order whatsoever.

The Contractor represents and warrants that, for a period of no fewer than six calendar years preceding the effective date of this Contract, has faithfully complied with: (A) All tax laws of this state, including but not limited to ORS 305.620 and ORS chapters 316, 317, and 318; (B) Any tax provisions imposed by a political subdivision of this state that applied to Contractor, to Contractor's property, operations, receipts, or income, or to Contractor's performance of or compensation for any work performed by Contractor; (C) Any tax provisions imposed by a political subdivision of this state that applied to Contractor, or to goods, services, or property, whether tangible or intangible, provided by Contractor; and (D) Any rules, regulations, charter provisions, or ordinances that implemented or enforced any of the foregoing tax laws or provisions.

#### 7. Confidential Information.

Contractor acknowledges that it and its employees or agents may, in the course of performing their responsibilities under this Contract, be exposed to or acquire information that is confidential to County or the State of Oregon. Any and all information of any form obtained by Contractor or its employees or agents in the performance of this Contract shall be deemed confidential information of County and of State ("Confidential Information"). Contractor agrees to hold Confidential Information in strict confidence, using at least the same degree of care that Contractor uses in maintaining the confidentiality of its own confidential information, and not to copy, reproduce, sell, assign, license, market, transfer or otherwise dispose of, give, or disclose Confidential Information to third parties or use Confidential Information for any purpose unless specifically authorized in writing under this Contract.

#### 8. Counterparts.

This Contract may be executed in several counterparts, all of which when taken together shall constitute an agreement binding on all Parties, notwithstanding that all Parties are not signatories to the same counterpart. Each copy of the Contract so executed shall constitute an original.

#### 9. Integration.

The Contract Documents constitute the entire agreement between the parties. There are no other understandings, agreements or representations, oral or written, not specified herein regarding this Contract. Contractor, by the signature below of its authorized representative, hereby acknowledges that it has read this Contract, understands it, and agrees to be bound by its terms and conditions.

#### 10. Liquidated Damages

The Contractor acknowledges that the County will sustain damages as a result of the Contractor's failure to substantially complete the Project in accordance with the Contract Documents, including Special Provision Section 00180.85 in Section 12 of the Bid Proposal, General Conditions for Construction for (Certified LPA) Clackamas County. These damages may include, but are not limited to delays in completion, use of the Project, and costs associated with Contract administration and use of temporary facilities. Liquidated damages are set forth in the Contract Documents and may include the following:

- 10.1 \$1,100 per Calendar day for failure to complete the Work on time required by 00180.50(h), as set forth in section 00180.85 (b);
- 10.2 \$500 per 15 minutes, or for a portion of 15 minutes, per lane, for any lane closure beyond the limits listed in 00220.40(e) or 00220.40(f), as set forth in 00180.85(c);
- 10.3 \$500 per 20 minutes, or for a portion of 20 minutes, for stopping or holding traffic longer than 20 minutes, as set forth in 00180.85 (e).
- 11. Compliance with Applicable Law. Contractor shall comply with all federal, state, county, and local laws, ordinances, and regulations applicable to the Work to be done under this Contract including, but not limited to, compliance with the prohibitions set forth in ORS 652.220, compliance of which is a material element of this Contract and failure to comply is a material breach that entitles County to exercise any rights and remedies available under this Contract including, but not limited to, termination for default.
- **12. Responsibility for Taxes.** Contractor is solely responsible for payment of any federal, state, or local taxes required as a result of the Contract or the Work including, but not limited, to payment of the corporate activity tax imposed under enrolled HB 3427 (2019 Oregon regular legislative session).
- **13. No Attorney Fees.** In the event any arbitration, action or proceeding, including any bankruptcy proceeding, is instituted to enforce any term of this Contract, each party shall be responsible for its own attorneys' fees and expenses.

**In witness whereof**, Clackamas County executes this Contract and the Contractor does execute the same as of the day and year first above written.

14. Contractor Data:

Emery & Sons Constructions Group, LLC P.O. Box 13069
Salem, Oregon 97309

Contractor CCB #221536 Expiration Date: 6/26/2024

Oregon Business Registry # 1447785-94 Entity Type: DLLC State of Formation: Oregon

Payment information will be reported to the IRS under the name and taxpayer ID# provided by the Contractor. Information must be provided prior to contract approval. Information not matching IRS records could subject Contractor to 28 percent backup withholding.

Emery & Sons Construction Group, LLC	Clackamas County	
Our January 18, 2024 Authorized Signature Date	Chair	Data
Authorized Signature Date	Chair	Date
Vince Makinson, Principal		
Name / Title Printed	Recording Secretary	
	APPROVED AS TO FORM	
	Ly	01/30/2024
	County Counsel	Date



# CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT OPPORTUNITY

### Table of Contents

Section 1	Notice of Public Improvement Contract Opportunity
Section 2	.Instructions to Bidders
Section 3	.Supplemental Instructions to Bidders
Section 4	.Bid Bond
Section 5	.Bid Proposal Form and Bid Schedule of Prices
Section 6	.First-Tier Subcontractors Disclosure Form
Section 7	.Affidavit of Non-Collusion and Congressional Lobbying Certificate
Section 8	.Certificate Regarding Ineligible Contractors and Conflict of Interest Disclosure Form Reference
Section 9	Performance Bond
Section 10	Payment Bond
Section 11	.Public Improvement Contract (Agreement Form)
Section 12	Project Information, Plans, General Conditions for Construction for Clackamas County and Special Provisions
	. Disadvantaged Business Enterprise (DBE) Commitment Requirements  DBE Information Page  DBE Commitment Certification and Utilization Form  Assigned DBE Contract Goal  ODOT DBE Policy Statement  Disadvantaged Business Enterprise (DBE) Supplemental Required Contract Provisions  Equal Employment Opportunity Provisions  Equal Employment Opportunity-Aspirational Target Provisions  On-site Workforce Affirmative Action Requirements for
Women and Minor	ities on Federal-Aid Contract Required Contract Provision

Federal-Aid Construction Contracts (FHWA 1273)

Reimbursable Federal on-the-job and Apprenticeship Training



# CLACKAMAS COUNTY NOTICE OF PUBLIC IMPROVEMENT CONTRACT OPPORTUNITY

### INVITATION TO BID #2023-90 Jennings Ave: OR99E to Oatfield Rd Project October 19, 2023

Clackamas County ("County") through its Board of County Commissioners is accepting sealed bids for the **Jennings Ave: OR99E to Oatfield Rd Project** until **November 16, 2023, 2:00 PM,** Pacific Time, ("Bid Closing") at the following location:

Bidding Documents can be downloaded from the state of Oregon procurement website ("OregonBuys") at the following address: <a href="https://oregonbuys.gov/bso/view/login/login.xhtml">https://oregonbuys.gov/bso/view/login/login.xhtml</a>, Document No.S-C01010-00008470.

Prospective Bidders will need to sign in to download the information and that information will be accumulated for a Plan Holder's List. Prospective Bidders are responsible for obtaining any Addenda from Website listed above.

#### **Submitting Proposals: Bid Locker**

Proposals will only be accepted electronically thru a secure online bid submission service, <u>Bid Locker</u>. *Email submissions to Clackamas County email addresses will no longer be accepted.* 

- A. Completed proposal documents must arrive electronically via Bid Locker located at <a href="https://bidlocker.us/a/clackamascounty/BidLocker">https://bidlocker.us/a/clackamascounty/BidLocker</a>.
- B. Bid Locker will electronically document the date and time of all submissions. Completed documents must arrive by the deadline indicated in Section 1 or as modified by Addendum. LATE PROPOSALS WILL NOT BE ACCEPTED.
- C. Proposers must register and create a profile for their business with Bid Locker in order to submit for this project. It is free to register for Bid Locker.
- D. Proposers with further questions concerning Bid Locker may review the Vendor's Guide located at <a href="https://www.clackamas.us/how-to-bid-on-county-projects">https://www.clackamas.us/how-to-bid-on-county-projects</a>.

Engineers Estimate: \$5,000,000 - \$5,500,000

#### **Contact Information**

Procurement Process and Technical Questions: Tralee Whitley at TWhitley@clackamas.us

Bids will be opened and publicly read aloud at the above Delivery address after the Bid Closing. Bid results will also be posted to the OregonBuys listing shortly after the opening.

To be eligible for award under this Invitation to Bid, bidders (prime contractors) must submit a prequalification application (either ODOT or County) to the County at least two business days prior to the Bid Closing. County will reject bids from bidders who are not prequalified for the class of work indicated prior to the Bid Closing. **Bidders must be prequalified in Earthwork and Drainage (EART).** 

#### **Prevailing Wage**

This is a public work contract subject to ORS 279C.800 to 279C.870 and the Federal Prevailing Rate of Wage required Under the Davis-Bacon Act (40 U.S.C. 3141 Et Seq.). All projects have minimum wage rate requirements. Each worker in each trade or occupation employed to perform work on the project shall be paid not less than the existing prevailing wage rate established by the Oregon Bureau of Labor and

Industries (BOLI) or the applicable federal prevailing wage rate required under the Davis-Bacon Act, whichever is higher.

Prevailing wage rates published in the wage determinations and any applicable modifications or amendments apply to this Project and are incorporated by reference:

- (1) U.S. Department of Labor, "General Wage Determinations Issued under the Davis-Bacon and Related Acts: Oregon Highway Construction Projects", and
- (2) Oregon Bureau of Labor and Industries (BOLI), "Prevailing Wage Rates For Public Works Contracts in Oregon".

The applicable Federal prevailing wage rates and the existing State prevailing wage rates last published prior to the time of Bid Closing as stated above, apply to this Project.

Wage Rates are Internet-Accessible - The applicable Davis-Bacon wage rates can be found on the US Department of Labor website at: https://www.wdol.gov/dba.aspx.

The BOLI wage rates can be found on the Oregon Bureau of Labor and Industries website at: <a href="https://www.oregon.gov/boli/WHD/PWR/pages/pwr\_state.aspx">https://www.oregon.gov/boli/WHD/PWR/pages/pwr\_state.aspx</a>.

Wage Rates are Subject to Change - Modifications or amendments to the Davis-Bacon and BOLI wage rates applicable to this Project may occur at any time before Bid Closing. Bidders are responsible to monitor the respective web page(s) for modifications and amendments up until Bid Closing.

The applicable Davis-Bacon and BOLI wage rates will be included in the Contract.

Clackamas County in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C. 2000d to 200-4 and Title 49, Code of Federal regulations, Department of Transportation, subtitle A, Office of the secretary, Part 21, nondiscrimination in federally assisted programs of the Department of Transportation issued pursuant to such Act, herby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for award.

All federally funded projects have "BUY AMERICA" requirements. The project is subject to the DBE policy statement as cited in 49 CFR 26. DBE Goal for this project is 10.0%. The Reimbursable On-the-job Training requirement is 500 hours.

Clackamas County encourages bids from Minority, Women, and Emerging Small Businesses.



# CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT

#### INSTRUCTIONS TO BIDDERS

Clackamas County Local Contract Review Board Rules ("LCRB Rules") govern this procurement process. LCRB Rules may be found at: <a href="http://www.clackamas.us/code/documents/appendixc.pdf">http://www.clackamas.us/code/documents/appendixc.pdf</a>. The Instructions to Bidders is applicable to the procurement process for Clackamas County, or any component unit thereof identified on the Notice of Public Improvement Contract Opportunity, herein after referred to as the "Owner."

#### Article 1. Scope of Work

The work contemplated under this contract with the Owner, includes all labor, materials, transportation, equipment and services necessary for, and reasonably incidental to, the completion of all construction work in connection with the project described in the Project Manual which includes, but is not necessarily limited to, the Notice of Public Improvement Contract Opportunity, Instructions to Bidders, Supplemental Instructions to Bidders, Bid Form, Bid Bond, Public Improvement Contract Form, Performance Bond, Payment Bond, and Plans, Specifications and Drawings.

### Article 2. Examination of Site and Conditions

Before making a Bid, the Bidder shall examine the site of the work and ascertain all the physical conditions in relation thereto. The Bidder shall also make a careful examination of the Project Manual including the plans, specifications, and drawings and other contract documents, and shall be fully informed as to the quality and quantity of materials and the sources of supply of the materials. Failure to take these steps will not release the successful Bidder from entering into the contract nor excuse the Bidder from performing the work in strict accordance with the terms of the contract at the price established by the Bid.

The Owner will not be responsible for any loss or for any unanticipated costs, which may be suffered by the successful Bidder, as a result of such Bidder's failure to be fully informed in advance with regard to all conditions pertaining to the work and the character of the work required, including site conditions. No statement made by an elected official, officer, agent, or employee of the Owner in relation to the physical or other conditions pertaining to the site of the work will be binding on the Owner, unless covered by the Project Manual or an Addendum.

### Article 3. Interpretation of Project Manual and Approval of Materials Equal to Those Provided in the Specifications

If any Bidder contemplating submitting a Bid for the proposed contract is in doubt as to the true meaning of any part of the plans, specifications or forms of contract documents, or detects discrepancies or omissions, such Bidder may submit to the Architect (read "Engineer" throughout in lieu of Architect as appropriate) a written request for an interpretation thereof at least ten (10) calendar days prior to the date set for the Bid Closing.

When a prospective Bidder seeks approval of a particular manufacturer's material, process or item of equal value, utility or merit other than that designated by the Architect in the Project Manual, the Bidder may submit to the Architect a written request for approval of such substitute at least ten (10) calendar days prior to the date set for the Bid Closing. The prospective Bidder submitting the request will be responsible for its prompt delivery.

Requests of approval for a substitution from that specified shall be accompanied by samples, records of performance, certified copies of tests by impartial and recognized laboratories, and such other information as the Architect may request.

To establish a basis of quality, certain processes, types of machinery and equipment or kinds of materials may be specified in the Project Manual either by description of process or by designating a manufacturer by name and referring to a brand or product designation or by specifying a kind of material. Whenever a process is designated or a manufacturer's name, brand or item designation is given, or whenever a process or material covered by patent is designated or described, it shall be understood that the words "or approved equal" follow such name, designation or description, whether in fact they do so or not.

Any interpretation of the Project Manual or approval of manufacturer's material will be made only by an Addendum duly issued. All Addenda will be posted to the OregonBuys listing and will become a part of the Project Manual. The Owner will not be responsible for any other explanation or interpretation of the Project Manual nor for any other approval of a particular manufacturer's process or item for any Bidder.

When the Architect approves a substitution by Addendum, it is with the understanding that the Contractor guarantees the substituted article or material to be equal or better than the one specified.

# Article 4. Security to Be Furnished by Each Bidder

Each Bid must be accompanied by either 1) a cashier's check or a certified check drawn on a bank authorized to do business in the State of Oregon, or 2) a Bid bond described hereinafter, executed in favor of the Owner, for an amount equal to ten percent (10%) of the total amount Bid as a guarantee that, if awarded the contract, the Bidder will execute the contract and provide a performance bond and payment bond as required. The successful Bidder's check or Bid bond will be retained until the Bidder has entered into a contract satisfactory to Owner and furnished a one hundred percent (100%) performance bond and one hundred percent (100%) payment bond. The Owner reserves the right to hold the Bid security as described in Article 10 hereof. Should the

successful Bidder fail to execute and deliver the contract as provided for in Article 12 hereof, including a satisfactory performance bond and payment bond within twenty (20) calendar days after the Bid has been accepted by the Owner, then the contract award made to such Bidder may be considered canceled and the Bid security may be forfeited as liquidated damages at the option of the Owner. The date of the acceptance of the Bid and the award of the contract as contemplated by the Project Manual shall mean the date of acceptance specified in the Notice of Intent to Award.

#### **Article 5. Execution of Bid Bond**

Should the Bidder elect to utilize a Bid bond as described in Article 4 in order to satisfy the Bid security requirements, such form must be completed in the following manner:

- A. Bid bonds must be executed on the County forms, which will be provided to all prospective Bidders by the Owner.
- B. The Bid bond shall be executed on behalf of a bonding company licensed to do business in the State of Oregon.
- C. In the case of a sole individual, the bond need only be executed as principal by the sole individual. In the case of a partnership, the bond must be executed by at least one of the partners. In the case of a corporation, the bond must be executed by stating the official name of the corporation under which is placed the signature of an officer authorized to sign on behalf of the corporation followed by such person's official capacity, such as president, etc. The corporation seal should then be affixed to the bond.
- D. The name of the surety must be stated in the execution over the signature of its duly authorized attorney-in-fact and accompanied by the seal of the surety corporation.

#### Article 6. Execution of the Bid Form

Each Bid shall be made in accordance with: (i) the sample Bid Form accompanying these instructions; (ii) the appropriate signatures for a sole individual,

partnership, corporation or limited liability corporation shall be added as noted in Article 5C above; (iii) numbers pertaining to base Bids shall be stated both in writing and in figures; and (iv) the Bidder's address shall be typed or printed.

The Bid Form relates to Bids on a specific Project Manual. Only the amounts and information asked for on the Bid Form furnished will be considered as the Bid. Each Bidder shall Bid upon the work exactly as specified and provided in the Bid Form. The Bidder shall include in the Bid a sum to cover the cost of all items contemplated by the Contract. The Bidder shall Bid upon all alternates that may be indicated on the Bid Form. When Bidding on an alternate for which there is no charge, the Bidder shall write the words "No Charge" in the space provided on the Bid Form. If one or more alternates are shown on the Bid Form, the Bidder shall indicate whether each is "add" or "deduct."

#### Article 7. Prohibition of Alterations to Bid

Bids that are incomplete, or contain ambiguities or have differing conditions required by the Bidder, including requested changes or exceptions to the Public Improvement Contract form or other portions of the Project Manual, may be rejected in Owner's sole and absolute discretion.

#### **Article 8. Submission of Bid**

Each Bid shall be sealed in an envelope, properly addressed to the Owner, showing on the outside of the envelope the name of the Bidder and the name of the project. Bids will be received at the time and place stated in the Notice of Public Improvement Contract Opportunity.

#### Article 9. Bid Closing and Opening of Bids

All Bids must be received by the Owner at the place and time set for the Bid Closing. Any Bids received after the scheduled Bid Closing time for receipt of Bids will be rejected.

At the time of opening and reading of Bids, each Bid received will be publicly opened and read aloud, irrespective of any irregularities or informalities in such Bids. Generally, Bid results will be posted to the Procurement Website within a couple hours of the opening.

# Article 10. Acceptance or Rejection of Bids by Owner

Unless all Bids are rejected, the Owner will award a contract based on the lowest responsive Bid from a responsible Bidder. If that Bidder does not execute the contract, it will be awarded to the next lowest responsible Bidder or Bidders in succession.

The Owner reserves the right to reject all Bids and to waive minor informalities. The procedures for contract awards shall be in compliance with the provisions of the LCRB Rules in effect at that time.

The Owner reserves the right to hold the Bid and Bid security of the three lowest Bidders for a period of thirty (30) calendar days from and after the time of Bid opening pending award of the contract. Following award of the contract the Bid security of the three lowest Bidders may be held twenty (20) calendar days pending execution of the contract. All other Bids will be rejected and Bid security will be returned.

In determining the lowest Bidder, the Owner reserves the right to take into consideration any or all authorized base Bids as well as alternates or combinations indicated in the Bid Form.

If no Bid has been accepted within thirty (30) calendar days after the opening of the Bids, each of the three lowest Bidders may withdraw the Bid submitted and request the return of the Bid security.

#### Article 11. Withdrawal of Bid

At any time prior to the Bid Closing, a Bidder may withdraw its Bid. This will not preclude the submission of another Bid by such Bidder prior to the time set for the Bid Closing.

After the time set for the Bid Closing, no Bidder will be permitted to withdraw its Bid within the time frames specified in Article 10 for award and execution, except as provided for in that Article.

# Article 12. Execution of Contract, Performance Bond and Payment Bond

The Owner will provide the successful Bidder with contract forms within seven (7) calendar days after the completion of the award protest period. The Bidder is required to execute the contract forms as provided, including a performance bond and a payment bond from a surety company licensed to do surety business in the State of Oregon, within seven (7) calendar days after receipt of the contract forms. The contract forms shall be delivered to the Owner in the number called for and to the location as instructed by the Owner.

#### **Article 13. Recyclable Products**

Contractors will use recyclable products to the maximum extent economically feasible in the performance of the Contract.

# Article 14. Clarification or Protest of the Solicitation Document or Specifications

Any request for clarification or protest of the solicitation document or specifications must be submitted in the manner provided for in the applicable section of the LCRB Rules to the Procurement Representative referenced in the Notice of Public Improvement Contract Opportunity.

A protest of the Solicitation Document must be received within seven (7) business days of the issuance of the Bid or within three (3) business days of issuance of an addendum.

Requests for clarification may be submitted no less than five (5) business days prior to the Bid Closing Date.

#### **Article 15. Protest of Intent to Award**

Owner will name the apparent successful Bidder in a "Notice of Intent to Award" letter. Identification of the apparent successful Bidder is procedural only and creates no right in the named Bidder to the award of the contract. Competing Bidders will be notified by publication of the Notice of Intent to Award on the Clackamas County Procurement Website of the selection of

the apparent successful Bidder(s) and Bidders shall be given seven (7) calendar days from the date on the "Notice of Intent to Award" letter to review the file at the Procurement Division office and file a written protest of award, pursuant to C-049-0450. Any award protest must be in writing and must be delivered by hand delivery or mail to the Procurement Division Director at: Procurement Division, 2051 Kaen Road, Oregon City, OR 97045.

# Article 16. Disclosure of First-Tier Subcontractors

Within two (2) working hours after the Bid Closing, all Bidders shall submit to the County a disclosure form identifying any first-tier subcontractors (those entities that would be contracting directly with the prime contractor) that will be furnishing labor and materials on the contract, if awarded, whose subcontract value would be equal to or greater than: (a) Five percent (5%) of the total contract price, but at least \$15,000; or (b) \$350,000, regardless of the percentage of the total contract price.

Disclosures may be submitted with the Bid or may be hand delivered to the Bid Closing address or emailed to procurement@clackamas.us.



# CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT

#### SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

Project Name: #2023-90 Jennings Ave: OR99E to Oatfield Rd Project

The following modify the Clackamas County "Instructions to Bidders" for this Project. Where a portion of the Instructions to Bidders has been modified by these Supplemental Instructions to Bidders, the unaltered portions shall remain in effect.

Add to Article 8, Submission of Bid in Section 2 with the following:

- 1. **Prequalification:** To be eligible for award under this Invitation to Bid, Bidders (prime contractors) must submit proof of ODOT prequalification in the Classes of **Earthwork and Drainage (EART),** to the County by the time of Bid Closing. County will reject Bids from Bidders who are not prequalified for the class of work indicated prior to the Bid Closing. (See 00120.00.)
- 2. Electronic Submission of Bids: The County is requiring all bids for this project be electronically submitted. Complete Bids (including all attachments) will only be accepted electronically thru a secure online bid submission service, Bid Locker. Email submissions to Clackamas County email addresses will no longer be accepted. <a href="https://bidlocker.us/a/clackamascounty/BidLocker">https://bidlocker.us/a/clackamascounty/BidLocker</a>.

Bids will be publicly read aloud via the computer application, Zoom. Bidders will be allowed to video conference or listen by phone to the bid results. The projects Zoom meeting can be accessed via the information below:

#### **ZOOM LINK**

Join Zoom Meeting

https://clackamascounty.zoom.us/j/82034374389

Meeting ID: 820 3437 4389

#### One tap mobile

+16699006833,,82034374389# US (San Jose) 17193594580,,82034374389# US

Dial by your location

- +1 669 900 6833 US (San Jose)
- +1 719 359 4580 US
- +1 253 205 0468 US
- +1 253 215 8782 US (Tacoma)
- +1 346 248 7799 US (Houston)
- +1 408 638 0968 US (San Jose)
- +1 669 444 9171 US
- +1 301 715 8592 US (Washington DC)

- +1 305 224 1968 US
- +1 309 205 3325 US
- +1 312 626 6799 US (Chicago)
- +1 360 209 5623 US
- +1 386 347 5053 US
- +1 507 473 4847 US
- +1 564 217 2000 US
- +1 646 876 9923 US (New York)
- +1 646 931 3860 US
- +1 689 278 1000 US

Meeting ID: 820 3437 4389

Find your local number: <a href="https://clackamascounty.zoom.us/u/kbzzuPEcgX">https://clackamascounty.zoom.us/u/kbzzuPEcgX</a>

\*\*The Apparent Low bid results will be posted to the projects OregonBuys listing as soon as possible following the bid opening.



# CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT

### **BID BOND**

Project Name: # 2023-90 Jennings Ave: OR99E to Oatfield Rd Project

We, Emery & Sons Construction Group, LLC (Name of Principal)	, as "Princip	al,"	
and Travelers Casualty and Surety Company of Am (Name of Surety)	erica, an	Connecticut	Corporation,
authorized to transact Surety business in Courselves, our respective heirs, executors, Clackamas County ("Obligee") the sum of (\$_	administrators,	ety," hereby successors	and assigns to pay unto
Ten Percent of Total Amount Bid			dollars.
WHEREAS, the condition of the obligation of bid to an agency of the Obligee in response project identified above which proposal or bid required to furnish bid security in an amount opursuant to the procurement document.	to Obligee's proc is made a part of	urement doo this bond by	cument (No. ) for the reference, and Principal is
NOW, THEREFORE, if the Obligee shall accordance into a Contract with the Obligee in accordance as may be specified in the bidding or Contract performance of such Contract and for the prosecution thereof, or in the event of the fails bond or bonds, if the Principal shall pay to the between the amount specified in said bid and faith contract with another party to perform the null and void, otherwise to remain in full force	e with the terms of Documents with corompt payment oure of the Principal Obligee the differd such larger amount of Work covered by	such bid, ar good and sub of labor and al to enter sub erence not to bunt for whice	nd give such bond or bonds fficient surety for the faithfuld material furnished in the uch Contract and give such exceed the penalty hereof h the Obligee may in good
IN WITNESS WHEREOF, we have caused authorized legal representatives this8th_	this instrument to	be execute November	ed and sealed by our duly, 20 <u>23</u> .
Principal: Emery & Sons Construction Group, LLC	Surety: Travelers Ca	sualty and Sur	ety Company of America
By: Signature  Principal  Official Capacity	By: Attorney-In-Fact  Tracy Stewart	Irac	y Stewart
Attest: Jush Pennir	1605 Liberty St	Name reet SE	
Corporation Secretary	•	Address	
	Salem, OR 973	02 State	Zip
	(503) 362-271 Phone		tracy@agsadowski.com
	THORIE		Eax Email



Travelers Casualty and Surety Company of America Travelers Casualty and Surety Company St. Paul Fire and Marine Insurance Company

#### POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, and St. Paul Fire and Marine Insurance Company are corporations duly organized under the laws of the State of Connecticut (herein collectively called the "Companies"), and that the Companies do hereby make, constitute and appoint Tracy Stewart of SALEM

Oregon

their true and lawful Attorney(s)-in-Fact to sign, execute, seal and acknowledge any and all bonds, recognizances, conditional undertakings and other writings obligatory in the nature thereof on behalf of the Companies in their business of guaranteeing the fidelity of persons, guaranteeing the performance of contracts and executing or guaranteeing bonds and undertakings required or permitted in any actions or proceedings allowed by law.

IN WITNESS WHEREOF, the Companies have caused this instrument to be signed, and their corporate seals to be hereto affixed, this 21st day of April, 2021.







State of Connecticut

City of Hartford ss.

On this the 21st day of April, 2021, before me personally appeared Robert L. Raney, who acknowledged himself to be the Senior Vice President of each of the Companies, and that he, as such, being authorized so to do, executed the foregoing instrument for the purposes therein contained by signing on behalf of said Companies by himself as a duly authorized officer.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

My Commission expires the 30th day of June, 2026



Anna P. Nowik, Notary Public

Robert L. Ranev. Senior Vice President

This Power of Attorney is granted under and by the authority of the following resolutions adopted by the Boards of Directors of each of the Companies, which resolutions are now in full force and effect, reading as follows:

RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President, any Senior Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary may appoint Attorneys-in-Fact and Agents to act for and on behalf of the Company and may give such appointee such authority as his or her certificate of authority may prescribe to sign with the Company's name and seal with the Company's seal bonds, recognizances, contracts of indemnity, and other writings obligatory in the nature of a bond, recognizance, or conditional undertaking, and any of said officers or the Board of Directors at any time may remove any such appointee and revoke the power given him or her; and it is

FURTHER RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President may delegate all or any part of the foregoing authority to one or more officers or employees of this Company, provided that each such delegation is in writing and a copy thereof is filed in the office of the Secretary; and it is

FURTHER RESOLVED, that any bond, recognizance, contract of indemnity, or writing obligatory in the nature of a bond, recognizance, or conditional undertaking shall be valid and binding upon the Company when (a) signed by the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary and duly attested and sealed with the Company's seal by a Secretary or Assistant Secretary; or (b) duly executed (under seal, if required) by one or more Attorneys-in-Fact and Agents pursuant to the power prescribed in his or her certificate or their certificates of authority or by one or more Company officers pursuant to a written delegation of authority; and it is

FURTHER RESOLVED, that the signature of each of the following officers: President, any Executive Vice President, any Senior Vice President, any Vice President, any Assistant Vice President, any Secretary, and the seal of the Company may be affixed by facsimile to any Power of Attorney or to any certificate relating thereto appointing Resident Vice Presidents, Resident Assistant Secretaries or Attorneys-in-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such Power of Attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding on the Company in the future with respect to any bond or understanding to which it is attached.

I, Kevin E. Hughes, the undersigned, Assistant Secretary of each of the Companies, do hereby certify that the above and foregoing is a true and correct copy of the Power of Attorney executed by said Companies, which remains in full force and effect.

Dated this 8th

day of November

2023







(Essence),

Kevin E. Hughes, Assistant Secretary



# CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT

### **BID PROPOSAL FORM**

BID C	ECT #: ECT NAME: LOSING: PENING:	Jennings Ave: OR99E to Oatf November 16, 2023, 2:00 PM, December 6 November 16, 2023, 2:05 PM		
FROM		s Construction Group, LLC ne (must be full legal name, not a	ABN/DBA)	_
TO:	Clackamas Co Procurement I	ounty Division – <u>https://bidlocker.us/a/c</u>	lackamascounty/BidLocker	
1.	Bidder is (che	ck one of the following and inse	rt information requested):	
	a. An inc	lividual; or		
	b. A part	nership registered under the law	s of the State of	; or
	c. A corp	poration organized under the law	vs of the State of	; or
		ited liability corporation organiz	ed under the laws	
	labor and perf		Oregon hereby proposes to furnish ed for the above project in strict accounts:	
and the	e Undersigned a	agrees to be bound by the follow	Thousand, Dollars (\$ 5, 253, 889) 7000 Ving documents and any other Contra 1 Conditions for Construction (Certif	act Documents
Oppo Instru Supp Bid E Bid P	ortunity actions to Biddo lemental Instru Bond Proposal Form a	ections to Bidders and Bid Schedule of Prices t Contract Form	<ul> <li>First-Tier Subcontractor Disclos</li> <li>Certificate Regarding Ineligible</li> <li>Performance Bond and Paymen</li> <li>Prevailing Wage Rates</li> <li>Plans, Special Provisions and D</li> <li>General Conditions for Constru (Certified LPA) Clackamas Court</li> <li>DBE, FHWA and ODOT Form</li> </ul>	e Contractors at Bond  Orawings action for anty
	• ADDENDA	numbered One through Tv	NO , inclusive (fill in blanks)	

- 2. The Undersigned proposes to accept the total Bid in the attached Schedule of Prices, subject to adjustment for actual quantities completed during the course of work and any Amendment between the parties, for the items or work designated in the Contract Documents, for which any adjustments in the Contract amount will be made in accordance with Section 12, General Conditions for Construction for (Certified LPA) Clackamas County.
- 3. The work shall be completed within the time stipulated and specified in Section 00180.50(h) of Section 12, Special Provisions that accompany the General Conditions for Construction for Clackamas County.
- 4. Accompanying herewith is Bid Security which is equal to ten percent (10%) of the total amount of the Basic Bid.
- 5. The Undersigned agrees, if awarded the Contract, to execute and deliver to Clackamas County, within ten (10) calendar days after receiving the Contract forms, a Contract Form, a Federal Tax Identification Number for the Contractor, and a satisfactory Performance Bond and Payment Bond each in an amount equal to one hundred percent (100%) of the Contract sum, using forms provided by the County. The surety requested to issue the Performance Bond and Payment Bond will be:

<u>Travelers Casualty and Surety Company of America</u>
(name of surety company - not insurance agency)

The Undersigned hereby authorizes said surety company to disclose any information to the County concerning the Undersigned's ability to supply a Performance Bond and Payment Bond each in the amount of the Contract.

- 6. The Undersigned further agrees that the Bid Security accompanying the Bid is left in escrow with Clackamas County; that the amount thereof is the measure of liquidated damages which the County will sustain by the failure of the Undersigned to execute and deliver the above-named Contract Form, Performance Bond and Payment Bond, each as published, and that if the Undersigned defaults in either executing the Contract Form or providing the Performance Bond and Payment Bond within ten (10) calendar days after receiving the Contract forms, then the Bid Security shall become the property of the County at the County's option; but if the Bid is not accepted within thirty (30) calendar days of the time set for the opening of the Bids, or if the Undersigned executes and timely delivers said Contract Form, Performance Bond and Payment Bond, the Bid Security shall be returned.
- 7. The Undersigned certifies that: (i) This Bid has been arrived at independently and is being submitted without collusion with and without any agreement, understanding, or planned common course of action with any other vendor of materials, supplies, equipment or services described in the invitation to bid designed to limit independent bidding or competition; and (ii) the contents of the Bid have not been communicated by the Undersigned or its employees or agents to any person not an employee or agent of the Undersigned or its surety on any Bond furnished with the Bid and will not be communicated to such person prior to the official opening of the Bid.
- 8. The undersigned HAS, HAS NOT (circle applicable status) paid unemployment or income taxes in Oregon within the past 12 months and HAS, HAS NOT (circle applicable status) a business address in Oregon. The undersigned acknowledges that, if the selected bidder, that the undersigned will have to pay all applicable taxes and register to do business in the State of Oregon before executing the Public Improvement Contract Agreement Form.
- 9. The Undersigned agrees, if awarded a contract, to comply with the provisions of ORS 279C.800 through 279C.870 pertaining to the payment of the prevailing rates of wage.

10. Contractor's CCB registration number is
11. The successful Bidder hereby certifies that all subcontractors who will perform construction work as described in ORS 701.005(2) were registered with the Construction Contractors Board in accordance with ORS 701.035 to 701.055 at the time the subcontractor(s) made a bid to work under the contract.
12. The successful Bidder hereby certifies that, in compliance with the Worker's Compensation Law of the State of Oregon, its Worker's Compensation Insurance provider is SAIF Corporation , Policy No. 885062 , and that Contractor shall submit Certificates of Insurance as required.
13. Contractor's Key Individuals for this project (supply information as applicable):
Project Executive:Vince Makinson, Cell Phone:(503) 931-5262,Project Manager:Aaron Slowik, Cell Phone:(971) 209-5968,Job Superintendent:Adam Vando, Cell Phone:(503) 602-1139,Project Engineer:Brandon Zaikoski, Cell Phone:(503) 997-2587.
14. The Undersigned pursuant to ORS 279A.110, the Bidder has not discriminated and will not discriminate against a disadvantaged business enterprise, a minority-owned business, a woman-owned business, a business that a service-disabled veteran owns, or an emerging small business in obtaining any required subcontracts. The Bidder understands that it may be disqualified from Bidding on this public improvement project if the Agency finds that the Bidder has violated subsection (1) of ORS 279A.110.
<b>REMINDER:</b> Bidder must submit a First-Tier Subcontractor Disclosure Form.
By signature below, Contractor agrees to be bound by this Bid.
NAME OF FIRM Emery & Sons Construction Group, LLC
ADDRESS P.O. Box 13069
Salem, OR 97309

NAME OF FIR	UVI	Emery & Sons Construction Group, LLC
ADDRESS		P.O. Box 13069
		Salem, OR 97309
TELEPHONE I	NO	(503) 588-7576
EMAIL		Aaron.Slowik@emeryandsons.com
SIGNATURE	1)	Sole Individual
or	2)	Partner
or	3)	Vena Makinson
	* * * *	Authorized Officer of Corporation (Vince Makinson)  * END OF BID *****

18306\_K19276 Jennings Ave: OR99E to Oatfield Rd Bid Schedule 9/8/2023

Bla	Dia Schedule		V	_		9/8/2023
100000000000000000000000000000000000000	Item #	Item Description	Unit	Quantity	Unit Price	Total Price
4		TRAINING	A CONTRACTOR OF THE PARTY OF TH			
1			HOUR	500	20.00	10,000.00
2	The state of the s		LS	1	414,000	414,000-
3		TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE	LS	1	230,000	230,000
4		TEMPORARY WATER MANAGEMENT FACILITY AT BOARDMAN CREEK	LS	1	40,000-	40.000-
5	0270-0114000F	TEMPORARY TYPE CL CHAIN LINK 6-FT FENCE	FOOT	3100	9.55	29,605
6	0270-0117000E	TEMPORARY GATES	EACH	5	500-	2,500-
7		EROSION CONTROL	LS	1	10.750	
8		PLASTIC SHEETING				10,750
9		MATTING, TYPE C	SQYD	200	2-	400-
		MATTING, TYPE F	SQYD	1850	7.50	13,875
10	( ( ( ( ( ( ( ( ( ( ( ( ( ( ( ( ( ( (		SQYD	360	8.50	3.060
11		COMPOST EROSION BLANKET	SQYD	5775	5, 25	30,318.75
12		CHECK DAM, TYPE 1	EACH	5	95-	475-
13	0280-0109200F	COMPOST FILTER BERM	FOOT	3560	4.75	16,910-
14	0280-0110020E	CONSTRUCTION ENTRANCE, TYPE 2	EACH	1	10,500-	10,500-
15	0280-0111020E	TIRE WASH FACILITY, TYPE 1	EACH	1	12,250	12,250
16	0280-0112500E	CONCRETE WASHOUT FACILITY	EACH	1	5,000	5,000
17		INLET PROTECTION, TYPE 3 (OLWSD TYPE 5)	EACH	38		
18		POLLUTION CONTROL PLAN			100-	3.800
		TURBIDITY MONITORING	LS	1	500-	500-
19			LS	1	4,750	4,750
20		HEALTH AND SAFETY PLAN	LS	1	500-	500-
21		CONTAMINATED SOIL MANAGEMENT	LS	1	23,000	23,000
22		CONTAMINATED SOIL DISPOSAL	TON	1400	98.50	137.900-
23		SOIL SAMPLE COLLECTION AND ANALYTICAL TESTING	EACH	10	800-	8.000-
24	0305-0100000A	CONSTRUCTION SURVEY WORK	LS	1	56,000	56.000
25		REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1	100,000	
26		CLEARING AND GRUBBING	LS	1	45,000	100.000
27		ADDITIONAL STUMPS 5 FT DIAMETER				
28		DITCH EXCAVATION	EACH	2	1,300	2,600-
			CUYD	48	42-	2,016
29		GENERAL EXCAVATION	CUYD	2200	49-	107.800
30		18 INCH SUBGRADE STABILIZATION	SQYD	340	76-	25,840
31	0350-0100000J	DRAINAGE GEOTEXTILE, TYPE 1	SQYD	340	1.50	510-
32	0350-0101000J	DRAINAGE GEOTEXTILE, TYPE 2	SQYD	1190	1.75	2,082.50
33	0350-0105000J	SUBGRADE GEOTEXTILE	SQYD	4950	1.50	7.425-
34	0390-0105000K	LOOSE RIPRAP, CLASS 50	CUYD	3	230-	690-
35		BOULDER EXCAVATION	CUYD	100	250	
36		TRENCH FOUNDATION				25,000
37		MAINLINE VIDEO INSPECTION	CUYD	25	127-	3,175-
			FOOT	2533	8.50	21,530.50
38		6 INCH DRAIN PIPE	FOOT	975	39-	38,025-
39		8 INCH STORM SEWER PIPE, 10 FT DEPTH	FOOT	79	110-	8,690-
40		12 INCH STORM SEWER PIPE, 10 FT DEPTH	FOOT	1291	111-	143,301
41		15 INCH STORM SEWER PIPE, 10 FT DEPTH	FOOT	17	203-	3,451-
42	0445-035018BF	18 INCH STORM SEWER PIPE, 10 FT DEPTH	FOOT	976	180-	175,680-
43	0445-035024BF	24 INCH STORM SEWER PIPE, 10 FT DEPTH	FOOT	234	301-	70,434-
44	0445-0700120E	SLOPED END SECTIONS, 12 INCH	EACH	3	350-	1.050-
45		TRENCH DRAIN, TYPE 2	FOOT	17	350-	
. 46		CONCRETE MANHOLES, SHALLOW				5,950
47			EACH	5	5,550	27,750
		CONCRETE INLETS, TYPE B	EACH	1	11.350	11.350-
48		CONCRETE INLETS, TYPE B	EACH	1	1,900-	1,900-
49		CONCRETE INLETS, TYPE D	EACH	2	4.000	8,000
50		CONCRETE INLETS, TYPE G-2	EACH	23	3,500-	80,500
51		CONCRETE INLETS, TYPE AREA DRAIN	EACH	3	1,250-	3,750
52	0480-0100000F	DRAINAGE CURBS	FOOT	200	22-	4.400
53		ADJUSTING BOXES	EACH	14	550-	7.700-
54		ADJUSTING CATCH BASINS	EACH	8	1,200	
55		CONNECTION TO EXISTING STRUCTURES				9,600
56		MINOR ADJUSTMENT OF MANHOLES	EACH	30	1,500	45,000
			EACH	1	3.060	3.000
57		MAJOR ADJUSTMENT OF MANHOLES	EACH	2	4,900	9,800
58		TRENCH RESURFACING	SQYD	42	175-	7,350-
59		STRUCTURE EXCAVATION	LS	1	105.000	105.000
60	0510-0106000A	GRANULAR WALL BACKFILL	LS	1	32,000	32,000-
61		RETAINING WALL, PREFABRICATED MODULAR GRAVITY (FILE 2/3)	LS	1	175,000	175,000
62		RETAINING WALL, PREFABRICATED MODULAR GRAVITY (FILE 28)	LS	1		
63		RETAINING WALL, PREFABRICATED MODULAR GRAVITY (FILE 38)	LS		16,500-	16.500
64			177.557	1	136,500	/36.500
		RETAINING WALL, PREFABRICATED MODULAR GRAVITY (FILE 44A)	LS	1	15,750	15,750
65		RETAINING WALL, PREFABRICATED MODULAR GRAVITY (FILE 44B)	LS	1	144,000-	144,000-
66	0596-B002000A	RETAINING WALL, PREFABRICATED MODULAR GRAVITY (FILE 47/62)	LS	1	35,000-	35,000
					2000	
67	0596-B002000A	RETAINING WALL, PREFABRICATED MODULAR GRAVITY (FILE 45 AND 45/60)	LS	1	22,800-	22,800

Item #   Item #   Item #   Item Description	
RETAINING WALL, PREFABRICATED MODULAR GRAVITY (REMOVE AND REBUILD FILE 55)   LS 1 2,700°	2,700 - 17,250 - 29,520 - 4,550 - 311,945 - 416,000 -
RETAINING WALL, PREFABRICATED MODULAR GRAVITY (REMOVE AND 69 0596-B002000A REBUILD FILE 55)	2,700 - 17,250 - 29,520 - 4,550 - 311,945 - 416,000 -
70       0596-C002000A       RETAINING WALL, CAST-IN-PLACE CONCRETE RIGID GRAVITY (FILE 3)       LS       1       /7.250°         71       0620-0104000J       COLD PLANE PAVEMENT REMOVAL, 0 - 2 INCHES DEEP       SQYD       4920       6°         72       0620-0120000J       COLD PLANE PAVEMENT REMOVAL, 2 INCHES DEEP       SQYD       175       2 6°         73       0640-0100000M       AGGREGATE BASE       TON       7010       4/4, 5°         74       0744-0202000M       LEVEL 2, 1/2 INCH ACP MIXTURE       TON       3200       /30°         75       0744-0302000M       LEVEL 3, 1/2 INCH ACP MIXTURE       TON       30       280°         76       0749-0100000E       EXTRA FOR ASPHALT APPROACHES       EACH       25       /,200°	17,250- 29,520- 4,550- 311,945- 416,000-
70       0596-C002000A       RETAINING WALL, CAST-IN-PLACE CONCRETE RIGID GRAVITY (FILE 3)       LS       1       /7, 250         71       0620-0104000J       COLD PLANE PAVEMENT REMOVAL, 0 - 2 INCHES DEEP       SQYD       4920       6         72       0620-0120000J       COLD PLANE PAVEMENT REMOVAL, 2 INCHES DEEP       SQYD       175       2 6         73       0640-0100000M       AGGREGATE BASE       TON       7010       44.59         74       0744-0202000M       LEVEL 2, 1/2 INCH ACP MIXTURE       TON       3200       /30         75       0744-0302000M       LEVEL 3, 1/2 INCH ACP MIXTURE       TON       30       280         76       0749-0100000E       EXTRA FOR ASPHALT APPROACHES       EACH       25       /.200	17,250- 29,520- 4,550- 311,945- 416,000-
71       0620-0104000J       COLD PLANE PAVEMENT REMOVAL, 0 - 2 INCHES DEEP       SQYD       4920       6         72       0620-0120000J       COLD PLANE PAVEMENT REMOVAL, 2 INCHES DEEP       SQYD       175       2 6         73       0640-0100000M       AGGREGATE BASE       TON       7010       741, 50         74       0744-0202000M       LEVEL 2, 1/2 INCH ACP MIXTURE       TON       3200       130         75       0744-0302000M       LEVEL 3, 1/2 INCH ACP MIXTURE       TON       30       280         76       0749-0100000E       EXTRA FOR ASPHALT APPROACHES       EACH       25       1,200	29,520° 4,550° 311,945° 416,000°
73       0640-0100000M       AGGREGATE BASE       TON       7010       4/4,59         74       0744-0202000M       LEVEL 2, 1/2 INCH ACP MIXTURE       TON       3200       /30 ~         75       0744-0302000M       LEVEL 3, 1/2 INCH ACP MIXTURE       TON       30       280 ~         76       0749-0100000E       EXTRA FOR ASPHALT APPROACHES       EACH       25       /,200 ~	4,550- 311,945- 416,000-
73       0640-0100000M       AGGREGATE BASE       TON       7010       4/4, 59         74       0744-0202000M       LEVEL 2, 1/2 INCH ACP MIXTURE       TON       3200       /30 ~         75       0744-0302000M       LEVEL 3, 1/2 INCH ACP MIXTURE       TON       30       280 ~         76       0749-0100000E       EXTRA FOR ASPHALT APPROACHES       EACH       25       /.200 ~	311,945 - 416,000 -
75         0744-0302000M         LEVEL 3, 1/2 INCH ACP MIXTURE         TON         30         280 °           76         0749-0100000E         EXTRA FOR ASPHALT APPROACHES         EACH         25         // 200 °	416,000
76 0749-0100000E EXTRA FOR ASPHALT APPROACHES EACH 25 /.200	8.400-
11000	01100
	30,000 -
77 0759-0103000F CONCRETE CURBS, CURB AND GUTTER FOOT 1765 48. 25	86.043.75
78 0759-0106000F CONCRETE CURBS, LOW PROFILE MOUNTABLE CURB FOOT 40 70	2,800
79 0759-0110000F CONCRETE CURBS, STANDARD CURB FOOT 2451 40	98.040-
80 0759-0126000J CONCRETE DRIVEWAYS SQFT 3421 /7. 25	59.012.25
81 0759-0127000J CONCRETE DRIVEWAYS, REINFORCED SQFT 1404 /9. 75	27,729-
82 0759-0128000J CONCRETE WALKS SQFT 27460 <b>9</b>	247,140-
83 0759-0154100E EXTRA FOR NEW CURB RAMPS EACH 37 1/./50-	42,550-
84 0759-0510000J TRUNCATED DOMES ON NEW SURFACES SQFT 474 44-	20,856-
85 0810-0104000F GUARDRAIL, TYPE 2A (WITH REFLECTORS) FOOT 260 42	10,920-
86 0810-0119000E GUARDRAIL ANCHORS, TYPE 1 EACH 1 //600	1,600-
87 0810-0131000E GUARDRAIL TERMINALS, NON-FLARED, TEST LEVEL 2 EACH 1 4,300	4,300-
88 0810-0133000E EXTRA FOR 8 FOOT POSTS EACH 36 54-	1.944-
89 0810-0145000E EXTRA FOR HAND DUG GUARDRAIL POST HOLES EACH 5 535 -	2,675 -
90 0856-0101000E PERMANENT SURFACE MOUNTED TUBULAR MARKERS EACH 27 /25 T	3.375-
91 0865-0116610F THERMOPLASTIC, EXTRUDED, SURFACE, NON-PROFILED FOOT 19310 /. 320	25,103
92 0867-0103100E PAVEMENT LEGEND, TYPE B-HS: ARROWS EACH 2 500 1	1.000-
93 0867-0131000E PAVEMENT LEGEND, TYPE B-HS: BICYCLE LANE STENCIL EACH 22 350	7.700
94 0867-0145100J PAVEMENT BAR, TYPE B-HS SQFT 1024 18	18,432-
95 0868-0100000J GREEN BICYCLE LANE, PREFORMED THERMOPLASTIC FILM SQFT 870 9-	7.830
96 0902-0101000E CROSSWALK CLOSURE SUPPORTS EACH 20 /, 250 -	25,000
97 0905-0100000A REMOVE EXISTING SIGNS LS 1 2,150	Z,150 -
98 0905-0101000A REMOVE AND REINSTALL EXISTING SIGNS LS 1 600	600-
99 0920-0100000A SIGN SUPPORT FOOTINGS LS 1 8,600	8,600-
100 0930-0114000A PERFORATED STEEL SQUARE TUBE SLIP BASE SIGN SUPPORTS LS 1 /7.750-	
101 0930-0117000A PERFORATED STEEL SQUARE TUBE ANCHOR SIGN SUPPORTS LS 1 4,800	4.800-
102 0940-0202000J SIGNS, STANDARD SHEETING, SHEET ALUMINUM SQFT 650 32 - 103 0970-0105000A SWITCHING, CONDUIT, AND WIRING IS 1 206 V//	20,800-
103 0970-0105000A SWITCHING, CONDUIT, AND WIRING  TRAFFIC SIGNAL MODIFICATION, JENNINGS AVE AT MCLOUGHLIN	708,466
104 0990-0102000A BLVD LS 1 35,500	35,500
105 0990-0102000A TRAFFIC SIGNAL MODIFICATION, JENNINGS AVE AT OATFIELD RD LS 1 95, 650	
FLASHING BEACON INSTALLATION (SPEED RADAR FEEDBACK SIGN),	95,650-
106 0990-0106000A AT COOK ST LS 1 7/,000	71.000-
FLASHING BEACON INSTALLATION (SPEED RADAR FEEDBACK SIGN),	7.7.300
107 0990-0106000A AT HOWARD ST LS 1 70,000 T	70,000
FLASHING BEACON INSTALLATION (RECTANGULAR RAPID FLASHING	20. 12 as as as as
108 0990-0106000A BEACON), AT PORTLAND AVE LS 1 /00,000	100,000
109 1011-0200000A STORMWATER CONTROL, WATER QUALITY BIOFILTRATION SWALE FACILITY LS 1 /24.000	- 124.000-
110 1030-0108000R PERMANENT SEEDING (DWARD GRASS MIX) ACRE 1.2 <b>2</b> , 800 -	3,360-
111 1030-0118000R WATER QUALITY SEEDING (BIOFILTRATION SWALE FACILITY MIX) ACRE 0.4 9.500	3,800
112 1050-0135000F TYPE CL-5R CHAIN LINK FENCE FOOT 357 <b>70</b>	24.990-
113 1050-0162000F TYPE CL-5R CHAIN LINK FENCE WITH PRIVACY SLATS FOOT 245 /02 ~	24.990-
114 1050-0240000F REMOVING AND REBUILDING FENCE FOOT 890 /23	109,470-
115 1065-0100000A MONUMENT BOXES EACH 4 600 -	2.400-
116 1069-0200000E PEDESTRIAN FENCE EACH 15 1/850	27.750-
117 1070-0101000E MULTIPLE MAILBOX SUPPORTS EACH 10 1/300	13,000-
118 1070-0102000E MAILBOX CONCRETE COLLARS EACH 18 //60	2.880-
119 1070-0103000E REMOVE AND REINSTALL MAILBOX SUPPORTS EACH 11 320	3,520-

PROPOSED COST BID SCHED	ULE 5, 253, 884. 15			
	(Numerically)			
PROPOSED COST BID SCHEDULE Five Million, Two Hundred Fifty Three Thousand, Eight Hundred (Written in Words) Eighty Four Dollars + 75/100				
COMPANY NAME	Emery & Sons Construction Group, LLC			
AUTHORIZED SIGNATURE	(Vince Makinson)			

# FIRST-TIER SUBCONTRACTOR DISCLOSURE FORM PROJECT: #2023-90

Jennings Ave: OR99E to Oatfield Rd Project

December 6

BID OPENING: November 16, 2023, 2:00 PM, Pacific Time

Failure to submit this Form by the disclosure deadline will result in a nonresponsive bid.

#### **INSTRUCTIONS:**

This First-Tier Subcontractor Disclosure Form ("Form") must be submitted and received at the location specified in the Notice of Public Improvement Contract Opportunity on the advertised Bid Closing, and within two working hours after the advertised Bid Closing Time.

The Form may be mailed, hand-delivered or emailed to:

https://bidlocker.us/a/clackamascounty/BidLocker. It is the responsibility of Bidders to submit this Form and any additional sheets with the Project name clearly marked on the envelope or the subject line of the email.

Subcontractor lists may be submitted with the bid in the same envelope or email at the Bid Closing date and time. Subcontractor lists <u>MUST</u> be submitted within **two (2) hours** of the Bid Closing date and time.

List below the name of each subcontractor that will be furnishing labor, or labor and materials, for which disclosure is required, the category of work that the subcontractor will be performing, and the dollar value of the subcontract. Enter "NONE" if the value of the project bid is less than \$100,000 or there are no subcontractors that need to be disclosed. ATTACH ADDITIONAL SHEETS IF NECESSARY.

	SUBCONTRACTOR NAME	DOLLAR VALUE	CATEGORY OF WORK
1.	Northstar Electrical	\$546,000.00	Electrical
2.	Anderson's Erosion Control	\$96,632.00	Landscaping
3.	Eagle Elsner	\$416,700.00	Paving
4.	High Quality Traffic Control	<u>\$126,000.00</u>	Flagging
5.	Cartello Construction	<u>\$131,400.00</u>	Signage
6.	Daybreak Construction	\$130,000.00	Walls

The above listed first-tier subcontractor(s) are providing labor, or labor and material, with a Dollar Value equal to or greater than:

- a) 5% of the total Contract Price, but at least \$15,000. If the Dollar Value is less than \$15,000 do not list the subcontractor above; or
- b) \$350,000 regardless of the percentage of the total Contract Price.

Firm Name:	Emery & Sons Construction Group, LLC			
Bidder Signature	e: Venu Mahenson	_ Phone #_	(503) 588-7576	

### AFFIDAVIT OF NON-COLLUSION

STATE OF	Oregon		181	
COUNTY OF	Marion			
I state that I am authorized to ma responsible in m	ake this affidavit on be	Emery & (title) of Construction half of my firm, and its ow and the amount of this Of	Group, LLC (name of tweethers, directors, and off	firm) and that I am ficers. I am the person
consultation, condisclosed on the  (2) approximate ame Proposer, and the (3) on this contract, Offer or other fo (4) or inducement fr (5) officers, director in the last four	mmunication or agreed attached appendix. That neither the price (ount of this Offer, have ey will not be disclose. No attempt has been nor to submit an Offer horm of complementary. The Offer of my firm it from, any firm or person Emery & Sons Constructs and employees are not years been convicted of this property.	s made in good faith and r n to submit a complement	offer, and neither the her firm or person who hing. Induce any firm or person submit any intentionally not pursuant to any agreement or other noncompet (name of firm), its gation by any government of the prohibited by Sta	approximate price(s) nor is a Proposer or potential on to refrain from bidding by high or noncompetitive ement or discussion with, itive Offer.  affiliates, subsidiaries, ental agency and have not te or Federal law in any
the above represe contract(s) for we affidavit is and s submission of O	hich this Offer is submall be treated as fraud fers for this contract.	and important, and will be nitted. I understand and m lulent concealment from C	e relied on by Clackama ny firm understands that	t any misstatement in this
(Authorized Sign	nature) (Vince Makinson)		_	
Emery & Sons C (Name of Compa	Construction Group, LL any/Position)		-	
Sworn to and sul	bscribed before me this	s6 <sup>72</sup>	_ day of	
Notary Public fo My Commission		-7	LANCE I NOTARY F COMMISS	ICIAL STAMP LEROY GREAVES PUBLIC - OREGON SION NO. 1042384 ES NOVEMBER 06, 2027

FAILURE TO SUBMIT THIS EXECUTED STATEMENT AS PART OF THE BIDING DOCUMENTS WILL MAKE THE BID NON-RESPONSIVE AND NOT ELIGIBLE FOR AWARD CONSIDERATION.

#### CONGRESSIONAL LOBBYING CERTIFICATE

The undersigned certifies, to the best of his or her knowledge and belief, that:

No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of ANY Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan or cooperative agreement.

If any funds other than Federal appropriated funds have been paid or will be paid to any person for making lobbying contacts to an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with THIS Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying", in accordance with its instructions [as amended by "Government-wide Guidance for New Restrictions on Lobbying," 61 Federal Regulations 1413 (1/19/96). Note: Language in paragraph (2) herein has been modified in accordance with Section 10 of the Lobbying Disclosure Act of 1995 (P.L. 104-65, to be codified at 2 U.S.C. 1601, et seq.)].

The undersigned shall require that the language of this certification be included in the award documents for all sub-awards at all tiers (including subcontracts, sub-grants, and contracts under grants, loans, and cooperative agreements) and that all sub-recipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by section 1352, title 31, U.S. Code (as amended by the Lobbying Disclosure Act of 1995). Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

[Note: Pursuant to 31 U.S.C. §1352(c)(1)-(2)(A), any person who makes a prohibited expenditure or fails to file or amend a required certification or disclosure form shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each expenditure or failure.]

The Bidder, Emery & Sons Construction Group, LLC, certifies or affirms the truthfulness and accuracy of each statement of its certification and disclosure, if any. In addition, the Proposer understands and agrees that the provisions of 31 U.S.C. §3801, et seq., apply to this certification and disclosure, if any.

NOTE: BIDDER IS REQUIRED PURSUANT TO FEDERAL LAW TO INCLUDE THE ABOVE LANGUAGE IN SUBCONTRACTS OVER \$100,000 AND TO OBTAIN THIS LOBBYING CERTIFICATE FROM EACH SUBCONTRACTOR BEING PAID \$100,000 OR MORE UNDER THIS CONTRACT.

FAILURE TO SUBMIT THIS EXECUTED STATEMENT AS PART OF THE BIDING DOCUMENTS WILL MAKE THE BID NON-RESPONSIVE AND NOT ELIGIBLE FOR AWARD CONSIDERATION.

### CERTIFICATE REGARDING INELIGIBLE CONTRACTORS

CERTIFICATION REGARDING DEBARMENT, SUSPENSION AND OTHER INELIGIBILITY AND VOLUNTARY EXCLUSION FROM TRANSACTIONS FINANCED IN PART BY THE U.S. **GOVERNMENT** 

Vince Makinson	Principal
(Name of Certifying Officer)	(Title of Certifying Officer)
Hereby certify that: Emery & Sons Construction Group (Name of Bidder)	, LLC
Are not presently debarred, suspended, proposed for deb from participation by any State or Federal department of Transportation projects;	parment, declared ineligible, or voluntarily excluded agency or from participation in Oregon Department of
Have not within a three (3)-year period preceding this be against them for commission of fraud or a criminal offer or performing a public (Federal, State or local) transactive Federal or State antitrust statues or commission of embedestruction of records, making false statements, or received.	on or contract under a public transaction; violation of ezzlement, theft, forgery, bribery, falsification or
Are not presently indicted for or otherwise criminally or or local) with commission of any of the offenses enumer	civilly charged by a governmental entity (Federal, State rated in Paragraph 2 of this certification; and
Have not within a three (3)-year period preceding this be local) terminated for cause or default.	id had one or more public transactions (Federal, State or
If Bidder is unable to certify to any of the statements in explanation to this certification.	this certification, such prospective Bidder shall attach an
I hereby certify and affirm the truthfulness and accuracy provisions of 31 United States Code (U.S.C.) §3801 et s Statements) are applicable hereto.	of the above statement, and I understand that the eq., (Administrative Remedies for False Claims and
Emery & Sons Construction Group, LLC	
Name of Bidder	
P.O. Box 13069	
Street Address	
Salem, OR 97309	
City State Zip	
Dener Mekenson	(503) 588-7576
Signature of Certifying Officer (Vince Makinson)	Telephone Number of Bidder

FAILURE TO SUBMIT THIS EXECUTED STATEMENT AS PART OF THE BIDING DOCUMENTS WILL MAKE THE BID NON-RESPONSIVE AND NOT ELIGIBLE FOR AWARD CONSIDERATION.

Telephone Number of Bidder

### DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM Are you a DBE prime contractor?

☐ Yes ☒ No

This DBE Certification and Utilization Form applies solely to meeting the assigned DBE contract goal for DBE participation. If the assigned DBE contract goal is greater than zero, each Bidder, including DBE prime Bidders, shall complete and submit this form with their Bid. SHOULD THE BIDDER FAIL TO COMPLETELY FILL OUT, SIGN, AND SUBMIT THIS FORM WITH THE BID WHEN THE ASSIGNED DBE CONTRACT GOAL IS GREATER THAN ZERO, THE BIDDER WILL BE CONSIDERED NON-RESPONSIVE. This certification shall be deemed a part of the resulting contract.

The Bidder acknowledges and certifies that this form accurately represents receipt of and consent from the listed DBE firm as to the use of the referenced itemized quote below for the performance of this project. Bidder certifies that it had direct contact with the named DBE firms regarding participation of this project. Bidder certifies, if awarded this project, that it shall award subcontracts to or enter into agreements with the named DBE. DBE Prime Contractor will receive a minimum 30% credit to be applied to the DBE goal. Part I of the form is not required if the Bidder is a DBE, the DBE contract goal is greater than zero, and the DBE meets the goal by selfperforming the minimum required 30% of the work. If the DBE is self-performing more than 30%, it must include any additional work to receive appropriate DBE credit for the goal.

If the Bidder is submitting evidence of good faith efforts to secure participation, Bidder certifies that the good faith efforts documentation is true, accurate and correctly reports the actions taken by the Bidder.

Vince Makinson

Bidder's Authorized Representative (PRINT)

Bidder's Authorized Representative (SIGN)

December 6, 2023 Date

Emery & Sons Construction Group, LLC Name of Contractor (Company Name)

#### PART I

These columns to be completed by Bidder				These columns to be completed by Agency	
Type of Work *	Function ** (examples: Sub., Supp., DBE Man., Serv., Brok.)	Subcontract Amount (or expenditure amount or fee/commission amount)	Goal Participation % ***	DBE Amount ****	
Landscaping	Sub	\$96,632.00			
TV	Sub	\$20,264.00			
Signage	Sub	\$131,400.00			
Fencing	Sub	\$26,310.00			
Walls	Sub	\$130,000.00			
Flagging	Sub	\$126,000.00			
	Type of Work *  Landscaping TV Signage Fencing Walls	Type of Work *  Function ** (examples: Sub., Supp., DBE Man., Serv., Brok.)  Landscaping  TV  Sub  Signage  Fencing  Walls  Sub  Sub  Sub  Sub	Type of Work *   Function ** (examples: Sub., Supp., DBE Man., Serv., Brok.)   Function ** (examples: Sub., Supp., DBE Man., Supp., DBE Man., Serv., Brok.)   Function ** (examples: Sub., Supp., Supp., DBE Man., Supp., DBE Man., Supp., Supp., DBE Man., Supp., Supp., Supp., Supp., Supp., Sub., Supp., Sub., Supp., Sub., S	Type of Work *   Function ** (examples: Sub., Supp., DBE Man., Serv., Brok.)   Sub \$96,632.00	

\* From " Certification Office of Business Inclusion and Diversity " \*\* From "Function" column below. \*\*\* From "Goal Participation %" column below.

Function	Goal Participation %	This section to be completed by Agency	
Subcontractor	100% (of subcontract amount)	ASSIGNED DBE CONTRACT GOAL	%
Supplier (Regular Dealer)	60% (of supply expenditure amount)	TOTAL DBE AMOUNT	\$
DBE Manufacturer	100% (of material expenditure amount)	TOTAL BID AMOUNT	\$
Service Provider	100% (of fee or commission)	DBE COMMITMENT	%
Broker	100%	(TOTAL DBE AMOUNT + TOTAL BID AMOUNT) (calculated to two decimal places (0.01))	

(of brokerage fee only)	
-------------------------	--

Additional sheets may be used by copying this form. Bidder must sign each additional sheet to certify its content and completion of form.

Jennings Ave: OR99E to	Oatfield Rd		
Earthwork and Drainage,	Bridges and Structures,	<b>Asphalt Concrete</b>	Paving and Oiling

#### **ASSIGNED DBE CONTRACT GOAL**

The minimum Assigned **DBE** Contract Goal for this Project is **10%**.

(Overall DBE program goal for ODOT is set at 23.43%for FHWA funded Contracts for federal fiscal years 2023, 2024 and 2025.)

A Certification Directory of DBEs is available from the Certification Office of Business Inclusion and Diversity (COBID) website at: https://oregon4biz.diversitysoftware.com/FrontEnd/VendorSearchPublic.asp or by telephone at 503-986-0075.

### **CONFLICT OF INTEREST (COI) DISCLOSURE FORM**

### **Oregon Department of Transportation**

Firms under Contract or proposing to enter into a Contract with Agency must be in conformance with the "ODOT Conflict of Interest Guidelines" available on the Internet at: <a href="https://www.oregon.gov/odot/business/procurement/docspsk/coiguidelines.pdf">https://www.oregon.gov/odot/business/procurement/docspsk/coiguidelines.pdf</a> (under "Misc. Procurement Related Forms"). The definitions of terms used in this COI Disclosure Form shall be those provided in the ODOT Conflict Of Interest Guidelines (note that "Public Official" includes all Agency employees).

Submit this form with your bid, if disclosure is required by the Contractor.

### **CONSENT RESOLUTION**

### **EMERY & SONS CONSTRUCTION GROUP, LLC**

WHEREAS, the undersigned is the sole Member of *Emery & Sons Construction Group, LLC*, an Oregon limited liability company (the "*Company*"); and

WHEREAS, the undersigned wishes to take the action as hereinafter set forth pursuant to the Operating Agreement dated June 14, 2018; and

WHEREAS, the Company wishes to authorize the following individuals, individually or together, to execute and submit any project or job bids and contracts on behalf of the Company:

- 1. Vince Makinson;
- 2. Dan Johnston;
- 3. Trish Perrin;
- 4. Daniel Vannoy; or
- 5. John Moore.

NOW, THEREFORE, the following resolutions are unanimously adopted:

BE IT RESOLVED, that the sole Member of the Company hereby authorizes and approves the following individuals, individually or together, to execute and submit all project or job bids and contracts on behalf of the Company.

- 1. Vince Makinson;
- 2. Dan Johnston:
- 3. Trish Perrin;
- 4. Daniel Vannoy; or
- 5. John Moore.

BE IT FURTHER RESOLVED, that Daniel Vannoy, on behalf of the sole Member of the Company, is hereby authorized to execute any other documents which he may determine to be reasonably necessary to effectuate such resolutions.

IN WITNESS WHEREOF, the undersigned has hereunto set his hand effective as of June 2018.

MEMBER:

**EMERY & SONS CONSTRUCTION NORTHWEST, LLC** 

Daniel Vannoy, Sole Member

CONSENT RESOLUTION (EMERY & SONS CONSTRUCTION GROUP, LLC) 29063 (CAW:kds)

### **SECTION 9**



### CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT

### PERFORMANCE BOND

Bond No.: 107926605 Solicitation: #2023-90 Project Name: Jennings Ave: OR99E to Oa	tfield Rd Project	
Travelers Casualty and Surety Company of America (Surety #1) (Surety #2)*  * If using multiple sureties	Bond Amount No. 1: Bond Amount No. 2:* Total Penal Sum of Bond:	\$_5,253,884.75 \$
We, Emery & Sons Construction Group, LLC identified Surety(ies), authorized to transact and severally bind ourselves, our respect assigns firmly by these presents to pay unto Bond)  * Sureties bind ourselves in such sum "joint"	et surety business in Oregon, a cive heirs, executors, adminis o Clackamas County, the sum	strators, successors and of (Total Penal Sum of Provided, that we the
purpose of allowing a joint action or action	ns against any or all of us, an	d for all other purposes

WHEREAS, the Principal has entered into a contract with Clackamas County, along with the plans, specifications, terms and conditions of which are contained in the above-referenced Solicitation; and

each Surety binds itself, jointly and severally with the Principal, for the payment of such sum only

WHEREAS, the terms and conditions of the contract, together with applicable plans, standard specifications, special provisions, schedule of performance, and schedule of contract prices, are made a part of this Performance Bond by reference, whether or not attached to the contract (all hereafter called "Contract"); and

WHEREAS, the Principal has agreed to perform the Contract in accordance with the terms, conditions, requirements, plans and specifications, and all authorized modifications of the Contract which increase the amount of the work, the amount of the Contract, or constitute an authorized extension of the time for performance, notice of any such modifications hereby being waived by the Surety:

NOW, THEREFORE, THE CONDITION OF THIS BOND IS SUCH that if the Principal herein shall faithfully and truly observe and comply with the terms, conditions and provisions of the Contract, in all respects, and shall well and truly and fully do and perform all matters and things undertaken by Contractor to be performed under the Contract, upon the terms set forth therein, and within the time prescribed therein, or as extended as provided in the Contract, with or without notice to the Sureties, and shall defend, indemnify, and save harmless Clackamas County and its elected officials, officers, employees and agents, against any direct or indirect damages or claim of every kind and description that shall be suffered or claimed to be suffered in connection with or arising out of the performance of the Contract by the Principal or its subcontractors, and shall in

Clackamas County Contract Form B-7 (6/2019)

as is set forth opposite the name of such Surety); and

all respects perform said contract according to law, then this obligation is to be void; otherwise, it shall remain in full force and effect for so long as any term of the Contract remains in effect.

Nonpayment of the bond premium will not invalidate this bond nor shall Clackamas County, be obligated for the payment of any premiums.

This bond is given and received under authority of Oregon Revised Statutes Chapter 279C and the Clackamas County Local Contractor Review Board Rules, the provisions of which hereby are incorporated into this bond and made a part hereof.

ted this	17th	day of _	January	, 20_24
			DDINCIDAL.	Emery & Sons Construction Group, LL
			By: Vene	Signature  Official Corposity
				Signature
			Principal	
			1 1	Official Capacity
			Attest: Wh	Lerun
				Corporation Secretary
				elers Casualty and Surety Company of a for each if using multiple bonds]
			BY ATTORNEY	V-IN-FACT
				ney must accompany each bond]
			Tracy Stewart	
			Tracy	St. Name
				Signature
			1605 Liberty Str	reet SE
				Address
			Salem, OR 9730	2
			City	State Zip
			(503) 362-2711	tracy@agsadowski.com

Phone

Kaxx Email

### **SECTION 10**



### CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT

### PAYMENT BOND

Bond No.: 107926605 Solicitation: #2023-90

Project Name: Jennings Ave: OR99E to Oatfield Rd Project

Travelers Casualty and Surety

Company of America (Surety #1) Bond Amount No. 1: \$ 5,253,884.75

(Surety #2)\* Bond Amount No. 2:\* \$

\* If using multiple sureties Total Penal Sum of Bond: \$ 5,253,884.75

WHEREAS, the Principal has entered into a contract with Clackamas County, along with the plans, specifications, terms and conditions of which are contained in above-referenced Solicitation; and

WHEREAS, the terms and conditions of the contract, together with applicable plans, standard specifications, special provisions, schedule of performance, and schedule of contract prices, are made a part of this Payment Bond by reference, whether or not attached to the contract (all hereafter called "Contract"); and

WHEREAS, the Principal has agreed to perform the Contract in accordance with the terms, conditions, requirements, plans and specifications, and schedule of contract prices which are set forth in the Contract and any attachments, and all authorized modifications of the Contract which increase the amount of the work, or the cost of the Contract, or constitute authorized extensions of time for performance of the Contract, notice of any such modifications hereby being waived by the Surety:

NOW, THEREFORE, THE CONDITION OF THIS BOND IS SUCH that if the Principal shall faithfully and truly observe and comply with the terms, conditions and provisions of the Contract, in all respects, and shall well and truly and fully do and perform all matters and things by it undertaken to be performed under said Contract and any duly authorized modifications that are made, upon the terms set forth therein, and within the time prescribed therein, or as extended therein as provided in the Contract, with or without notice to the Sureties, and shall defend, indemnify, and save harmless Clackamas County and its elected officials, officers, employees and agents, against any claim for direct or indirect damages of every kind and description that shall be suffered or claimed to be suffered in connection with or arising out of the performance of the Contract by the Contractor or its subcontractors, and shall promptly pay all persons supplying labor, materials or both to the Principal or its subcontractors for prosecution of the work provided in the Contract; and shall promptly pay all contributions due the State Industrial Accident Fund and the State Unemployment Compensation Fund from the Principal or its subcontractors in connection with the performance of the Contract; and shall pay over to the Oregon Department of Revenue all sums required to be deducted and retained from the wages of employees of the Principal and its subcontractors pursuant to ORS 316.167, and

shall permit no lien nor claim to be filed or prosecuted against Clackamas County on account of any labor or materials furnished; and shall do all things required of the Principal by the laws of this State, then this obligation shall be void; otherwise, it shall remain in full force and effect for so long as any term of the Contract remains in effect.

Nonpayment of the bond premium will not invalidate this bond nor shall Clackamas County be obligated for the payment of any premiums.

This bond is given and received under authority of Oregon Revised Statutes Chapter 279C and the Clackamas County Local Contractor Review Board Rules, the provisions of which hereby are incorporated into this bond and made a part hereof.

IN WITNESS WHEREOF, WE HAVE CAUSED THIS INSTRUMENT TO BE EXECUTED AND SEALED BY OUR DULY AUTHORIZED LEGAL REPRESENTATIVES:

Dated this17thday ofJanuary	, 20 <u>24</u>
	100
PRINCIPA	AL: Emery & Sons Construction Group, LLC
By: Ve	Signature  Official Conscient
	Signature
Peir	ncipal
	Official Capacity
Attest:	ligh Kerlin
	Corporation Secretary
	<u>Travelers Casualty and Surety Company of Americ</u> tures for each if using multiple bonds]
DV ATTO	DAILY DI LACT.
	RNEY-IN-FACT:
[Power-oj-	Attorney must accompany each bond]
Tracy Stew	rart
Syn	V PS Name
	Signature
1605 Libe	rty Street SE
1000 1100	Address
Salem, OI	
outem, or	(9/30/

(503) 362-2711

Phone

tracy@agsadowski.com

FXXX Email



Travelers Casualty and Surety Company of America **Travelers Casualty and Surety Company** St. Paul Fire and Marine Insurance Company

#### POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, and St. Paul Fire and Marine Insurance Company are corporations duly organized under the laws of the State of Connecticut (herein collectively called the "Companies"), and that the Companies do hereby make, constitute and appoint Tracy Stewart , their true and lawful Attorney(s)-in-Fact to sign, execute, seal and Oregon acknowledge any and all bonds, recognizances, conditional undertakings and other writings obligatory in the nature thereof on behalf of

the Companies in their business of guaranteeing the fidelity of persons, guaranteeing the performance of contracts and executing or guaranteeing bonds and undertakings required or permitted in any actions or proceedings allowed by law.

IN WITNESS WHEREOF, the Companies have caused this instrument to be signed, and their corporate seals to be hereto affixed, this 21st day of April, 2021.







State of Connecticut

City of Hartford ss.

On this the 21st day of April, 2021, before me personally appeared Robert L. Raney, who acknowledged himself to be the Senior Vice President of each of the Companies, and that he, as such, being authorized so to do, executed the foregoing instrument for the purposes therein contained by signing on behalf of said Companies by himself as a duly authorized officer.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

My Commission expires the 30th day of June, 2026



Robert L. Ranev. Senior Vice President

This Power of Attorney is granted under and by the authority of the following resolutions adopted by the Boards of Directors of each of the Companies, which resolutions are now in full force and effect, reading as follows:

RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President, any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary may appoint Attorneys-in-Fact and Agents to act for and on behalf of the Company and may give such appointee such authority as his or her certificate of authority may prescribe to sign with the Company's name and seal with the Company's seal bonds, recognizances, contracts of indemnity, and other writings obligatory in the nature of a bond, recognizance, or conditional undertaking, and any of said officers or the Board of Directors at any time may remove any such appointee and revoke the power given him or her; and it is

FURTHER RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President may delegate all or any part of the foregoing authority to one or more officers or employees of this Company, provided that each such delegation is in writing and a copy thereof is filed in the office of the Secretary; and it is

FURTHER RESOLVED, that any bond, recognizance, contract of indemnity, or writing obligatory in the nature of a bond, recognizance, or conditional undertaking shall be valid and binding upon the Company when (a) signed by the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary and duly attested and sealed with the Company's seal by a Secretary or Assistant Secretary; or (b) duly executed (under seal, if required) by one or more Attorneys-in-Fact and Agents pursuant to the power prescribed in his or her certificate or their certificates of authority or by one or more Company officers pursuant to a written delegation of authority; and it is

FURTHER RESOLVED, that the signature of each of the following officers: President, any Executive Vice President, any Senior Vice President, any Vice President, any Assistant Vice President, any Secretary, any Assistant Secretary, and the seal of the Company may be affixed by facsimile to any Power of Attorney or to any certificate relating thereto appointing Resident Vice Presidents, Resident Assistant Secretaries or Attorneys-in-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such Power of Attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding on the Company in the future with respect to any bond or understanding to which it is attached.

I, Kevin E. Hughes, the undersigned, Assistant Secretary of each of the Companies, do hereby certify that the above and foregoing is a true and correct copy of the Power of Attorney executed by said Companies, which remains in full force and effect.

Dated this 17th day of January



2024







### **SECTION 12**



# CLACKAMAS COUNTY PUBLIC IMPROVEMENT CONTRACT PROJECT INFORMATION, PLANS, SPECIFICATIONS AND DRAWINGS

PROJECT: #2023-90 Jennings Ave: OR99E to Oatfield Rd

**Project Scope:** The Clackamas County Department of Transportation and Development is requesting bids to construct roadway improvements on Jennings Avenue that includes sidewalks on the north side and ADA curb ramps and bike lanes on both sides of the roadway. The improvements include, but are not limited to grading, drainage, retaining wall structures, paving and performing additional and incidental work as called by the specifications and plans.

Estimated Cost Range: \$5,000,000.00 - \$5,500,000.00

The project is anticipated to take approximately 7 months.

This Work must be completed by the completion date(s) as specified in the Special Provisions that accompany the General Conditions for Construction for Clackamas County, Section 00180.50(h) Contract Time.

The Scope further includes the Plans, Standard Drawings, General Conditions for Construction for Clackamas County and Special Provisions. The following reports and resource agency permits are included in the Contract Documents and can be found at the attached link: <u>K19276</u> <u>Jennings Ave Rnd2 Rebid</u>. The documents in the link include:

- Project Plans (file name: 1831-22234 K129276 Plans)
- Standard Drawings (file name: 1831-22234 K129276 15.4 Std Dwgs)
- Geotechnical and Pavement Design Reports (file names: 18306-22234\_Jennings Ave OR99E to Oatfield Rd\_RPT\_Geotechnical\_061821 and 18306-22234\_Jennings Ave OR99E to Oatfield Rd\_RPT\_Pavement\_061721)
- Hazardous Materials Corridor Study by Northwest Geotech, Inc. (file name: 1831-22234 K129276 3.4.1 HMCS-Final v2)
- Shoulder Material Investigation by Northwest Geotech, Inc. (file name: 1831-22234 K129276 3.4.5.1 Shoulder-Report-Final)
- Department of Environmental Quality Nationwide 401 Water Quality Certification Approval (file name: 18306\_K19276\_20210922\_WQC\_401Cert\_SEJenningsAve OR99E\_Oatfield)
- Department of State Lands Permit Approval No. 63001-RF (file name: 18306\_K19276\_Jennings\_Ave DSL Permit Approval\_63001RF Authorization 20210707)
- Department of State Lands Permit No. 63001-RF Renewal (file name: 18306\_K19276\_Jennings\_Ave DSL Permit 63001RF RenewalAuth20230413)
- US Army Corps of Engineers Permit Approval No. NWP-2020-449 (file name: 18306-K19276 20220307 Compiled USACE Permit Ltr-Encl NWP-2020-449)

• Oak Lodge Conditional Approval (file name: OLWSD\_Ltr Permit\_Issued\_Draft\_SD2020-014\_EC1200CA2020-007)

## SPECIAL PROVISIONS FOR CONSTRUCTION

# DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT CLACKAMAS COUNTY, OREGON

Earthwork and Drainage, Bridges and Structures, Asphalt Concrete Paving and Oiling

Jennings Ave: OR99E to Oatfield Rd

September 2023

### CLACKAMAS COUNTY DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT

#### SPECIAL PROVISIONS

**FOR** 

Earthwork and Drainage, Bridges and Structures, Asphalt Concrete Paving and Oiling

Jennings Ave: OR99E to Oatfield Rd

Pacific Highway East

Clackamas County

### PROFESSIONAL OF RECORD CERTIFICATION:

Seal w/signature



I certify the Special Provision Section(s) listed below are applicable to the design for the subject project for \_\_\_(list specific design elements, e.g. "Bridge XYZ" or "Traffic Signals") \_\_\_. Modified Special Provisions were prepared by me or under my supervision.

Section(s) 00210, 00220, 00221, 00222, 00223, 00224, 00225, 00228, 00245, 00270, 00280, 00290, 00294, 00305, 00310, 00320, 00330, 00331, 00350, 00390, 00405, 00415, 00430, 00440, 00445, 00446, 00470, 00490, 00495, 00510, 00596B, 00596C, 00620, 00641, 00730, 00738, 00744, 00756, 00759, 00810, 00970, 01011, 01030, 01050, 01065, 01069, 01070, 02001, 02030, 02050, 02080, 02415, 02440, 02510, 02690, 02830, 02926

FINAL ELECTRONIC DOCUMENT AVAILABLE UPON REQUEST

### PROFESSIONAL OF RECORD CERTIFICATION:



I certify the Special Provision Section(s) listed below are applicable to the design for the subject project for traffic control, signing, striping and traffic signals. Modified Special Provisions were prepared by me or under my supervision.

Section(s) 00220, 00221, 00222, 00223, 00224, 00225, 00228, 00440, 00850, 00856, 00865, 00867, 00868, 00902, 00905, 00920, 00930, 00940, 00950, 00960, 00962, 00990, 02560

### TABLE OF CONTENTS FOR SPECIAL PROVISIONS

WORK TO BE DONE	1
SECTION 00110 - ORGANIZATION, CONVENTIONS, ABBREVIATIONS, AND	
DEFINITIONS	2
SECTION 00120 - BIDDING REQUIREMENTS AND PROCEDURES	
SECTION 00130 - AWARD AND EXECUTION OF CONTRACT	
SECTION 00140 - SCOPE OF WORK	
SECTION 00150 - CONTROL OF WORK	7
SECTION 00160 - SOURCE OF MATERIALS	
SECTION 00165 - QUALITY OF MATERIALS	
SECTION 00170 - LEGAL RELATIONS AND RESPONSIBILITIES	
SECTION 00190 - MEASUREMENT OF PAY QUANTITIES	
SECTION 00195 - PAYMENT	29
SECTION 00196 - PAYMENT FOR EXTRA WORK	
SECTION 00197 - PAYMENT FOR FORCE ACCOUNT WORK	
SECTION 00199 - DISAGREEMENTS, PROTESTS, AND CLAIMS	
SECTION 00210 - MOBILIZATION	32
SECTION 00220 - ACCOMMODATIONS FOR PUBLIC TRAFFIC	32
SECTION 00221 - COMMON PROVISIONS FOR WORK ZONE TRAFFIC	
CONTROL	33
SECTION 00222 – TEMPORARY TRAFFIC CONTROL SIGNS	
SECTION 00223 - WORK ZONE TRAFFIC CONTROL LABOR AND VEHICLES	
SECTION 00224 - TEMPORARY TRAFFIC CHANNELIZING DEVICES	
SECTION 00225 - TEMPORARY PAVEMENT MARKINGS	
SECTION 00228 - TEMPORARY PEDESTRIAN AND BICYCLIST ROUTING	
SECTION 00245 - TEMPORARY WATER MANAGEMENT	
SECTION 00270 - TEMPORARY FENCES	
SECTION 00280 - EROSION AND SEDIMENT CONTROL	
SECTION 00290 - ENVIRONMENTAL PROTECTION	
SECTION 00294 - CONTAMINATED MEDIA	
SECTION 00305 - CONSTRUCTION SURVEY WORK	
SECTION 00310 - REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
SECTION 00320 - CLEARING AND GRUBBING	
SECTION 00330 - EARTHWORK	
SECTION 00331 - SUBGRADE STABILIZATION	
SECTION 00350 - GEOSYNTHETIC INSTALLATION	
SECTION 00390 - RIPRAP PROTECTION	67
SECTION 00405 - TRENCH EXCAVATION, BEDDING, AND BACKFILL	67
SECTION 00415 - VIDEO PIPE INSPECTION	
SECTION 00430 - SUBSURFACE DRAINSSECTION 00440 - COMMERCIAL GRADE CONCRETE	
	67
SECTION 00445 - SANITARY, STORM, CULVERT, SIPHON, AND IRRIGATION	60
PIPESECTION 00446 - TRENCH DRAINS	80
SECTION 00446 - TRENCH DRAINSSECTION 00470 - MANHOLES, CATCH BASINS, AND INLETS	80
SECTION 00490 - WORK ON EXISTING SEWERS AND STRUCTURES	
SECTION 00495 - TRENCH RESURFACINGSECTION 00510 - STRUCTURE EXCAVATION AND BACKFILL	
SECTION 005 TO - STRUCTURE EXCAVATION AND BACKFILL	/()

SECTION 00596B - PREFABRICATED MODULAR RETAINING WALLS	70
SECTION 00596C - CAST-IN-PLACE CONCRETE RETAINING WALLS	
SECTION 00620 - COLD PLANE PAVEMENT REMOVAL	
SECTION 00640 - AGGREGATE BASE AND SHOULDERS	
SECTION 00730 - EMULSIFIED ASPHALT TACK COAT	
SECTION 00738 - SAFETY EDGESECTION 00744 - ASPHALT CONCRETE PAVEMENT	74
SECTION 00749 - MISCELLANEOUS ASPHALT CONCRETE STRUCTURES	75
SECTION 00756 - PLAIN CONCRETE PAVEMENT	
SECTION 00759 - MISCELLANEOUS PORTLAND CEMENT CONCRETE	
STRUCTURES	76
SECTION 00810 - METAL GUARDRAIL	79
SECTION 00850 - COMMON PROVISIONS FOR PAVEMENT MARKINGS	79
SECTION 00856 - SURFACE MOUNTED TUBULAR MARKERS	80
SECTION 00865 - LONGITUDINAL PAVEMENT MARKINGS - DURABLE	80
SECTION 00867 - TRANSVERSE PAVEMENT MARKINGS - LEGENDS AND	
BARS	
SECTION 00868 - COLORED LANE MARKINGS	
SECTION 00902 - CROSSWALK CLOSURE SUPPORTS	83
SECTION 00905 - REMOVAL AND REINSTALLATION OF EXISTING SIGNS	83
SECTION 00920 - SIGN SUPPORT FOOTINGS	
SECTION 00930 - METAL SIGN SUPPORTS	
SECTION 00940 - SIGNS	84
SECTION 00950 - REMOVAL OF ELECTRICAL SYSTEMS	
SECTION 00960 - COMMON PROVISIONS FOR ELECTRICAL SYSTEMS	
SECTION 00962 - METAL ILLUMINATION AND TRAFFIC SIGNAL SUPPORTS	
SECTION 00970 - HIGHWAY ILLUMINATION	
SECTION 00990 - TRAFFIC SIGNALS	87
SECTION 01011 - STORMWATER CONTROL, BIOFILTRATION SWALE	
FACILITY	
SECTION 01030 - SEEDING	
SECTION 01050 - FENCES	
SECTION 01065 - MONUMENT BOXES	
SECTION 01069 - METAL HANDRAIL AND PEDESTRIAN FENCE	
SECTION 01070 - MAILBOX SUPPORTS	
SECTION 02001 - CONCRETE	
SECTION 02030 - SUPPLEMENTARY CEMENTITIOUS MATERIALS	
SECTION 02050 - CURING MATERIALS	
SECTION 02415 - PLASTIC PIPE	
SECTION 02510 - REINFORCEMENT	
SECTION 02560 - FASTENERS	104
SECTION 02690 - PCC AGGREGATES	104
SECTION 02830 - METAL HANDRAILSECTION 02926 - HIGHWAY ILLUMINATION MATERIALS	
SECTION UZ9Z0 - MIGMVAT ILLUIVIINATION IVIATERIALS	106

### **SPECIAL PROVISIONS**

### **WORK TO BE DONE**

The Work to be done under this Contract consists of the following on the OR99E to Oatfield Road Section of the Jennings Avenue in Clackamas County:

- 1. Install and remove temporary traffic control measures.
- 2. Install and remove erosion and sediment control measures.
- 3. Perform construction survey work.
- 4. Perform earthwork.
- Install storm drain facilities.
- 6. Construct retaining walls.
- 7. Construct curbs, sidewalks, and ADA Ramp improvements.
- 8. Furnish and place aggregate base and hot mix asphalt concrete.
- 9. Furnish and place guardrail.
- 10. Furnish and install permanent signs and striping.
- 11. Furnish and install detector loops and appurtenances.
- 12. Install miscellaneous ITS facilities.
- 13. Construct water quality facilities.
- 14. Complete seeding and landscaping.
- 15. Perform additional and incidental Work, as called for by the Specifications and Plans.

### **APPLICABLE SPECIFICATIONS**

The Specifications that are applicable to the Work on this Project are the General Conditions for Construction for Clackamas County published by the Agency, which contain Part 00100 General Conditions and the 2021 "Oregon Standard Specifications for Construction," Parts 00200 through 03000, published by the Oregon Department of Transportation which contain the detailed "Technical Specifications".

All number references in these Special Provisions shall be understood to refer to the Sections and subsections of the General Conditions or Standard Specifications bearing like numbers and to Sections and subsections contained in these Special Provisions in their entirety.

### **CLASS OF PROJECT**

This is a Federal-Aid Project.

### SECTION 00110 - ORGANIZATION, CONVENTIONS, ABBREVIATIONS, AND DEFINITIONS

Comply with Section 00110 of the General Conditions for Construction for Clackamas County modified as follows:

**00110.05(e)** Reference to Websites - Add the following bullet list to the end of this subsection:

American Traffic Safety Services Association (ATSSA)

www.atssa.com

- Clackamas County's Local Contract Review Board (LCRB) Rules
   <a href="https://dochub.clackamas.us/documents/drupal/ef976bc9-14f4-495b-9bd8-c69ee7334685">https://dochub.clackamas.us/documents/drupal/ef976bc9-14f4-495b-9bd8-c69ee7334685</a>
  - ODOT Construction Section

www.oregon.gov/odot/construction/pages/index.aspx

- ODOT Construction Section Qualified Products List (QPL) www.oregon.gov/ODOT/Construction/Pages/Qualified-Products.aspx
  - ODOT Construction Surveying Manual for Contractors

<u>www.oregon.gov/ODOT/ETA/Documents\_Geometronics/Construction-Survey-Manual-Contractors.pdf</u>

ODOT Estimating

www.oregon.gov/ODOT/Business/Pages/Steel.aspx

Oregon Legislative Counsel

www.oregonlegislature.gov/lc

ORPIN

Orpin.oregon.gov

 ODOT Procurement Office - Conflict of Interest Guidelines and Disclosure Forms

www.oregon.gov/ODOT/Business/Procurement/Pages/PSK.aspx

- ODOT Procurement Office Construction Contracts Unit Notice of Intent www.oregon.gov/ODOT/Business/Procurement/Pages/NOI.aspx
  - ODOT Procurement Office Construction Contracts Unit prequalification forms

www.oregon.gov/odot/business/procurement/pages/bid\_award.aspx

- Oregon Secretary of State: State Archives sos.oregon.gov/archives/Pages/default.aspx
- ODOT Traffic Control Plans Unit www.oregon.gov/ODOT/Engineering/Pages/Work-Zone.aspx
- ODOT Traffic Standards
   www.oregon.gov/ODOT/Engineering/Pages/Signals.aspx

### SECTION 00120 - BIDDING REQUIREMENTS AND PROCEDURES

Comply with Section 00120 of the General Conditions for Construction for Clackamas County modified as follows:

**00120.70 Rejection of Nonresponsive Bids** - Add the following bullet to the end of the bullet list:

• The Agency determines that any Pay Item is significantly unbalanced to the potential detriment of the Agency.

### SECTION 00130 - AWARD AND EXECUTION OF CONTRACT

Comply with Section 00130 of the General Conditions for Construction for Clackamas County.,

### **SECTION 00140 - SCOPE OF WORK**

Comply with Section 00140 of the General Conditions for Construction for Clackamas County.

### **SECTION 00150 - CONTROL OF WORK**

Comply with Section 00150 of the General Conditions for Construction for Clackamas County, modified as follows:

**00150.15(b) Agency Responsibilities** - Replace this subsection, except for the subsection number and title, with the following:

The Engineer will perform the Agency responsibilities described in the Construction Surveying Manual for Contractors, Chapter 1.5 (see Section 00305).

**00150.15(c) Contractor Responsibilities** - Replace this subsection, except for the subsection number and title, with the following:

The Contractor shall perform the Contractor responsibilities described in the Construction Surveying Manual for Contractors, Chapter 1.6 (see Section 00305).

The Contractor shall perform slope staking including intersections and set stakes defining limits for clearing which approximate Right-of-Way and easements.

**00150.50(c)** Contractor Responsibilities – Replace the 5<sup>th</sup>, 7<sup>th</sup>, and 10<sup>th</sup> bulleted sections, with the following:

- Protect from damage or disturbance any Utility that remains within the area in which Work is being performed. Maintain and re-establish location marks according to OAR 952-001-0090(3)(a). Coordinate re-establishment of the location marks with the associated Utility;
- Determine the exact location before excavating within the tolerance zone according to OAR 952-001-0090(3)(c);
- In addition to the notification required in OAR 952-001-0090(6), notify the Engineer
  and the Utility as soon as the Contractor discovers any previously unknown Utility
  conflicts or issues. Contrary to the OAR, stop excavating until directed by the
  Engineer and allow the Utility a minimum of two weeks to relocate or resolve the
  previously unknown Utility issues; and

Add the following bullet to the end of the bulleted list:

 Hold a Utility scheduling meeting and monthly Utility coordination meetings (see also 00180.42)

Add the following subsection:

### 00150.50(f) Utility Information (No Relocations):

Subsection	Utility	Contact Person's Name, Address, Email, and Phone Number
00150.50(f)(1)	Comcast	Todd Royer
	Corporation	7900 NE Killingsworth St
		Portland, OR 97218

		Todd_Royer@Comcast.com
00150.50(f)(2)	AT&T/TCA-LNS	Bobby Akhter
		4513 Western Ave
		Lisle, II 60532
		ba3817@att.com
		630-719-1483
00150.50(f)(3)	Verizon-MCI	Steve Carscallen
		2550 NE Aloclek Dr
		Hillsboro, OR 97124
		Steven.Carscallen@verizon.com
		503-307-8212
00150.50(f)(4)	Lumen	Don Sheeran
		8021 SW Capitol Hill Rd
		Portland, OR 97219
		Donal.Sheeran@Lumen.com
		503-422-0483
00150.50(f)(5)	Clackamas	Duke Dexter
	Broadband	121 Library Ct
	Exchange	Oregon City, OR 97045
	_	DDexter@Clackamas.us
		971-219-3339

Add the following subsection:

### 00150.50(g) Utility Information (Anticipated Relocations):

The following organizations may be adjusting Utilities within the limits of the Project during the period of the Contract with relocation Work estimated to be completed by the following dates and times:

		Contact Person's Name, Address, Email,	Estimated Completion
Subsection	Utility	and Phone Number	Date
00150.50(g)(1)	NW Natural	Jeremy Lorence 220 NW 2 <sup>nd</sup> Ave Portland, OR 97209 <u>Jeremy.Lorence@nwnatural.com</u> 503-781-4467	During Construction
00150.50(f)(2)	Portland General Electric	Chris Quines 3700 SE 17 <sup>th</sup> Ave Portland, OR 97202 Chris.Quines@pgn.com 503-522-8103	During Construction
00150.50(g)(3)	Oak Lodge Water Services – Sanitary Sewer	Brad Albert 14611 SE River Rd Oak Grove, OR 97267 brad.albert@olws.org 503-353-4202	During Construction
00150.50(g)(4)	Oak Lodge Water Services – Water	Brad Albert 14611 SE River Rd Oak Grove, OR 97267 brad.albert@olws.org 503-353-4202	During Construction

The Contractor shall contact the Engineer to view the approved Utility Relocation Plans.

The Contractor shall notify, in writing, the Utilities listed above, with a copy to the Engineer, at least 14 Calendar Days before beginning Work on the Project.

Within seven (7) days of being requested by either the Agency or a utility, the contractor's licensed surveyor shall perform staking of the design's proposed locations of utilities, limits of structures to be installed and the nearest overall limits of construction itself to reference with.

### (#1) NW Natural Gas(Name of Utility) -- ""Gas Utility"":

The Contractor shall notify the Gas Utility in writing, with a copy to the Engineer, 28\_Calendar Days before the Contractor is scheduled to begin performing roadway construction, retaining wall construction, stormwater installation, and grading operations. After the Gas Utility receives the notification, the Contractor shall then allow the Gas Utility 28\_\_ Calendar Days to schedule and complete the relocation and adjustment work before the contractor begins performing roadway construction, retaining wall construction, stormwater installation, and grading operations.

### (2#) Portland General Electric(Name of Utility) -- ""Power Supplier"":

The Contractor shall notify the Power Supplier(s) in writing, with a copy to the Engineer, at least 14 Calendar Days before beginning Work within 10 feet of the power line(s).

The Contractor shall notify the Power Supplier in writing, with a copy to the Engineer, 28 Calendar Days before the Contractor is scheduled to begin performing roadway construction, retaining wall construction, stormwater installation, and grading operations. After the Power Supplier receives the notification, the Contractor shall then allow the Power Supplier 28 Calendar Days to schedule and complete the relocation and adjustment work before the Contractor begins performing roadway construction, retaining wall construction, stormwater installation, and grading operations.

Due to slopes and terrain the Contractor shall coordinate with Power Supplier to place new pole in PSUE behind proposed retaining wall once the wall is completed. Refer to Sheet C-13 and construction note 44 at approximate Station 46+58L.

### (3) Oak Lodge Water Services – Sanitary Sewer - "Sewer Facility":

The Contractor shall notify the Sewer Facility in writing, with a copy to the Engineer, at least 14 Calendar Days before beginning Work within 10 feet of the Sewer facilities.

The Contractor shall notify the Sewer Facility in writing, with a copy to the Engineer, 28 Calendar Days before the Contractor is scheduled to begin performing roadway construction, retaining wall construction, stormwater installation, and grading operations. After the Sewer Facility receives the notification, the Contractor shall then allow the Sewer Facility 28 Calendar Days to schedule and complete the relocation and adjustment work before the Contractor begins performing roadway construction, retaining wall construction, stormwater installation, and grading operations.

The Contractor shall notify the Sewer Facility in writing, with a copy to the Engineer, 14 Calendar Days before the Contractor's estimated completion of retaining wall excavation near engineer's station 47+40. After the Contractor has completed this Work or 14 Calendar Days after the Sewer Facility receives the notification, whichever occurs later, the Contractor shall then allow the Sewer Facility 14 Calendar Days to schedule and complete the relocation and adjustment work.

### (4) Oak Lodge Water Services - Water - "Water Utility":

The Contractor shall notify the Water Utility in writing, with a copy to the Engineer, at least 14 Calendar Days before beginning Work within 10 feet of the Water Utility facilities.

The Contractor shall notify the Water Utility in writing, with a copy to the Engineer, 28 Calendar Days before the Contractor is scheduled to begin performing roadway construction, retaining wall construction, stormwater installation, and grading operations. After the Water Utility receives the notification, the Contractor shall then allow the Water Utility 28 Calendar Days to schedule and complete the relocation and adjustment work before the Contractor begins performing roadway construction, retaining wall construction, stormwater installation, and grading operations.

### **SECTION 00160 - SOURCE OF MATERIALS**

Comply with Section 00160 of the General Conditions for Construction for Clackamas County.

Comply with Section 00160 of the General Conditions for Construction for Clackamas County modified as follows:

**00160.20 Preferences for Materials** - Add the following paragraph to the beginning of this subsection:

Section 1518 of Moving Ahead for Progress in the 21st Century Act provides that Buy America applies to all Contracts eligible for federal assistance under Title 23, United States Code, included within the scope of an applicable National Environmental Policy Act (NEPA) finding, determination or decision, regardless of the funding source of such Contracts, where at least one Contract is funded with Title 23 funds. This Contract includes Title 23 funds under such a NEPA finding, determination or decision and Buy America under subsection (a) and Build America Buy America under subsection (d) apply to this Contract.

Add the following subsection:

**00160.20(d)** Build America Buy America Act Requirements - If federal highway funds are involved on the Project, the Contractor shall comply with the Build America Buy America Act and implementing regulations (Infrastructure Investment and Jobs Act ("IIJA"), Pub. L. No. 117-58, which includes the Build America, Buy America Act ("the Act"). Pub. L. No. 117-58, Sections 70901-70941).

All of the manufacturing processes must occur in the United States for the applicable construction materials permanently incorporated in the Project as listed below.

Construction materials include an article, Material, or supply that is or consists primarily of:

- · non-ferrous metals;
- plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables);
- glass;
- · lumber; or
- drywall.

The Contractor shall provide the Engineer with a Certificate of Materials Origin, on a form furnished by the Engineer, before incorporating any applicable construction materials into the Project. Unless a Certificate of Materials Origin has been provided to the Engineer, the products and Materials shall be considered of foreign origin.

No de minimis amount has been established for applicable construction materials permanently incorporated into the Project. Strict compliance is required.

The Contractor shall retain manufacturers' certificates verifying the origin of all applicable construction materials for 3 years after the date of final payment for the Project, and shall furnish copies to the Engineer upon request.

Manufactured products assembled outside the Project Site are not subject to the Build America Buy America requirements. Manufactured products are items that consist of two or more of the listed construction materials that have been combined together through a manufacturing process, and items that include at least one of the listed construction materials combined with a Material that is not listed through a manufacturing process, and should be treated as manufactured products, rather than as construction materials.

Iron and steel Materials are subject to 00160.20(a).

The Contractor shall include this provision in all subcontracts.

**00160.21 Cargo Preference Act Requirements** - Add the following to the end of this subsection:

Additional information may be available at the following websites:

https://www.fhwa.dot.gov/construction/cqit/cargo.cfm https://www.fhwa.dot.gov/construction/cqit/cargo/qa.cfm.

### **SECTION 00165 - QUALITY OF MATERIALS**

Comply with Section 00165 of the General Conditions for Construction for Clackamas County modified as follows:

**00165.35(d) Certificate of Origin of Steel Materials -** Replace this subsection, except for the subsection number and title, with the following:

When a certificate of material origin for steel or iron Materials is specified, complete ODOT Form 734-2126 as required by 00160.20(a) for Federal-aid projects.

**00165.35(e)** Certificate of Origin of Construction Materials – This subsection is added after subsection 00165.35(d):

When a certificate of material origin for construction materials is specified, complete ODOT Form 734-5378 as required by 00160.20(d) for Federal-aid projects.

### **SECTION 00170 - LEGAL RELATIONS AND RESPONSIBILITIES**

Comply with Section 00170 of the Standard Specifications modified as follows:

**00170.00 General –** Replace the first sentence in the first paragraph with the following:

The Contractor shall comply with all laws, ordinances, codes, regulations, executive orders, and administrative rules (collectively referred to as "Laws" in this Section) that relate to the Work or to those engaged in the Work.

Add the following subsection:

**00170.06 Federal-Aid Participation** - This Project is to be conducted according to the regulations applying to Federal-Aid Highway Projects.

**00170.65(b)(4) Owner/Operator Date –** Replace the bulleted sections with the following:

- Driver's name;
- Present driver license upon request;
- Vehicle identification number;
- · Present vehicle registration upon request;
- Motor vehicle license plate number;
- · Motor Carrier account number;
- Present ODOT Motor Carrier 1A Permit upon request; and
- Name of owner/operator from the side of the truck.

**00170.65(e)** Additional Requirements When Federal Funds are Involved - Replace this subsection, except for the subsection number and title, with the following:

For this Federal-Aid Project, the Contractor shall comply with 00170.65(a) through 00170.65(d) and the provisions of FHWA Form 1273, "Required Contract Provisions Federal-Aid Construction Contracts", except Section IV of FHWA Form 1273 does not apply.

**00170.70(a)** Insurance Coverages - Add the following to the end of this subsection:

The following insurance coverages and dollar amounts are required pursuant to this subsection:

Insurance Coverages	Combined Single Limit per Occurrence	Annual Aggregate Limit	
Commercial General Liability	\$2,000,000	\$4,000,000	
Commercial Automobile Liab	ility \$1,000,000	(aggregate limit not required)	
Pollution Liability	\$1,000,000	\$1,000,000	

With Lead Liability Endorsement or separate coverage

Pollution Liability Insurance - With a minimum limit of \$1,000,000, if pollution coverage is provided outside of a P&I Club entry or outside of Protection and Indemnity Insurance coverage evidenced on the SP-23 form or equivalent.

**00170.70(d)** Additional Insured - Add the following sentence to the beginning of the first paragraph:

The liability insurance coverages of 00170.70(a) shall include the Agency, the Agency's governing body, board, or Commission and its members, and their respective officers, agents, and employees as Additional Insureds, but only with respect to the Contractor's activities to be performed under the Contract.

Add the following as Additional Insureds under the Contract:

- Clackamas County and its officers, agents, and employees
- Clackamas County Board of Commissioners
- Oregon Department of Transportation and its officers, employees, and agents

**00170.70(h) Agency Acceptance -** Replace the paragraph in this subsection with the following:

All insurance and insurance providers are subject to Agency acceptance. In addition, all of the following are subject to Agency acceptance and, if requested by Agency, the Contractor shall provide complete copies of the following to Agency's representatives responsible for verification of the insurance coverages required by the Contract: insurance policies, endorsements, self-insurance documents and related insurance documents.

**00170.70(j) Builders' Risk Installation Floater –** Replace the paragraph in this subsection with the following:

If specified by Special Provision, the Contractor shall obtain, at its expense, and keep in effect during the term of the Contract, Builder's Risk Installation Floater Insurance covering the Contractor's Materials and Equipment to be used for completion of the Work performed under the Contract. The minimum amount of coverage to be carried shall be equal to the full amount of the Contractor's Equipment, Materials, or fixtures to be installed, in-transit, or stored offsite during the performance of the Contract. This insurance shall include as loss payees the Agency, State of Oregon, the building or structure owner, as loss payees.

**00170.72 Indemnity/Hold Harmless** - Add the following paragraph and bullets to the end of this subsection:

Extend indemnity, defense and hold harmless to the Agency and the following:

- Clackamas County and its officers, agents, and employees
- Clackamas County Board of Commissioners
- Oregon Department of Transportation and its officers, employees, and agents

### **SECTION 00180 - PROSECUTION AND PROGRESS**

Comply with Section 00180 of the General Conditions for Construction for Clackamas County modified as follows:

**00180.40(c) Specific Limitations** - Limitations of operations specified in these Special Provisions include, but are not limited to, the following:

Limitations	Subsection
Cooperation with Utilities	
Cooperation with Other Contractors	00150.55
Contract Time	00180.50(h)
Right-of-Way and Access Delays	00180.65
Closed Lanes	
Special Events	00220.40(e)(2)(b)
Limited Duration Road Closure	00220.40(f)
Regulated Work Areas	00290.34(a)
Noise Control	00290.32
Maintenance Under Traffic	00620.43
Opening Sections to Traffic	00744.51
Opening Sections to Traffic	00745.51

The Contractor shall not begin work other than Clearing and Grubbing Work before March 15, 2023, unless approved by the Engineer.

The Contractor shall be aware of and subject to schedule limitations in the Standard Specifications that are not listed in this subsection.

**00180.41 Project Work Schedules** - After the paragraph that begins "One of the following Type..." add the following paragraph:

In addition to the "look ahead" Project Work schedule, a Type B schedule as detailed in the Standard Specifications is required on this Contract.

**00180.42 Preconstruction Conference** - Add the following to the end of this subsection:

• Videotape of private properties affected by construction per 00150.70.

Before beginning On-Site Work and before the preconstruction conference, the Contractor shall conduct a Utility scheduling meeting with representatives from the Utilities involved with this Project and with the Engineer. The Contractor shall incorporate the time needs of the Utilities into the Contractor's schedule submitted at the preconstruction conference.

The Contractor shall submit a written Utility Coordination Report to the Engineer not later than seven Calendar Days after the Utility scheduling meeting. The Utility Coordination Report shall:

Identify each specific Utility;

- Identify Utility contact names and numbers;
- · Identify dates for Utility scheduling for the entire Project;
- Contain documents showing that the Contractor has accomplished Utility locates; and
- Contain documents showing that Utility locates, along with applicable construction activities, have been reviewed and discussed on-site with Utility representatives.

The Contractor shall hold monthly Utility coordination meetings with Utilities and the Engineer to coordinate Project activities with Utilities and on-going Utility relocation work. The Contractor shall hold monthly Utility coordination meetings in the office or in the field, as appropriate. The Utility coordination meetings shall include, but not be limited to:

- Detailed discussions of existing and abandoned Utilities,
- Detailed discussions of de-energizing and re-energizing service lines,
- Detailed discussions of critical locations for potholing of Utilities,
- · Detailed discussions of Project activities, and
- Detailed discussions of on-going Utility relocations in upcoming Project activity areas.

During the monthly Utility coordination meetings, the Utilities will provide Utility drawings and discuss the scope, extent, locations, and significance of all Utility facilities before the Contractor begins work in a new activity area. The Contractor shall incorporate this information into the Project schedules and furnish the Utilities copies of the updated Project schedules.

The Contractor shall plan and schedule all Utility adjustment operations well in advance of On-Site Work. When the Contractor becomes aware of Utility conflicts not previously identified, the Contractor shall notify the applicable Utilities in writing the same Calendar Day. The Contractor shall allow Utilities at least 28 Calendar Days to relocate (adjust) the Utility conflicts not previously identified.

Add the following subsection:

**00180.50(h)** Contract Time - There is one Contract Time on this Project as follows:

The Contractor shall complete all Work to be done under the Contract, except for seeding establishment, not later than October 31, 2024.

**00180.65** Right-of-Way and Access Delays - Add the following paragraph and table to the end of this subsection:

The Contractor shall incorporate the special conditions for each property listed in the table below to progress the Work to be done under the Contract:

In addition to any specific time frames noted for each property below and in addition to requirements of Section 270.40, the contractor's representative shall make personal contact and notification in writing, with each property owner a minimum 7 days prior to entering property for construction purposes, removal of materials, installation of temporary fencing or limiting of access.

ROW File #	Tax Lot / Map	Owner	Phone	Eng. Station, Approximate	Special Conditions
02	701 / 2 2E 18CD	Weston Investme nt Co.	503-784- 2912	12+00 to 12+45	Not applicable
03	600 / 2 2E 18CD	Gettel	503- 999- 0904	12+45 to 16+80	Reconstruct existing driveway with asphalt and connect to the County right of way improvements. 16+17
04	300 / 2 2E 18CD	Tacha	503-752- 5906	17+20 to 18+20	<ol> <li>Maintain driveway access at all times.</li> <li>Protect the wooden fence and retaining wall located in the County right of way.</li> </ol>
05	200 / 2 2E 18CD	Payne	503-804- 8993	18+20 to 76	<ol> <li>Reconstruct existing driveway with asphalt as shown on the plans 18+25</li> <li>Maintain driveway access at all times.</li> <li>Protect existing concrete retaining wall.</li> <li>Protect the existing brick wall.</li> </ol>
06	100 / 2 2E 18CD	Payne	503-804- 8993	18+76 to 19+66	<ol> <li>Reconstruct existing driveway with asphalt as shown on plans 19+22</li> <li>Maintain driveway access at all times.</li> <li>Protect the existing chain link fence.</li> </ol>
10	5500 / 2 2E 18DB	Turnbow	503-809- 9983	22+70 to 23+25	Reconstruct existing concrete driveway as shown on the plans. 22+95     Protect the vinyl fence enclosing the front yard.
11	5400 / 2 2E 18DB	Wiseman	503-701- 1579	23+25 to 23+95	Reconstruct existing concrete driveway as shown on plans 19+22
12	5300 / 2 2E 18DB	Vargas	503-653- 7935	23+95 to 24+82	<ol> <li>Maintain driveway access at all times.</li> <li>Contractor shall replace the existing asphalt driveway with asphalt as shown on the plans.</li> </ol>
13	5200 / 2 2E 18DB	Persons	503-810- 8626	24+82 to 25+80	Maintain driveway access from Cook St at all times.     Protect the storage shed in the Permanent Slope and

						Public Utility Easement during construction.
15	4501 / 2 2E 18DB	Fleming	503-659- 5603	27+10 28+15	to	<ol> <li>Maintain driveway access on Hymie at all times.</li> <li>Protect the wood fence and landscaping within the easement areas and replace if damaged by the project.</li> </ol>
16	4505 / 2 2E 18DB	Gabriel	503-659- 8894	20+35 29+10	to	<ol> <li>Maintain driveway access on Hymie Wy at all times.</li> <li>Protect the wood fence and landscaping within the easement areas and replace if damaged by the project.</li> </ol>
17	4400 / 2 2E 18DB	Tomasze wski	971-344- 0478	29+10 29+90	to	<ol> <li>Maintain driveway access at all times.</li> <li>The Contractor shall remove the tree stump located at approximate engineering station 29+47 LT 31'.</li> </ol>
18	4300 / 2 2E 18DB	Sadowski	303-304- 4683	29+90 30+35	to	<ol> <li>Maintain driveway access at all times</li> <li>Install temporary fencing along the back of the Permanent Slope and Utility Easement areas during construction. Provide the property owner 90 days advance notice of when the temporary fence will be removed.</li> </ol>
19	2300 / 2 2E 18DB	Grime	971-344- 0110	31+00 31+70	to	Maintain driveway access at all times
20	2200 /22E 18DB	Lyons	971-275- 3859	31+70 32+30	to	<ol> <li>Protect the wood fence and landscaping within the easement areas and replace if damaged by the project.</li> <li>Maintain driveway access at all times.</li> <li>Protect the trees within the temporary construction easement areas Contractor shall be responsible for replacing in kind if disturbed by the project.</li> </ol>

21	2100 / 2 2E 18DB	Lerma Family Trust	503-645- 0488	32+30 32+90	to	<ol> <li>Protect the electric light post on Parcel 2 in place. The contractor shall be responsible for replacing in kind if disturbed by the project</li> <li>Maintain driveway access at all times.</li> </ol>
22	2000 / 2 2E 18DB	Sullivan	971-263- 6339	32+90 33+45	to	Maintain driveway     access at all times.
23	300 / 2 2E 18DB	Evans & Cox	503-799- 2234	33+60 35+05	to	<ol> <li>Maintain driveway access at all times.</li> <li>Contractor shall replace the gravel within easement areas to an in kind or better condition if disturbed by the project.</li> </ol>
24	211 / 2 2E 18DB	Budil	503-307- 3216	35+05 35+85	to	<ol> <li>Maintain driveway access at all times.</li> <li>The Contractor shall protect the owner's in-ground irrigation system located between approximate engineering stations 35+07 Lt 26' to 35+59 Lt 26'.</li> </ol>
25	200 / 2 2E 18DB	Congdon	(503) 413- 0200	35+85 37+10	to	<ol> <li>Maintain driveway access at all times.</li> <li>Protect the mature trees and root system to the greatest extent possible located within subject property between approximate engineering stations 35+87 LT to 37+07 LT. Trim the mature trees, per the contract only as necessary to support project construction.</li> <li>Install temporary fencing, (6 feet in height and lined with fabric), along the back of the Permanent Slope and Public Utility Easement areas between engineering stations 35+87 LT to 37+07 LT. Provide the property owner 90 days advance notice of when the temporary fencing will be removed.</li> </ol>

	I	ı		l	-	
						<ul> <li>4. The Contractor shall remove and relocate the redwood tree located at approximate engineering station 37+07 LT 12' onto the remaining portion of the property for the property owner's future use or disposal.</li> <li>5. The Contractor shall notify the property owner with 24-hour advance notice of driveway work at approximate engineering stations 36+05 LT to 36+17 LT and 36+75 LT to 36+87 LT.</li> </ul>
26	102 / 2 2E 18DB	Gaitan & Torres	503-442- 7138	37+10 37+90	to	<ol> <li>Install temporary fencing along the back of the easement area during project construction. Provide the property owner 90 days advance notice of when the temporary fence will be removed.</li> <li>Cut a portion of the fence along its sides, running perpendicular to SE Jennings Ave, at the right of way line. Remove and re-construct the remaining sections of the existing fence and parts, so that the completed fence is behind the right of way line. Any remaining portions of the existing fence are to be placed onto the owner's remaining property for their use or disposal.</li> </ol>
27	104 / 2 2E 18DB	Marl	530-484- 8851	38+40 39+15	to	Not applicable
28	100 / 2 2E 18DB	Leppert	503-312- 2222	39+15 40+40	to	<ol> <li>Contract shall replace the existing retaining wall to an inkind or better condition, per Section 00596B.01.</li> <li>Contractor shall replace the existing wood fence, located atop the existing wall, to an inkind or better condition. See Sheet R-04</li> <li>Install 2, H-20 utility boxes for electrical and sprinkler</li> </ol>

			1	1		
					6	systems at back of curb line as directed.  Concrete apron driveway shall be colored to match existing concrete.  Existing ran and footing drains to be reconnected to storm system. Filed fit with as directed by County Inspector.  Notify Home owner two weeks prior to commencing work to allow scheduling and removal/salvage of selected landscaping.  Maintain Driveway access.
31	1304 / 2 2E 18DA	King	503-705- 3191	40+65 to 41+40		. Maintain driveway access at all times Protect the sewer line and water line located on the owner's property. Contractor shall repair the sewer line and/or water line if it is impacted by the project to a like condition or better.
32	1202 /2 2E 18DA	Sarsten	503-310- 5837	41+40 to 42+20	3	. Maintain driveway access at all times Protect the wood and rock retaining walls located within the Permanent Slope and Public Utility and Temporary Easement areas Contractor shall replace the asphalt, concrete and gravel surfaces within the Permanent Slope and Public Utility and Temporary Easement areas to an in kind or better condition if disturbed by the project Contractor shall remove two (2) mature evergreen trees, per the contract, located at approximate engineering stations 42+40, 30' LT and 42+42, 40' LT Protect the sewer line located on the owner's property. Contractor shall repair the sewer line if it is impacted by

						the project to a like condition or better.
33	1203 /22E 18DA	Hellekso n	503-481- 6319	42+20 42+55	to	<ol> <li>Maintain driveway access, located between approximate engineering stations 42+45 Lt and 42+55 Lt, at all times.</li> <li>Contractor shall remove one         <ul> <li>(1) large evergreen tree located at approximate engineering station 42+42 Lt, 41' LT.</li> </ul> </li> <li>Provide the property owner 24-hour advance notice when work will be performed on driveway access located between approximate engineering stations 42+45 Lt and 42+55 Lt.</li> </ol>
34	7500 / 2 2E 18AD	Schlottm an	503-320- 0660	42+55 43+45	to	<ol> <li>Maintain side street access at all time with brief interruptions.</li> <li>Protect the wood and rock retaining walls located within the Temporary Easement areas.</li> </ol>
37	4800 / 2 2E 18AD	State	503-794- 1809	45+60 46+50	to	<ol> <li>Maintain driveway access at all times.</li> <li>Provide the property owner 24-hour advance notice when work will be performed on driveway access and minimizing closures to the greatest extent possible.</li> <li>Protect the portion of chain link fence located within the temporary easement.</li> <li>Contractor shall reconstruct property owner driveway, per the contract (sheet D-3), and restore any damage made within the easement areas to an in kind or better condition if disturbed by the project.</li> </ol>
38	4700 / 2 2E 18AD	Adler & Rackerby	503-358- 5843	46+50 48+10	to	The Contractor shall cut and cap the landscape irrigation located within the proposed 3-point turnaround (hammerhead), but will not be responsible for its repairs or reconfiguration.

39	4600 / 2 2E	Hughes	503-481- 6229	48+10 49+00	to	<ol> <li>Remove the lantern light post and cut and cap the associated electrical line. The Contractor will not be responsible for repairs or reconfiguration of either feature.</li> <li>Maintain driveway access at all times.</li> </ol>
	18AD					
40	4500 / 2 2E 18AD	Wiley	503-875- 4574	49+00 50+10	to	<ol> <li>Maintain driveway access at all times.</li> <li>Protect 64 LF of 4-foot tall chain link fencing from approximate engineering stations 49+00 LT to 49+65 LT.</li> </ol>
44	7600 /22E 18AD	Noble	503-341- 1178	42+60 50+10	to	<ol> <li>Protect Blueberry Bushes located within the Temporary Construction Easement Areas.</li> <li>Install Black Chain-Link Fencing with Black Privacy Slats.</li> <li>The Contractor shall install temporary chain-link fencing within the right of way during construction.</li> </ol>
45	200 / 2 2E 18DA	De Their	503-709- 2060	44+95 45+70	to	Install black chain-link fence with privacy slats, per the contract.
46	1000 /22E 18DA	French	503-709- 0439	43+65 44+65	to	<ol> <li>The Contractor shall protect the six (6) trees located adjacent the proposed right of way and within the temporary construction easement areas. Work performed to support the proposed sidewalk is to remain beyond and not exceed the tree trunk "threshold" distances detailed below. Measurements are taken at the base of the tree, where the trunk meets the existing grade.</li> <li>Tree # 1 – 21 linear inches</li> <li>Tree # 2 – 15 linear inches</li> </ol>

			I			
						<ul> <li>Tree # 3 – 25 linear inches</li> <li>Tree # 4 – 25 linear inches</li> <li>Tree # 5 – 25 linear inches</li> <li>Tree # 6 – 15 linear inches</li> <li>The Contractor shall install a silt fence or similar demarcation around the tree trunk "thresholds" to provide a visual reminder of the recommended "threshold" distances not to be exceeded.</li> </ul>
47	1100 / 2 2E 18DA	Mountain Ridge Homes, LLC	503-473- 4559	42+00 43+65	to	Not applicable
48	1401 / 2 2E 18DA	Von & Oneill	503-750- 3223	40+52 41+50	to	Not applicable
49	1500 / 2 2E 18DA	Tinsley	503-504- 5603	38+80 39+85	to	Maintain driveway     access at all times.
50	2100 / 2 2E 18DA	Wellbau m	(503) 701- 1579	37+20 38+35	to	Maintain driveway access at all times.
54	1900 / 2 2E 18DB	Wood	503-577- 0874	29+44 30+70	to	<ol> <li>Maintain driveway access at all times</li> <li>Cut a portion of the fence in the easement areas at the right of way line.         Remove and re-construct the remaining sections of the existing fence and parts, so that the completed fence is behind the right of way line. Any remaining portions of the existing fence are to be placed onto the owner's remaining property for their use or disposal.</li> <li>Install temporary fencing along the back of the Temporary Construction Easement areas during construction.</li> </ol>

55	201 / 2 2E 18DC	Tiliano	503-804- 0521	28+15 28+85	to	4. Provide the property owner 90 days advance notice of when the temporary fence will be removed.  1. Maintain driveway access at all times
56	225 / 2 2E 18DC	Chu	971-533- 0659	26+60to 27+60		Maintain driveway access at all times
58	1000 / 2 2E 18CD	Hales	971-401- 3481	15+20 16+80	to	Maintain driveway access at all times.
60	100 / 2 2E 18DA	Inocencio & Kern	541-514- 2089	45+80 42+65	to	<ol> <li>The residential driveway approach is approximately 11 ft. wide and of asphalt composition. Maintain driveway access at all times. Maintain at least one open lane along SE Jennings Avenue with occasional brief interruptions.</li> <li>Contractor shall replace the asphalt within the Temporary Construction Easement area to an in kind or better condition if disturbed by the project.</li> <li>Install Black Chain-Link fencing with Black Privacy Slats.</li> <li>The Contractor shall remove and relocate the trees located at approximate engineering station 37+07 LT 12' onto the remaining portion of the property for the property owner's future use or disposal.</li> </ol>
61	502 / 2 2E 18DC	Roozenb oom	503-650- 0700	24+05 24+60	to	Not applicable
72	701 / 2 2E 18DC	Neilson	503-998- 4018	19+18 19+92	to	Maintain driveway access at all times.

**00180.70(b) Contractor's Responsibility during and after Suspension** - Replace the paragraph that begins "During periods of suspension of the Work ..." with the following paragraph:

During periods of suspension of the Work, the Contractor shall continue to be responsible for protecting and repairing the Work according to 00170.80, and for ensuring that a single designated representative responsible for the Project remains available according to 00150.40.

**00180.85(b)** Liquidated Damages - Add the following to the end of this subsection:

The liquidated damages for failure to complete the Work on time required by 00180.50(h) will be \$1,100 per Calendar Day \*.

\* Calendar Day amounts are applicable when the Contract time is expressed on the Calendar Day or fixed date basis.

Add the following subsection:

**00180.85(c)** Lane Closures - Lane closures beyond the limits specified will inconvenience the traveling public and will be a cost to the Agency.

It is impractical to determine the actual damages the Agency will sustain in the event Traffic Lanes are closed beyond the limits listed in 00220.40(e) or 00220.40(f). Therefore, the Contractor shall pay to the Agency, not as a penalty, but as liquidated damages, \$500 per 15 minutes, or for a portion of 15 minutes, per lane, for any lane closure beyond the limits listed in 00220.40(e) or 00220.40(f). In addition to the liquidated damages, all added cost for traffic control measures, including flagging, required to maintain the lane closures beyond the allowed time limits, will be at no additional cost to the Agency. The required traffic control measures will be as determined by the Engineer.

The Engineer will determine when it is safe to reopen lanes to traffic. Assessment of liquidated damages will stop when all lanes have been safely reopened. Any liquidated damages assessed under these provisions will be in addition to those listed in 00180.85(b).

Add the following subsection:

**00180.85(e)** Traffic Delays Beyond 20 Minutes - Stopping or holding vehicles beyond the limits specified will inconvenience the traveling public and will be a cost to the Agency.

It is impractical to determine the actual damages the Agency will sustain in the event traffic is stopped or held longer than the 20-minute limit listed in 00220.02. Therefore, the Contractor shall pay to the Agency, not as a penalty, but as liquidated damages, \$500 per 20 minutes, or for a portion of 20 minutes, for stopping or holding traffic longer than 20 minutes. In addition to the liquidated damages, any added cost for traffic control measures, including flagging, required to stop or hold traffic beyond the 20-minute time limit, will be at no additional cost to the Agency. The required traffic control measures will be as determined by the Engineer.

Assessment of liquidated damages will stop when the Engineer determines that traffic is no longer stopped or held beyond the 20-minute limit. Any liquidated damages assessed under these provisions will be in addition to those listed in 00180.85(b).

#### **SECTION 00190 - MEASUREMENT OF PAY QUANTITIES**

Comply with Section 00190 of the General Conditions for Construction for Clackamas County modified as follows:

**00190.20(a) General** – Delete the 3rd paragraph and replace with the following:

Unless otherwise provided in the Contract, Pay Items to be measured by weight shall include all Contractor costs for providing, maintaining, inspecting, and testing scales; for furnishing appropriate weigh tickets; for self-printing scales; for electronic weigh memo system(s); and for transporting Materials to the scales or to check weighing.

**00190.20(f)(1) Scale with Automatic Printer** – Replace the 1<sup>st</sup> sentence in the 1st paragraph with the following:

If the scales have an automatic weigh memo printer or an approved electronic weigh memo system that does not require manual entry of gross weight information, the Agency may periodically have a representative at the scales to observe the weighing procedures.

**00190.20(f)(2) Scale Without Automatic Printer** - Add the following paragraph after the paragraph that begins " If the scales require manual entry...":

Pay costs for the weigh witness at \$35.00 per hour.

**00190.20(f)(3) Duties of Weigh Technician** – Delete the last paragraph in the bulleted section and replace with the following:

- Furnish a legible, serially numbered weigh memo for each load of Materials to the Agency's Materials receiver at the point of delivery, or as directed by the Engineer. The memo shall identify the Project, the Materials, the date, net weight (gross and tare as appropriate), and identification of the vehicle and weigh technician. If approved by the Engineer an electronic weigh memo system may be used. Requests to use an electronic weigh memo system shall be submitted to the Engineer according to 00150.37, providing sufficient detail for the Engineer to perform an evaluation. If approved, the Contractor shall provide training, technical support, reports, and weigh memo information to the Engineer at no additional cost to the Agency. The electronic weigh memo system shall be:
- Capable of recording and securely retaining the same required "weigh memo" information identified above. For retention see 00170.07(c).
- Fully integrated with the provided weigh scale system.
- Designed in such a way that the data electronically read from scales cannot be altered by the Contractor, Subcontractor, Supplier, Engineer, or other system users.
- Designed to allow the Engineer remote access to all the weigh memo data in realtime and allow the Engineer to add comments to the individual weigh memo regarding waste, temperature, stations, yield or other information. The system shall identify the system user or individual that adds comments to the electronic weigh memo or otherwise access the system. The Contractor shall provide the Engineer a means to access the data if the Engineer cannot use an Agency provided hand held device for access.

 Capable of providing all the weigh memo information, including any added comments, in an electronic data file the Engineer can easily access without proprietary software.

**00190.20(g)** Agency-Provided Weigh Technician - Add the following paragraph to the end of this subsection:

Pay costs for the weigh technician at \$35.00 per hour.

**00190.30 Plant Scales** – Add the following sentence after the bulleted section:

If approved by the Engineer an electronic weigh memo system may be used in place of a printer system. See 00190.20(f)(3).

#### **SECTION 00195 - PAYMENT**

Comply with Section 00195 of the General Conditions for Construction for Clackamas County, modified as follows:

**00195.10 Payment For Changes in Materials Costs** - Replace this subsection with the following subsection:

**00195.10 Asphalt Cement Material Price Escalation/De-escalation** - An asphalt cement escalation/de-escalation clause will be in effect during the life of the Contract.

The Agency reserves all of its rights under the Contract, including, but not limited to, its rights for suspension of the Work under 00180.70 and its rights for termination of the Contract under 00180.90, and this escalation/de-escalation provision shall not limit those rights.

(a) Monthly Asphalt Cement Material Price (MACMP) - The Monthly Asphalt Cement Material Price (MACMP) will be established by the Agency each month and will be based on the published prices of PG 64 22 asphalt cement furnished by Poten & Partners, Inc. If any portion of the Project Site is located within the boundaries of ODOT Maintenance District 13 or 14, the MACMP will be based on the average prices for the Boise, Idaho area. If no portion of the Project Site is within the boundaries of ODOT Maintenance District 13 or 14, the Contractor may elect to have the MACMP based on the average prices of either the Portland, Oregon area or the Boise, Idaho area. If electing to use Boise, Idaho average prices for determination of the MACMP, the Contractor shall notify the Engineer in writing of the Contractor's election before or within 7 Calendar Days after the date of the preconstruction conference. This election, once acknowledged by the Engineer, will be binding for the entire duration of the Contract. If no such written notification is made, the Portland, Oregon area prices will be used as the basis of the MACMP. The area selected as the basis of the MACMP, once chosen, will become the sole area to be used as the basis for all asphalt cement used on the Project. Each MACMP for a given month will be the average of the published prices for that MACMP for each Friday in that month.

For information regarding the calculation of the MACMP, and for the actual MACMP, go to the Agency website at:

https://www.oregon.gov/ODOT/Business/Pages/Asphalt-Fuel-Price.aspx

If the Agency-selected index ceases to be available for any reason, the Agency in its discretion will select and begin using a substitute price source or index to establish the MACMP each month. The MACMP will apply to all asphalt cement including but not limited to paving grade, polymer modified, and emulsified asphalts, and recycling agents. The Agency does not guarantee that asphalt cement will be available at the MACMP.

- **(b)** Base Asphalt Cement Material Price (Base) The Base asphalt cement material price for this Project is the MACMP published on the Agency website for the month immediately preceding the Bid Opening date.
- **(c) Monthly Asphalt Cement Adjustment Factor** The Monthly Asphalt Cement Adjustment Factor will be determined each month as follows:
  - If the MACMP is within ± 5% of the Base, there will be no adjustment.
  - If the MACMP is more than 105% of the Base, then:

Adjustment Factor =  $(MACMP) - (1.05 \times Base)$ 

• If the MACMP is less than 95% of the Base, then:

Adjustment Factor =  $(MACMP) - (0.95 \times Base)$ 

(d) Asphalt Cement Price Adjustment - A price adjustment will be made for the items containing asphalt cement listed below. The price adjustment as calculated in (c) above will use the MACMP for the month the asphalt is incorporated into the Project. The price adjustment will be determined by multiplying the asphalt incorporated during the month for subject Pay Items by the Adjustment Factor.

The Pay Items for which price adjustments will be made are:

### Pay Item(s)

Level 2 Asphalt in 1/2 inch ACP

**00195.12(d) Steel Materials Pay Item Selection** - Add the following paragraph to the end of this subsection:

No Pay Items under this Contract qualify for the steel escalation/de-escalation program for this Project.

**00195.50(a) Progress Payments** – Replace the last sentence in the first paragraph with the following:

If the Contractor uses these estimates as a basis for making payments to Subcontractors and Suppliers, the Contractor assumes all risk and bears any losses that result.

#### **SECTION 00196 - PAYMENT FOR EXTRA WORK**

Comply with Section 00196 of the General Conditions for Construction for Clackamas County.

### SECTION 00197 - PAYMENT FOR FORCE ACCOUNT WORK

Comply with Section 00197 of the General Conditions for Construction for Clackamas County.

### **SECTION 00199 - DISAGREEMENTS, PROTESTS, AND CLAIMS**

Comply with Section 00199 of the General Conditions for Construction for Clackamas County.

#### **SECTION 00210 - MOBILIZATION**

Comply with Section 00210 of the Standard Specifications.

#### SECTION 00220 - ACCOMMODATIONS FOR PUBLIC TRAFFIC

Comply with Section 00220 of the Standard Specifications modified as follows:

**00220.02(a)** General Requirements - Add the following bullet to the end of the bullet list:

 When an abrupt edge is created by excavation, protect traffic according to the "Excavation Abrupt Edge" and the "Typical Abrupt Edge Delineation" configurations shown on the Standard Drawings.

### 00220.40(e)(1) Closed Lanes – See the following items:

Traffic Lanes may be closed on the SE McLoughlin Blvd (Highway OR99E) when allowed, shown, or directed during the following periods of time except as specified in 00220.40(e)(2):

**Single Lane Closures** – One Traffic Lane in Northbound direction on SE McLoughlin Blvd (Highway OR99E) may be closed during the following times:

• Nightly, Monday night through Friday morning, between 6:00 p.m. and 6:00 a.m.

One Traffic Lane may be closed on all other adjacent Roadways within the Project Site not listed above, when allowed, shown, or directed during the following periods of time except as specified in 00220.40(e)(2):

- Daily, Monday through Saturday, between 8:00 a.m. and 8:00 p.m. Lane closures within 250 feet of SE McLoughlin Blvd. (OR99E) and 250 feet of SE Oatfield Rd. may only be between the hours of 9:00 a.m. and 3:00 p.m.
- Sunday, no work allowed.
- No Night work allowed.

Add the following subsection:

#### **00220.40(f)** Limited Duration Road Closures – See the following items:

• The Contractor will be permitted to close all Traffic Lanes to through traffic on Jennings Ave between OR99E (McLoughlin Blvd) and Addie Street one time for up to four consecutive weeks for completion of roadway widening and sidewalk work in

that area. The road closure will not be allowed until the area and the detour route are signed according to the TCP and the requirements of the Special Provisions. Contractor shall maintain access to property driveways at all times.

• The Contractor will be permitted to close all Traffic Lanes to through traffic on Jennings Ave between Colina Vista Ave and Oatfield Rd one time for up to four consecutive weeks for completion of roadway widening and sidewalk work in that area. The road closure will not be allowed until the area and the detour route are signed according to the TCP and the requirements of the Special Provisions. Contractor shall maintain access to property driveways at all times.

These road closures shall not occur simultaneously.

#### SECTION 00221 - COMMON PROVISIONS FOR WORK ZONE TRAFFIC CONTROL

Comply with Section 00221 of the Standard Specifications modified as follows:

**00221.03 Traffic Safety and Operations** - Replace the bullet that begins "When paving operations create..." with the following bullet:

 When paving operations create an abrupt or sloped edge drop off greater than 1 inch, protect traffic by installing signing according to the "2 Lane, 2 Way Roadway Overlay Area" detail shown on the Standard Drawings. Protect longitudinal and transverse Pavement joints by placing and maintaining an asphalt concrete wedge according to 00221.07(c)(1).

**00221.07(c)(1) Paving** - Replace this subsection, except subsection number and title, with the following:

When the longitudinal joint is greater than 1 inch in height, install additional TCD according to 00221.03. Complete the placing of ACP and construction of paving joints according to 00735.48, 00735.49, 00743.45, 00744.44, 00744.45, 00745.47, and 00745.48, as applicable.

**00221.88 Measurement, Method "B"** – Under this method, no measurement of quantities will be made.

**00221.90(b) Temporary Protection and Direction of Traffic** - Delete the bullet that begins "Moving temporary barrier to and from Contractor's stockpile areas".

Replace the bullet that begins "When the Schedule of Items does not include ..." with the following bullet:

• Preparing and signing the daily "Traffic Control Inspection Report", when a TCS is not included in the Schedule of Items or when a TCS is not onsite for a work shift.

**00221.98 Payment, Method "B"** – Add the following to this section:

"This method is relevant to items in Sections 00222, 00223, 00224, 00225, 00226, 00227 and 00228."

#### **SECTION 00222 – TEMPORARY TRAFFIC CONTROL SIGNS**

Comply with Section 00222 of the Standard Specifications modified as follows:

### **00222.40(e)** Temporary Sign Placement - Add the following to the end of the bullet list:

- At least ten Calendar Days before closing the sidewalks along SE Jennings Ave, place a "SIDEWALK CLOSED, Full Time" (CW11-4) sign in advance of each future closure point. Locate the sign so it is legible from the nearest alternate pedestrian pathway facing incoming pedestrian traffic. The sign may be mounted between the panels of a Type II barricade or on a single-post TSS. Do not place the sign or sign support such that it narrows the pedestrian pathway to a width of less than 4 feet.
- Before opening the TPAR, place TPAR signing and other TCM as shown, or as directed. Maintain the "SIDEWALK CLOSED, Full Time" (CW11-4) signs while the TPAR is open to pedestrian traffic.
- At least ten Calendar Days prior to the start of work, place a "SIDEWALK OPEN" (CW11-3) sign in advance of each end of the Work Area. Locate the sign so it is legible from the nearest alternate pedestrian pathway facing incoming pedestrian traffic. The sign may be mounted between the panels of a Type II barricade, or on a single-post TSS. Do not place the sign or support such that it narrows the pedestrian pathway to a width less than 4 feet.
- Before starting work, place pedestrian-specific TCM as shown in the TCP, or as directed. Maintain "SIDEWALK OPEN" (CW11-3) signs while work is affecting the pedestrian pathway.
- Place a "PEDESTRIANS ON ROADWAY" (CW11-2) sign at the beginning of each end
  of the Work Area, facing incoming traffic as shown, or as directed.
- Install two sign flag boards, as shown on the Standard Drawings, above the following detour and road closed advance warning signs, where applicable:
  - "DETOUR AHEAD", "DETOUR XXXX FT", "DETOUR X/X MILE" (W20-2) signs.
  - "ROAD CLOSED AHEAD", "ROAD CLOSED XXXX FT", "ROAD CLOSED X/X MILE" (W20-3) signs.
- For paving operations on non-freeways, place "ABRUPT EDGE" (CW21-9) and "ROAD WORK XX MPH" (CW20-1a) signs as shown. Use an "XX" value equal to 10 mph below the current posted regulatory speed. If a speed is posted for a temporary regulatory speed reduction, that speed is the current posted regulatory speed.
- For all other moving operations that do not create an abrupt edge adjacent to traffic, omit the "ABRUPT EDGE" signs.

- When construction requires bicycles to use the Traffic Lanes, install a "Bicycle ON ROADWAY" (CW11-1) symbol sign on 1/2 mile spacing through the affected area.
   Keep the signs in place until completion of the Shoulder or bikeway final surface.
- At least seven Calendar Days before work starts, place one or more PCMS displaying the following message as shown, or as directed:

Panel 1	Panel 2
(Jennings Ave)	CONSTRUCTION
(99 to Oatfield)	(3/23 to 11/23)
CLOSURE	(Time Frame)

**00222.45(c)** Radar Speed Trailers - Add the following bullet(s) to the end of the bulleted list:

 Place a radar speed trailer app as directed by the Engineer, as shown on Standard Drawing TM880

#### SECTION 00223 - WORK ZONE TRAFFIC CONTROL LABOR AND VEHICLES

Comply with Section 00223 of the Standard Specifications modified as follows:

**00223.31(b) Traffic Control Inspection Without TCS** - Replace the bullet that begins "Prepares and signs a daily "Traffic Control Inspection Report"..." with the following bullet:

• Prepares and signs a "Traffic Control Inspection Report" (Form No. 734-2474) upon the initial installation of TCM and each working day when any modification, removal, or reinstallation of TCM are made, or as directed by the Engineer. Submit completed reports to the Engineer no later than the end of the next working day.

#### **SECTION 00224 - TEMPORARY TRAFFIC CHANNELIZING DEVICES**

Comply with Section 00224 of the Standard Specifications modified as follows:

**00224.46 Pavement Edge Delineation** - Replace the paragraph that begins "Place tubular or conical markers..." with the following paragraph:

Place tubular or conical markers to delineate the edge of Pavement immediately after construction Work or paving operations create an abrupt or sloped edge drop-off greater than 1 inch in height along the right hand or left hand Shoulder.

#### **SECTION 00225 - TEMPORARY PAVEMENT MARKINGS**

Comply with Section 00225 of the Standard Specifications modified as follows:

**00225.40 Temporary Pavement Markers** - Replace the paragraph that begins "Unless otherwise shown..." and the three bullets with the following paragraphs and bullets:

Install temporary flexible overlay pavement markers for temporary centerline marking as follows:

- Place and maintain one temporary flexible overlay pavement marker on 40 foot spacing in tangent and curve sections except as below.
- Place and maintain one temporary flexible overlay pavement marker on 20 foot spacing in curved alignment sections identified by a speed rider displaying less than the posted speed and channelization areas.

Establish alignment for placing the temporary flexible overlay pavement markers as follows:

- Control markers at:
  - 200 foot intervals on tangents
  - 50 foot intervals on curves
  - 40 foot intervals on curves with speed rider
- Use string line or other appropriate means to maintain proper alignment of the markers. Adjust placement to avoid straddling a longitudinal joint, while maintaining a suitable alignment of markers.
- Remove and replace misaligned markers at no additional cost to the Agency.

### **SECTION 00228 - TEMPORARY PEDESTRIAN AND BICYCLIST ROUTING**

Comply with Section 00228 of the Standard Specifications modified as follows:

**00228.00 Scope** - Replace this subsection, except subsection number and title, with the following:

In addition to the requirements of Section 00221, this Work consists of furnishing, installing, operating, maintaining, inspecting, and removing temporary devices for accommodating pedestrians and bicyclists through a work zone.

**00228.13 Temporary Curb Ramps** - Add the following sentence to the end of this subsection:

Furnish truncated dome detectable warning surface for temporary curb ramps from the QPL according to 00759.12.

**00228.43 Temporary Curb Ramps** - Add the following paragraph to the end of this subsection:

Install a minimum 2 foot wide truncated dome detectable warning surface on temporary curb ramps at pedestrian street crossings. Omit truncated dome detectable warning surfaces on temporary curb ramps that are not at a pedestrian street crossing.

#### **SECTION 00245 - TEMPORARY WATER MANAGEMENT**

Section 00245, which is not a Standard Specification, is included in this Project by Special Provision.

#### Description

**00245.00 Scope** - This Work consists of furnishing, installing, operating, maintaining, and removing temporary water management facilities in regulated Work areas.

#### 00245.01 Abbreviations:

**TWM** - Temporary Water Management

**TWMF** - Temporary Water Management Facility at Boardman Creek

**TWMP** - Temporary Water Management Plan

#### 00245.02 Definitions:

**Temporary Water Management Facility** - A TWMF that conveys water around or through Work areas, removes water from Work areas, and treats and discharges water at locations outside Work areas.

**00245.03 Temporary Water Management Plan** - 28 Calendar Days before beginning Work in regulated Work areas, submit stamped Working Drawings of a Contractor-developed TWMP, according to 00150.35, based on either the Agency's concept plan or an independent plan that meets water quality and environmental guideline requirements and does not negatively affect neighboring properties or water rights.

Include the following minimum information in the TWMP:

- The sequence and schedule for dewatering and re-watering. This sequence and schedule must include when to contact the Engineer prior to dewatering and rewatering.
- How the Work area is isolated from the active stream flow upstream, through, and downstream.
- How the stream flow is routed and conveyed around or through the isolated Work area.
- How fish passage is provided around the Work area, if required.
- · How the isolated Work area is de-watered.
- How the pumped water is treated, if necessary, before it is discharged downstream.
- Description of all construction stages, including appropriate contact points for each stage.

- A list of on-site backup Materials and Equipment.
- Provide the name of the TWM Subcontractor (if applicable) and Contractor's superintendent, and their 24-hour contact phone number 10 Days before the pre-Work meeting. If changes in the appointment of the TWM Subcontractor or Contractor's superintendent occur during the term of the Contract, provide written notice to the Engineer within 5 Calendar Days of the change.
- Calculations of water withdraw pump's capacity.
- Details of the proposed water intake screen used to isolate in-water Work area and how it meets the requirements of 00290.34(c)(3).

Any change to the TWMP during construction requires approval prior to implementation.

Obtain the Engineer's written approval before beginning Work in in-water Work areas.

**00245.04 Pre-Work Meeting** - Before beginning any TWM Work, attend a pre-work meeting at the Project Site with the Engineer no more than 8 Calendar Days prior to implementation of TWM. Required meeting attendees include:

- Engineer
- Contractor
- TWM Subcontractor (if applicable)
- Agency Environmental Coordinator or their appointed representative

The pre-Work meeting agenda typically includes the method of TWM, the TWMP, fish salvage plan and strategy, describe environmental risks, turbidity monitoring, energy dissipation, dewatering and re-watering plan and strategy, site clean-up expectations, and the circumstances under which contacting the Engineer is required.

#### **Materials**

**00245.10 Materials** - Furnish Materials meeting the following requirements:

Pipe	00445.11
Plastic Sheeting	00280.14(a)
Riprap	
Sandbags	00280.15(a)
Water Intake Screening	00290.34(c)

#### Furnish pumps that are:

- Self-priming.
- Equipped with a variable speed governor.
- Equipped with a power source.
- Able to pump water that contains soft and hard solid.

#### Construction

**00245.40 Fish Removal** - Remove fish and other aquatic organisms from the isolation Work areas. Coordinate fish removal with the Engineer at least 28 Calendar Days before beginning Work in regulated Work areas. Furnish a Scientific Take Permit from the Oregon Department of Fish an Wildlife before beginning work. Allow access into the isolation Work areas before, during and after installation of the TWMF to perform the specified tasks as follows:

- Before Installation of TWMF Before any in-water Work, including installing TWMF, qualified personnel will remove fish and other native aquatic organisms from within the proposed isolated Work area.
- After Installation of TWMF After installing TWMF and the reduction of the water level
  through the isolated Work area has begun, qualified personnel will remove all fish and
  aquatic organisms as the water level is reduced. Do not completely de-water the
  isolation area until all fish and aquatic organisms have been removed.

**00245.41 Installation** - During installation of the temporary water management facility, maintain a downstream water flow rate of at least 50 percent of the upstream water flow rate.

**00245.42 Operation** - Operate temporary water management as follows:

- Protect fish and fish habitat according to 00290.34.
- Maintain and control water flow downstream of the isolated Work area for the duration of the diversion to prevent downstream de-watering.
- Clean, maintain and repair water intake screening to ensure adequate flows and protection of aquatic organisms.
- In the event of containment failure immediately notify the Engineer so arrangements can be made to remove fish and aquatic organisms from the isolation Work areas prior to the continuation of Work within the ordinary high water limits.
- When using a pump for bypassing water during temporary water management, physically monitor the pump in-person and maintain the pump at all times including non-work hours. Provide a back-up pump on-site and ready for use as necessary. Provide the Engineer with a daily report documenting monitoring activities.

#### **Maintenance**

**00245.60 Maintenance** - Monitor water turbidity according to 00290.30(a)(8).

### Finishing and Cleaning Up

**00245.70** Removal - Prior to removal of the TWMF, obtain approval from the Engineer after completion of all Work within ordinary high water limits. Remove the TWMF and re-water and restore the stream flow. Maintain downstream water flow during removal of the facility. Staged or metered re-watering may be required and will be determined by the Engineer.

#### Measurement

**00245.80 Measurement** - No measurement of quantities will be made for temporary water management facilities.

The estimated quantities of Materials required for the temporary water management facility are:

Temporary Water Management Facility at Boardman Creek:

Pipe	500 Feet
Plastic Sheeting	15 Square Yard
Pumped Treatment Sediment Bag	1 Each
Riprap	
Sandbags	

Turbidity monitoring will be measured according to 00290.80.

### **Payment**

**00245.90 Payment** - The accepted quantities of temporary water management facilities will be paid for at the Contract lump sum amount for the item "Temporary Water Management Facility at Boardman Creek".

The location of the facility will be inserted in the blank.

Payment will be payment in full for furnishing and placing all Materials, and for furnishing all Equipment, labor, and Incidentals necessary to complete the Work as specified.

Turbidity monitoring will be paid for according to 00290.90.

No separate or additional payment will be made for TWMP, maintaining, operating, monitoring, moving, or removing the facility.

#### **SECTION 00270 - TEMPORARY FENCES**

Comply with Section 00270 of the Standard Specifications modified as follows:

**00270.00 Scope** – Add the following paragraph to the end of this subsection:

Provide temporary fencing and gates at the following locations:

File No.	Fence	Fence	Gate*	Notes*
	Туре	Length		
		(ft)*		
2 Western Investment Co.	Chain Link	140		Retaining Wall
3 Gettle	Chain Link	320		Retaining Wall
5 Payne	Chain Link	70		Secure
6 Payne	Chain Link	180	1	Secure
14 McKenzie	Chain Link	120		Secure
17 Tomaszewski	Chain Link	140	1	Secure
18 Sadowski	Chain Link	140		Secure
25 Congdon	Chain Link	240	2	Secure

26 Gaitan & Torres	Chain Link	120		Secure
27 Marl	Chain Link	90		Secure
28 Leppert	Chain Link	75		Secure
37 State	Chain Link	90		Retaining Wall
38 Adler & Rackerby	Chain Link	240		Retaining Wall
44 Noble	Chain Link	500		Retaining Wall
46 French	Chain Link	120		Secure
47 Mountain Ridge Homes	Chain Link	115		Retaining Wall
54 Wood	Chain Link	80		Secure
55 Tiliano	Chain Link	50		Secure
62 (tbd)	Chain Link	90		Retaining Wall
72 Nielson	Chain Link	50		Retaining Wall
74 PGE	Chain Link	130	1	Secure

<sup>\*</sup>Note: Fence length includes gate dimension. Gates shall span 12 feet width of the exiting driveway width, whichever is smaller. Secure fencing intends to convey requirement to enclose property so that children and pets remain bound to the parcel.

#### **Materials**

**00270.10 Material** – Add the following sentence at the end of the first sentence:

Provide temporary barrier if the existing guardrail along the frontage of File 44 is removed before completing retaining wall and new guardrail construction.

Add the following paragraph to the end of this subsection:

Provide Type 2 fence rectangular woven wire fabric and metal line posts as shown in Oregon Standard Drawing RD810. Modify the standard drawing as follows:

- Do not provide barbed wire as shown in this drawing.
- Provide 1-inch square opening maximum wire mesh, with an overall minimum height of 48-inches.
- Modify distance P as necessary adjust the fence alignment for tree protection and to avoid impacting landscaping features.
- Only provide line posts as shown for fencing. End, corner and intermediate end posts are not required.
- Provide gate posts sufficient to support gates as required for successful operation.

Provide temporary gates as shown in Oregon Standard Drawing RD820.

#### Construction

**00270.40 Construction** – Add the following paragraph to the end of this subsection;

Comply with the Right of Way obligation requirements furnished by the Agency for temporary fencing.

Furnish and distribute initial property notification letters to each affected property owner at least 30 calendar days preceding existing fence removal.

- 30 day notifications shall be by both certified mail and hand delivered or "door hanger".
- 30 day Notification shall note to the property owner they may remove the existing fencing within this time frame.

Furnish and distribute a subsequent property notification letter to each affected property owner at least 5 calendar days preceding existing fence removal.

Furnish and distribute a third property notification letter within 90 calendar days of completing construction to notify owners of temporary fence removal.

Obtain Agency approval for all information and content within each property owner notification letter before distribution.

When removing existing fence within a secure yard, install temporary fence within the same working day as the removal.

Field verify fence alignment, line post locations, and width of temporary gates before furnishing material. Replace

#### **SECTION 00280 - EROSION AND SEDIMENT CONTROL**

Comply with Section 00280 of the Standard Specifications modified as follows:

**00280.00 Scope** - Replace the paragraph that begins "This Work also consists of providing temporary ..." with the following paragraph:

This Work also consists of providing temporary erosion and sediment control (ESC) measures and furnishing, installing, moving, operating, maintaining, inspecting, and removing ESC throughout the Project area according to the Standard Drawings, the erosion and sediment control plan (ESCP) with an environmental management plan (EMP), when required for the Project, the Specifications, or as directed, until the site is permanently stabilized. Included also is the monitoring of weather, of stormwater and receiving waters, the reporting of monitoring observations, the reporting of corrective actions (when necessary) and the updates and revisions of the ESCP, including ESCP cover sheet, necessary to keep it representative of current site conditions and compliant with the 1200-CA Permit.

Add the following paragraph to the end of this subsection:

The Agency's NPDES 1200-CA Permit is applicable to the Project (effective date 9/15/2022).

**00280.02 Definitions -** Replace the sentence that begins "Temporary Stabilization" with the following sentence:

**Temporary Stabilization** - Measures or methods necessary to prevent erosion until permanent stabilization measures are in place and established.

**00280.04 Erosion and Sediment Control Plan on Agency Controlled Lands -** Replace the bullets with the following bullets:

- When using the Agency's ESCP with only modifications required to keep the ESCP current during construction, submit a written notification indicating the Agency's ESCP is used without modifications prior to construction.
  - Prior to beginning construction, edit the ESCP to provide a list of all contractors working on the site.
  - Prior to beginning construction, edit the ESCP cover sheet to list all personnel by name and position who are responsible for the installation and maintenance of stormwater control measures including their individual responsibilities and certifications. Keep list current for the duration of the project.
- When using a Contractor modified version of the Agency's ESCP, include the following:
  - Proposed ESCP showing all ESC Work, and quantities of Work.
  - An EMP that addresses pollution prevention and control of potentially contaminated sites or Materials.
  - Implementation schedules for the ESCP
  - Plans for each phase of Contractor's Work
  - Names and positions of all personnel engaged in construction activities.
  - Names and positions of all personnel responsible for the installation and maintenance of stormwater control measures.
  - Information required under 1200-CA permit.
- When using a Contractor developed ESCP, develop and stamp the ESCP by a professional with one of the following credentials. Include their name and credentials in the ESCP. The ESCP preparer shall be one of the following:
  - · Oregon Registered Professional Engineer,
  - · Oregon Registered Landscape Architect; or
  - Oregon Certified Engineering Geologist
- When using a Contractor developed ESCP where engineered facilities such as sedimentation basins or diversion structures for erosion and sediment control are required, prepare and stamp the ESCP by one of the following:
  - Oregon Registered Professional Engineer; or
  - Oregon Registered Landscape Architect.
- When using a Contractor developed ESCP, provide plans for each phase of Contractor's work implementation schedule and information required under the 1200-CA permit and as directed in ODOT's Erosion Control Manual.

**00280.15(d) Temporary Slope Drains –** Replace this subsection, except subsection number and title, with the following:

Furnish either plastic pipe and flared end sections meeting the requirements of Section 02415 or metal pipe and flared end sections meeting the requirements of Section 02420.

**00280.16(a)** Construction Entrances - Add the following bullets to the end of the bullet list:

- **Prefabricated Construction Entrance**: Furnish reusable prefabricated construction entrance mats (track out mats) with the following characteristics:
  - Track out mats consisting of irregular driving surface provided by ridges, knobs or pyramidal extensions (protrusions) not less than 2 1/2 inches height that collects dislodged material off Equipment tires and surface below protrusions.
  - Modular and designed to be fixed together into widths and lengths as needed and anchored in place.
  - High visibility coloration
  - Chemical and UV resistant
  - Crush strength not less than 20,000 pounds

**00280.16(i)** Concrete Washout – Replace this subsection, except subsection number and title, with the following:

Furnish impermeable, spill resistant, leak proof concrete washout basin of sufficient size and quantity to retain all concrete wash water and concrete waste developed during construction, meeting the following requirements:

- (1) Field fabricated washout basin as shown and consisting of the following:
  - **Straw Bales** Standard rectangular straw bales, with straw Material according to 01030.15, except no certification is required.
  - Plastic Sheeting Minimum 10-mil thick polyethylene plastic sheeting.
  - **Staples** 1/8-inch diameter steel wire staples. 2-inch "U" width with a length of 6 inches minimum
- **(2)** Manufactured basins sufficiently durable to be removed intact, or cleaned of content without releasing concrete material or concrete washout water.

**00280.30 Erosion and Sediment Control Manager** - Replace this subsection, except for the subsection number and title, with the following:

Prepare or otherwise furnish all submittal requirements required by the Agency's 1200-CA permit, which is available from the Engineer. Contractor is responsible to confirm 1200-CA submittal requirements during preparation of bids.

If the Agency's NPDES 1200-CA Permit is applicable to the Project, designate and provide an ESCM who possesses a valid ODOT ESCM certificate or who has successfully completed an erosion control training that is acceptable to the Engineer.

The ESCM duties include:

- Manage and ensure proper implementation of the ESCP.
- Accompany the Engineer during field review of the ESCP prior to construction activities.
- Monitor rainfall, snow melt and runoff on and in the vicinity of the Project Site.
- Monitor water quality in receiving streams in the vicinity of the Project Site.
- Monitor water in sediment traps receiving runoff from soils amended with cementitious material for acidity or alkalinity.
- Monitor locations identified in Section 00294 for compliance.

- Inspect ESC and monitor receiving waters on active construction site on initial date and every 14 Days for effective functioning.
- Inspect ESC on inactive sites every 14 Days for effective functioning.
- Inspect ESC for effective functioning and monitor receiving waters, on all active and inactive sites at least within 24 hours of rainfall events sufficient to result in runoff from the Project Site.
- Ensure that ESC are regularly cleaned and maintained.
- Mobilize crews to make immediate repairs to ESC or install additional ESC during working and non-working hours when ESC is not effectively functioning.
- Record actions taken to clean up discharged sediment.
- Report potential permit violations to the Agency immediately upon discovery.
- Repair conditions that caused permit violations and prepare submittals for corrective actions that document repairs for Agency review and submittal to regulatory agencies.
- Update the ESCP monthly and within 7 Days after changes or major ESC modifications are implemented in the field.
- Submit ESCP revisions in electronic format, to Engineer within 30 Days after making revisions.
- Prepare a contingency plan in preparation for emergencies and for the periods between October 1 and May 31.
- Accompany the Engineer on inspections and, if required, on inspections by representatives of regulating agencies. If any of the following occur, revise the ESCP to reflect the change(s) within 7 Days.
  - Changes to the construction plans that impact erosion and sediment control measures;
  - Changes to the stormwater control BMPs, their location, maintenance required, and any other revisions necessary to prevent erosion and control sediment runoff:
  - An increase in the area impacted by construction activities;
  - Other activities at the site that are no longer accurately reflected in the ESCP. This includes changes made in response to corrective actions triggered;
  - To reflect areas on the site map where operational control has been transferred (and the date of transfer) since initiating permit coverage;
  - If inspections by DEQ determine that ESCP revisions are necessary for compliance with the 1200-CA permit;
  - Where DEQ determines it is necessary to install or implement additional controls at the site in order to meet the requirements of the 1200-CA permit. Include the following in the ESCP:
    - A copy of any correspondence describing such measures and requirements; and
    - A description of the controls to be used to meet such requirements.
- Change of Subcontractors that engage in construction activities on site, and the areas of the site where the Subcontractor(s) engage in construction activities;
- Change of any personnel (by name and position) that are responsible for the design, installation and maintenance of stormwater control measures;
- Change of the certified erosion and sediment control inspector, or of their contact information and any applicable certification and training experience;
- To reflect any revisions to applicable federal, state, tribal, or local requirements that affect the stormwater controls implemented at the site; and
- If a change in chemical treatment systems or chemically enhanced stormwater control is made, including use of a different treatment chemical, different dosage

rate, or different area of application as applicable. Furnish temporary sediment trap as shown on drawings, stamped and signed by licensed engineer.

Submit revised ESCP to Engineer for signature by licensed professional (see 00280.04) and submission to DEQ when changes are made for the following reasons:

- Part of a corrective action requirement;
- · An increase or decrease in project size;
- An increase or decrease in size or location of disturbed areas;
- Changes to BMPs, such as type, design or location;
- Change of the ESCM.

**00280.41(e) Buffers –** This Section is added after Section 00280.41(d) Disturbance Restrictions.

Retain and preserve buffer zones of natural, undisturbed vegetation, 50 feet in width between Work and Waters of the State. Where 50 foot buffers are not attainable, provide erosion, runoff and sediment control BMPs with effectiveness equivalent to a 50 foot buffer. Identify and mark buffer zones with flagging, construction fencing or other readily identifiable means.

**00280.46(a)** Construction Entrances - Add the following to the end of this subsection:

Construct the construction entrances as shown or directed.

**00280.46(h) Temporary Sediment Trap -** Add the following paragraph to the end of this subsection:

Where location of Temporary Sediment Trap is used post-construction for water quality treatment, storage or infiltration, remove sediment and soil to a depth of 18" and replace to finish grade with material approved by engineer.

**00280.46(i) Concrete Washout -** Add the following paragraph to the end of this subsection:

Locate concrete wash basins and concrete waste disposal to prevent stormwater that has been in contact with concrete wash or waste concrete from contaminating Waters of the State or stormwater inlets or conveyances. Handle wash water as waste. Do not dispose of concrete wash water or wash out concrete trucks or tools onto the ground, or into storm drains, open ditches, streets, or streams.

**00280.48 Emergency Materials** - Add the following paragraphs after the paragraph that begins "Provide, stockpile, and protect...":

Provide and stockpile the following emergency materials on the Project site:

item	Quantity
Inlet Projection, Type 3	10 Each
Sediment Barrier, Type 3	
Certified Weed-Free Straw Bales	20 Each

i lactic Chocking	Plastic Sheeting	200	Square	Yards
-------------------	------------------	-----	--------	-------

#### **SECTION 00290 - ENVIRONMENTAL PROTECTION**

Comply with Section 00290 of the Standard Specifications modified as follows:

**00290.20(c)(2) Clean Fill** - Add the following paragraph to the end of this subsection:

Manage all excavated soil that does not meet the definition of clean fill according to Section 00294.

Add the following subsection:

### 00290.30(a)(7) Water Quality:

- Do not discharge contaminated or sediment-laden water, including drilling fluids and waste, or water contained within a work area isolation, directly into any waters of the State or U.S. until it has been satisfactorily treated (using a best management practice such as a filter, settlement pond, bio-bag, dirt-bag, or pumping to a vegetated upland location).
- Do not use permanent stormwater quality treatment facilities to treat construction runoff unless prescribed by an ESCP approved under Section 00280.
- If construction discharge water is released using an outfall or diffuser port, do not exceed velocities more than 4 feet per second, and do not exceed an aperture size of 1 inch.
- Do not use explosives under water.
- Implement containment measures adequate to prevent pollutants or construction and demolition materials, such as waste spoils, fuel or petroleum products, concrete cure water, silt, welding slag and grindings, concrete saw cutting by-products and sandblasting abrasives, from entering waters of the State or U.S.
- Implement containment measures adequate to prevent flowing stream water from coming into contact with concrete or grout within the first 24 hours after placement.
- Do not end-dump riprap into the waters of the State or U.S. Place riprap from above the ordinary high water line.
- Cease Project operations under high flow conditions that may result in inundation of the Project area, except for efforts to avoid or minimize resource damage.
- The Engineer retains the authority to temporarily halt or modify the Work in case of excessive turbidity or damage to natural resources.
- If Work activities violate permit conditions or any requirement of this subsection, stop all in-water work activities and notify the Engineer.

Add the following subsection:

**00290.30(a)(8) Meter Turbidity Monitoring** - In addition to any turbidity monitoring required by 00280.62(c) to comply with NPDES 1200 series requirements, monitor turbidity using a turbidity meter every two hours during in-water work according to the following:

- Use a turbidity meter that has been maintained and calibrated according to the manufacturer's specifications.
- Measure stream turbidity before beginning each day's in-water work to establish preconstruction turbidity levels.
- Measure upcurrent and downcurrent turbidity at two-hour intervals during in-water work and perform work based on turbidity measurements according to the following:
  - Take upcurrent samples at a location representative of background turbidity approximately 100 feet from the in-water work area.
  - Take downcurrent samples at a location approximately 100 feet from the in-water work area at approximately mid-depth of the water body and within any visible turbidity plume.
  - If the downcurrent reading is less than 5 nephelometric turbidity units (NTU) higher than the upcurrent reading, continue to work and take readings every two hours.
  - If the downcurrent reading is greater than or equal to 5 and less than 30 NTU higher than the upcurrent reading, modify work procedures and repair or implement best management practices (BMP), continue work, and continue to take readings every two hours. If after four hours the downcurrent reading is still greater than or equal to 5 NTU higher than the upcurrent reading, stop all in-water work and repair or implement additional BMP. Resume in-water work activities only after the downcurrent reading is less than 5 NTU above the upcurrent reading.
  - If the downcurrent reading is greater than or equal to 30 and less than 50 NTU higher than the upcurrent reading, modify work procedures, repair or implement BMP and continue work. If, at the subsequent two-hour reading, the downcurrent reading is still more than 30 NTU higher than the upcurrent reading, stop all in-water work and repair or implement additional BMP. Resume in-water work activities only after the downcurrent reading is less than 5 NTU above the upcurrent NTU reading.
  - If the downcurrent reading is 50 NTU or more higher than the upcurrent reading, stop all in-water work, repair or implement additional BMP, and inform the Agency. Resume in-water work activities only after the downcurrent reading is less than 5 NTU above the upcurrent NTU, as determined by continued readings made at least every two hours, or the next day's initial turbidity reading.
  - Document all turbidity monitoring observations on form 734-2755, "Turbidity Monitoring Report", or another form approved by the Agency. Submit reports to the Engineer weekly during in-water work and keep copies of the reports at the Project Site.

#### **00290.32 Noise Control** – Change the first bullet to:

Do not operate equipment or perform construction activities within 1,000 feet of an occupied dwelling on Sundays or legal holidays, or between the hours of 9:00 p.m. and 7:00 a.m. on other days, without the approval of the Engineer.

#### 00290.34(a) Regulated Work Areas - Add the following to the end of this subsection:

The regulated work area is the area at or below the ordinary high water (OHW) elevation shown on the plans. Additional 'No Work Zones' are indicated on the erosion control plans.

Perform work within the regulated work area only during the in-water work period. The in-water work period is from July 1 to September 30.

The total volume of material filled or discharged into waters of the State and waters of the U.S. shall not exceed 27 cubic yards.

The total volume of material excavated from the waters of the State and waters of the U.S. shall not exceed 164 cubic yards.

Submit a schedule to complete all work within the regulated work area within the in-water work period at least 10 days prior to the preconstruction conference.

Add the following subsection:

## 00290.34(c) Aquatic Species Protection Measures Required by Environmental Permits:

### (1) General Requirements:

- Do not install fish ladders (for example: pool and weirs, vertical slots, fishways) or fish trapping systems.
- Do not apply surface fertilizer within 50 feet of any stream channel.

Use heavy equipment as follows:

- Choice of equipment must have the least adverse effects on the environment (for example: minimally sized, low ground pressure).
- Secure absorbent material around all stationary power equipment (for example: generators, cranes, drilling equipment) operated within 150 feet of wetlands, waters of the State, waters of the U.S., drainage ditches, or water quality facilities to prevent leaks, unless suitable containment is provided to prevent spills from entering waters of the State or waters of the U.S.
- Do not cross directly through a stream for construction access, unless shown or approved. If shown or approved, cross perpendicular to the stream and do not block stream flow. When a crossing is no longer needed, completely remove the crossing and restore the soils and vegetation to the original condition.
- Store fuel and maintain all equipment in staging areas that are at least 150 feet away
  from any waters of the State, waters of the U.S., or storm inlet or on an impervious
  surface that is isolated from any waters of the State, waters of the U.S., or storm
  inlet.
- If temporary access roads are needed within 150 feet of any body of water, use existing routes unless new routes are shown or approved.
- Before beginning work on temporary access routes that are not shown, submit a proposal to the Engineer for approval.
- **(2) Work Area Isolation** Provide work isolation according to Section 00245. Provide safe passage around or through the isolated work area for adult and juvenile migratory fish unless passage did not previously exist.

- (3) Water Intake Screening Install, operate, and maintain fish screens on each water intake used for project construction, including pumps used to isolate an in-water work area. When drawing or pumping water from any stream, protect fish by equipping intakes with screens having a minimum 27 percent open area and meeting the following requirements:
  - Perforated plate openings shall be 3/32 inch or smaller.
  - Mesh or woven wire screen openings shall be 3/32 inch or smaller in the narrowest direction.
  - Profile bar screen or wedge wire openings shall be 1/16 inch or smaller in the narrow direction.

Choose size and position of screens to meet the following criteria in Table 00290-1:

Table 00290-1

Туре	Approach Velocity <sup>1</sup> (Ft./Sec.)	Sweeping Velocity <sup>2</sup> (Ft./Sec.)	Wetted Area of Screen (Sq. Ft.)	Comments
Ditch Screen	≤ 0.4	Shall exceed approach velocity	Divide max. water flow rate (cfs) by 0.4 fps	If screen is longer than 4 feet, angle 45° or less to stream flow
Screen with proven self-cleaning system	≤ 0.4	_	Divide max. water flow rate (cfs) by 0.4 fps	-
Screen with no cleaning system other than manual	≤ 0.2	_	Divide max. water flow rate (cfs) by 0.2 fps	Pump rate 1 cfs or less

<sup>&</sup>lt;sup>1</sup> Velocity perpendicular to screen face at a distance of approximately 3 inches

Provide ditch screens with a bypass system to transport fish safely and rapidly back to the stream.

- **(4) Special Aquatic Habitats** The following exploration or construction activities are not allowed in special aquatic habitats:
  - Use of pesticides and herbicides, unless allowed according to Section 01030.
  - Use of short pieces of plastic ribbon to determine flow patterns.
  - Temporary roads or drilling pads built on steep slopes, where grade, soil type, or other features suggest a likelihood of excessive erosion or slope failure.
  - Exploratory drilling in estuaries that cannot be conducted from a work barge, or an existing bridge, dock, or wharf.
  - Installation of a fish screen on any permanent water diversion or intake that is not already screened.

<sup>&</sup>lt;sup>2</sup> Velocity parallel to screen

- Drilling or sampling in an EPA-designated Superfund Site, a state-designated cleanup area, or the likely impact zone of a significant contaminant source, as identified by historical information, U. S. Army Corps of Engineers representative, or the Agency.
- **(5) Site Restoration** Restore damaged streambanks to a natural slope, pattern, and profile suitable for establishment of permanent woody vegetation unless precluded by pre-project conditions (for example: natural rock substrate):
  - Replant all damaged streambanks before the first April 15 following construction.
  - If use of large wood, native topsoil, or native channel material is required for the site restoration according to the roadside development plans, stockpile all large wood, native vegetation, weed-free topsoil, and native channel material displaced by construction. Cut trees or large wood and trees into pieces of no less than 20 feet in length, or as shown on the roadside development plans or as directed. Stockpiled native wood and vegetation remain the property of the Agency.
  - Stabilize all disturbed soils, including obliteration of temporary access roads, following any break in work unless construction will resume in 4 Calendar Days.
- **(6) Surface Water Diversions** Surface water may be diverted to meet construction needs other than work area isolation, consistent with Oregon law, only if water from sources that are already developed, such as municipal supplies, small ponds, reservoirs, or tank trucks, is unavailable or inadequate, and meeting the following conditions:
  - When alternative surface sources are available, divert from the stream with the greatest flow.
  - Install, operate, and maintain a temporary fish screen.
  - Do not exceed a pumping rate and volume of 10 percent of the available flow. For streams with less than 5 cubic feet per second, do not exceed drafting of 18,000 gallons per day. Do not use more than one pump for each site.
- **(7) Hydro-Acoustic** Unless otherwise shown or approved, steel piling may be installed below the ordinary high water as follows:
  - Minimize the number and diameter of pilings, as feasible.
  - Repairs, upgrades, and replacement of existing pilings consistent with these conditions are allowed. In addition, up to 5 single pilings or 1 dolphin consisting of 3 to 5 pilings may be added to an existing facility.
  - Whenever feasible, use vibratory hammer for piling installation. Otherwise, use the smallest drop or impact hammer necessary to complete the job, and set the drop height to the minimum necessary to drive the piling.
  - For all pile installed or removed, maintain a pile installation and removal log and submit the log when the related work is completed. Include types, sizes, locations, installation or removal methods, and dates in the log.
  - When using an impact hammer to drive or proof steel piling within a body of water, or as directed, use one of the following sound attenuation devices to effectively dampen sound:

- Completely isolate the pile from the waters of the State and waters of the U.S. by dewatering the area around the pile according to Section 00245.
- If water velocity is 1.6 feet per second or less, surround the pile being driven with a bubble curtain that distributes small air bubbles around 100 percent of the piling perimeter for the full depth of the water column and is in accordance to the guidance in the Appendix of The ODOT-FHWA Federal Aid Highway Program Programmatic User's Guide titled NMFS and USFWS Impact Pile Driving Sound Attenuation Specifications. The FAHP User's Guide is available on the Agency's website at:

### https://www.oregon.gov/ODOT/GeoEnvironmental/Pages/Manuals.aspx

- If water velocity is greater than 1.6 feet per second, surround the piling being driven by a confined bubble curtain (for example: a bubble ring surrounded by a fabric or metal sleeve) that will distribute air bubbles around 100 percent of the piling perimeter for the full depth of the water column and is in accordance to the guidance in the Appendix of The ODOT-FHWA FAHP User's Guide titled NMFS and USFWS Impact Pile Driving Sound Attenuation Specifications.
- **(8) Drilling, Boring, or Jacking** If drilling, boring, or jacking is used, the following conditions apply:
  - Design, build, and maintain facilities to collect and treat all construction and drilling discharge water using the best available technology applicable to site conditions. Provide treatment to remove debris, nutrients, sediment, petroleum hydrocarbons, metals, and other pollutants likely to be present. An alternate to treatment is collection and proper disposal offsite.
  - Isolate drilling operations from wetted stream to prevent drilling fluids from contacting waters of the State or waters of the U.S.
  - Use casing to prevent loss of drilling fluid to the subsurface formation. Do not drill
    without a containment method to keep drilling fluids and slurry isolated.
  - If it is necessary to drill through an over-water bridge deck, use containment measures to prevent drilling debris from entering the stream channel.
  - If drilling fluid or waste is released to surface water, wetland or other sensitive environment, cease all drilling pending written approval from appropriate regulatory agencies through the Engineer to resume drilling.
  - Recover all waste and spoils if precipitation is falling or imminent. Recover, recycle, or dispose of all drilling fluids and waste to prevent entry into flowing water.
    - Recycle drilling fluids using a tank instead of drill recovery/recycling pits, whenever feasible.
    - When drilling is completed, make attempts to remove the remaining drilling fluid from the sleeve (for example: by pumping) to reduce turbidity when the sleeve is removed.
- **(9) Treated Wood** Treated wood includes any wood treated with any pesticide or wood preservatives. Do not use lumber, pilings, or other wood products that are treated or

preserved with pesticidal compounds below the ordinary high water (OHW) or as part of an in-water or over-water structure, except as described below:

- Store treated wood shipped to the Project out of contact with standing water and wet soil, and protected from precipitation.
- Visually inspect each load and piece of treated wood. Reject for use in or above aquatic environments if visible residues, bleeding of preservative, preservativesaturated sawdust, contaminated soil, or other matter is present.
- Use pre-fabrication to the extent feasible. When field fabrication is necessary, all
  cutting and drilling of treated wood, and field preservative treatment of wood
  exposed by cutting and drilling, shall occur above the OHW. Use tarps, plastic tubs,
  or similar devices to contain the bulk of any fabrication debris, and wipe off any
  excess field preservative.
- All treated wood structures, including pilings, shall have design features to avoid or minimize impacts and abrasion by livestock, pedestrians, vehicles, vessels, and floats.
- Treated wood may be used to construct a bridge, over-water structure or an in-water structure, with the exception of the work containment system, provided that all surfaces exposed to leaching by precipitation, overtopping waves, or submersion are coated with a water-proof seal or barrier are maintained. Apply and contain coatings and paint-on field treatment to prevent contamination. Surfaces that are not exposed to precipitation or wave attack, such as parts of a timber bridge completely covered by the bridge deck, are exempt from this requirement.
- During demolition of treated wood, ensure that no treated wood debris falls into the water. If treated wood debris does fall into the water, remove it immediately.
- Store removed treated wood debris in appropriate dry storage areas, at least 150 feet away from the regulated work area.
- (10) Piling Removal Remove temporary or permanent piling according to the following:
  - Dislodge the piling with a vibratory hammer, whenever feasible.
  - Once loose, place the piling onto the construction barge or other appropriate dry storage site.
  - **a. Non-Treated Piling** Use the following methods to remove non-creosote piling:
    - Fill holes left by each pile with clean, native sediments whenever feasible.
    - Do not excavate to remove piling.
  - **b. Treated Piling** To minimize toxic release, sediment disturbance, and total suspended solids, use the following methods to remove treated piling:
    - Install a floating surface boom to capture floating surface debris.
    - Keep all equipment out of the water, grip piles above the waterline, and complete all work during low water and low current conditions.
    - Dislodge the piling with a vibratory hammer, whenever feasible. Do not intentionally break a pile by twisting or bending.

- Slowly lift the pile from the sediment and through the water column.
- Place the pile in a containment basin on a barge deck, pier, or shoreline without attempting to clean or remove any adhering sediment.
- Fill the hole left by each removed or partially removed pile with clean, native sediments and cap with clean, native substrates that match surrounding streambed materials immediately after removal.
- Dispose of all removed piles, floating surface debris, contaminated supplies, and sediment spilled on work surfaces at a permitted upland disposal site.
- (11) Ditch and Culvert Cleaning Complete ditch cleaning, culvert and trash rack cleaning by working from the top of bank, unless work area isolation would result in less habitat disturbance.
  - Do not work more than 20 feet upstream or downstream the culvert or trash rack.
  - Remove only the minimum amount of wood, sediment, or other natural debris necessary to maintain the facility's function, without disturbing spawning gravel or changing the configuration of the original ditch, unless the new configuration is part of the project design.
  - Place all large wood, cobbles, and gravels recovered from during culvert and trash rack cleaning downstream from the structure.
  - Complete drift removal in the following priority, as directed:
    - Pull and release whole logs or trees downstream.
    - Pull whole logs and trees and place in the riparian area, as directed.
    - Remove whole logs or trees only if roadside development plans have been developed for replacement in-kind.
    - Pull, cut only as necessary, and release logs and trees downstream.
- **(12) Floating Structures** The following types of over-water or in-water structures are not allowed:
  - boat house
  - · boat ramp made of asphalt
  - · buoy or float in an active anchorage or fleeting area
  - covered moorage
  - floating storage unit
  - houseboat
  - marine
  - pier
  - non-water related facilities (including staging areas) inside riparian management areas
  - any other over-water structure more than 6-feet wide unless otherwise approved in writing by appropriate regulatory agencies through the Engineer

The following conditions apply to over-water or in-water structures:

- Concrete boat ramps that consist of pre-cast concrete slabs below the ordinary high
  water elevation, and higher elevation portions that are completed in the dry so that
  no wet concrete that has cured less than 24 hours is allowed to contact any wetland
  or waters of the State or waters of the U.S.
- Rock may be used to construct a boat ramp footing, or other protection necessary to prevent scouring, down-cutting, or failure of the boat ramp, provided that the rock does not extend further than 4 feet from the edge of the ramp in any direction.
- Any replacement roof, wall, or garage door for covered moorages and boat houses
  must be made of translucent materials or skylights. In addition, each side, except
  the door, of the boat house shall have windows at least 4 feet wide installed the
  length of the boat house, subject to breaks only for structural support.
- An existing marina may be modified within the existing footprint of the moorage, or in the water more than 50 feet from the shoreline and more than 20 feet deep, except do not place structures in areas that support aquatic vegetation or areas where boat operations may damage aquatic vegetation.
- Fit all pilings, mooring buoys, and navigational aids with devices to prevent perching by piscivorous birds.
- Permanently encapsulate all synthetic flotation material to prevent breakup into small pieces and dispersal in water.
- Install small temporary floats less than 7 Calendar Days before a scheduled event, remove them 5 Days after a scheduled event is concluded, and do not leave them in place longer than 21 Calendar Days.
- Install mooring buoys and temporary floats (for example: shellfish traps) more than 300 feet from native submerged aquatic vegetation, more than 50 feet from the shoreline, and in water deeper than 20 feet deep at all times, or as necessary to ensure that gear does not ground out unnecessarily, and boats do not prop wash the bottom.
- (13) Temporary Power, Communication and Water Lines Before installing temporary power, communication, or water lines across streams or bodies of water, submit a proposed plan to the Engineer for approval. Do not begin installation before receiving approval from the Engineer. Proposed plans for installation of temporary power, communication, and water lines and stream crossings shall utilize the following design methods in the listed order of priority:
  - 1. Aerial lines, including lines hung from existing bridges.
  - **2.** Directional drilling, boring and jacking that spans the channel migration zone and any associated wetland.
  - **3.** Trenching, which is restricted to intermittent streams and may only be used when the stream is naturally dry. For all sections of trenches below the ordinary high water line, backfill with native material and cap with clean gravel suitable for fish use in the project area.

Align each crossing as perpendicular to the watercourse as possible. For drilled, bored, or jacked crossings, ensure that the line is below the total scour prism. Return any large wood displaced by trenching or plowing as nearly as possible to its original position, or otherwise arranged to restore habitat functions.

(14) Injured Fish Notification - If a dead or injured fish is found in the project area, immediately notify the Agency. If the injured fish is in a location where further injury or stress may take place, attempt to move the fish to a safer location, if one is available, near the capture site while keeping the fish in the water and reducing its stress as much as possible. Do not disturb the fish after it has been moved. If the fish is dead or dies while being captured or moved, save the fish and any tags. The Agency will notify appropriate regulatory agencies about the injured or dead fish and provide additional direction to the Contractor.

## **00290.36(a) Migratory Birds** - Add the following to the end of this subsection:

Bird management activities to comply with the Migratory Bird Treaty Act (16 U.S.C. 703 712) will be performed by Clackamas County and its permitted agents, as documented in the Clackamas County MBTA permit, Section J. Ensure that the County and its permitted agents have access to the project area, including existing work platforms, as needed to prevent migratory bird nesting. Nesting prevention may include daily bird harassment and the installation and maintenance of devices that exclude birds.

Do not disturb migratory bird nesting habitat (shrubs, trees, and structures), or clear vegetation from March 1 to September 1 of each year without prior written approval from the Engineer. Notify the Engineer, in writing, a minimum of 10 calendar days prior to starting activities that could harm nesting birds.

(1) Bird Management - Submit a migratory bird protection plan and implementation schedule for review and approval at least 10 Calendar Days before the pre-construction conference. Do not begin Work until the migratory bird protection plan and implementation schedule are approved.

The migratory bird protection plan shall include the following elements:

- (a) The name of the individual who will oversee bird management activities for the project and a summary of their qualifications. This individual must have a biology or related natural resources degree and a minimum of 2 years of work experience identifying nesting birds, preferably in the Pacific Northwest.
- **(b)** A description of measures to prevent birds from nesting on structures or vegetation at the project site, from March 1 to September 1 of each calendar year, that could result in project conflicts; include the timing, intensity and location of the activities. If exclusionary devices will be used (e.g., netting), install them prior to March 1 and remove them at the completion of the project or by September 1 each calendar year, whichever comes first. Include how exclusionary devices will be installed and document their inspection schedule. Exclusionary devices must be inspected daily to ensure their functionality. Repair damaged exclusionary devices as soon as the damage is discovered. Document inspections and maintain documentation on site.
- **(c)** A description of measures to avoid disturbing active migratory bird nests if they are encountered. The typical avoidance measure is to move project activities away from the active nest until the young have left the nest.

**00290.41 Protection of Waters of the U.S. or State** - Add the following to the end of this subsection:

Permits have been obtained for this project from the (US Army Corps of Engineers (Corps) and the Department of State Lands (DSL). Keep a copy of Corps and DSL permits at the project site during construction. Changes to the project that may increase the amount of fill placed or material removed in waters of the U.S. or State, or the acreage of waters impacted are not authorized. The following waters of the U.S. or State are present and have been determined to be unavoidable as indicated in Table 00290-2:

#### Table 00290-2

Impact Waters of the US or State	Removal Volume (cu yds.)	Fill Volume (Cu	Station	Duration of Impact (Temporary	Area of impact (Acres)
		yds)		or Permanent)	
Boardman Creek	164	27	Approximately 23+00	Permanent	0.1

The accepted quantities of turbidity monitoring will be paid for at the Contract lump sum amount for the item "Turbidity Monitoring".

Payment for turbidity monitoring will be payment in full for furnishing and placing all Materials and for furnishing all Equipment, labor, and Incidentals necessary to complete the Work as specified.

## **SECTION 00294 - CONTAMINATED MEDIA**

Section 00294, which is not a Standard Specification, is included in this Project by Special Provision.

## **Description**

**00294.00 Scope** - In addition to the requirements of Section 00290 and the Specifications, this Work consists of the following:

• Excavate, segregate, stockpile, transport, and dispose of Contaminated Soils and contaminated grubbing materials, as defined by 00294.01, from the following locations:

## **Contaminated Soil Location Table 00294-1**

From Deptil Location/Station to Location/Station (feet)	Annrovimate	Known Contaminants
---	-------------	--------------------

12+00 to 50+24, Rt and Lt	0 – 1.5 feet	1,267	Non-point roadway runoff of petroleum hydrocarbons and metals in shoulder soils
12+00 to 13+50 LT	0 – 5 feet	1	Residual petroleum impact
41+75 Lt	0 – 5 feet	1	Creosote-treated retaining walls
0+00 to 3+30, File 61	0 – 5 feet	26	Metals
Approximate 1	Total Quantity	1,295	су
Quantity to be reus	sed on Project	828	су
Quantity to be dispo	sed at landfill	850	tons

The reuse quantity listed in Table 00294-1 includes both pipe trench backfill and wall backfill. Reuse quantities were estimated as follows:

•	Wall backfill File 47/62	116 cubic yards
•	Wall backfill File 60	84 cubic yards
•	Wall backfill File 44A	26 cubic yards
•	Wall backfill File 44B	435 cubic yards
•	Pipe removal backfill	167 cubic yards

- In areas where excavation is not required, leave contaminated Material and clearing and grubbing Material in place.
- Pump, test, treat, and dispose of contaminated groundwater from the following locations in Table 00294-2:

Table 00294-2

Location/Station	Depth below grade (feet)	Known Contaminants	
0+00 to 3+30, File 61	0 – 5 feet	Metals	

 Prepare a Health and Safety Plan (HASP) for work within the contaminated areas of the Project.

The Hazardous Materials Corridor Study, Jennings Avenue: OR99E to Oatfield Road, Clackamas County, Oregon (Northwest Geotech, Inc., March 18, 2020) documenting the contaminated media identified within the Project, is available from the Engineer.

The Shoulder Material Investigation, Jennings Avenue: OR99E to Oatfield Road, Clackamas County, Oregon (Northwest Geotech, Inc., July 8, 2020) documenting the contaminated media identified within the Project, is available from the Engineer.

The Site-Specific Preliminary Site Investigation, Jennings Avenue: OR99E to Oatfield Road, Clackamas County, Oregon (Northwest Geotech, Inc., November 17, 2020) documenting the contaminated media identified within the Project, is available from the Engineer.

Contractor is responsible to obtain and confirm contaminated media documentation during preparation of bids.

#### 00294.01 Definitions:

**Contaminated Soil** - Soil that does not meet the DEQ definition of "Clean Fill", as defined by OAR 340-093-0030(18). This Contaminated Soil is a regulated waste, subject to OAR 340-093-0005 through OAR 340-093-0290. If the grubbing Material has been determined to be contaminated, it will be considered and treated as Contaminated Soil for the purposes of this Section.

**Shoulder Soil** - Soil outside of the existing Highway Pavement and within Highway Right-of-Way generated during Highway maintenance or construction activities. This definition applies to excess Soil generated to a maximum depth of 1.5 feet below ground surface. This definition does not apply to Soil that is covered by existing impervious surfaces, including but not limited to curbs, sidewalks and parking lots constructed of asphalt or concrete.

**ODOT Beneficial Use Determination (ODOT BUD)** - The statewide ODOT Beneficial Use Determination (ODOT BUD), approved by DEQ (No. BUD-20181204), outlines a series of pre-approved non-residential reuse options for excess Soil Materials that do not meet DEQ's Clean Fill Standards in some circumstances. These options may vary based on project scope and location, and documentation may vary, as directed by the Engineer.

**00294.02 Testing of Contaminated Soil and Groundwater** - When additional testing of Contaminated Soil or groundwater is required or directed by the engineer, to characterize the Material for reuse, recycle, or disposal, conduct the tests according to 00290.20(c).

Use analytical methods meeting DEQ's Clean Fill Guidance Screening Levels for each analyte. Contaminated Soil and groundwater sampling must be conducted by an Oregon Registered Geologist or Professional Engineer who has experience characterizing contaminated media.

In addition to above the contractor shall:

Collect at least 3 composite Soil samples and submit for the following required testing:

- TPH-Gx and TPH-Dx by Northwest methods.
- The following volatile organic compounds (VOCs) by EPA Method 8260.
  - Benzene, toluene, ethylbenzene, xylenes.
  - Iso-propylbenzene and n-propylbenzene.
  - 1,2,4-trimethylbenzene and 1,3,5-trimethylbenzene.
  - Ethylene dibromide (EDB), ethylene dichloride (EDC), and Methyl tert-butyl ether MTBE.
- Polynuclear aromatic hydrocarbons (PAHs) by EPA Method 8270SIM.
- Total metals (RCRA 8) by EPA 6000 and 7000 series.
- One TCLP lead by using EPA Method 1311.

## **00294.03 Submittals** - Submit the following documents:

A site specific HASP at least 10 Calendar Days before the pre-construction conference.

- The site specific HASP, completed and signed by a qualified health and safety professional meeting the requirements of 00294.30.
- The name and qualifications of the qualified health and safety professional.

Submit all modifications to the HASP that are requested by the Engineer or the qualified health and safety professional within 7 Calendar Days of the request.

• Current employee training certificates and medical surveillance information before beginning Work within the contaminated areas.

Submit the following documents within 48 hours of removal of contaminated media:

- Permits, permit applications, and documentation of compliance.
- · All reuse, recycled, and disposal receipts.
- Final quantities of Soil and groundwater reused, recycled, and disposed and their final location.
- All analytical test results.
- Documentation of final disposition of any reused Soil Material that is reused under ODOT's Beneficial Use Determination.

#### Labor

**00294.30 Personnel Qualifications** - Provide employees meeting the following requirements:

- For removal of Contaminated Soil, provide employees trained in:
  - Lead awareness according to 29 CFR 1926.62(I).
  - Chromium according to 29 CFR 1926.1126(j)(2).
  - Cadmium according to 29 CFR 1926.1127(m)(4).

#### Construction

**00294.40 Contaminated Soil Excavation** - Excavate and handle Contaminated Soil from Project excavations according to the following:

- Notify the Engineer 3 Calendar Days before beginning excavation activities within contaminated areas.
- Allow the Agency to collect Soil and groundwater samples during excavation activities.
- Segregate non-Contaminated Soil from Contaminated Soil during excavation activities, based on the field screening and the provided Contaminated Soil location information.
- Load Contaminated Soil directly into trucks and transport directly to the recycling or disposal facility, or on-site reuse areas or, when approved by the Engineer, temporarily store Contaminated Soil on-site.
- Remove contaminated media from the exterior of all vehicles before they leave the Project Site

- Cover trucks transporting contaminated Materials to prevent spillage during transit to the disposal facility according to OAR 340-093-0220.
- Where over excavation is required, backfill the excavation according to 00330.42.

**00294.41 Contaminated Soil Management** - Reuse, recycle, or dispose of Contaminated Soil according to the following:

# (a) Landfill Disposal:

(Est 750-1050cy)

- Obtain the Engineer's approval of the disposal facility before disposing of the Contaminated Soil.
- Transport the Contaminated Soil to a DEQ permitted municipal solid waste landfill
  or a permitted construction and demolition landfill for disposal. Dispose of
  temporarily stored Contaminated Soils within 30 Days of beginning excavation work
  or before Second Notification, whichever occurs first.
- Complete and sign all manifests and bill-of-lading forms for handling, loading, transporting, and disposing of the Contaminated Soil.
- Pay all filing and permit fees.

## (c) Reuse On-Site:

(Estimated 500-900cy)

- Temporarily stockpile the Contaminated Soil from Table 00294-1, when approved by the Engineer.
- Reuse the Contaminated Soil on the Project between Station 34+50 and Station 45+00 as existing pipe removal trench backfill when indicated as suitable material by the Engineer.
- Reuse the Contaminated Soil on the Project as wall backfill for retaining walls on File 47/62, 60, 44A, 44B, when indicated as suitable material by the Engineer.
- Within 30 Calendar Days of completing on-site reuse or before Second Notification, whichever occurs first, transport all Contaminated Soil that is not reused on the Project to a DEQ Tier 3 Solid Waste Beneficial Determination Permit (BUD 20181204) facility, or a DEQ permitted municipal solid waste landfill, or a permitted construction and demolition landfill.

**00294.43 Contaminated Groundwater Pumping** - Remove and handle contaminated groundwater as follows:

- Allow the Agency to collect groundwater samples during pumping activities and subsequent storage.
- Remove contaminated groundwater from the Project Site or, when approved temporarily store contaminated groundwater on-site in water tight containers compatible with the contaminants. Label each container with the contents and dates of accumulation.
- Dispose of stored contaminated groundwater within 30 Days from the date of beginning generation of it or before Second Notification, whichever occurs first, according to 00294.44.

**00294.44 Contaminated Groundwater Management** - Recycle or dispose of contaminated groundwater according any of the following:

## Discharge to a Permitted Sanitary Sewer Facility:

- Submit all groundwater analytical data and proposed treatment information to the local sewer authority and obtain written permission or a permit to discharge the contaminated groundwater to the sanitary sewer system.
- Complete and sign the sewer permit application as the applicant and pay all associated fees.
- Comply with all permit requirements and all other local sewer authority requirements.

## Transport to an Off-Site Recycling or Disposal Facility:

- Submit all groundwater analytical data to the receiving facility and obtain written acceptance from that Entity.
- Complete and sign bill-of-lading forms and all other documentation required by the receiving facility.
- Pay all permit fees.

#### Measurement

**00294.80 Measurement** - Work performed under this Section will be measured according to the following:

No measurement of quantities will be made for the following:

- HASP.
- Lead compliance plan
- Segregating and stockpiling Contaminated Soil.
- Recycle/reuse of contaminated soils
- Contaminated Groundwater Management and Disposal.
- Furnishing permits.

The quantities of Contaminated Soil disposed will be measured on the weight basis, based on weigh tickets from the recycling or disposal facility.

Clearing and grubbing will be measured according to 00320.80.

## **Payment**

**00294.90 Payment** - The accepted quantities of Work performed under this Section will be paid for at the Contract unit price, per unit of measurement, for the following items:

## Pav Item

## **Unit of Measurement**

(a)	Health and Safety Plan	Lump Sum
(b)	Contaminated Soil Management	Lump Sum
(d)	Soil Sample Collection and Analytical Testing	Each
(e)	Contaminated Soil Disposal	Ton

Item (b) includes excavating, transporting, preserving, sorting, segregating, handling, and stockpiling Contaminated Soil within the Project Site for on-site reuse, or disposal.

Item (c) includes segregating, handling, and stockpiling Contaminated Soil within the Project Site for the purpose of analytical testing, on-site reuse, or disposal.

Item (d) includes mobilization, Soil sampling, testing, analyses, and preparation of reports for tests required in 00294.02. Additional testing beyond that listed in 00294.02 will only be paid if authorized by the Engineer.

Item (e) will be payment in full for removing and disposing of all Materials, and for furnishing all Equipment, transportation, labor, Plans, test results, and Incidentals necessary to complete the Work as specified. All disposal costs include the disposal of Contaminated Soil at a recycling or disposal facility.

No separate or additional payment will be made for reuse of Contaminated Soil or contaminated Shoulder Soil. Payment for reuse will be included in payment made for the appropriate items under which the excavation or reuse of Contaminated Soils or contaminated Shoulder Soil is required.

Clearing and grubbing will be paid for according to 00320.90.

Payment will be payment in full for removing and disposing of all Materials, and for furnishing all Equipment, labor, Plans, testing and test results, and Incidentals necessary to complete the Work as specified.

When the Contract Schedule of Items does not indicate payment Work required under this Section, no separate or additional payment will be made. Payment will be included in payment made for the appropriate items under which this Work is required.

## **SECTION 00305 - CONSTRUCTION SURVEY WORK**

Comply with Section 00305 of the Standard Specifications.

# SECTION 00310 - REMOVAL OF STRUCTURES AND OBSTRUCTIONS

Comply with Section 00310 of the Standard Specifications modified as follows:

## 00310.41 Removal Work- Delete bullet (c) and replace with the following

**(c) Drainage Structures** - Remove drainage Structures, such as box culverts, catch basins, man holes and field inlets completely. Remove culverts, sewers, siphons, and other conduits according to 00330.41(a)(7).

**00310.90 Payment** - Add the following to the end of this subsection:

No separate or additional payment will be made for removal or disposal Work included in Section 00330 according to 00310.02.

### **SECTION 00320 - CLEARING AND GRUBBING**

Comply with Section 00320 of the Standard Specifications modified as follows:

**00320.00** Scope – Add the following paragraph to the end of this subsection:

Remove additional existing stumps up to 5 feet in diameter at locations shown on the plans or as directed by the engineer.

**00320.80 Measurement** – Add the following bulleted paragraph to the end of this subsection:

Unit Basis - Additional stump removal will be on the unit basis.

**00320.90** Payment – Add the following paragraph to the end of this subsection:

Additional stump removal is intended for stumps at address 5421 SE Jennings Ave.

### **SECTION 00330 - EARTHWORK**

Comply with Section 00330 of the Standard Specifications modified as follows:

**00330.03 Basis of Performance** - Add the following paragraph to the end of this subsection:

Perform all earthwork under this Section on the excavation basis. The total amount of calculated embankment material in place is 1,970 cubic yards.

**00330.14 Selected Granular Backfill** - Delete the sentence that begins "Reclaimed glass meeting the requirements of Section 02695..."

**00330.15 Selected Stone Backfill** - Delete the sentence that begins "Reclaimed glass meeting the requirements of Section 02695..."

**00330.41(a)(4) Excess Materials** - Replace this subsection, except for the subsection number and title, with the following:

If the quantities of excavated materials are greater than required to construct embankments and to do all filling and backfilling, the Contractor may use the remaining materials to uniformly widen embankments or to flatten slopes in a manner satisfactory to the Engineer.

**00330.41(a)(5) Waste Materials** - Replace this subsection, except for the subsection number and title, with the following:

Unless otherwise specifically allowed and subject to the requirements of Section 00280, dispose of materials, classed as waste materials in 00330.41(a)(3), outside and beyond the limits of the Project and Agency controlled property according to 00290.20. Do not dispose of materials on Wetlands, either public or private, or within 300 feet of rivers or streams.

**00330.41(a)(7) Abandoned Pipes and Miscellaneous Matter** - Remove and dispose of abandoned pipes and miscellaneous matter in the Work zone as a part of the earthwork, unless otherwise specified.

For abandoned pipes not revealed in the project plans or specifications remove ends of remaining abandoned pipe or portions of other miscellaneous matter remaining exposed in slopes or at Subgrade after excavation Work to at least 2 feet back of the finished slope or below Subgrade.

Place a watertight cap or plug in the inlet ends of remaining abandoned pipes. Leave outlet ends open. Place free-draining cover material and/or take other measures as directed to allow for free passage of drainage at remaining outlet ends. Shape and finish the affected area so no evidence of their existence is apparent upon completion of the Work.

**00330.41(a)(9)** Excavation Below Grade - Delete subsection 00330.41(a)(9)(c).

**00330.42(c)(3) Embankment Slope Protection** - Add the following paragraph to the end of this subsection:

Construct the outer 12 inches of embankments with suitable materials to establish slope stabilization through permanent seeding. If suitable material is not available, provide suitable materials from a Contractor-provided source which conforms to the requirements of 00330.11 or 00330.13 and provides favorable conditions for germination of seed and growth of grass.

**00330.91(d) General Excavation** - Delete the bullet that begins "Includes Unsuitable Material...".

**00330.92 Kinds of Incidental Earthwork** - Add the following bullets to the end of the bullet list:

• Excess material used to widen embankments or flatten slopes according to 00330.41(a)(4).

 Earthwork required for driveways and road approaches. Earthwork for driveways and road approaches will be that which is outside the Neat Line limits shown on the typical sections.

#### **SECTION 00331 - SUBGRADE STABILIZATION**

Comply with Section 00331 of the Standard Specifications.

## **SECTION 00350 - GEOSYNTHETIC INSTALLATION**

Comply with Section 00350 of the Standard Specifications modified as follows:

**00350.01 Definitions** - Replace the sentence that begins "**Embankment Geotextile** - For installation..." with the following sentence:

**Embankment Geotextile** - Embankment geotextile is used as a reinforcement within embankments and as a separation and reinforcement under embankments.

Replace the bullet that begins "Nonwoven Geotextile - A textile..." with the following bullet:

• **Nonwoven Geotextile** - A textile produced by bonding or interlocking of fibers by mechanical, heat or chemical means.

Replace the sentence that begins "**Riprap Geotextile** - For installation..." with the following sentence:

**Riprap Geotextile** - Riprap geotextile is used as a filter and separator behind or beneath riprap, Buttresses, inlays, shear keys and erosion control applications.

Replace the sentence that begins "Subgrade Geotextile - For installation..." with the following sentence:

**Subgrade Geotextile** - Subgrade geotextile is used as a separator and reinforcement on Subgrades and in other material separation applications.

**00350.41(f)(5) Geotextile Placement** - Replace the paragraph that begins "**Slit wrinkles or folds** ..." with the following paragraph:

Slit wrinkles or folds exceeding 1 inch and lay flat. Shingle-lap not more than 6 inches in the direction of the paving. Broom or squeegee to smooth the geotextile and pneumatic roll to maximize geotextile contact with the Pavement surface. Additional hand-placed sealant material may be required at laps as determined.

### **SECTION 00390 - RIPRAP PROTECTION**

Comply with Section 00390 of the Standard Specifications.

## SECTION 00405 - TRENCH EXCAVATION, BEDDING, AND BACKFILL

Comply with Section 00405 of the Standard Specifications.

## **SECTION 00415 - VIDEO PIPE INSPECTION**

Comply with Section 00415 of the Standard Specifications modified as follows:

**00415.42(a)** Remote Video Inspection with Laser Profiler - Replace the paragraph that begins "Use video inspection equipment meeting..." with the following paragraph:

Use video inspection equipment meeting the requirements of 00415.22. Calibrate the laser profiler according to the manufacturer's specifications and ASTM F3080 Section 9.

### **SECTION 00430 - SUBSURFACE DRAINS**

Comply with Section 00430 of the Standard Specifications.

### **SECTION 00440 - COMMERCIAL GRADE CONCRETE**

Comply with Section 00440 of the Standard Specifications modified as follows

**00440.12 Properties of Commercial Grade Concrete** - Replace the bullet that begins "Slump - 5 inches..." with the following bullets:

- Slump 5 inches or less
  - For concrete sidewalks, ramps, driveways, or other hand finished surface applications, and when using a high range water reducing admixture, provide a slump of 8 inches or less as approved by the Engineer.

**00440.13 Field-Mixed Concrete** - Replace the subsection, except for subsection number and title, with the following:

CGC Work items listed in 00440.14(a) may be field-mixed conventionally, or by volumetric/mobile mixers conforming to ASTM C685. When approved, concrete sidewalks,

concrete curb ramps, concrete driveways, and other flat concrete surfaces may be field-mixed using volumetric/mobile mixers conforming to ASTM C685, request approval prior to placement. For all other CGC applications, submit written request to the Engineer for approval to use volumetric/mobile mixers conforming to ASTM C685 at least 21 Days prior to placement.

Pre-packaged dry blended concrete from the QPL may be used for Work items listed in 00440.14(a).

**00440.40(b)** Placing - Add the following bullet to the end of the bullet list:

 When haul time or placement conditions warrant exceeding the time of discharge, submit a detailed breakdown of the estimated time needed from batching to discharge of a load along with the measures that will be taken to ensure slump, temperature and uniformity will be maintained. Submit in advance to establish a new time limit at the Engineer's discretion.

## SECTION 00445 - SANITARY, STORM, CULVERT, SIPHON, AND IRRIGATION PIPE

Comply with Section 00445 of the Standard Specifications modified as follows:

Add the following subsection:

00445.11 Materials - Modify as follows:

Storm Sewer Pipe: No Polyvinyl Chloride (PVC) Pipe allowed.

#### **SECTION 00446 - TRENCH DRAINS**

Comply with Section 00446 of the Standard Specifications modified as follows:

## **Materials**

Add the following subsection:

**00446.13 Trench Drain Structures** – Furnish trench drain end structures compatible with the materials provides per 00446.10. Furnish roof downspout connection piping per 00445.11.

#### Construction

**00446.40 General** – Add the following paragraph to the end of this subsection:

(d) Associated Work – Install roof downspout connection piping and make watertight connection to existing roof drain. Connect the piping into the trench drain structure, catch basin, manhole, or storm drain pipe.

## **Payment**

**00446.90** Payment – Add the following paragraph to the end of this subsection:

When the Contract Schedule of Items does not indicate payment for structures, connections or other Work under this Section, no separate or additional payment will be made. Payment will be included in payment made for the appropriate items under which this Work is required.

# SECTION 00470 - MANHOLES, CATCH BASINS, AND INLETS

Comply with Section 00470 of the Standard Specifications modified as follows:

**00470.41(c) Grates, Frames, Covers and Fittings** - Replace this subsection, except for the subsection number and title, with the following:

Set metal frames for manholes on full non-shrink grout beds to prevent infiltration of surface water or groundwater between the frame and the concrete of the manhole section. If concrete is to be poured around the frames, coat the portion of the frame that will contact the concrete with hot asphalt before placing the concrete. Set frames, covers and grates true to the locations and grades established. Clean bearing surfaces and provide uniform contact. The use of a bolt adjustment system for frames from the QPL is allowed. Secure all fastenings. Construct all mortared, sanitary sewer manhole necks and all riser ring joints made with non-shrink grout using an approved commercial concrete bonding agent applied to all cured concrete surfaces being grouted.

**00470.42** Precast Concrete Catch Basins and Inlets - Add the following sentence to the end of this subsection:

Grade adjustments using a bolt system from the QPL is allowed.

## SECTION 00490 - WORK ON EXISTING SEWERS AND STRUCTURES

Comply with Section 00490 of the Standard Specifications.

## **SECTION 00495 - TRENCH RESURFACING**

Comply with Section 00495 of the Standard Specifications.

### SECTION 00510 - STRUCTURE EXCAVATION AND BACKFILL

Comply with Section 00510 of the Standard Specifications modified as follows:

**00510.80(b)(1)** Lump Sum - Add the following to the end of this subsection:

The estimated quantity of structure excavation is:

Retaining Wall Location	Structure Excavation (Cubic Yard)
Prefabricated Modular Gravity File 47/62	125
Prefabricated Modular Gravity File 38	313
Prefabricated Modular Gravity File 28	35
Prefabricated Modular Gravity File 44B	350
Prefabricated Modular Gravity File 2/3	349
Cast-In-Place Concrete Rigid Gravity File 3	12
Prefabricated Modular Gravity File 72	27
Prefabricated Modular Gravity File 45 & 45/60	83
Prefabricated Modular Gravity File 44A	38
Remove and Rebuild Wall File 55	4

**00510.80(d)(1)** Lump Sum - Add the following to the end of this subsection::

The estimated quantities of granular wall backfill and or recycled or reused contaminated Soil are:

Granular Wall Backfill	Contaminated Soil Wall Backfill
(Cubic Yard)	(Cubic Yard)
0	56
0	161
0	29
0	272
0	152
10	0
14	0
0	37
0	30
4	0
	Wall Backfill (Cubic Yard) 0 0 0 0 0 10 14

# SECTION 00596B - PREFABRICATED MODULAR RETAINING WALLS

Comply with Section 00596B of the Standard Specifications modified as follows:

**00596B.01 Proprietary Prefabricated Modular Walls** - Add the following paragraph and bullet list to the end of this subsection:

The Contractor shall incorporate the special conditions for each property listed in the table below to progress the Work to be done under the Contract:

ROW File #	Tax Lot / Map	Owner	Phone	Eng Station	Special Conditions
28	100 / 2 2E 18DB	Leppert	503- 312- 2222	39+20 to 40+40	Per Section 00180.65, Contractor shall replace the existing retaining wall and wood fence to an in-kind or better condition. The contractor shall match the existing wall color and style color, shape, and appearance as closely as possible, and submit three material samples for review and approval 28 days in advance of work.

Select one of the following preapproved Prefabricated Modular proprietary retaining wall systems for the walls, as shown on the plans:

- Ultrablock Gravity Wall Retaining Wall System, Quarrystone face, provided by Ultrablock, Inc., telephone: 800-377-2877.
- MESA (MSE system), Mesa Standard Units, provided by Tensar International Corp., telephone: 770-344-2090.
- KeySystem III Retaining Wall System, Compact III blocks, Sierra Blend color, provided by Willamette Graystone, LLC, telephone: 503-319-2746.
- Allan Block, AB Classic AB6 (Gravity system) Retaining Wall System, "Rocky Mt. Blend" color, provided by Oregon Block and Paver Mfg., telephone: 541-233-7856.

**00596B.04(b) Design Calculations** - Add the following to the end of this subsection:

The following retaining wall design parameters have been established for this Project:

The Geotechnical Report, Jennings Avenue: OR99E to Oatfield Road, Clackamas County, Oregon (Northwest Geotech, Inc., March 5, 2021) documenting the retaining wall design parameters for the Project, is available from the Engineer.

**00596B.11(b) Modular Block Core and Drainage Backfill** - Replace this subsection, except for the subsection number and title, with the following:

Furnish 3/4" - No. 4 PCC Aggregate Material meeting the requirements of 02690.20(a) through (e).

Add the following subsection:

## 00596B.15 Associated Materials:

(a) **Fence post sleeves** – Furnish appurtenances for 'Sleeve-It' type fence post sleeves or equal.

Add the following subsection:

### 00596B.48 Fall Protection:

- (a) **Handrails** Install handrails as shown. Coordinate handrail attachment to wall system with wall manufacturer, using either the 'bolt down option' or 'embedded' options as shown in Oregon Standard Drawing RD770.
- (b) **Fences** Install appurtenances, such as fence post sleeves as shown. Coordinate penetrations into retaining wall backfill and geotextile with wall manufacturer.

Add the following subsection:

**00596B.49 Connections to Existing Walls** – Tie into existing walls by removing existing wall blocks, chipping out and/or sawcutting the existing wall to a competent structural section void of cracks or obvious sign of settlement, leaving a clean, smooth edge for connection to existing retaining wall.

**00596B.80 Measurement** - Add the following to the end of this subsection:

The estimated quantities of retaining walls are:

Retaining Wall Location	Area (sq.ft.)
File 47/62	746
File 38	1,640
File 28	180
File 44B	2,126
File 2/3	2,122
File 72	134
File 45 & 45/60	500
File 44A	218
File 55	40

**00596B.90** Payment - Add the following pay item to this subsection:

(d) Removing and Rebuilding Prefabricated Modular Retaining Wall..... Lump Sum

Add the following bullet to the end of this subsection:

• Evaluating and coordinating the existing wall material for removal and rebuild the existing retaining wall at File 55.

**00596B.90** Payment - Add the following bullets to the end of this subsection:

- Connections to existing walls
- Surface restoration behind walls

## SECTION 00596C - CAST-IN-PLACE CONCRETE RETAINING WALLS

Comply with Section 00596C of the Standard Specifications modified as follows:

Add the following subsection:

#### 00596C.44 Fall Protection:

(c) **Handrails** – Install handrails as shown. Coordinate handrail attachment to wall system, using either the 'bolt down option' or 'embedded' options as shown in Oregon Standard Drawing RD770.

Add the following subsection:

**00596C.45 Connections to Existing Walls** – Tie into existing walls by chipping out and sawcutting the existing wall to a competent structural section void of cracks or obvious sign of settlement, leaving a clean, smooth edge for connection to existing retaining wall. Drill into existing walls to facilitate connection with resin bonded anchor system to new wall, consisting of #4 deformed tie bars with 12 inches minimum length spaced 12 inches on center.

**00596C.80 Measurement** - Add the following to the end of this subsection:

The estimated quantities of retaining walls are:

Retaining Wall Location	Area (sq.ft.)
File 3	63

The estimated quantities, for estimating purposes only, of concrete and steel reinforcement for retaining wall systems are:

Material	Estimated Quantities
Concrete	5 cu. yd.
Steel Reinforcement	300 lb.

**00596C.90** Payment - Add the following bullets to the end of this subsection:

- Connections to existing walls
- Surface restoration behind walls

## **SECTION 00620 - COLD PLANE PAVEMENT REMOVAL**

Comply with Section 00620 of the Standard Specifications modified as follows:

**00620.40(e) Warning Signs** - Replace this subsection, except for the subsection number and title, with the following:

Provide warning signs as required where abrupt or sloped drop-offs occur at the edge of the existing or new surface according to Sections 00221 and 00222.

**00620.43 Maintenance Under Traffic** - Replace this subsection, except for the subsection number and title, with the following:

Traffic is not allowed on the cold planed surface. Before opening the area to traffic, pave the surface according to 00744.51.

### **SECTION 00640 - AGGREGATE BASE AND SHOULDERS**

Comply with Section 00640 of the Standard Specifications.

#### **SECTION 00730 - EMULSIFIED ASPHALT TACK COAT**

Comply with Section 00730 of the Standard Specifications modified as follows:

**00730.11 Emulsified Asphalt -** In the paragraph that begins "Obtain samples according to AASHTO T 40..." replace the words "AASHTO T 40" with the words "AASHTO R 66".

**00730.90 Payment** - Replace this subsection, except for the subsection number and title, with the following:

No separate or additional payment will be made for Emulsified Asphalt tack coat. Approximately 20 Tons of Emulsified Asphalt in tack coat will be required on this Project.

## **SECTION 00738 - SAFETY EDGE**

Comply with Section 00738 of the Standard Specifications.

### **SECTION 00744 - ASPHALT CONCRETE PAVEMENT**

Comply with Section 00744 of the Standard Specifications modified as follows:

**00744.11(a) Asphalt Cement** - Add the following to the end of this subsection:

Provide 64-22 Level 2, 1/2 Inch Dense grade asphalt cement for this Project.

## SECTION 00749 - MISCELLANEOUS ASPHALT CONCRETE STRUCTURES

Comply with Section 00749 of the Standard Specifications.

#### **SECTION 00756 - PLAIN CONCRETE PAVEMENT**

Comply with Section 00756 of the Standard Specifications modified as follows:

**00756.15(a)** Concrete Mixture - Replace this subsection, except for the subsection number and title, with the following:

- · Sample and test according to the MFTP.
- For all plain concrete pavement, provide personnel according to 00756.30 to sample and test the mix for temperature, air content, slump, water-cementitious ratio, density and yield, from the first load of each placement, whenever there is a visible change in the slump of the concrete, and when a set of cylinders is obtained.
- If the results of any test are outside of the Specification limits, stop the placement of the load. Correct the load or reject it and do not incorporate it into the Work. Test subsequent loads before any further concrete placement. Correct the subsequent loads if any of the tests are still outside the Specification limits. If the load cannot be corrected, reject it and do not incorporate it into the Work. Testing of subsequent loads may return to the specified frequency when the test results from two consecutive loads are shown to meet the Specification limits.

**00756.95(a) General** - Replace the bullet that begins "The average of the IRI for both..." with the following bullet:

The IRI in each wheel path is 65.0 inches per mile or less.

**00756.80 Measurement -** Replace this subsection, except for the subsection number and title, with the following:

No measurement of quantities will be made for Work performed under this Section.

**00756.90 Payment -** Replace this subsection, except for the subsection number and title, with the following:

When the Contract Schedule of Items does not indicate payment for Work performed under this Section, no separate or additional payment will be made. Payment will be included in payment made for the appropriate items under which this work is required.

No separate or additional payment will be made for construction joint reinforcement bars, tie bars, dowel bars, curing materials or saw cutting.

No separate or additional payment will be made for attendance at the Prepaying Conference.

### SECTION 00759 - MISCELLANEOUS PORTLAND CEMENT CONCRETE STRUCTURES

Comply with Section 00759 of the Standard Specifications modified as follows:

**00759.03(b) Curb Ramp Plan** - Replace the bullet that begins "Compliance with Working Drawings and details..." with the following bullet:

Comply with Working Drawings and details submitted under 00759.03(a)

Add the following subsection:

**00759.03(d) Corrective Action Plan** - Unless otherwise approved, notify the Engineer before performing corrective action. Include TPAR necessary to complete corrective action work.

At least 21 Calendar Days before concrete Structures Work is scheduled to begin, submit a corrective action plan. The corrective action plan shall address procedures to correct deficient Structures through minor corrective action or replacement according to 00759.55(a), and include:

- List of minor corrective actions that will be used to correct deficiencies, according to 00759.50 and 00759.55.
- · Procedures for performing corrective action.
- Proposed concrete grinding Equipment and method of grinding.
- Proposed concrete repair Material used for resurfacing ground concrete surfaces according to Section 02015.
- Construction activities, Equipment and staging necessary to complete corrective action Work.

The Engineer will review the corrective action plan(s) and provide a response to the Contractor within 5 Days after receiving the plan. Do not begin concrete Structure Work until the corrective action plan is approved by the Engineer.

Add the following subsection:

**00759.23 Concrete Resurfacing Equipment** - Furnish power-operated scarifying Equipment capable of uniformly removing and preparing the existing surface to depths required. For concrete grinding operations, furnish 12 segment grinders, fine-toothed scarifying Equipment, or other approved grinding Equipment.

**00759.46 Concrete** - Replace this subsection, except for the subsection number and title, with the following:

- a. Construct the Structures between suitable forms or by the extrusion method. Place concrete according to the Plans, Section 00440, and this Section.
- b. Per Project Plan Sheet C-02 (construction notes 62 and 106), complete construction of the driveway from SE McLoughlin Blvd. (OR99E) to the gas station and

convenience store within 48 hours. Use quickset concrete or equally approved product from the ODOT QPL.

Construct the Structures between suitable forms or by the extrusion method. Place concrete according to the Plans, Section 00440, and this Section.

## **00759.47 Weep Holes** – Add the following subsection:

Install weep holes in concrete curbs at retaining wall ends or as shown or directed. Install 3 inch diameter PVC drain pipe before placing concrete sidewalk and curb sections. Extend the end of the pipe to the 3 inch diameter openings in the face of curb. Protect pipe ends during placement of concrete and clear weep hole drain pipes after concrete is placed.

**00759.50(a)** General - Add the following paragraphs to the end of this subsection:

Install truncated domes as shown. Place according to the manufacturer's recommendation. Install abutting truncated dome panels with no more than 1/4 inch spacing. Install anchors along cut edges of truncated dome panels according to manufacturer's recommendations.

In addition, finish concrete surfaces of Structures to be within the established Slopes and dimensions allowed by the Standard Drawings and Plans. Repair or remove and replace Structures not meeting the Standard Drawings and Plans at no additional cost to the Agency.

Submit a corrective action plan for each non-compliant Structure after receiving notice of non-compliance from the Engineer. Perform correction of defects according to 00759.55.

**00759.50(c) Driveways, Walks, and Surfacings** - Replace this subsection, except for the subsection number and title, with the following:

Prevent segregation of the concrete during placement. Strike-off the concrete to the grade shown, and float the surface smooth. After the water sheen disappears, edge the joints and remove edging tool marks prior to final finishing. Lightly cross-broom the surface to a uniform texture. Do not trowel joints or edges after brooming surface.

The 24 inch smart level will be used to measure driveway and sidewalk cross slopes on the Pedestrian Access Route.

**00759.50(d) Curb Ramps** - Replace this subsection, except for the subsection number and title, with the following:

Prevent segregation of the concrete during placement. Strike-off the concrete to the grade shown and float the surface smooth. After the water sheen disappears, edge the joints and remove edging tool marks prior to final finishing. Lightly cross-broom the surface to a uniform texture. Do not trowel joints or edges after brooming surface.

The 6 inch smart level will be used to measure curb running slope. The 6 inch smart level will be used to measure slopes on portions of the curb ramp, gutter pan, or adjacent surfaces that cannot accommodate a 24 inch smart level. All other curb ramp locations will use a 24 inch smart level to measure slopes.

Add the following subsection:

- **00759.55 Correction of Deficient Structures** Unless otherwise approved, notify the Engineer before performing corrective action. Correct deficiencies at no additional cost to the Agency. Perform corrective actions as directed, according to the approved corrective action plan, and according to the following:
  - (a) Minor Corrective Action Submit Equipment and procedure for minor corrective action to the Engineer for approval. Minor corrective action can be performed to correct a deficiency up to 1 square foot per panel. Limit minor corrective action to one area per panel. Perform minor corrective action according to the following:
    - (1) Concrete Grinding Grinding to correct high area deficiencies is limited to 3/16 inch. Use equipment meeting the requirements of 00759.23. Resurface all ground concrete surfaces according to 00759.55(a)(2).
    - **(2) Concrete Resurfacing** Resurfacing to correct low area deficiencies is limited to 3/16 inch depth. Existing concrete is to be at least 7 Days old prior to resurfacing. Resurface repair areas according to the following:
      - a. **Keyway** Sawcut a keyway at the boundaries of repair areas that are not already defined by panel control joints. Sawcut is to be 1/8 inch wide by 1/4 inch deep. Bevel inside edge of keyway at a 45 degree angle.
      - b. **Surface Preparation** Prepare limits of repair area by grinding using Equipment from 00759.23. After grinding, sandblast the surface of the repair area. Clean the surface using a low pressure washer, less than 5,000 psi.
      - c. **Presoak** Presoak the repair area for a minimum of 30 minutes to saturated surface dry. Prior to resurfacing, ensure there is no ponding water on the surface.
      - d. **Resurface** Provide concrete resurfacer from the QPL according to 02015.60; refer to QPL remarks to select an appropriate material based on allowable installation depths. Furnish resurfacer in a color that closely matches the color of surrounding concrete surfaces. Mask boundaries of the repair area. Use hand tools to work resurfacer into keyways and match existing grade at boundaries. Apply a light broom-finish to achieve non-slip surface.
      - e. **Curing and Return to Traffic** Wet cure for a minimum of 1 hour or per the manufacturer's recommendation, whichever is more restrictive. Follow manufacturer's recommendation for return to traffic time.
    - (3) ACP Grinding Taper grind to match existing Pavement with a minimum grinding width of 1 foot for each 1/4 inch of ACP removed.
  - **(b) Acceptance of Structures** Once the corrective work or replacement has been completed, acceptance will be based on the Engineer's inspection and approval of the Structure.
- **00759.90 Payment** Replace the paragraph that begins "Item (k) includes the additional Work required ..." with the following paragraph:

Item (k) includes the additional Work required to construct a curb ramp or replace an existing curb ramp. Payment for the area of the curb ramp will be made under the concrete walks Pay Item.

Replace the paragraph that begins "No separate or additional payment will be..." with the following paragraph and bullet list:

No separate or additional payment will be made for:

- curb ramp Working Drawings
- curb ramp plan,
- · preplacement conference
- · concrete form verification
- any necessary repair or removal and replacement of curb ramps
- providing supervisory personnel who have an active ODOT ADA Certification for Contractors to directly supervise the curb ramp Work
- · developing corrective action plans

### **SECTION 00810 - METAL GUARDRAIL**

Comply with Section 00810 of the Standard Specifications modified as follows:

**00810.13 Guardrail Anchors** - Replace this subsection, except for the subsection number and title, with the following:

Furnish steel guardrail anchors according to Section 02820.

**00810.41 Excavation and Backfill** - Add the following paragraph to the end of this subsection:

Hand dig guardrail post holes or use other non-invasive methods when posts are located within 24 inches surrounding the outside dimension of all sides of underground utilities as shown or directed.

## **00810.90** Payment -Add the following paragraph:

The words "with reflectors" will be added to the applicable pay item name in the Contract Schedule of Items.

No separate or additional payment will be made for furnishing and installing reflectors.

## **SECTION 00850 - COMMON PROVISIONS FOR PAVEMENT MARKINGS**

Comply with Section 00850 of the Standard Specifications modified as follows:

**00850.47(c) Retroreflectivity** - Replace the sentence that begins "Except for paint applications..." with the following sentence:

Except for paint and colored lane marking applications, evaluate longitudinal and transverse marking retroreflectivity according to ODOT TM 777.

#### **SECTION 00856 - SURFACE MOUNTED TUBULAR MARKERS**

Comply with Section 00856 of the Standard Specifications modified as follows:

**00856.10 Materials** – Surface mounted tubular markers shall be the following or an approved equal:

Tuff Curb Traffic Delineator System Mdl. No. XLP (High-Performance, Low-Profile Traffic Separator Curb)

**00856.90 Payment** – Add the following sentence to the paragraph that begins "Payment will be...."

Payment will also include furnishing and installing the Tuff Curb Traffic Delineator System Mdl. No. XLP product per manufacturer's recommendations.

#### SECTION 00865 - LONGITUDINAL PAVEMENT MARKINGS - DURABLE

Comply with Section 0865 of the Standard Specifications.

## SECTION 00867 - TRANSVERSE PAVEMENT MARKINGS - LEGENDS AND BARS

Comply with Section 00867 of the Standard Specifications.

### **SECTION 00868 - COLORED LANE MARKINGS**

Section 00868, which is not a Standard Specification, is included in this Project by Special Provision.

### **Description**

**00868.00 Scope** - In addition to the requirements of Section 00850, install colored lane markings according to the following Specifications.

### Labor

**00868.30 Manufacturer's Representative** - Provide a manufacturer's representative according to 00850.30.

**00868.31 Manufacturer-Certified Installers** - Provide certified installers according to 00850.31.

#### Construction

**00868.45 Installation** - Place markings only when the manufacturer's representative determines that the pavement is ready for the pavement marking material.

Apply the material to the pavement according to the manufacturer's installation instructions to the full width shown in the Plans. Joints will be allowed with no overlap or gap allowed at the joint.

Do not install reflective elements.

Install the pavement marking material surface according to the manufacturer's installation instructions to achieve a uniform initial skid resistance greater than or equal to 50 British Pendulum Number (BPN) when tested according to ASTM E303.

Apply one or more of the following marking material types:

- Preformed, Fused Thermoplastic Film High Skid Install preformed, fused thermoplastic film high skid that has factory installed crushed glass or Aggregate on the surface.
- Methyl Methacrylate Apply methyl methacrylate to the pavement to the full width shown in a single application. Colored lane markings shall be 90 mils to 120 mils in thickness, exclusive of projecting surface-applied friction elements, with a continuous and uniform cross sectional configuration.

**00868.75 Manufacturer's Warranty** - Furnish a manufacturer warranty that unconditionally warrants to the Agency the product(s) and installation under this Section against failure, according to this subsection and 00170.85(c)(1). Use Agency-supplied warranty forms, available from the Engineer.

"Unconditionally warrant" means that the warranty covers all failures, regardless of the source or cause of the failure, including, without limitation, whether the source or cause is or may be related to workmanship, inspection, or choice of materials.

The Agency inspection of any portion of the Work during the Contract and during the product installation, the Agency acceptance of the Work, corrections under the warranty, or expiration of the warranty shall not relieve the obligations under this warranty.

- (a) Warranty Period The warranty period shall be for 18 months.
- **(b) Failure** For purposes of this warranty, failure is defined as one or more of the following:

- · Insufficient Color Stability:
  - Green markings fail to meet the requirements of the Federal Highway Administration Interim Approval for Optional Use of Green Colored Pavement for Bike Lanes (IA-14) tested according to ASTM D6628.
- Loss of Adhesion Markings show 5 percent or greater loss of marking material due to non-adhesion.
- **Skid Resistance** Markings fail to maintain an average skid resistance greater than or equal to 50 British Pendulum Number (BPN) when tested in an equal number of test locations in both wheel path and non-wheel path locations according to ASTM E303.
- **(c) Remedy** Upon notification by the Engineer of a failure, provide the following remedy at no additional cost to the Agency:
  - Repair or replace, at the discretion of the Engineer, all failed pavement markings within 6 months of the Agency's request to do so.
  - · Use materials and procedures meeting the Specifications.
  - Match repairs to adjoining Work.
  - Coordinate timing of repair Work with the Engineer.
- (d) Agency's Right to Make Repairs If, in the opinion of the Engineer, a failure causes or may cause a hazard, the failure may be temporarily corrected by Agency or other forces at no additional cost to the Agency. Replace temporary repairs with permanent repairs at no additional cost to the Agency and according to the Specifications and within the time specified in 00868.75(c).

#### Measurement

**00868.80 Measurement** - The quantities of colored lane markings will be measured on the area basis.

## **Payment**

**00868.90 Payment** - The accepted quantities of Work performed under this Section will be paid for at the Contract unit price, per unit of measurement, for the following items:

#### Pay Item

**Unit of Measurement** 

(a) Green Bicycle Lane, Preformed Thermoplastic Film .... Square Foot

Payment will be payment in full for furnishing and placing all Materials, and for furnishing all Equipment, labor, and Incidentals necessary to complete the Work as specified.

Payment for Work under this Section will be limited to 75 percent of the amount due until the Agency has received the signed warranty.

#### SECTION 00902 - CROSSWALK CLOSURE SUPPORTS

Section 00902, which is not a Standard Specification, is included in this Project by Special Provision.

## **Description**

**00902.00 Scope** - This Work consists of constructing crosswalk closure supports and associated signs as shown.

#### **Materials**

**00902.10 Materials** - Furnish Materials meeting the following requirements:

Commercial Grade Concrete	00440
Steel	01070.10 and 01070.12
Signs	00940

### Construction

**00902.40 General** - Install crosswalk closure supports and associated signs as shown or directed.

#### Measurement

**00902.80 Measurement** - The quantities of crosswalk closure supports will be measured on the unit basis. No separate measurement will be made for signs attached to crosswalk closure supports.

## **Payment**

**00902.90 Payment** - The accepted quantities of Work done under this Section will be paid for at the Contract unit price, per each, for the item "Crosswalk Closure Supports".

Payment will be payment in full for furnishing and placing all Materials, including signs, and for furnishing all Equipment, labor, and Incidentals necessary to complete the Work as specified.

## SECTION 00905 - REMOVAL AND REINSTALLATION OF EXISTING SIGNS

Comply with Section 00905 of the Standard Specifications.

### **SECTION 00920 - SIGN SUPPORT FOOTINGS**

Comply with Section 00920 of the Standard Specifications modified as follows:

**00920.80 Measurement** - Add the following to the end of this subsection:

The estimated quantities of concrete for minor sign supports are:

Support Type	Quantity
Perforated Steel Square Tube Slip Base Sign Supports Perforated Steel Square Tube Anchor Sign Supports	1 cu. yd. 3 cu. yd.

## **SECTION 00930 - METAL SIGN SUPPORTS**

Comply with Section 00930 of the Standard Specifications modified as follows:

**00930.80 Measurement** - Add the following to the end of this subsection:

The estimated quantities of structural steel are as follows:

Item	Estimated Quantity (Pound)	
Minor Sign Supports		
Perforated Steel Square Tube Slip Base Sign Supports Perforated Steel Square Tube Anchor Sign Supports	1637 7777	

## SECTION 00940 - SIGNS

Comply with Section 00940 of the Standard Specifications.

## **SECTION 00950 - REMOVAL OF ELECTRICAL SYSTEMS**

Comply with Section 00950 of the Standard Specifications modified as follows:

**00950.02 Definitions** - Delete this subsection.

## **SECTION 00960 - COMMON PROVISIONS FOR ELECTRICAL SYSTEMS**

Comply with Section 00960 of the Standard Specifications modified as follows:

**00960.02 Equipment List and Drawing Submittals** – Replace this subsection with the following subsection:

Within 30 Calendar Days after execution of the Contract, submit the following:

# 00960.02 Equipment List and Drawing Submittals:

- (a) For the intersection of SE Jennings Ave & SE McLoughlin Blvd. (OR99E) Two copies of the ODOT Blue Sheets (see 00160.00 and 00160.07) and two copies of the ODOT Green Sheets (see 00160.00 and 00160.07) according to 00150.37 for all materials the Contractor proposes to install. Blue Sheets and Green Sheets contain submittal instructions and will be made available to the Contractor by the Engineer.
  - Within 14 Calendar Days after receipt of submittals, the Engineer will review the submittals and designate them in writing as "approved", "approved as noted", or "returned for correction". Do not proceed with the Work before receiving written approval of the submittals from the Engineer.
- (b) For the intersection of SE Jennings Ave & SE Outfield Rd Submit two electronic PDF copies of the Blue Sheets (see 00160.00 and 001607.07) and the Green Sheets (see 00160.00 and 00160.07) according to 00150.37 for all materials the Contractor proposes to install. Refer to 00990 for exemptions to the Blue Sheets and Green Sheets on Clackamas County operated traffic signals.
  - Within 14 Calendar Days after receipt of submittals, the Engineer will review the submittals and designate them in writing as "review" or "reviewed with comments". Then within the follow 7 Calendar Days after the Engineer review, Clackamas County Traffic Staff will review the submittals and designate them in writing "approved", "approved as noted", or "revise and resubmit". Do not proceed with the Work before receiving written approval of the submittals from the Engineer or Clackamas County.

**00960.10 Materials** – Add the following to the end of this subsection:

Use only Schedule 80 PVC conduits and fittings for all underground conduits.

**00960.30 Licensed Electricians** - Replace the paragraph that begins "According to the Oregon Administrative Rule ..." with the following paragraph:

According to the Oregon Administrative Rule 918-282-0120(1), no person or entity shall allow any individual to perform electrical work for which the individual is not properly registered or licensed. Every person who installs electrical systems on the Project shall submit a copy of their electrical license or apprentice registration to the Engineer prior to performing any Work. They must be licensed as an S or a J under Oregon Administrative Rule 918-282.

Add the following subsection:

**00960.42(c) Connecting Non-Metallic Conduit to Metallic Conduit** - Use a nonmetallic female threaded connector to connect nonmetallic conduit to metallic conduit.

Add the following subsection:

**00960.42(g) Conduit on Wood Poles** - Mount conduit on wood poles with two-hole, galvanized, steel conduit straps spaced no more than 3 feet apart. Mount conduit on Utility-owned wood poles according to local Utility regulations. Use stand-off brackets if required.

**00960.43 Foundations** – Add the following to the end of this subsection.

Separate the aluminum from the concrete with one layer of 30 pound nonperforated, asphalt-saturated felt. Neatly trim the felt pad to the size and shape of the base contact surface.

**00960.46 Service Cabinet and Electrical Energy** - Replace this subsection, except for the subsection number and title, with the following:

Install service cabinet and associated equipment, then arrange for the Utility providing power to have the service cabinet inspected and make the electrical hook-up prior to field testing. Field test according to 00990.70(g) for traffic signals, or according to 00970.70 for illumination.

Table 00960-1 contains Utility contact information to arrange for the Utility to make electrical hookups:

### Table 00960-1

	PGE Contact Person's Name,	
Location	Email and Phone Number	PGE Job Number
SE Jennings Ave &	Service Coordinators 503-323-6700	M2923417
SE Portland Ave;	Email: service.coordinators@pgn.com	
Flashing Beacon		
SE Jennings Ave &	Service Coordinators 503-323-6700	M2923419
SE Howard Ave;	Email: service.coordinators@pgn.com	
Speed Radar		
SE Jennings Ave &	Service Coordinators 503-323-6700	M2923420
SE Cook St;	Email: service.coordinators@pgn.com	
Speed Radar		

Furnish and install a meter base approved by the serving Utility (with cover by the Utility), where shown.

### SECTION 00962 - METAL ILLUMINATION AND TRAFFIC SIGNAL SUPPORTS

Comply with Section 00962 of the Standard Specifications.

#### **SECTION 00970 - HIGHWAY ILLUMINATION**

Comply with Section 00970 of the Standard Specifications.

## **SECTION 00990 - TRAFFIC SIGNALS**

Comply with Section 00990 of the Standard Specifications modified as follows:

Add the following subsection:

**00990.10 Materials** - Furnish Materials meeting the following requirements:

Crosswalk Closure Support	00902.10
Backer Rod	02440.14

Furnish the following Materials from the QPL:

Hot-Melt Loop Sealant

**Speed Feedback Assembly** – Speed Feedback Signs shall be the following:

- Carmanah SpeedCheck Part Number SC-15, AC Power 110-240, Package 01, and TrafficAnalyzer software to collect and provide time and speed data. With a warranty of three years on all products, five years on white LED panels, ten years on amber LED panels. Free technical support for up to three years.
- Carmanah SpeedCheck Part Number SC-18, AC Power 110-240, Package 01, and TrafficAnalyzer software to collect and provide time and speed data. With a warranty of three years on all products, five years on white LED panels, ten years on amber LED panels. Free technical support for up to three years.
- Carmanah Speedcheck cabinet with factory installed Applied Information FMU 2 Al-500-070 with optional RS-485 port and five years of data, to start at system acceptance/turn-on.

Add the following subsections:

**00990.13 Power Service Cabinet** - Service cabinets shall be the following or an approved equal:

Fouch Drwg #0600-0074-00 (NEMA 3-R Metered Base Mount Service Cabinet Clackamas County).

**00990.15 Pedestrian Push Buttons and Mount** - Pedestrian pushbuttons for installation at traffic signals shall be as follows:

For the intersection of SE Jennings Ave & SE McLoughlin Blvd. (OR99E) – Use ODOT standard Specification 02925.66.

For the intersection of SE Jennings Ave & SE Outfield Rd - Pedestrian push button system shall be a Polara iNavigator 2-Wire (iNS2) Push Button Station (P/N: iNS2-3-T-N-0-B) or approved equal. See the Contract Plans for additional details. The following components make up the push button system:

- (a) Push Button Station (P/N: iNS2 PBS) The main body with pushbutton for installation on the signal or pedestrian pole using 2-Wire push button wired as a 3-Wire system.
- **(b) Ped Head Control Unit (P/N: iPHCU3W)** Interface device for installation in pedestrian signal head. One per Push Button Station.
- **(c) Pedestrian Push Button Decal** The pedestrian push button sign shall be a Polara option T (Hi-Intensity Retroreflective MUTCD R10-3e) 9"x15" sign.
- (d) Interconnect Cables (iN3-CABLE-X) Pre-cut lengths (12', 25', or 50') of interconnect cable from Push Button Station to Ped Head Control Unit.
- **(e) iNav Bluetooth Dongle (iN-DGL)** Bluetooth dongle to communicate from personal computer with Polar iN3 Push Button Station.

**00990.16 Rectangular Rapid Flashing Beacons** – The installation of rectangular rapid flashing beacons (RRFB) shall be as follows:

- (a) RRFB Assembly Unit The RRFB shall be a Carmanah (P/N: SC315-G) with AC Power Kit and uni- or bi-directional light bar configurations as shown on the Contract Plans or approved equal.
- **(b) Push Button System** RRFB push button system shall be a Polara Crosswalk Button Station (P/N: iNX9WN0-Y) or approved equal.

## 00990.17 Traffic Signal Circuits

All high-voltage wiring smaller than #10 AWG shall be IMSA 19-1 cable.

#### 00990.40 Cable and Wire -

(a) For the intersection of SE Jennings Ave & SE McLoughlin Blvd. (OR99E) – Wiring signal use TM 470.

- (b) For the intersection of SE Jennings Ave & SE Outfield Rd The #14 AWG, multiconductor cables ran for traffic signal circuits will conform to IMSA Specification 19-
  - 1. Color coding of the conductors will be as follows:

## **Traffic Signal Color Code**

Clackamas County, Oregon #14 AWG IMSA 19-1 Traffic Signal Cable Mast Arms Only

	Function (Phase)	20 Conductor [Feed]	10 Conductor [Branch]	7 Conductor [Branch]	5 Conductor [Branch]	4 Conductor [Branch]
Main Street	Phase Red	Red	Red	Red	Red	Red
	Phase Yellow	Orange	Orange	Orange	Orange	Orange
	Phase Green	Green	Green	Green	Green	Green
iet	Phase Red	Red/Black	Red/Black	Red	Red	Red
Side Street	Phase Yellow	Orange/Black	Orange	Orange	Orange	Black
	Phase Green	Green/Black	Green/Black	Green	Green	Green
c	Phase Red	Red/Black	White/Black	White/Black	Red	Red
Left Turn	Phase Yellow	White/Red	Black	Black	Orange	Black
ت ا	Phase Green	Black/White	Blue	Green	Green	Green
	Phase Red	Red/Green	White/Black	White/Black	Red	Red
Overlap	Yellow/Flashing Yellow Arrow	Orange/Red	Black	Black	Orange	Black
	Phase Green	Blue/Red	Blue	Blue	Green	Green
Main Street	Phase Don't Walk	Red/White	Red	Red	Red	-
	Phase Walk	Green/White	Green	Green	Green	
Street	Phase Don't Walk	Black	Red/Black	Red	Red	-
Side S	Phase Walk	Blue/White	Green/Black	Green	Green	-
ton	Common	White/Black	White/Black	White/Black	Orange	-
Push-Button	Main Street Phase	Blue	Blue	Blue	Black	-
Pus	Side Street Phase	Blue/Black	Black	Black	Black	-
	Spare	White	-	-	-	-
	AC Common (Branch Only)	-	Spare	White		

**00990.40** Work in Existing Controller Cabinets - Install new field wiring as shown into the existing controller cabinet without terminating.

New control equipment installed as shown in an existing controller cabinet will be tested prior to installation according to 00990.70.

At existing controller cabinets, including existing temporary controller cabinets already in service, the Agency will be responsible for:

- Storage, delivery, installation, and activation of new control equipment
- Any required modifications to existing control equipment or existing field wiring terminations
- · Terminating new field wiring

Prior to the anticipated installation of new control equipment, modification of existing control equipment, or modification of existing field wiring terminations, schedule field testing according to 00990.70(g). Field testing and activation of the new control equipment or modifications will occur within the same work shift. Be present at the Project Site during field testing.

Add the following subsection:

## 00990.41 Inductive Loop Detectors:

(a) General - Do not begin saw cutting until the loop layout has been inspected by the Engineer.

Do not place wire in saw cuts until the cuts have been inspected by the Engineer.

**(b) Saw Cut and Wire Installation** - Saw cut in a manner that is the most practicable, direct line between loops and junction boxes.

Immediately after saw cutting and before the cuttings dry, thoroughly flush each cut with a high-pressure water stream. Before the cuts dry, blow cuts free of water, debris, rock, and grit with compressed air. Slots may also be cleaned by means of a high-pressure water injection/vacuum extraction system. Remove rocks or other material that may be wedged in the cut. Remove and dispose of all cuttings according to 00290.20.

Dry cuts before placing wire.

After the saw cut is cleaned of debris, place the loop wire by pushing it into the slot with a blunt nonmetallic object. Use care to avoid damaging the insulation.

**(c) Sealant** - Install the sealant in slots according to the manufacturer's instructions. Furnish a copy of the manufacturer's specifications including application procedures. The Engineer may order a test run of any application method or material before filling saw cuts.

In order to prevent heat damage to the insulation, do not allow the temperature of the sealant to exceed 410 °F during application. Install hot-melt sealants in layers to prevent damage to wire insulation. Allow each layer to cool before the next layer is installed. Do not use water to accelerate cooling.

Sealants that crack or pull away from the saw cuts after curing will be rejected.

- (d) Resistance and Continuity Testing The resistance to ground of the loop and loop feeder combinations, shall be 500 M $\Omega$  or greater when checked at the following conditions:
  - · Before splicing and sealing continuity test
  - · Before splicing after sealing resistance test
  - After splicing and sealing resistance test

Furnish a report of the resistance and continuity results for each loop at each testing condition.

Add the following subsection:

**00990.42(b)** Loop Feeder Cables – When terminating loop feeder cable inside the controller cabinet, do not remove the outside jacket and shield more than 6 inches from the end of the cable. Crimp lugs used for loop wire field terminals may be insulated or non-insulated. Terminate loop feeder shield drain wire to the cabinet input panel grounding bus nearest the feeder wire termination point.

**00990.30 Video/Radar Detector Manufacturer's Representative** - Provide the services of a manufacturer's representative on-site within 1 week in advance of the anticipated signal completion date to set up devices with Agency electrical crew present.

**00990.90 Payment** - Delete Pay Item (c) from the pay item list.

Delete the paragraph that begins "Item (c) includes furnishing and installing..."

Replace the paragraph that begins "In Items (a), (b), (c), (d), (f) ..." with the following paragraph:

In Items (a), (b), (d), (f) and (g), the intersection location will be inserted in the blank.

Replace the paragraph that begins "Item (b) includes furnishing and replacing..." with the following paragraph:

Item (b) includes furnishing and replacing or installing items for an existing traffic signal installation and the detection system.

Crosswalk closure supports will be paid for according to 00902.90.

**00990.90 Payment** – Add the following after the sentence that reads "Item (f) includes furnishing and installing all items of the flashing beacon system.

This item also includes furnishing and installing all items of the speed feedback system including but not limited to conduit, trenching, junction boxes, directional drilling, wiring, speed signs, power, control cabinets, foundations, stainless steel clamps for sign attachment, modems, vehicle signal pedestals and other necessary items to facilitate a complete system.

Contractor will be responsible for all wiring necessary for each speed feedback sign assembly installation including the modem for activation.

For each speed feedback sign, provide flasher timer switch with cellular modem from Applied Information (AI) Park# AI-500-070. Includes Glance (Cloud Based) Perpetual License & Configuration and 5 years Cellular Data (10MB/month) with access to Clackamas County. Refer to project plan sheets for school zone flashers, signs, poles, and foundation details.

# SECTION 01011 - STORMWATER CONTROL, BIOFILTRATION SWALE FACILITY

Section 01011, which is not a Standard Specification, is included for this Project by Special Provision.

# **Description**

**01011.00 Scope** - This Work consists of furnishing and installing stormwater biofiltration swale facility and combined detention ponds as shown, also referred to as a biofiltration swale facility. See 00290 and 00294 for other requirements associated with the biofiltration swale facility.

## **Materials**

**01011.10 Materials** - Furnish Material meeting the following requirements:

Concrete	00440
Riprap	00390.11
Storm Sewer Pipe	00445.11

**01011.12 Water Quality Mixture** - Furnish medium compost meeting the requirements of Section 03020. Furnish soil meeting the following gradation requirements:

Sieve Size	Percent Passing (by Weight)
No. 4	100
No 10	95 - 100
No. 40	40 - 60
No. 100	10 - 25
No. 200	5 - 10

Sample soil according to AASHTO R 90. Determine sieve analysis according to AASHTO T 27 and AASHTO T 11.

Blend the medium compost and soil so that the mixture:

- Is composed of between 20 percent and 25 percent medium compost material and between 75 percent and 80 percent soil material.
- Has a pH between 5.5 and 8.0.
- Does not have clumps greater than 3 inches in any direction.

## Construction

**01011.40 General** - Construct biofiltration swale facility as shown. Perform excavation and fine grading work only when the facility area is dry and only from the top of the pond area. Do not stockpile material in the facility area.

# 01011.41 Biofiltration Swale Facility:

- (a) Scarify Scarify the subsoil area a minimum 12 inches deep. Do not scarify subsoil supporting riprap, concrete curbs and flow spreaders.
- **(b) Laying Pipe** Lay the pipe according to Section 00445. Place pipe with perforations down unless otherwise directed.
- **(c) Joining Pipe** Fasten pipes together with coupling fittings or bands as specified for the type of pipe used. Cap the upstream end of the pipe.
- **(d) Inspection and Repair** Place Type 2 water quality mixture only after all the flow spreaders, curb and pipe is laid, joined, and inspected. Remove and reinstall or replace all flow spreaders, curb and pipe that is out of alignment, has settled, or is damaged at no additional cost to the Agency.
- **(e)** Placement of Water Quality Mixture Place water quality mixture in maximum 12 inch Lifts. Compact each Lift by using a water filled roller.

## Maintenance

**01011.70 Cleaning** - If a stormwater control facility is used for erosion and sediment control, remove all accumulated sediment and debris before completing the facility.

#### Measurement

**01011.80 Measurement** - No measurement of quantities will be made for Work performed under this Section. The estimated quantities of Materials are:

# **Water Quality Biofiltration Swale Facility Quantities:**

Item	Quantity
Excavation	2,500 Cu. Yd.
Loose Riprap, Class 50	8 Cu. Yd.
Water Quality Mixture,	310 Cu. Yd.
Biofiltration Swale Curb	120 Foot
Biofiltration Swale Level Spreader	60 Foot

**01011.90 Payment** - The accepted quantities of Work performed under this Section will be paid for at the Contract lump sum amount for the item(s):

	Pay Item	Unit of Measurement
(a)	Stormwater Control,	Lump Sum

The drainage facility identification number will be inserted in the blank.

Payment will be payment in full for furnishing and placing all Materials, and for furnishing all Equipment, labor, and Incidentals necessary to complete the Work as specified.

## **SECTION 01030 - SEEDING**

Comply with Section 01030 of the Standard Specifications modified as follows:

**01030.13(c) Pure Live Seed** - Replace this subsection, except subsection number and title, with the following subsection:

Use the PLS specified rate listed in 01030.13(f) for determining PLS application rates. Ensure the PLS application rate meets the PLS specified rate. Apply pre blended seed mixes, with multiple species, at a PLS application rate ensuring all species meet or exceed the PLS specified rate for each species in the seed mix.

PLS application rate for an individual seed species is determined as follows:

- PLS specified rate is listed in 01030.13(f)
- PLS factor is obtained by multiplying the seed label germination percentage times the seed label purity percentage. Use the purity and germination percentages from the label on actual bags of seed to be used on the Project.
- PLS application rate is obtained by dividing the PLS specified rate by the PLS factor.

For a seed mix, make this calculation for each seed species in the mix and then adjust as follows:

- Using the seed tag, determine the weight of each seed species in the bag and use this
  information to find the percentage, by weight, of each seed species is in 1 pound for
  the pre-blended mix.
- Divide the percentage by weight of each seed species, per pound, for the pre-blended mix, by the PLS application rate for that specific seed species.

Determine the highest application rate in the seed mix and apply the seed mix at that application rate.

**01030.13(f)** Types of Seed Mixes - Add the following to the end of this subsection:

Provide the following seed mix formulas:

## Permanent Seeding: Dwarf Grass Mix

Botanical Name	PLS Specified Rate
(Common Name)	(lb/acre)
Dwarf Perennial Ryegrass	80
()	
Creeping Red Fescue	20
()	

# Water Quality Seeding: Biofiltration Swale Facility Mix

Botanical Name (Common Name)	PLS Specified Rate (lb/acre)
Festuca rubra rubra*	44
() Bromus carinatus* ( )	14
Bymun glaucos*	14
() Triticum Aestivum x Secale (	 Cereal 14
Lupinus bicolor*	14
\	<del></del>

<sup>\*</sup> Oregon Certified Seed

**01030.13(g)** Availability - Add the following sentence to the end of this subsection:

Submit the seed and seed mixes to be used on the project according to 00150.37.

Add the following subsection:

**01030.14(b)(4) Organic Fertilizer** - Furnish organic fertilizer that analyzes >7 % nitrogen, 2 % phosphoric acid, and 3 % soluble potash. Furnish fertilizer that has no toxicity to sites where it will be applied.

Biosol is a manufacturer that provides an equivalent product as specified.

**01030.15 Mulch** - Add the following paragraph and bullets to the end of this subsection:

Furnish straw mulch for all temporary roadside erosion control seeding, except hydromulch may be used under the following conditions:

- Spring planting west of the Cascades between March 1 and May 15.
- Slopes are steeper than 1V to 1.5H and longer than 16 feet.
- Residential or commercial sites with low erosion potential such as sidewalk, median, or parking lot planter strips.

Projects that have variable slopes may include straw mulch and hydromulch when approved.

**01030.40 General** - Add the following sentence after the sentence beginning "Notify the Agency...":

Notify the Agency of the acreage to be seeded at least 7 Days before seeding begins.

**01030.42 Weed Control** - Add the following paragraph and bullets after the paragraph that begins "If a pesticide has been approved for..." and before subsection (a):

The Specified Weeds and plant species to be removed include the following:

- Himalayan blackberry
- Canary grass
- English ivy

Add the following subsection:

**01030.43(c) Seed Application Rates** - Determine the seeding application rate according to 01030.13(c). Apply seed mixes at the highest application rate calculated to provide not less than the specified application rate for each individual seed species in the mix.

Add the following subsection:

**01030.44(c)** Organic Fertilizer - Apply organic fertilizer at a rate of 1,800 pounds per acre at the following locations:

Biofiltration Swale Facility

## **SECTION 01050 - FENCES**

Comply with Section 01050 of the Standard Specifications.

## **SECTION 01065 - MONUMENT BOXES**

Section 01065, which is not a Standard Specification, is included in this Project by Special Provision.

# **Description**

**01065.00 Scope** - In addition to the requirements of Section 00470 and the Specifications, this Work consists of the following:

- Installing new monument frames and covers at the locations shown and where designated by the Engineer.
- Adjusting existing monument boxes to finish grade.

#### **Materials**

**01065.10 Materials** – Furnish Materials meeting the following requirements:

**01065.11 Concrete** – Provide Commercial Grade Concrete according to Section 00470, modifying the compressive strength requirement of 00440.12 from 3,000 to 4,000 psi at 28 days.

## 01065.12 Monument Box Frame and Cover -

- SE Jennings Avenue has a speed designation of 35 MPH or less.
- (a) Roadways With 35 MPH Speed, or Less Provide frames and covers consistent with Clackamas County Standard Drawing No. M100.
- **(b) Roadways Exceeding 35 MPH Speed** Provide frames and covers consistent with Clackamas County Standard Drawing No. M150.

Source materials from the following manufacturers, or approved equal:

## East Jordan Iron Works, Inc.

13127 State Avenue Marysville, WA 98271 (360) 651-6144 Fax (360) 651-6150

Anders Jorgenson Oregon Sales Representative (503) 774-4144 Fax (503) 775-3263 Cell (503) 367-7925 ajorgenson@ejiw.com

- Product No. 00367311 12" x 7-7/8" Monument Frame (catalog #3673Z)
- Product No. 00367324 Monument Cover with drop handle (catalog #3673A)
- Paving riser rings available

## Olympic Foundry Inc.

6530 NE 42nd Avenue Portland, OR 97218 (503)-281-3381 Fax (503)-284-5880

- o Part No. 14-6329 for 12" Monument Frame
- o Part No. 14-6338 for Cover
- Paving riser rings available

## Construction

**01065.40** General - Set monument case just below the pavement finished surface (0.00 inch to 0.25 inch) at the slope of the street surface.

For asphalt streets, there are two acceptable installation methods:

- When paving sequence allows for a break between base lifts and final lift, contractor shall construct base lift paving before installing monument boxes. Upon completion of base lifts, contractor shall excavate and install monument boxes, filling the void spaces with commercial grade concrete. The contractor will then pave final lift around monument boxes.
- When paving sequence does not allow for a break between base lifts and final lift, contractor shall complete paving before installing monument boxes. Upon completion of paving, contractor shall core drill through asphalt and install monument box, filling void spaces with commercial grade concrete to match finished grade.

For concrete streets, monument boxes must be set and secured in place prior to concrete pour.

The location of the required monument boxes have not been indicated on the plans. The location of the required monument boxes will be determined during construction. The County or designated representative will mark the locations of the required monument boxes. At a minimum, the P.C.'s, P.T.'s, P.R.C.'s, P.C.C.'s, and tangents at a minimum of 1000 foot increments along the centerline will be marked. Following acceptance of installed boxes, the Engineer will install monumentation.

#### Measurement

**01065.80 Measurement** – The quantity of monument boxes will be measured on the unit basis.

# **Payment**

**01065.90 Payment** - The accepted quantities of Work performed under this Section will be paid for at the Contract unit price, per unit of measurement, for the following items:

Pay Item	Unit of Measurement
(a) Monument Boxes	Each

No separate or additional payment will be made for adjusting existing monument boxes to finish grade. When the Contract Schedule of Items does not indicate payment for Work performed under this Section, no separate or additional payment will be made. Payment will be included in payment made for the appropriate items under which this Work is required.

Payment will be payment in full for furnishing and placing all Materials, and for furnishing all Equipment, labor, and Incidentals necessary to complete the Work as specified.

## SECTION 01069 - METAL HANDRAIL AND PEDESTRIAN FENCE

Section 01069, which is not a Standard Specification, is included in this Project by Special Provision.

# **Description**

**01069.00 Scope** - This Work consists of furnishing and installing metal handrails and pedestrian rail units as shown or directed.

#### **Materials**

**01069.10 Materials** - Furnish Materials meeting the following requirements:

Commercial Grade Concrete	00440
Metal Handrail	02830
Pedestrian Fence	02831

## Construction

## 01069.40 Metal Handrail and Pedestrian Fence:

- (a) Handrail Fabricate and install imbedded and bolted down metal handrail as shown.
- **(b) Pedestrian Fence** Fabricate and install pedestrian fence units as shown.

**01069.41 Welding** - Welding, welder qualifications, prequalification of weld details and inspection of welds shall conform to AWS D1.1 or AWS D1.2. Submit all welding procedure specifications 7 Days prior to fabrication to the Engineer for approval.

**01069.42 Concrete Footings** - Dimensions of footings shall not be less than shown and shall fill the excavated areas. Place the concrete with contact against firm Soil at the sides and bottom and tamp around the posts and brace ends after the posts and braces have been brought to and firmly held in proper position. Strike off, slope or crown and smooth the surface of the concrete at the ground level to shed water. Allow to cure for at least 5 Calendar Days before subjecting the posts to strain.

Excavate for concrete footings to reasonably Neat Lines, but not less than the specified dimensions in Soil, or not less than 18 inches deep in Rock. Prevent disturbance of original ground at the sides and bottom of the excavation.

Dispose of Materials removed under these provisions, including excess excavation, in a satisfactory manner.

# 01069.43 Bolt Holes:

(a) Punched Holes - Use a die with a diameter not exceeding the diameter of the punch by more than 1/16 inch. Ream holes that are required to be enlarged to admit the anchor bolts. Make clean cut holes without torn or ragged edges.

**(b)** Accuracy of Punched Holes - After punching the holes in the plate, stack the plates with the edges even and insert a cylindrical pin, 1/8 inch smaller in diameter than the nominal size of the punched hole, through the punched holes perpendicular to the face of the plate. No drifting of the rod while passing through each of the punched holes in the stack is allowed. Ensure that the edges of the stack stay in alignment. Non-conforming pieces will be rejected.

#### Measurement

**01069.80 Measurement** - The quantities of Work performed under this Section will be measured according to the following:

- Length Basis Metal handrail will be measured on the length basis, by measuring along the top rail member, from center of end post to center of end post.
- **Unit Basis** Pedestrian fence will be measured on the unit basis. Pedestrian fence will be counted for each 62 inch long unit.

## **Payment**

**01069.90 Payment** - The accepted quantities of Work performed under this Section will be paid for at the Contract unit price, per unit of measurement, for the following items:

Pay Item	Measuren	nent	
(a) Metal Han	drail,	Rails	Foot
(b) Pedestrian	FenceE	ach	

In item (a), the number of rails will be inserted in the blank.

Payment will be payment in full for furnishing and placing all Materials, and for furnishing all Equipment, labor, and Incidentals necessary to complete the Work as specified.

# **SECTION 01070 - MAILBOX SUPPORTS**

Comply with Section 01070 of the Standard Specifications.

## **SECTION 02001 - CONCRETE**

Comply with Section 02001 of the Standard Specifications modified as follows:

02001.02 Abbreviations and Definitions:

Add the following definition:

**Lightweight Concrete** - Structural concrete having a specified density using lightweight Aggregates.

Replace the sentence that begins "Pozzolans - Fly ash, silica fume..." with the following sentence:

Pozzolans - Fly ash, natural Pozzolans, silica fume, and high-reactivity Pozzolans.

Replace the sentence that begins "**Supplementary Cementitious Materials** - Fly ash, silica fume..." with the following sentence:

**Supplementary Cementitious Materials** - Pozzolans and ground granulated blast furnace slag.

**02001.15(a) Current Mix Designs** - Replace this subsection, except for the subsection number and title, with the following:

Mix designs that meet the requirements for the specified class of concrete and are currently being used or have been used within the past 24 months on any project, public or private, may be submitted for review. Provide individual test results that comprise the average if more than one data point exists. For paving designs the flexural strength testing must be from within the last two years. For HPC designs the length change and permeability tests must be from within the last two years.

**02001.15(b)(1) Trial Batch Plastic Properties** - Replace this subsection, except for the subsection number and title, with the following:

For each trial batch, test according to the following test methods:

Test	Test Method
Sampling Fresh Concrete	WAQTC TM 2
Concrete Temperature	AASHTO T 309
Slump	AASHTO T 119 <sup>1</sup>
Air Content	AASHTO T 152 or T 196 <sup>2</sup>
Density	AASHTO T 121
Yield	AASHTO T 121
Molding Concrete Specimens	AASHTO T 23 or R 39 $^{3}$
Water Cement Ratio	4

- <sup>1</sup> For drilled shaft concrete test the slump retention by subsequent tests at half-hour intervals for the duration of the estimated drilled shaft placement, including temporary casing extraction. Report in table or graphical format.
- <sup>2</sup> Use AASHTO T 196 for lightweight concrete.
- Cast cylinders in single use plastic molds.
- Use ODOT's Field Operating Procedure for AASHTO T 121 in the MFTP.

**02001.15(c)(12) Documentation of Average Compressive Strength** - Replace this subsection, except for the subsection number and title, with the following:

Provide an analysis, showing applicable data and calculations for documentation of average compressive strength according to ACI 301.

02001.20(a) Strength - Replace Table 2001-1 with the following Table 2001-1:

Table 02001-1

Concrete Strength and Water/Cementitious Material (w/cm) Ratio								
Type of Concrete	Strength f'c (psi)	Maximum w/cm Ratio						
	3300	0.50						
Structural	3300 (Seal)	0.45						
	4000							
	4000 (Drilled Shaft)	0.48						
	HPC4500							
	HPC(IC)4500	0.40						
	5000 +							
Paving	4000	0.44						
PPCM's	5000	0.48						
(with cast-in- place decks and	5500	0.44						
no entrained air)	6000 +	0.42						

**02001.20(a)(1)** Required Average Compressive Strength (f'<sub>cr</sub>) - Replace this subsection, except for the subsection number and title, with the following:

Except for PPCM designs, provide the required average compressive strength according to ACI 301 for mix design approval.

**02001.30(e)(1) HPC Coarse Aggregate Content** - Delete the paragraph that begins "Two or more Aggregate products or sources..."

## SECTION 02030 - SUPPLEMENTARY CEMENTITIOUS MATERIALS

Comply with Section 02030, of the Standard Specifications modified as follows:

**02030.00 Scope** - Replace this subsection, except for the subsection number and title, with the following:

This Section includes the requirements for fly ash, natural pozzolans, silica fume, ground granulated blast furnace slag and high reactivity pozzolans used in portland cement concrete.

**02030.10** Fly Ash - Replace this subsection, except for the subsection number and title, with the following:

Furnish Class C and Class F fly ash from the QPL and conforming to AASHTO M 295 (ASTM C618).

Add the following subsection:

**02030.15 Natural Pozzolans** - Furnish Class N natural pozzolans from the QPL and conforming to AASHTO M 295 (ASTM C618).

**02030.50 Metakaolin** - Replace this subsection with the following:

**02030.50 High Reactivity Pozzolans** - Furnish high-reactivity pozzolans from the QPL and conforming to AASHTO M 321.

## **SECTION 02050 - CURING MATERIALS**

Comply with Section 02050 of the Standard Specifications modified as follows:

**02050.10 Liquid Compounds** - Replace the paragraph that begins "Furnish liquid membrane-forming curing..." with the following paragraph:

Furnish liquid membrane-forming curing compounds from the QPL and meeting the requirements of ASTM C309. Before use, submit a one quart sample from each lot for testing. Samples will be tested according to ODOT TM 721. Samples are not required for curing compounds used on Commercial Grade Concrete.

#### **SECTION 02080 - GROUT**

Comply with Section 02080 of the Standard Specifications.

## **SECTION 02415 - PLASTIC PIPE**

Comply with Section 02415 of the Standard Specifications modified as follows:

**02415.40** Polypropylene Pipe - Replace the sentence that begins "Dual wall polypropylene pipe ..." with the following sentence:

Dual wall polypropylene pipe and fittings ...... ASTM F2764

### **SECTION 02440 - JOINT MATERIALS**

Comply with Section 02440 of the Standard Specifications.

#### **SECTION 02510 - REINFORCEMENT**

Comply with Section 02510 of the Standard Specifications modified as follows:

**02510.11(c)** Coated Reinforcement Ties and Supports - Replace this subsection, except for the subsection number and title, with the following:

Ties and supports for coated reinforcement, including ties for coated to uncoated reinforcement connections, shall be nonmetallic coated.

### **SECTION 02560 - FASTENERS**

Comply with Section 02560 of the Standard Specifications.

# **SECTION 02690 - PCC AGGREGATES**

Comply with Section 02690 of the Standard Specifications modified as follows:

**02690.20(e)** Grading and Separation by Sizes for Prestressed Concrete - Replace this subsection with the following subsection:

**02690.20(e) Grading and Separation by Sizes -** Sampling shall be according to AASHTO R 90. Sieve analysis shall be according to AASHTO T 27 and AASHTO T 11. Provide aggregates meeting the gradation requirements of Table 02690-1 for structural concrete. Provide a CAgT to perform sampling and testing when required.

#### Table 02690-1

Gradation of Coarse Aggregates Percent passing (by Weight)

			Sieve Size										
Size Number	Nominal Size Square Openings	(2½ in.)	(2 in.)	(1½ in.)	(1 in.)	(¾ in.)	(½ in.)	(¾ in.)	(No. 4)	(No. 8)	(No. 16)	(No. 50)	(No. 200)
3	(2 to 1 in.)	100	90 to 100	35 to 70	0 to 15	_	0 to 5	_	_	_	_	_	**
357*	(2 in. to No. 4)	100	95 to 100	_	35 to 70	_	10 to 30	_	0 to 5	_	_	_	**
4	(1½ to ¾ in.)	_	100	90 to 100	20 to 55	0 to 15	_	0 to 5	_	_	_	_	**
467*	(1½ to No. 4)	_	100	95 to 100	_	35 to 70	_	10 to 30	0 to 5	_	_	_	**
5	(1 to ½ in.)	_	_	100	90 to 100	20 to 55	0 to 10	0 to 5	_	_	_	_	**
56	(1 to ¾ in.)	_	_	100	90 to 100	40 to 85	10 to 40	0 to 15	0 to 5	_	_	_	**
57	(1 to No. 4)	_	_	100	95 to 100	_	25 to 60	_	0 to 10	0 to 5	_	_	**
6	(¾ to ¾ in.)	_	_	_	100	90 to 100	20 to 55	0 to 15	0 to 5	_	_	_	**
67	(¾ to No. 4)	_	_	_	100	90 to 100	_	20 to 55	0 to 10	0 to 5	_	_	**
68	(¾ to No. 8)	_	_	_	100	90 to 100	_	30 to 65	5 to 25	0 to 10	0 to 5	_	**
7	(½ to No. 4)	_	_	_	_	100	90 to 100	40 to 70	0 to 15	0 to 5	_	_	**
78	(½ to No. 8)	_	_	_	_	100	90 to 100	40 to 75	5 to 25	0 to 10	0 to 5	_	**
8	(¾ to No. 8)	_	_	_	_	_	100	85 to 100	10 to 30	0 to 10	0 to 5	_	**
89	(% to No. 16)	_	_	_	_	_	100	90 to 100	20 to 55	5 to 30	0 to 10	0 to 5	**

<sup>\*</sup> Use two or more seperated sizes which when combined meet these gradation limits.

**02690.20(f) Grading and Separation by Sizes for Other Concrete** - Delete this subsection.

**02690.30(g) Grading** - In the paragraph that begins "Sampling shall be according to...", replace the words "AASHTO T 2" with the words "AASHTO R 90".

## **SECTION 02830 - METAL HANDRAIL**

Section 02830, which is not a Standard Specification, is included in this Project by Special Provision.

## **Description**

**02830.00 Scope** - This Section includes the requirements for the steel in handrail for stairways and pedestrian facilities.

#### **Materials**

**02830.10 Shapes, Plates, and Bars** - Shapes, plates, and bars shall conform to ASTM A36.

Punch anchor plate bolt holes at the locations shown before fabrication.

**02830.20 Steel Pipe** - Steel pipe shall conform to ASTM A500, seamless, Grade B.

**02830.21 Steel Tube** - Steel tube shall conform to ASTM A500, seamless, Grade B.

<sup>\*\*</sup> See 02690.20(a). Do Not evaluate material passing the No. 200 sieve according to 00165.40.

**02830.22 Fasteners** - Fasteners shall meet the requirements of Section 02560. Machine screws shall be SAE 18 8 stainless steel.

**02830.30 Galvanizing** - Hot-dip galvanize all handrail components according to AASHTO M 111 (ASTM A123) after shop fabrication.

**02830.31 Repair of Hot-Dip Galvanizing** - Repair damaged hot-dip galvanizing according to ASTM A780 and ASTM A123. Minimum zinc content for Method A2 is 94 percent on the dry film.

**02830.40 Incidentals** - Plates, caps, and miscellaneous pieces necessary to complete the rail shall be as shown.

**02830.50** Acceptance - Acceptance of handrail Materials will be according to 00165.35 and this Section.

## **SECTION 02926 - HIGHWAY ILLUMINATION MATERIALS**

Comply with Section 02926 of the Standard Specifications modified as follows:

Add following subsection:

**02926.41(f) Electrical Splice Materials** - Furnish electrical splice materials meeting the following requirements:

- **Split bolt** Made of silicon bronze to securely join the wires both mechanically and electrically.
- **Heat-shrink tubing** Split-resistant and adhesive-lined tube made of polyolefin complying with UL 224 or UL 486D, temperature range -67 °F to 230 °F, with 600 V rated inner melting wall or liner to provide void-free encapsulated insulation.
- **Insulating rubber tape** Electrical grade, nondrying, rubber based, elastic type complying with ASTM D4388.
- **Insulating vinyl plastic tape** Low temperature (0 °F) resistant, vinyl chloride plastic, electrical insulating tape with pressure-sensitive adhesive. Comply with ASTM D3005.

# GENERAL CONDITIONS FOR CONSTRUCTION FOR CLACKAMAS COUNTY

## **TABLE OF CONTENTS**

PARTUU	IUU - GENERAL CONDITIONS	1
Section 0	0110 - Organization, Conventions, Abbreviations, and Definitions	1
00110 00	Organization of Specifications	1
00110.05	Conventions Used throughout the Specifications Include	1
	Abbreviations	
	Definitions	
Section 0	0120 - Bidding Requirements and Procedures	15
00120.00	Prequalification of Bidders	15
	General Bidding Requirements – See Bid Documents, and:	
00120.10	Bid Booklet	16
00120.15	Examination of Work Site and Solicitation Documents; Consideration of	
0040040	Conditions to be Encountered	16
00120.16	Material, Equipment, and Method Substitutions- See Section 2, Instructions to Bidders, Article 3	10
00120 17	Use of Agency-Owned Land for Staging or Storage Areas	
	Interpretation of Quantities in Bid Schedule	
	Subsurface Investigations	
00120.25	Changes to Plans, Specifications, or Quantities before Opening of Bids	۱۲۱۲
00120.30	Preparation of Bids	۱۲۱۲
	Submittal of Bids	
	Revision or Withdrawal of Bids	
	Opening and Comparing Bids	
	Rejection of Non-responsive Bids	
	Reciprocal Preference for Oregon Resident Bidders	
	Disqualification of Bidders	
00120.91	Rejection of Bid on Grounds of Nonresponsibility of Bidder	22
	0130 - Award and Execution of Contract	
	Award of Contract	
	Right to Protest Award  Cancellation of Award	
	Contract Booklet	
	Contract Submittals	
	Execution of Contract and Bonds	
	Failure to Execute Contract and Bonds	
	Release of Bid Guaranties	
	Project Site Restriction	
	Notice to Proceed	
	0140 - Scope of Work	
	Purpose of Contract	
	Typical Sections	
	Thickness	
	Agency-Required Changes in the Work	
	Differing Site Conditions	
	Environmental Pollution Changes	
	Extra Work Disputed Work	
	Cost Reduction Proposals	
+U./U	Qual NeuroliVII F 1000ada	28

00140.80	Use of Publicly Owned Equipment	31
00140.90	Final Trimming and Cleanup	31
	0150 - Control of Work	
	Authority of the Engineer	
	Project Manager's Authority and Duties	
	Inspector's Authority and Duties	
	Coordination of Contract Documents	
	Construction Stakes, Lines, and Grades	
	Acceptability of Materials and Work	
	Delivery of Notices -	35
00150.35	Plans, 3D Engineered Models, Working Drawings, and 3D Construction	0.0
00450.07	ModelsEquipment Lists and Other Submittals	عد
	Cooperation and Superintendence by the Contractor	
	Cooperation with Utilities	
	Cooperation with Other Contractors	
	Construction Equipment Restrictions	
	Detrimental Operations	
	Protection and Maintenance of Work During Construction	
	Removal of Unacceptable and Unauthorized Work	
	Final Inspection	
	Post-Construction Review	
00150.95	Final Acceptance	43
	Maintenance Warranties and Guarantees	
00150.97	Responsibility for Materials and Workmanship	43
Section 0	0160 - Source of Materials	44
	Definitions	
	Notification of Source of Supply and Materials	
00100.01	Qualified Products List (QPL)	<del>٦</del> -
	Electrical Equipment and Materials	
	Ordering, Producing, and Furnishing Materials	
	Preferences for Materials	
	Cargo Preference Act Requirements	
	Agency-Furnished Materials	
	Agency-Furnished Sources	
	Agency-Controlled Land; Limitations and Requirements	
	Contractor-Furnished Materials and Sources	
	Requirements for Plant Operations	
	Requirements for Sources of Borrow and Aggregate	
Section 0	0165 - Quality of Materials	51
00165.00	General	51
	Rejected Materials	
00165.02	Materials Conformance and Quality Compliance Documents	51
	Testing by Agency	
	Costs of Testing.	
	Materials Acceptance Guides	
00165.20	Materials Specifications and Test Method References	52
00165.30	Field-Tested Materials	53
	Nonfield-Tested Materials	
	Statistical Analysis	
	Statistical Acceptance Sampling and Testing	
00165.70	Use of Materials without Acceptable Materials Conformance Documents	62
	Storage and Handling of Materials	62 62

00.60100	Measurement	. 63
00165.90	Incidental Basis	. 63
00165.91	Fabrication Inspection Expense	63
Section 0	0170 - Legal Relations and Responsibilities	64
	General	
	Other Agencies Affecting Agency Contracts	
00170.02	Permits, Licenses, and Taxes	. 67
00170.03	Furnishing Right-of-Way and Permits	. 67
00170.04	Patents, Copyrights, and Trademarks	. 67
00170.05	Assignment of Antitrust Rights	67
00170.07	Record Requirements	. 68
00170.10	Required Payments by Contractors	. 71
	Public Works Bond	
	Protection of Navigable Waters	
00170.60	Safety, Health, and Sanitation Provisions	. 73
	Industrial Accident Protection	
	Labor Nondiscrimination	
	Payment for Medical Care	
00170.65	Minimum Wage and Overtime Rates for Public Works Projects	. 74
	Insurance	
	Independent Contractor Status	
00170.71	Employee Drug Testing Program	. o <u>z</u>
00170.71	Conflict of Interest	. ๐๐
	Third Party Beneficiary	
	Responsibility for Damage to Work	
	Responsibility for Damage to Property and Facilities	
	Responsibility for Defective Work	
00170.00	Responsibility for Defective Work	. 00
	Protection of Utility Fire control and Pailroad Property and Services: Popair:	
	Protection of Utility, Fire-control, and Railroad Property and Services; Repair;	88
00170.89	Roadway Restoration	
00170.89 00170.92	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations	. 89
00170.89 00170.92 00170.93	Roadway Restoration	. 89 . 89
00170.89 00170.92 00170.93 00170.94	Roadway Restoration	. 89 . 89 . 89
00170.89 00170.92 00170.93 00170.94 Section 0	Roadway Restoration	. 89 . 89 . 89
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00	Roadway Restoration	. 89 . 89 . 89 . <b>90</b>
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05	Roadway Restoration	. 89 . 89 . 89 . <b>90</b> . 90
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05	Roadway Restoration	. 89 . 89 . 89 . <b>90</b> . 90
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.10	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  0180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract	. 89 . 89 . <b>90</b> . 90 . 90
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.10 00180.15	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  0180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense	. 89 . 89 . 90 . 90 . 90 . 90
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.10 00180.15 00180.20	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  0180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations	. 89 . 89 . 90 . 90 . 90 . 90 . 91
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.10 00180.15 00180.20	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  0180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense	. 89 . 89 . 90 . 90 . 90 . 90 . 91
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.10 00180.15 00180.20 00180.21	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  0180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting	. 89 . 89 . 90 . 90 . 90 . 90 . 90 . 91 . 93
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.10 00180.15 00180.20 00180.21 00180.22 00180.30	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  0180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor.  Materials, Equipment, and Work Force	. 89 . 89 . 90 . 90 . 90 . 90 . 90 . 91 . 93 . 96
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.10 00180.15 00180.20 00180.21 00180.22 00180.30	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  0180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor.  Materials, Equipment, and Work Force	. 89 . 89 . 90 . 90 . 90 . 90 . 90 . 91 . 93 . 96
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.15 00180.20 00180.21 00180.22 00180.30 00180.31	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  O180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor Materials, Equipment, and Work Force Required Materials, Equipment, Products, and Methods.	. 89 . 89 . 90 . 90 . 90 . 90 . 91 . 93 . 96 . 96
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.15 00180.20 00180.21 00180.22 00180.30 00180.31 00180.32	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  O180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor Materials, Equipment, and Work Force Required Materials, Equipment, Products, and Methods Alternative Materials, Equipment, and Methods	. 89 . 89 . 90 . 90 . 90 . 90 . 90 . 93 . 96 . 96
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.10 00180.15 00180.20 00180.21 00180.22 00180.30 00180.31 00180.32 00180.32	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  O180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor Materials, Equipment, and Work Force Required Materials, Equipment, Products, and Methods.	. 89 . 89 . 90 . 90 . 90 . 90 . 90 . 93 . 96 . 96 . 97 . 98
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.15 00180.20 00180.21 00180.22 00180.30 00180.31 00180.32 00180.32 00180.40 00180.41	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  O180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor Materials, Equipment, and Work Force Required Materials, Equipment, Products, and Methods Alternative Materials, Equipment, and Methods Limitation of Operations. Project Work Schedules	. 89 . 89 . 90 . 90 . 90 . 90 . 91 . 93 . 96 . 96 . 97 . 98 . 98
00170.89 00170.92 00170.93 00170.94 <b>Section 0</b> 00180.00 00180.05 00180.06 00180.15 00180.20 00180.21 00180.22 00180.30 00180.31 00180.32 00180.32 00180.40 00180.41 00180.42	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  O180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor Materials, Equipment, and Work Force Required Materials, Equipment, Products, and Methods Alternative Materials, Equipment, and Methods Limitation of Operations. Project Work Schedules Preconstruction Conference	. 89 . 89 . 90 . 90 . 90 . 90 . 93 . 96 . 96 . 97 . 98 . 98
00170.89 00170.92 00170.93 00170.94 Section 0 00180.05 00180.05 00180.15 00180.20 00180.21 00180.22 00180.30 00180.31 00180.32 00180.40 00180.41 00180.42 00180.42	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass Use of Explosives  O180 - Prosecution and Progress Scope Assignment/Delegation of Contract Assignment of Funds Due under the Contract Responsibility for Contract Agency's Right to Do Work at Contractor's Expense Subcontracting Limitations Subcontracting Payments to Subcontractors and Agents of the Contractor Materials, Equipment, and Work Force Required Materials, Equipment, Products, and Methods Alternative Materials, Equipment, and Methods Limitation of Operations. Project Work Schedules Preconstruction Conference Commencement and Performance of Work	. 89 . 89 . 90 . 90 . 90 . 90 . 91 . 93 . 96 . 96 . 96 . 98 . 98 107
00170.89 00170.92 00170.93 00170.94 Section 0 00180.05 00180.05 00180.15 00180.20 00180.21 00180.21 00180.31 00180.32 00180.31 00180.32 00180.40 00180.41 00180.42 00180.43 00180.43	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass	. 89 . 89 . 90 . 90 . 90 . 90 . 91 . 93 . 96 . 96 . 97 . 98 . 98 . 107 107
00170.89 00170.92 00170.93 00170.94  Section 0 00180.05 00180.05 00180.15 00180.20 00180.21 00180.22 00180.30 00180.31 00180.31 00180.32 00180.40 00180.41 00180.42 00180.43 00180.43 00180.43 00180.60	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass	. 89 . 89 . 90 . 90 . 90 . 90 . 91 . 93 . 96 . 96 . 97 . 98 107 108
00170.89 00170.92 00170.93 00170.94  Section 0 00180.05 00180.05 00180.15 00180.20 00180.21 00180.22 00180.31 00180.32 00180.31 00180.32 00180.40 00180.41 00180.42 00180.43 00180.43 00180.50 00180.65	Roadway Restoration Fencing, Protecting Stock, and Safeguarding Excavations Trespass	. 89 . 89 . 90 . 90 . 90 . 90 . 91 . 93 . 96 . 96 . 97 . 98 . 107 108 109

00180.85	Failure to Complete on Time; Liquidated Damages	112
00180.90	Termination of Contract and Substituted Performance	113
Section (	00190 - Measurement of Pay Quantities	115
00190 00	Scope	115
	Measurement Guidelines	
	Contractor to Provide Vehicle Weigh Scales	
	Plant Scales.	
00100.00	Tidit Godios	120
	00195 - Payment	
	Scope and Limit	
	Payment For Changes in Materials Costs	
00195.12	Steel Material Price Escalation/De-Escalation Clause	121
00195.20	Changes to Plans or Character of Work	123
00195.30	Differing Site Conditions	124
00195.40	Unreasonable Delay by the Agency	124
00195.50	Progress Payments and Retained Amounts	124
00195.60	Advance Allowance for Materials on Hand	128
00195.70	Payment under Terminated Contract	129
00195.80	Allowance for Materials Left on Hand	130
	Final Payment	
00195.95	Error in Final Quantities and Amounts	131
Section (	00196 - Payment for Extra Work	122
	Negotiated Price	
	Force Account	
Section (	0197 - Payment for Force Account Work	134
	Scope	
	General	_
	Materials	
	Equipment	
	Labor	
	Invoices for Special Services	
	Percentage Allowances	
00197.90	Billings	138
Section (	00199 - Disagreements, Protests, and Claims	139
00199 00	General	139
	Procedure for Resolving Disagreements	
	Protest Procedure	
	Claims Procedure	
	Claim Review Procedure	

#### **PART 00100 - GENERAL CONDITIONS**

## Section 00110 - Organization, Conventions, Abbreviations, and Definitions

#### Organization

#### 00110.00 Organization of Specifications - The Specifications are comprised of the following:

- The "General Conditions for Construction for (Certified LPA) Clackamas County" published by the Agency, which contain Part 00100 "General Conditions", which deal with the solicitation process and contractual relationships.
- The "2021 Oregon Standard Specifications for Construction," Parts 00200 through 03000, published by the Oregon Department of Transportation which contain the detailed "Technical Specifications" involved in prosecution of the Work, organized by subject matter; and
- · The Special Provisions.

#### In addition, throughout the Specifications:

- Each Part is divided into Sections and Subsections.
- Reference to a Section includes all applicable requirements of the Section.
- When referring to a Subsection, only the number of the Subsection is used; the word "Subsection" is implied.
- Where Section and Subsection numbers are not consecutive, the interval has been reserved for use in the Special Provisions or future expansion of the Standard Specifications.

#### Conventions

#### 00110.05 Conventions Used throughout the Specifications Include:

- **a) Grammar** The "General Conditions for Construction for (Certified LPA) Clackamas County", Part 00100 "General Conditions", is written in the indicative mood, in which the subject is expressed. The "2021 Oregon Standard Specifications for Construction", published by the Oregon Department of Transportation, Parts 00200 through 03000, the detailed "Technical Specifications", are generally written in the imperative mood, in which the subject is implied. Therefore, throughout Parts 00200 through 03000, and on the Plans:
  - The subject, "the Contractor", is implied.
  - "Shall" refers to action required of the Contractor, and is implied.
  - "Will" refers to decisions or actions of the Agency and/or the Engineer.
  - The following words, or words of equivalent meaning, refer to the actions of the Agency and/or the Engineer, unless otherwise stated: "allowed", "directed", "established", "permitted", "ordered", "designated", "prescribed", "required", "determined".
  - The words "approved", "acceptable", "authorized", "satisfactory", "suitable", "considered", and "rejected", "denied", "disapproved", or words of equivalent meaning, mean by or to the Agency and/or the Engineer, subject in each case to Section 00150 of the General Conditions.
  - The words "as shown", "shown", "as indicated", or "indicated" mean "as indicated on the Plans".
  - Certain Subsections labeled "Payment" contain statements to the effect that the accepted quantities "will be paid for at the Contract unit price, per unit of measurement, for the following

items" (followed by a list of items). In such cases, the Agency will pay for only those Pay Items listed in the Schedule of Items.

- **(b) Capitalization of Terms** Capitalized terms, other than titles, abbreviations, and grammatical usage, indicate that they have been given a defined meaning in the Standard Specifications. Refer to Section 00110.20 "Definitions". Defined terms will always be capitalized in Part 00100; in Parts 00200 through 03000, defined terms will generally not be capitalized, with the notable exception of "the Contractor", "the Agency", and "the Engineer".
- **(c) Punctuation** In this publication the "outside method" of punctuation is employed for placement of the comma and the period with respect to quotation marks. Only punctuation that is part of the quoted matter is placed within quotation marks.
- (d) References to Laws, Acts, Regulations, Rules, Ordinances, Statutes, Orders, and Permits References are made in the text of the Specifications to "laws", "acts", "rules", "statutes", "regulations", "ordinances", etc. (collectively referred to for purposes of this Subsection as "Law"), and to "orders" and "permits" (issued by a governmental authority, whether local, state, or federal, and collectively referred to for purposes of this Subsection as "Permits"). Reference is also made to "applicable laws and regulations". The following conventions apply in interpreting these terms, as used in the Specifications.
  - Statutes and Rules Oregon Revised Statutes (ORS) and Oregon Administrative Rules (OAR) referenced in the Specifications are accessible on line, including through the Oregon Legislative Counsel Committee website (see 00110.05(e)) and through the Oregon Secretary of State Archives Division web site. Clackamas County's Local Contract Review Board (LCRB) Rules are accessible online on the County's website (see 00110.05(e)).
  - Law In each case, unless otherwise expressly stated therein, the Law is to be understood to be the current version in effect. This also applies where a specific Law is referenced or cited, regardless of whether the text of the Law has been included in the Specifications or not, and regardless of whether the text of the Law has been summarized or paraphrased. In each case, the current version of the Law is applicable under any contract. The reader is therefore cautioned to check the actual text of the Law to confirm that the text included in the Specifications has not been modified or superseded.
  - Permits Orders and permits issued by a government agency may be modified during the course of performing the work under a contract. Therefore, wherever the term "order" or "permit" is used in the Specifications, it is intended to refer to the then-current version. That version may be embodied in a modified, superseding order or permit, or it may consist of all terms and conditions of prior orders or permits that have not been superseded, as well as the additional terms added by amendment or supplement. In certain cases, the orders and/or permits are identified by name in the Specifications; in other cases the terms are used in the generic sense. The reader is cautioned to check the text(s) of each order and permit identified either by name or by generic reference.
  - Applicable Laws and Regulations Where phrases such as "applicable law", "applicable laws and regulations", "applicable legal requirements" or similar phrases appear, they are to be understood as including all applicable laws, acts, regulations, administrative rules, ordinances, statutes, and orders and permits issued by a governmental or regulatory authority. The words "law" or "laws" may or may not be capitalized in such phrases.
- **(e)** Reference to Websites For Specifications that reference this Subsection, the Agency will identify the website addresses in the Special Provisions.

#### **Abbreviations**

**00110.10 Abbreviations** - Following are meanings of abbreviations used in the Standard Specifications, in the Special Provisions, on the Plans, and in other Contract Documents. Other abbreviations and meanings of abbreviations may be used in the individual Sections of the Standard Specifications to which they apply, in the Special Provisions, and in OAR 731-005 and OAR 731-007.

CCDA - Clackamas County Development Agency

DTD - Clackamas County Department of Transportation and Development

LCRB - Local Contract Review Board

NCPRD - North Clackamas Parks and Recreation District

ODFW - Oregon Department of Fish and Wildlife

UNS - Utility Notification System

WES - Water Environment Services of Clackamas County

AAR - Association of American Railroads

AASHTO - American Association of State Highway and Transportation Officials

ABC - Associated Builders and Contractors, Inc.

AC - Asphalt Concrete

ACI - American Concrete Institute
ACP - Asphalt Concrete Pavement

ACWS - Asphalt Concrete Wearing Surface

AGC - Associated General Contractors of America

AIA - American Institute of Architects

AISC - American Institute of Steel Construction

AISI - American Iron and Steel Institute

AITC - American Institute of Timber Construction
ANSI - American National Standards Institute

APA - Engineered Wood Association
APWA - American Public Works Association

AREMA - American Railway Engineering and Maintenance of Right-of-Way Association

ASCE - American Society of Civil Engineers

ASME - American Society of Mechanical Engineers
ASTM - American Society for Testing and Materials

ATPB - Asphalt Treated Permeable Base

ASTV - Actual Strength Test Value AWG - American Wire Gauge

AWPA - American Wood Protection Association

AWS - American Welding Society

AWWA - American Water Works Association
CAgT - Certified Aggregate Technician
CAT-I - Certified Asphalt Technician I
CAT-II - Certified Asphalt Technician II

CBM - Certified Ballast Manufacturers
CCO - Contract Change Order

CCT - Concrete Control Technician
CDT - Certified Density Technician

CEBT - Certified Embankment and Base Technician

CFR - Code of Federal Regulations

CMDT - Certified Mixture Design Technician

CPF - Composite Pay Factor

CRSI - Concrete Reinforcing Steel Institute

CS - Commercial Standard, Commodity Standards Division, U.S. Department of

Commerce

CSTT - Concrete Strength Testing Technician

D1.1 - Structural Welding Code - Steel, American Welding Society, current edition

D1.5 - Bridge Welding Code, American Welding Society, current edition

DBE - Disadvantaged Business Enterprise

DEQ - Department of Environmental Quality, State of Oregon

DOGAMI - Department of Geology and Mineral Industries, State of Oregon

DSL - Department of State Lands, State of Oregon

EAC - Emulsified Asphalt Concrete

EPA - U.S. Environmental Protection Agency
ESCP - Erosion and Sediment Control Plan

FHWA - Federal Highway Administration, U.S. Department of Transportation
FSS - Federal Specifications and Standards, General Services Administration

GSA - General Services Administration

ICEA - Insulated Cable Engineers Association (formerly IPCEA)

IES - Illuminating Engineering Society

IMSA - International Municipal Signal Association
 ISO - International Standards Organization
 ISSA - International Slurry Surfacing Association
 ITE - Institute of Transportation Engineers

JMF - Job Mix Formula

MFTP - Manual of Field Test Procedures (ODOT)

MIL - Military Specifications
MSC - Minor Structure Concrete

MUTCD - Manual on Uniform Traffic Control Devices for Streets and Highways, FHWA,

U.S. Department of Transportation

NEC - National Electrical Code

NEMA - National Electrical Manufacturer's Association

NESC - National Electrical Safety Code

NIST - National Institute of Standards and Technology
NPDES - National Pollutant Discharge Elimination System

NPS - Nominal Pipe Size (dimensionless)
 OAR - Oregon Administrative Rules
 ODA - Oregon Department of Agriculture
 ODOT - Oregon Department of Transportation

ORS - Oregon Revised Statutes

OR-OSHA - Oregon Occupational Safety and Health Division of the Department of Consumer

and Business Services

OSHA - Occupational Safety and Health Administration, U.S. Department of Labor

PCA - Portland Cement Association
PCC - Portland Cement Concrete

PCI - Precast/Prestressed Concrete Institute

PCP - Pollution Control Plan
PF - Pay Factor of a constituent
PLS - Professional Land Surveyor
PMBB - Plant Mixed Bituminous Base
PTI - Post-Tensioning Institute

PUC - Public Utility Commission, State of Oregon

QA - Quality Assurance QC - Quality Control QCT - Quality Control Technician

QL - Quality Level

QPL - Qualified Products List

RAP - Reclaimed Asphalt Pavement

REA - Rural Electrification Administration, U.S. Department of Agriculture
RMA - Radio Manufacturers Association or Rubber Manufacturers Association

SAE - Society of Automotive Engineers

SI - International System of Units (Système Internationale)

SRCM - Soil and Rock Classification Manual (ODOT)

SSPC - Society for Protective Coatings T - Tolerances, AASHTO Test Method

TM - Test Method (ODOT)

TV - Target Value

UBC - Uniform Building Code (as adopted by the State of Oregon)

UL - Underwriters Laboratory, Inc.

UPC - Uniform Plumbing Code (as adopted by the State of Oregon)

USC - United States Code

WAQTC - Western Alliance for Quality Transportation Construction

WCLIB - West Coast Lumber Inspection Bureau
WWPA - Western Wood Products Association

#### **Definitions**

**00110.20 Definitions** - Following are definitions of words and phrases used in the Standard Specifications, in the Special Provisions, on the Plans, and in other Contract Documents. Other definitions may be in the individual Sections of the Standard Specifications to which they apply, in the Special Provisions, and in OAR 731-005 and OAR 731-007.

**3D Engineered Model** - The Agency-prepared electronic file(s) that identify northing, easting, and elevation to represent the Work to be performed. The 3D Engineered Model may include the surface model(s) or other designed Work elements and is an electronic representation of the line, grade, and Cross Section applicable to the Project.

**3D Construction Model** - Supplemental unstamped 3D model, not furnished by the Agency, that the Contractor is required to submit to the Engineer.

**Act of God or Nature** - A natural phenomenon of such catastrophic proportions or intensity as would reasonably prevent performance.

**Actual Strength Test Value (ASTV)** - The ASTV at 28 Days is the average compressive strength of the three cylinders tested. All specimens that show definite evidence, other than low strength, of improper sampling, molding, handling, curing, or testing shall be discarded. The average strength of the remaining cylinders shall then be considered the test result.

**Addendum** - A written or graphic modification, issued before the opening of Bids, which revises, adds to, or deletes information in the Solicitation Documents or previously issued Addenda.

**Additional Work** - Increased quantities of any Pay Item, within the scope of the Contract, for which a unit price has been established.

**Advertisement** - The public announcement (Notice to Contractors) inviting Bids for Work to be performed or Materials to be furnished.

Agency - The County, as defined below, which has entered into a Contract with the Contractor.

**Agency-Controlled Lands** - Lands owned by the Agency, or controlled by the Agency under lease or agreement, or under the jurisdiction and control of the Agency for the purposes of the Contract.

**Aggregate** - Rock of specified quality and gradation.

**Agreement Form** – The written agreement between the Owner and Contractor covering the work to be performed under the contract.

**Amendment** – A contract modification for Additional Work, Changed Work, Extra Work, Field Directives, or other changes. An Amendment changes the contract value, scope, and/or time. Amendments require formal approval by the Board of County Commissioners, pursuant to LCRB Rule Division 160, prior to approval of such work.

**Approved Equal** - Materials or services proposed by the contractor and approved by the County as equal or better substitutes for those materials or services specified.

**Attorney-in-Fact** - An Entity appointed by another to act in its place, either for some particular purpose, or for the transaction of business in general.

Award - Written notification to the Bidder that the Bidder has been awarded a Contract.

Base - A Course of specified material of specified thickness placed below the Pavement.

**BCC** – The Clackamas County Board of County Commissioners

**Bid** - A written offer by a bidder on forms furnished by the County to do work stated in the bid documents at the prices quoted. "Bid" is synonymous with "proposal" in the bid documents.

**Bid Bond** - The Surety bond for Bid guaranty.

**Bid Booklet** - The bound paper version included in the Solicitation Documents, or the electronic version that is available to be downloaded from the ORPIN website that contain the information identified in 00120.10 (see 00110.05(e)).

**Bid Closing** - The date and time after which Bids, Bid modifications, and Bid withdrawals will no longer be accepted. The date and time for Bid Closing is the same as the date and time for Bid Opening.

**Bid Documents**- The following documents together comprise the Bid Documents including but not limited to:

- INVITATION TO BID
  - Class of Project
- INSTRUCTIONS TO BIDDERS
  - Description and location of the proposed Project
  - o Time, date, and location for opening Bids
- BID SUPPLEMENTAL CHECK LIST
- BID PROPOSAL
  - Bid Signature page
- SCHEDULE OF PRICES
- FIRST-TIER SUBCONTRACTOR DISCLOSURE FORM
- AFFIDAVIT OF NON COLLUSION

- CERTIFICATE REGARDING INFLIGIBLE CONTRACTORS
- CONFLICT OF INTEREST (COI) FORM
- BID BOND
- PERFORMANCE AND PAYMENT BONDS
- CERTIFICATE OF INSURANCE
- PREVAILING WAGE RATES
- GENERAL INFORMATION, STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS
- PLANS AND DRAWINGS
- AGREEMENT FORM
  - Project completion time
- DISADVANTAGED BUSINESS ENTERPRISE (DBE) COMMITMENT REQUIREMENTS
- DBE INFORMATION PAGE
- DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM
- ASSIGNED DBE CONTRACT GOAL
- ODOT DBE POLICY STATEMENT
- DISADVANTAGED BUSINESS ENTERPRISE (DBE) SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS
- EQUAL EMPLOYMENT OPPORTUNITY PROVISIONS
- EQUAL EMPLOYMENT OPPORTUNITY-ASPIRATIONAL TARGET PROVISIONS
- ON-SITE WORKFORCE AFFIRMATIVE ACION REQUIREMENTS FOR WOMEN AND MINORITIES ON FEDERAL-AID CONTRACTS
- REQUIRED CONTRACT PROVISION FEDERAL-AID CONSTRUCTION CONTRACTS (FHWA 1273)
- INSURANCE CERTIFICATION APPROACH ROAD, UTILITY OR MISCELLANEOUS PERMITS

**Bid Opening** - The date and time Bids are opened.

**Bid Schedule** - The list of Pay Items, their units of measurement, and estimated quantities. (When a Contract is awarded, the Bid Schedule becomes the Schedule of Items.)

**Bid Section** - The portion of the Bid Booklet containing all pages after the Bidder's checklist and before the appendix.

**Bidder** - An Entity that submits a Bid in response to an invitation to bid.

**Bike Lane** - A lane in the Traveled Way, designated by striping and Pavement markings for the preferential or exclusive use of bicvclists.

**Borrow** - Material lying outside of planned or required Roadbed excavation used to complete Project earthwork.

Boulders - Particles of Rock that will not pass a 12-inch square opening.

**Bridge** - A single or multiple span Structure, including supports, that carries motorized and non-motorized vehicles, pedestrians, or utilities on a Roadway, walk, or track over a watercourse, Highway, Railroad, or other feature.

**Buttress** - A Rock fill placed at the toe of a landslide or potential landslide in order to resist slide movement.

Calendar Day - Any Day shown on the calendar, beginning and ending at midnight.

**Camber** - A slight arch in a surface or Structure to compensate for loading.

**Change Order** - A price agreement for Extra Work, Changed Work, field directives, or other changes. A Change Order does not change the contract value, scope, or time until it is incorporated into an Amendment. Change Orders will be agreed upon, in writing, by the County Project Manager and the Contractor's designated representative.

**Changed Work** - Work included in a Pay Item and within the scope of the Contract that is different from that reflected in the Contract Documents. (See 00140.30.)

Class of Project - A designation based on a Project's funding source, (i.e., State or Federal-aid).

**Class of Work** - A designation referring to the type of Work in which Bidders must be prequalified. Classes of Work are limited to those listed in ODOT's Contractor's Prequalification Application.

**Clay** - Soil passing a No. 200 sieve that can be made to exhibit plasticity (putty-like properties) within a range of water contents.

**Clear Zone** - The total roadside border area, starting at the edge of the Traveled Way, available for safe use by errant vehicles. This area may consist of a shoulder, a recoverable slope, a non-recoverable slope, and/or a clear run-out area. The desired width is dependent upon the traffic volumes and speeds and on the roadside geometry.

**Close Conformance** - Where working tolerances are given on the Plans or in the Specifications, Close Conformance means compliance with those tolerances. Where working tolerances are not given, Close Conformance means compliance, in the Engineer's judgment, with reasonable and customary manufacturing and construction tolerances.

Coarse Aggregate - Crushed Rock or crushed Gravel retained on a 1/4-inch sieve, with allowable undersize

**Cobbles** - Particles of Rock, rounded or not, that will pass a 12-inch square opening and be retained on a 3-inch sieve.

**Commercial Grade Concrete** - Concrete furnished according to Contractor proportioning, placed in minor Structures and finished as specified.

Construction Contracts Unit – Agency's office that administers construction contracts

**Contract** - The written Contract Documents, including amendments, signed by the Contractor and Clackamas County, which describes the work to be done, the contract amount, and defines the relationships and obligations of the Contractor and the County.

**Contract Amount** - Sum of the Pay Item amounts computed by multiplying the Pay Item quantities by the unit prices in the Schedule of Items.

**Contract Documents** - The Invitation to Bid, the Instructions to Bidders, the accepted Bid Proposal and Schedule of Prices, the Subcontractor List, the Bid Bond, the Performance and Payment Bond, the Certificate of Insurance, the Prevailing Wage Rates, the Standard Specifications and Special Provisions, Amendments, the Plans and Drawings, the Agreement, the Disadvantaged Business Enterprise Provisions, the Federal Contract Provisions, as well as all documents incorporated by reference therein, and any and all addenda prepared by or at the direction of and adopted by the County and further identified by the signature of the parties and all modifications thereof incorporated in the documents before their execution.

Contract Time - The amount of time allowed to complete the Work under the Contract.

**Contractor** - The Entity awarded the Contract according to the solicitation.

**County** - The term "County" shall mean Clackamas County, the Department of Transportation and Development including the Board of County Commissioners, its officers, employees and agents of the County authorized to administer the conditions of these contract documents.

**Course** - A specified Surfacing Material placed in one or more Lifts to a specified thickness.

**Coverage** - One Pass by a piece of Equipment over an entire designated area.

**Cross Section** - The exact image formed by a plane cutting through an object, usually at right angles to a central axis, to determine area.

Day - A Calendar Day including weekdays, weekends, and holidays, unless otherwise specified.

**Department** – A subdivision of the Agency.

**Durable Rock** - Rock that has a slake durability index of at least 90% based on a two-cycle slake durability test, according to ASTM D4644. In the absence of test results, the Engineer may evaluate the durability visually.

Emulsified Asphalt - Emulsified asphalt cement.

Emulsified Asphalt Concrete - A mixture of Emulsified Asphalt and graded Aggregate.

Engineer - The Engineer who represents the Agency and who is designated by the Agency to administer the Contract.

**Entity** - A natural person capable of being legally bound, sole proprietorship, limited liability company, corporation, partnership, limited liability partnership, limited partnership, for-profit or nonprofit unincorporated association, business trust, two or more persons having a joint or common economic interest, or any other person with legal capacity to contract, or a government or governmental subdivision.

**Equipment** - All machinery, tools, manufactured products, and fabricated items needed to complete the Contract or specified for incorporation into the Work.

**Establishment Period** - The time specified to assure satisfactory establishment and growth of planted Materials.

**Existing Surfacing** - Pavements, slabs, curbs, gutters, walks, driveways, and similar constructions of bricks, blocks, portland cement concrete, bituminous treated materials, and granular Surfacing materials on existing Highways.

**Extra Work** - Work not included in the Contract, but deemed by the Engineer to be necessary to complete the Project.

**Final Acceptance** - Written confirmation by the Agency that the Project has been completed according to the Contract, with the exception of latent defects and Warranty obligations, if any, and has been accepted.

**Final Inspection** - The inspection conducted by the Engineer to determine that the Project has been completed according to the Contract.

Fine Aggregate - Crushed Rock, crushed Gravel, or Sand that passes a 1/4-inch sieve, with allowable oversize.

**First Notification** - Written acknowledgment by the Engineer of the date on which workers employed by the Contractor or a Subcontractor have begun performance of the Contract, including Aggregate source development or erection of a plant, but not including installation of covered temporary signs according to Section 00222.

**Force Account Work** - Items of Extra Work ordered by the Engineer that are to be paid according to Section 00197.

**Granular Material** - Graded and selected free-draining material composed of particles of Rock, Sand, and Gravel.

**Gravel** - Particles of Rock, rounded or not, that will pass a 3-inch sieve and be retained on a No. 4 sieve.

**Highway** - Every road, street, thoroughfare and place, including Bridges, viaducts and other Structures within the boundaries of the State, open, used or intended for use by vehicular traffic.

**Incidental** - A term identifying those acts, services, transactions, property, Equipment, labor, Materials, or other items for which the Agency will make no separate or additional payment.

**Inspector** - The representative of the Engineer authorized to inspect and report on Contract performance.

**Invitation to Bid** - The public announcement (Notice to Contractors) inviting bids for work to be performed or materials to be furnished.

**Legal Holiday** - As defined in 00170.65 "Minimum Wage and Overtime Rates for Public Works Projects".

**Leveling** - Placing a variable-thickness Course of Materials to restore horizontal and vertical uniformity to existing Pavements, normally continuous throughout the Project.

Lift - The compacted thickness of material placed by Equipment in a single Pass.

**Mandatory Source** - A material source provided by the Agency from which the Contractor is required to obtain Materials. (See 00160.00(b) and 00160.40.)

**Materials** - Any natural or manmade substance specified for use in the construction of the Project or for incorporation into the Work.

**Median** - The portion of a divided Highway separating traffic traveling in opposite directions.

**Multiple Course Construction** - Two or more Courses, exclusive of Patching or Leveling, placed over the entire Roadway width.

**Multi-Use Path** - That portion of the Highway Right-of-Way or a separate Right-of-Way, physically separated from motor vehicle traffic and designated for use by pedestrians, bicyclists and other non-motorized users.

**Neat Line** - Theoretical lines specified or indicated on the Plans for measurement of quantities.

**Nondurable Rock** - Rock that has a slake durability index of less than 90% based on a two-cycle slake durability test, as tested by ASTM D4644, or Rock that is observed to readily degrade by air, water, and mechanical influence.

**Notice of Intent to Award** - A written notice from the County notifying bidders that the County intends to award to the responsible bidder submitting lowest responsive bid.

**Notice to Contractors** - The public announcement inviting Bids for Work to be performed or Materials to be provided.

Notice to Proceed - Written notice authorizing the Contractor to begin performance of the Work.

**On-Site Work** - Any Work taking place on the Project Site, including designated staging areas adjacent to the Project Site, except for installation of covered temporary signs according to Section 00222.

Organic Soil - A Soil with sufficient organic content to influence the Soil properties.

**ORPIN** – Oregon Procurement Information Network (orpin.oregon.gov).

Owner - Synonymous with Agency.

Panel - The width of specified Material being placed by Equipment in a single Pass.

Pass - One movement of a piece of Equipment over a particular location.

**Patching** - Placing a variable-thickness Course of Materials to correct sags, dips, and/or bumps to the existing grade and Cross Section, normally intermittent throughout the Project.

**Pavement** - Asphalt concrete or portland cement concrete placed for the use of motor vehicles, bicycles, or pedestrians on Roadways, Shoulders, Multi-Use Paths and parking areas.

Pay Item (Contract Item) - A specific unit of Work for which a price is provided in the Contract.

**Payment Bond** - The approved security furnished by the Contractor's Surety as a guaranty of the Contractor's performance of its obligation to pay promptly in full all sums due for Materials, Equipment, and labor furnished to complete the Work.

**Peat** - A Soil composed primarily of vegetative matter in various stages of decomposition, usually with an organic odor, dark brown to black color, and a spongy consistency.

**Performance Bond** - The approved security furnished by the Contractor's Surety as a guaranty of the Contractor's performance of the Contract.

**Plan Holder's List** – A list of contractor's names, contact names, phone and fax numbers that the County's Procurement Department creates during bidding of the Project.

**Plans** - Standard and Supplemental Drawings, and approved unstamped and reviewed stamped Working Drawings. (See 00150.10 and 00150.35.)

**Project** - The sum of all Work to be performed under the Contract.

**Project Manager** – The Owner's representative who directly supervises the engineering and administration of the Contract.

**Project Site** - The geographical dimensions of the real property on which the Work is to be performed, including designated contiguous staging areas.

**Prospective Source** - A Material source provided by the Agency, from which the Contractor has the option of obtaining Materials. (See 00160.00(a) and 00160.40.)

**Publicly-Owned Equipment** - Equipment acquired by a state, county, municipality or political subdivision primarily for use in its own operations.

**Public Traffic** - Vehicular or pedestrian movement, not associated with the Contract Work, on a public way.

**Railroad** - Publicly or privately owned rail carriers, including passenger, freight, and commuter rail carriers, their tenants, and licensees. Also, Utilities that jointly own or use such facilities.

**Right-of-Way** - Land, property, or property interest, usually in a strip, acquired for or devoted to transportation or other public works purposes.

**Roadbed** - Completed excavations and embankments for the Subgrade, including ditches, side slopes, and slope rounding, if any.

**Roadside** - The area between the outside edges of the Shoulders and the Right-of-Way boundaries. Unpaved Median areas between inside Shoulders of divided Highways and infield areas of interchanges are included.

**Roadway** - That portion of a Highway improved, designed, or ordinarily used for vehicular travel, exclusive of the berm or Shoulder. If a Highway includes two or more separate Roadways, the term "Roadway" refers to any such Roadway separately, but not to all such Roadways collectively. (See Traveled Way.)

**Rock** - Natural deposit of solid material composed of one or more minerals occurring in large masses or fragments.

Sand - Particles of Rock that will pass a No. 4 sieve and be retained on a No. 200 sieve.

**Schedule of Items** - The list of Pay Items, their units of measurement, estimated quantities, and prices.

**Schedule of Values** - The breakdown of the values of the component elements comprising a lump sum Pay Item.

**Second Notification** - Written acknowledgment by the Engineer of the end of Contract Time according to 00180.50(g).

**Shop Drawings** – Synonymous with Working Drawings.

**Shoulder** - The part of a Roadbed contiguous to the Traveled Way or Roadway, whether paved or unpaved, for accommodating stopped vehicles, for emergency use and for lateral support of Base and surface Courses.

Silt - Soil passing a No. 200 sieve that is nonplastic or exhibits very low plasticity.

**Single Course Construction** - A wearing Course only, not including patching or Leveling Courses or partial width Base Course.

**Slope** - Vertical distance to horizontal distance, unless otherwise specified.

**Soil** - Accumulations of particles produced by the disintegration of Rock, which sometimes contains organic matter. Particles may vary in size from Clay to Boulders.

**Solicitation Document** - Synonymous with Bid Documents.

**Special Provisions** - The special directions, provisions, and requirements specific to a Project that supplement or modify the Standard Specifications. Permits and orders governing the Project that are issued directly to the Agency by a governmental or regulatory authority are considered to be part of the Special Provisions, to the extent and under the conditions stipulated in the Special Provisions. This includes any amended or supplemental permits or orders issued during the course of performing the Work under a Contract.

**Special Services** - Work services that the Contractor and Engineer agree cannot be satisfactorily performed by the Contractor's and Subcontractors' forces, (e.g., fabrication and machining work that is most effectively performed away from the Project Site, or rental of operated Equipment as defined in 00180.20(c)).

**Specifications** - The Standard Specifications and Special Provisions, together with all provisions of other documents incorporated therein by reference.

**Standard Drawings** – The Agency-prepared detailed drawings for Work or methods of construction that normally do not change from project to project. The Standard Drawings include the ODOT Standard Drawings.

**Standard Specifications** - "General Conditions for Construction for Clackamas County" published by the Agency and the "2021 Oregon Standard Specifications for Construction", Parts 00200 through 03000, "Technical Specifications", current edition, published by the Oregon Department of Transportation and as amended by the Agency. It provides directions, provisions, and requirements necessary for performing public improvement projects.

State - The State of Oregon.

**Structures** - Bridges, retaining walls, endwalls, cribbing, buildings, culverts, manholes, catch basins, drop inlets, sewers, service pipes, underdrains, foundation drains, and other similar features which may be encountered in the Work.

Subbase - A Course of specified material of specified thickness between the Subgrade and a Base.

**Subcontractor** - An Entity having a direct contract with the Contractor or another Subcontractor, at any tier, to perform a portion of the Work.

**Subgrade** - The top surface of completed earthwork on which Subbase, Base, Surfacing, Pavement, or a Course of other Material is to be placed.

**Substructure** - Those parts of a Structure which support the Superstructure, including bents, piers, abutments, and integrally built wing walls, up to the surfaces on which bearing devices rest. Substructure also includes portions above bearing surfaces when those portions are built integrally with a Substructure unit (e.g., backwalls of abutments). When Substructure and Superstructure elements are built integrally, the division between Substructure and Superstructure is considered to be at the bottom soffit of the longitudinal or transverse beam, whichever is lower. Culverts and rigid frames are considered to be entirely Substructure.

**Superstructure** - Those parts of a Structure above the Substructure, including bearing devices.

**Supplemental Drawings** - The Agency-prepared detailed drawings for Work or methods of construction that are Project specific, and are denoted by title in the Project title block.

**Supplier** - The Entity that furnishes goods to be incorporated into the Work.

Surety - The Entity that issues the bond.

**Surfacing** - The Course or Courses of Material on the Traveled Way, auxiliary lanes, Shoulder, or parking areas for pedestrian, bicycle or vehicle use.

**Third Notification** - Written acknowledgment by the Engineer, subject to Final Acceptance, that as of the date of the notification the Contractor has completed the Project according to the Contract, including, without limitation, completion of all minor corrective work, Equipment and plant removal, site clean-up, and submittal of all certifications, bills, forms and documents required under the Contract.

Ton - One short ton of 2,000 pounds (Ton, ton, Tn, or T).

**Topsoil** - Soil ready for use in a planting bed.

Traffic Lane - That part of the Traveled Way marked for moving a single line of vehicles.

Traveled Way - That part of the Highway for moving vehicles, exclusive of berms and Shoulders.

**Typical Section** - That Cross Section established by the Plans or the 3D Engineered Model which represents in general the lines to which the Contractor shall work in the performance of the Contract.

**Unsuitable Material** - Frozen material, or material that contains organic matter, muck, humus, Peat, sticks, debris, chemicals, toxic matter, or other deleterious materials not normally suitable for use in earthwork.

**Utility** - A line, facility, or system for producing, transmitting, or distributing communications, power, electricity, heat, gas, oil, water, steam, waste, stormwater not connected with highway drainage, or any other similar commodity which directly or indirectly serves the public. The term may also mean the utility company, district, or cooperative owning and operating such facilities, including any whollyowned or controlled subsidiary.

**Warranty Bond** - The approved security furnished by the Contractor's, Subcontractor's, or Supplier's Surety as a guaranty of the Contractor's performance of its warranty obligations.

**Wetlands** - Areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, vegetation typically adapted for life in saturated Soil conditions. Wetlands generally include swamps, marshes, bogs, and similar areas.

**Work** - The furnishing of all Materials, Equipment, labor, and Incidentals necessary to successfully complete any individual Pay Item or the entire Contract, and the discharge of duties and obligations imposed by the Contract.

Work Day or Working Day - Every Calendar Day excluding Saturdays, Sundays and legal holidays as listed in ORS 187.010.

**Working Drawings** - Supplemental Plans, not furnished by the Agency, that the Contractor is required to submit to the Engineer. (See 00150.35.)

#### Section 00120 - Bidding Requirements and Procedures

**00120.00 Prequalification of Bidders** - The Agency requires Contractors to be prequalified with the Oregon Department of Transportation (ODOT), which will prequalify Bidders according to ODOT's Oregon Administrative Rules and prequalification procedures. A Bidder must file for prequalification and pay a fee. Bidders shall make application for prequalification, and for required renewals, on standard forms available from the ODOT Procurement Office - Construction Contracts Unit website (see 00110.05(e)). Bidders shall return the completed application and fee to the ODOT Procurement Office - Construction Contracts Unit by one of the following methods:

If hand delivered, the application shall be date stamped with the provided date stamping device
and the application and fee shall be placed in the ODOT Procurement Office Bid Box located
in the lobby of:

Oregon Department of Transportation 355 Capitol Street NE Salem, OR 97301.

• If delivered by mail or parcel delivery service, the application and fee shall be sent to:

ODOT Procurement Office - Construction Contracts Unit, MS# 2-2 355 Capitol Street NE Salem, OR 97301.

Contracts will only be awarded to Bidders who, at the time of Bid Opening, are prequalified in the Class or Classes of Work specified in the Special Provisions, except that a Bidder whose prequalification has been revoked or revised as provided in ORS 279C.430(4) may also be eligible for Award under that statute if the Project was advertised prior to the revocation or revision. The Agency will consider a Bid from a Bidder whose complete application for prequalification has been received by the ODOT Procurement Office - Construction Contracts Unit at least 10 Calendar Days before the opening of Bids. Bidders shall submit Bids in the same company name used on the prequalification application; provided however, if Bidder's legal name has changed since the submittal of its application for prequalification, it shall submit its Bid under its current legal name with the former name referenced by "formerly known as".

The Agency will regularly evaluate the performance of Contractors on its projects for purposes of responding to reference checks, future prequalification and determinations of responsibility.

Also See Section 2, Instructions to Bidders.

#### 00120.01 General Bidding Requirements - See Bid Documents, and:

As and when applicable, the Contractor shall maintain the certifications required by ORS 279A.107.

**00120.05** Requests for Solicitation Documents – See Notice of Public Improvement Contract Opportunity. Anyone requesting Solicitation Documents will receive electronic versions of the Bid Documents, Construction Plans and Drawings, referenced environmental permits and subsurface investigations.

Electronic version of the 2021 Oregon Standard Specifications for Construction, might be found on the Oregon Department of Transportation's website (see 00110.05(e)).

**00120.10** Bid Booklet - The Bid Booklet is synonymous with the Bid Documents (see definition in 00110.20)

**00120.15** Examination of Work Site and Solicitation Documents; Consideration of Conditions to be Encountered - Before submitting a Bid, Bidders shall make a careful visual examination of the site of the proposed Work, the Bid Booklet, Plans, and Specifications. Each Bidder shall thoroughly examine and be familiar with legal and procedural documents, General Conditions for Construction for (Certified LPA) Clackamas County, Specifications, drawings, Plans, Addenda (if any), and all other Contract Documents. The submission of a Bid shall constitute an acknowledgment upon which the County may rely, that the Bidder is experienced in the uses and interpretation of Plans and Specifications such as those included in the Contract Documents and has thoroughly examined and is familiar with the Contract Documents.

Bidders shall also contact Utility owners to verify all Utilities' anticipated involvement on the Project Site. Bidders shall also review any subsurface investigation material referenced in 00120.25 that may be available and conduct additional investigation of any unusual condition apparent during the visual site examination. As soon as reasonably practicable after noting any such unusual condition, Bidder shall notify Agency, in writing, of any such unusual condition and the additional investigation undertaken by Bidder. Submission of a Bid will constitute confirmation that the Bidder has examined the Project Site and finds the Plans and Specifications to be sufficiently detailed and accurate to enable Bidder to properly perform the Work and understands the conditions to be encountered in performing the Work and all requirements of the Contract.

The Bidder is responsible for loss or unanticipated costs suffered by the Bidder because of the Bidder's failure to fully examine the site and become fully informed about all conditions of the Work, or failure to request clarification of Plans and Specifications Bidder believes to be erroneous or incomplete. The failure or neglect of a bidder to receive or examine any of the Contract Documents, perform site investigations and/or other investigations or examinations shall in no way relieve the Bidder from any obligations with respect to the bid or the contract.

Any clarification of Plans and Specifications needed by the Bidder shall be requested in writing through the Engineer. Unless the procurement period is shorter than one week, requests for changes or clarification shall be submitted at least five days prior to the date of Bid Closing. The Agency will respond to each request at least 72 hours prior to the date of Bid Closing. If the Procurement period is less than seven days, requests shall be submitted within one day after the Procurement is issued and the Agency will issue its response to each such request at least 24 hours prior to Bid Closing. Failure to timely request clarification or changes shall be deemed acceptance of all of the terms and conditions of the Procurement. Oral explanations or interpretations given before receiving Bids for a Project will not be binding. To be binding, interpretation of the Plans and Specifications by the Agency must be made by written Addendum furnished to all Holders of Bidding Plans according to 00120.30. Notification of erroneous or incomplete Plans or Specifications shall also be submitted to the Engineer. Such notification shall also be made in sufficient time for the Agency to make any necessary modifications and issue Addenda to Bidders prior to Bid Closing.

**00120.16 Material, Equipment, and Method Substitutions-** See Section 2, Instructions to Bidders, Article 3 - When the Contract specifies certain Materials, Equipment, products, and/or methods, the Bidder shall include those Materials, Equipment, products, and/or methods in the Bid unless the Engineer has issued an Addendum granting approval to substitute. Unless the Engineer has approved substitutions of Materials, Equipment, products, and/or methods prior to opening of Bids, the Bidder shall furnish the items specified in the Contract. Substitution after Award is specified in 00180.31(b), 00180.31(c), and 00180.31(d). The procedure for requesting approval is as follows:

- (a) Written Request Unless specified as the subject of an exemption per ORS 279C.345, if a Bidder proposes to use Materials, Equipment, products, and/or methods other than those specified, the Bidder shall send a written request to the Engineer, at least 7 Calendar Days prior to Bid Opening, including complete descriptive and technical information on the proposed Materials, Equipment, products, and/or methods.
- **(b) Functional Similarity** Materials, products, and Equipment proposed for substitution shall be similar in design, and equal or better in quality and function to those specified.
- **(c) Manufacturer's Information** If manufacturers' brochures or information is needed, the Bidder shall submit three copies of each with all pertinent information clearly marked.
- **(d) Differences** The Bidder shall specifically note all differences between the specified Materials, Equipment, products, and/or methods and the proposed substitutes.
- **(e)** Cost Where a substitute will result in alteration of the design or space requirements, or any other modifications to the Plans, the Bidder shall include in the substitution request all items of cost for the revised design and construction.
- **(f) Notification of Holders of Bidding Plans** If the Engineer approves any proposed substitution, such approval, and any modifications necessitated to the design and construction by the substitution, will be acknowledged by Addenda.
- **00120.17** Use of Agency-Owned Land for Staging or Storage Areas The Contractor may use Agency-owned property for staging or storage areas, subject to the following limitations:
  - (a) Within Normal Right-of-Way Limits If approved by the Engineer, the Contractor may use available property within the normal Right-of-Way limits for the purpose of constructing improvements under the Contract. Where the Agency owns, or has rights to, other adjacent properties in the Project area, "normal Right-of-Way" is limited to a line drawn across that property connecting the normal Right-of-Way limits on either side of the property.
  - **(b) Outside Normal Right-of-Way Limits** The Contractor may not use Agency-owned property outside of normal Right-of-Way limits for the Project without the approval of the Engineer.

If a Bidder obtains approval before submitting a Bid, use of the property will be at no cost to the Contractor, or at a cost stated by the Engineer upon granting approval, as confirmed by Addendum.

If approval is not obtained before submitting a Bid, and the Contractor proposes to use Agency-owned property outside the normal Right-of-Way limits, then use of the property may be approved by the Engineer, but the Contractor will be assessed fair market value, as determined by the Engineer, for use of the property.

- **(c) Restrictions on Use** Contractors shall comply with all applicable laws, ordinances, and regulations pertaining to use of Agency-owned property, and shall:
  - · Not cause unreasonable impacts on traffic and other facility users.
  - Clean up all hazardous materials deposited by, or resulting from, Contractor operations.
  - Be responsible for all costs associated with use of the property.

**00120.20** Interpretation of Quantities in Bid Schedule - Quantities appearing in the Bid Schedule are approximate and are provided only for comparison of Bids. The Agency does not warrant that the

actual individual items, amount of Work, or quantities will correspond to those shown in the Bid Schedule. Payment to the Contractor will be made only for actual quantities of Work performed and accepted or Materials furnished and accepted, as required by the Contract. Quantities of Work to be performed and Materials to be furnished may each be increased, decreased, or omitted as provided in 00120.30 and 00140.30.

**00120.25 Subsurface Investigations** - If the Agency or its consultant has conducted subsurface or geologic investigations of the proposed Project Site, the results of the investigations may be included in written reports. If reports have been prepared, copies will be available at the Engineer's office. If the Agency has retained subsurface samples, they will also be available for inspection. Bidders and the Contractor may make arrangements for viewing the samples through the Engineer's office. The availability of subsurface information from the Agency is solely for the convenience of the Bidder and shall not relieve the Bidder or the Contractor of any risk, duty to make examinations and investigations as required by 00120.15, or other responsibility under the Contract Documents. It is mutually agreed to by all parties that:

- The written report(s) are reference documents and not part of the Contract Documents.
- The subsurface investigations made by the Agency are for the purpose of obtaining data for planning and design of the Project.
- The data for individual test boring logs apply only to that particular boring and is not intended to be conclusive as to the character of any material between or around test borings.
- If Bidders use this information in preparing a Bid, it is used at their own risk, and Bidders are responsible for all conclusions, deductions, and inferences drawn from this information.

**00120.30** Changes to Plans, Specifications, or Quantities before Opening of Bids - :The County reserves the right to make necessary changes or corrections to the Contract Documents at any time prior to the opening of bids via Addenda. The County will notify Bidders whose names and electronic mail (email) addresses appear on the Plan Holder's List, of change or corrections by electronic mail (email). The County may elect to notify Bidders by telephone initially and follow up with an electronic mail notification. All Addenda will be posted to the project's ORPIN listing.

The County is not responsible for failure of Bidders to receive notifications of changes or corrections made by the County, and sent as stated above. Bids opened and found not to be based on the changes or corrections will not be considered and will be deemed non-responsive.

### 00120.40 Preparation of Bids -:

# (a) General:

- (1) Paper Bids See Section 2, Instructions to Bidders, Article 6.
- (2) Email Bids See Section 2, Instructions to Bidders, Article 6.
- **(b) Bidding Considerations** Bidders may refer to the following Subsections for requirements that may affect bidding considerations:

Subsection	Requirements
00120.80	Reciprocal Preference for Oregon Resident Bidders
00130.80	Project Site Restrictions
00150.55	Cooperation with Other Contractors
00150.75	Protection and Maintenance of Work during Construction
00160.20(a)	Buy America
00160.20(b)	Buy Oregon

00170.07	Record Requirements
00180.20	Subcontracting Limitations
00180.21	Subcontracting
00195.00(a)	Cost of Insurance and Bonds
00195.50(a)(1)	Progress Estimates
00199.30	Claims Procedure

### (c) Bid Schedule Entries:

- (1) Paper Bid Schedule Entries Using figures, Bidders shall fill in all blank spaces in the paper Bid Schedule. For each item in the paper Bid Schedule, Bidders shall enter the unit price and the product of the unit price multiplied by the quantity given. The unit price shall be greater than zero, shall contain no more than two decimal places to the right of the decimal point, and shall be expressed in U.S. dollars and cents (for example, \$150.25 or \$0.37). Unit prices submitted which contain more than two decimal places, will be truncated by the Agency at the second decimal place to determine the product of the unit price and quantity. No rounding will be considered or paid. Bidders Bid shall also enter the total amount of the Bid obtained by adding amounts for all items in the paper Bid Schedule. Corrections or changes of item entries shall be in ink, with incorrect entry lined out and correct entry entered and initialed.
- (d) Bidder's Address and Signature Pages See Section 2, Instructions to Bidders, Article 6.
- (e) Bid Guaranty See Section 2, Instructions to Bidders, Article 4.
- (f) Disclosure of First-Tier Subcontractors See Section 2, Instructions to Bidders, Article 16.
- **(g) Disclosure of Conflict of Interest** Agency has adopted the ODOT Conflict of Interest Guidelines and disclosure requirements. Bidders shall review the Agency's Conflict of Interest Guidelines, and if any disclosures are required (with the exception of any required disclosures for Subcontractors, which are addressed under 00180.21), Bidders shall complete the Conflict of Interest Disclosure Form(s) and submit to the Agency, before the time Bids are due to be submitted according to 00120.45(a). The ODOT Conflict of Interest Guidelines and Conflict of Interest Disclosure Form are available on the ODOT Procurement Office website (see 00110.05(e)).

If disclosures are not required under the Agency's Conflict of Interest Guidelines, no disclosures need be submitted.

00120.45 Submittal of Bids: See Section 2, Instructions to Bidders, Article 8.

00120.60 Revision or Withdrawal of Bids: See Section 2, Instructions to Bidders, Article 11.

**00120.65** Opening and Comparing Bids - Bids will be opened and the total price for each Bid will be read publicly at the time and place specified in the Bid Advertisement. Bidders and other interested parties are invited to be present.

Bids for each Project will be compared on the basis of the total amount of each Bid. The total amount of the Bid will be the total sum computed from quantities listed in the Bid Schedule and unit prices entered by the Bidder.

In case of conflict between the unit price and the corresponding extended amount, the unit price shall govern, and the Agency may make arithmetic corrections on extension amounts.

#### 00120.68 Mistakes in Bids -

General - Clarifications to or withdrawal of a bid after Bid Closing because of an inadvertent mistake in the Bid requires careful consideration by the County to protect the integrity of the competitive bidding system and to assure fairness to all Bidders. Bid corrections or withdrawal by reason of a non-judgmental mistake is permissible, but only to the extent it is not contrary to the interest of the County or the fair treatment of other Bidders. Mistakes in Bids are governed under LCRB Rule C-049-350.

**00120.70** Rejection of Non-responsive Bids - A Bid will be considered irregular and will be rejected if the irregularity is deemed by the Agency to render the Bid non-responsive. Examples of irregularities include, without limitation:

- The Bid Section documents provided are not properly used or contain unauthorized alterations.
- · The Bid is incomplete or incorrectly completed.
- The Bid contains improper additions, deletions, alternate Bids, or conditions.
- The Bid is submitted on documents not obtained directly from the Agency, or is submitted by a Bidder who has not been identified by the Agency as a Holder of Bidding Plans, as required by 00120.05.
- The Bid or Bid modifications are not signed by a person authorized to submit Bids or modify Bids, as required by 00120.01.
- A member of a joint venture and the joint venture submit Bids for the same Project. Both Bids may be rejected.
- The Bid has entries not typed or in ink, or has signatures or initials not in ink (save for changes received by email as provided by 00120.60).
- · Each change or correction is not individually initialed.
- White-out tape or white-out liquid is used to correct item entries.
- · The price per unit cannot be determined.
- The Agency finds that it is in the public interest to do so (ORS 279C.395).
- The Bid guaranty is insufficient or improper.
- The original Bid Bond form is not used or is altered.
- Pre-Qualification submission requirements are not met.
- The Oregon Construction Contractors Board registration number and expiration date are not shown on the Bid if required in the Solicitation Document. This requirement applies to Agency and State-funded Projects, with the exception of Aggregate production and landscape Projects. (Not required on Federal-aid Projects.)
- A disclosure of first-tier Subcontractors, if required under 00120.40(f), is not received within two
  working hours of the time Bids are due to be submitted, or the disclosure form is not complete.
- The Agency determines that any Pay Item is significantly unbalanced to the potential detriment of the Agency.
- The Bidder has not complied with the DBE requirements of the solicitation.
- · The Bid does not acknowledge all issued Addenda.
- The Bid contains entries that are not greater than zero.
- · The Bid contains entries with more than two decimals to the right of the decimal point.
- The Bid entries are not expressed in U.S. dollars and cents.

• The Bidder has not submitted required Conflict of Interest Disclosure Form(s), if any. (See 00120.40(g).)

In addition, the Agency may reject all Bids for good cause upon its finding that it is in the public interest to do so. The Agency may also waive minor informalities or irregularities.

**00120.80** Reciprocal Preference for Oregon Resident Bidders - This Subsection applies only to Contracts for Projects financed without federal funds.

Bidders shall complete the certificate of residency provided by the Agency in the Bid Booklet. Failure to properly complete the form will be cause to reject the Bid.

As used in the certificate of residency and this Subsection, "Resident Bidder" means a Bidder who has:

- Paid unemployment taxes or income taxes in the State of Oregon during any of the 12 calendar months immediately preceding submission of the Bid;
- · A business address in the State of Oregon; and
- · Certified in the Bid that the Bidder qualifies as a Resident Bidder.

In determining the lowest Bid, the Agency will, for the purpose of awarding the Contract, add a percentage increase to the Bid of a Nonresident Bidder equal to the percentage, if any, of the preference given to that Bidder in the state in which the Bidder resides (ORS 279A.120). The percentage preference applied in each state will be published on or before January 1 of each year by the Oregon Department of Administrative Services. The Agency may rely on these percentages without incurring liability to any Bidder (ORS 279A.120).

This increase will only be applied to determine the lowest Bid, and will not cause an increase in payment to the Contractor after Award of the Contract.

**00120.90 Disqualification of Bidders** - The Bid(s) of a disqualified Bidder will be rejected. Any of the following reasons is sufficient to disqualify a Bidder:

- More than one Bid is submitted for the same Work by an Entity under the same or different name(s).
- Evidence of collusion among Bidders. Participants in collusion will be found not responsible, and may be subject to criminal prosecution.
- Any of the grounds for disqualification cited in ORS 279C.440.

A Bidder will be disqualified if the Bidder has:

- Not been prequalified as required by 00120.00;
- Been declared ineligible by the Commissioner of the Bureau of Labor and Industries under ORS 279C.860;
- Not been registered (licensed) by the Oregon Construction Contractors Board (CCB) or has not been licensed by the State Landscape Contractors Board before submitting a Bid (ORS 279C.365(1)(k), ORS 701.021, ORS 701.026, and ORS 671.530). The Bidder's registration number and expiration date shall be shown in the Bid form, if requested. Failure to

<sup>&</sup>quot;Nonresident Bidder" means a Bidder who is not a Resident Bidder as defined above.

- furnish the registration number, if requested, will render the Bid non-responsive and subject to rejection. (Not required on Federal-aid projects.); or
- Been determined by the CCB under ORS 701.227 not to be qualified to hold or participate in a public contract for a public improvement.

**00120.91** Rejection of Bid on Grounds of Nonresponsibility of Bidder - The Bid of a Bidder who is found to be nonresponsible according to the criteria listed in 00130.10 or ORS 279C.375(3) will be rejected.

#### Section 00130 - Award and Execution of Contract

**00130.00 Consideration of Bids** - After opening and reading Bids, the Agency will check them for correct extensions of unit prices and totals. (See 00120.65.) The total of extensions, corrected where necessary, will be used by the Agency for Award purposes.

The Agency reserves the right to waive minor informalities and irregularities, seek clarification of any Bid or response that, in its sole discretion, it deems necessary or advisable, and to reject any or all Bids for irregularities under 00120.70 or for good cause after finding that it is in the public interest to do so (ORS 279C.395). An example of good cause for rejection in the public interest is the Agency's determination that any of the unit Bid prices are significantly unbalanced to the Agency's potential detriment. The Agency may correct obvious clerical errors, when the correct information can be determined from the face of the documents, if it finds that the best interest of the Agency and the public will be served thereby.

Bids will be considered and a Contract awarded, if at all, within 30 Calendar Days from the date of Bid Opening, unless an extension beyond that time is agreed to by both parties and acknowledged in writing by the Bidder.

**00130.10 Award of Contract** - After the Bids are opened and a determination is made that a Contract is to be awarded, the Contract will be awarded to the lowest responsible Bidder. For the purposes of this Section, "lowest responsible Bidder" means the responsible Bidder who submitted the lowest responsive Bid, who is not on the list created by the Construction Contractors Board according to ORS Chapter 701, and who has:

- Substantially complied with all prescribed public bidding procedures and requirements.
- Available the appropriate financial, Materials, Equipment, facility and personnel resources and expertise, or ability to obtain the resources and expertise, necessary to indicate the capability of the prospective Bidder to meet all contractual responsibilities.
- A satisfactory record of performance. In evaluating a Bidder's record of performance, the Agency may consider, among other things, whether the Bidder completed previous contracts of a similar nature with a satisfactory record of performance. For purposes of evaluating a Bidder's performance on previous contracts of a similar nature, a satisfactory record of performance means that to the extent that the costs associated with and time available to perform a previous contract remained within the Bidder's control, the Bidder stayed within the time and budget allotted for the procurement and otherwise performed the contract in a satisfactory manner. Satisfactory performance of the Contract also includes compliance with the requirements for records in 00170.07 for Contracts with the Agency.
- A satisfactory record of integrity. In evaluating a Bidder's record of integrity, the Agency may
  consider, among other things, whether the Bidder has previous criminal convictions for offenses
  related to obtaining or attempting to obtain a contract or subcontract or in connection with the
  Bidder's performance of a contract or subcontract.
- · Qualified legally to contract with the Agency.
- Supplied all necessary information in connection with the inquiry concerning responsibility. If a
  prospective Bidder fails to promptly supply information requested by the Agency concerning
  responsibility, the Agency will base the determination of responsibility upon any available
  information, or may find the prospective Bidder not to be responsible.
- Not been disqualified by the public contracting agency under ORS 279C.440.
- An unexpired certificate issued by the Oregon Department of Administrative Services (under ORS 279A.167) upon completion of the curriculum and assessment that the Bidder understands the prohibitions set forth in ORS 652.220 and in other laws or rules that prohibit discrimination

in compensation or wage payment. The certificate is only required if the Bidder employs 50 or more full-time workers and submitted a Bid for a procurement with an estimated contract price that exceeds \$500,000.

If the Bidder is found not to have a satisfactory record of performance or integrity, the Agency will document the record and the reasons for the unsatisfactory finding.

The Agency will mail the Notice of Intent to Award to the Bidders, and may provide Notice of Intent to Award on the Agency's website. (See 00110.05(e).)

The Award will not be final until the later of the following:

- Three Working Days after the Notice of Intent to Award has been posted as specified in the advertised solicitation or Addendum thereto; or
- The Agency has provided a written response to each timely protest, denying the protest and affirming the Award.

If the Agency accepts a Bid and awards a Contract, the Agency will send the successful Bidder written notice of acceptance and Award.

Notice of Award and Contract booklets ready for execution will be sent within 60 Calendar Days of the opening of Bids or within the number of Calendar Days specified in the Special Provisions or a written mutual agreement.

00130.15 Right to Protest Award - See Section 2, Instructions to Bidders, Article 15.

**00130.20 Cancellation of Award** - Without liability to the Agency, the Agency may for good cause cancel Award at any time before the Contract is executed by all parties to the Contract, as provided by ORS 279C.395 for rejection of Bids, upon finding it is in the public interest to do so.

00130.30 Contract Booklet - The Contract booklet may include, but is not limited to:

- General Conditions for Construction for Clackamas County
- Special Provisions
- Addenda
- · Schedule of Items
- Contract
- · Performance Bond
- Payment Bond
- Certification of workers' compensation coverage

Other documents are part of the Contract Documents by reference. These include, but are not limited to:

- The "Oregon Standard Specifications for Construction", 2021 Edition, Sections 00200 through 03000, as published by the Oregon Department of Transportation (ODOT).
- · "Oregon Standard Drawings" latest edition, as published by ODOT.

**00130.40 Contract Submittals** - See Section 2, Instructions to Bidders. The instructions include the following items to be furnished by the Contractor:

- Performance and Payment Bonds See Section 2, Article 12.
- Certificates of Insurance See Section 11, Paragraph 5 of the Agreement Form.
- Workers Compensation See Section 5, Paragraph 12 of the Bid Form.
- Registration Requirements See Section 5, Paragraphs 10 and 11 of the Bid Form.
- Tax Identification Number See Section 11, Paragraph 11 of the Agreement Form.

### 00130.50 Execution of Contract and Bonds:

### (a) By the Bidder -

See Section 2, Instructions to Bidders, Article 12, Section 5, Paragraph 12 of the Bid Form, and Section 11, Paragraph 5 of the Agreement Form.

**(b) By the Agency** - Within 10 Working Days after the Agency has received and verified the properly executed documents specified in Section 11, Public Improvement Contract Agreement Form and, and received legal sufficiency approval from the Agency's attorney (if required), the Agency will request Clackamas County Board of Commissioner's or the County Administrator's Approval of the Contract. Approval will occur within 21 Calendar Days after the Agency has received and verified the properly executed documents. The Agency will then send a fully-executed Public Improvement Contract (Agreement Form) to the successful Bidder, who then officially becomes the Contractor.

**00130.60 Failure to Execute Contract and Bonds** - Failure of the successful Bidder to execute the Contract and provide the required certificates, certifications, and bonds may be cause for cancellation of the Award, and may be cause for forfeiture of the Bid guaranty under ORS 279C.385.

Award may then be made to the next lowest responsible Bidder, the Project may be re-advertised, or the Work may be performed otherwise as the Agency decides.

The forfeited Bid guaranty will become the Agency's property, not as a penalty but as liquidation of damages resulting from the Bidder's failure to execute the Contract and provide the certificates, certifications, and bonds as required by these Specifications.

**00130.70** Release of Bid Guaranties - Security deposited by unsuccessful bidders will be returned as soon as practicable after the Bid Opening.

**00130.80 Project Site Restriction** - Until the Agency sends the Contractor written Notice to Proceed with the Work, and the Contractor has filed the public works bonds required in 00170.20, the Contractor shall not go onto the Project Site on which the Work is to be done, nor move Materials, Equipment, or workers onto that Project Site.

The Contractor will not automatically be entitled to extra compensation because the commencement of Work is delayed by failure of the Agency to send the Contract for execution. However, if more than 60 Calendar Days elapse between the date the Bid is opened and the date the Agency sends the Contract to be executed, the Agency will consider granting an adjustment of time for completion of the Work to offset any actual delay to Contract completion resulting directly from delay in commencement.

**00130.90 Notice to Proceed** - Notice to Proceed will be issued within 5 Calendar Days after the Contract is executed by the Agency.

Should the Agency fail to issue the Notice to Proceed within 5 Calendar Days of Contract execution, the Contractor may apply for an adjustment of Contract Time according to 00180.80(c).

The Engineer will issue a First Notification recording the date the performance of the Contract has begun.

# Section 00140 - Scope of Work

**00140.00 Purpose of Contract** - The purpose of the Contract is to set forth the rights and obligations of the parties and the terms and conditions governing completion of the Work. The Contractor's obligations shall include without limitation the following:

- The Contractor shall furnish all Materials, Equipment, labor, transportation, and Incidentals required to complete the Work according to Plans, Specifications, and terms of the Contract.
- The Contractor shall use every reasonable and practicable means to avoid damage to property and injury to persons.
- The Contractor shall use no means or methods that will endanger, unnecessarily, either persons or property.
- The Contractor shall perform the Work according to the lines, grades, Cross Section data, Typical Sections, dimensions, and other details shown on the Plans or in the 3D Engineered Model, as modified by written order, or as directed by the Engineer.
- The Contractor shall perform all Work determined by the Engineer to be necessary to complete the Project.
- The Contractor shall contact the Engineer for any necessary clarification or interpretation of the Contract.

**00140.10 Typical Sections** - The Typical Sections are intended to apply in general. At other locations where the Typical Section is not appropriate, the Contractor shall perform construction to the identified alignment as directed by the Engineer.

**00140.20 Thickness** - The thickness of Courses of Materials shown on the Plans, given in the Specifications, or established by the Engineer is considered to be the compacted thickness. Minor variations are acceptable when within tolerances specified in the Specifications or Plans, or when approved by the Engineer.

**00140.30** Agency-Required Changes in the Work - Changes to the Plans, quantities, or details of construction are inherent in the nature of construction and may be necessary or desirable during the course of Project construction.

Without impairing the Contract, the Agency reserves the right to require changes it deems necessary or desirable within the scope, which in the Specifications means general scope, of the Project. These changes may modify, without limitation:

- · Specifications and design
- · Grade and alignment
- · Cross Sections and thicknesses of Courses of Materials
- 3D Engineered Model
- Method or manner of performance of Work
- · Project Limits

### or may result in:

- · Increases and decreases in quantities
- Additional Work
- Elimination of any Contract item of Work

Acceleration or delay in performance of Work

Upon receipt of an Engineer's written order modifying the Work, the Contractor shall perform the Work as modified via approved Change Order, which may be subject to approval as an Amendment.

If an Amendment incorporating changes to the Work increases the Contract amount, the Contractor shall notify its Surety of the increase and shall provide the Agency with a copy of any resulting modification to bond documents. The Contractor's performance of Work pursuant to Amendments shall neither invalidate the Contract nor release the Surety. Payment for changes in the Work shall be made in accordance with 00195.20. Contract Time adjustments shall be made in accordance with 00180.80.

**"As-Built" Records** – The Contractor shall maintain a current and accurate record of the work completed during the course of this contract. This may be in the form of "as-built" drawings kept by accurately marking a designated set of the contract plans with the specified information as the Work proceeds. Accurate, complete and current "as-built" drawings are a specified requirement before final Release of Retainage. At project completion and as a condition of final payment, the Contractor shall deliver to the Engineer or Project Manager a complete and legible set of "as-built" drawings.

The "as-built" drawings must show the information listed below. Where the term "locate" or "location" is used, it shall mean record of position with respect to both the construction vertical datum and either construction horizontal datum or a nearby permanent improvement.

- 1) Record location of underground services and utilities as installed.
- Record location of existing underground utilities and services that are to remain and that are encountered during the course of the work.
- 3) Record changes in dimension, location, grade or detail to that shown on the plans.
- 4) Record changes made by Change Order or approved Amendment.
- 5) Record details not in the original plans.
- 6) Provide fully completed shop drawings reflecting all revisions.

**00140.40 Differing Site Conditions** - The following constitute differing Project Site conditions provided such conditions are discovered at the Project Site after commencement of the Work:

- Type 1 Subsurface or latent physical conditions that differ materially from those indicated in the Contract Documents; or
- Type 2 Unknown physical conditions of unusual nature that differ materially from those
  ordinarily encountered and generally recognized as inherent in the Work provided for in the
  Contract.

The party discovering such a condition shall promptly notify the other party, in writing, of the specific differing conditions before they are disturbed and before the affected Work is performed. The Contractor shall not continue Work in the affected area until the Engineer has inspected such condition according to 00195.30 to determine whether an adjustment to Contract Amount or Contract Time is required.

Payment adjustments due to differing Project Site conditions, if any, will be made according to 00195.30. Contract Time adjustments, if any, will be made according to 00180.80.

**00140.50 Environmental Pollution Changes** - ORS 279C.525 will apply to any increases in the scope of the Work required as a result of environmental or natural resources laws enacted or amended after the submission of Bids for the Contract. The Contractor shall comply with the applicable notice and other requirements of ORS 279C.525. The applicable rights and remedies of that statute will also apply.

In addition to ORS 279C.525, the Agency has compiled a list at 00170.01 of those federal, State, and local agencies, of which the Agency has knowledge, that have enacted ordinances, rules, or regulations dealing with the prevention of environmental pollution and the preservation of natural resources that may affect the performance of Agency contracts.

**00140.60 Extra Work** - If directed by the Engineer's written order, the Contractor shall perform work not included in the Contract. The Contractor shall perform this work according to:

- Standard Specifications
- Other Plans and Specifications issued by the Engineer

Payment for Extra Work will be made according to Section 00196. Contract Time adjustments, if any, will be made according to 00180.80.

**00140.65 Disputed Work** - The Contractor may dispute any part of a Change Order, written order, or an oral order from the Engineer by the procedures specified in Section 00199.

**00140.70 Cost Reduction Proposals** - The Contractor may submit written proposals to the Engineer or Project Manager that modify Plans, Specifications, or other Contract Documents for the sole purpose of reducing the total cost of construction. Unless otherwise agreed to in writing by the Agency, a proposal that is solely or primarily a proposal to reduce estimated quantities or delete Work, as determined by the Engineer, is not eligible for consideration as a cost reduction proposal and will instead be addressed under 00140.30, whether proposed or suggested by the Agency or the Contractor.

(a) Proposal Requirements - The Agency will not adopt a cost reduction proposal that impairs essential functions or characteristics of the Project, including, but not limited to, service life, economy of operation, ease of maintenance, designed appearance, or design and safety standards.

To conserve time and funds, the Contractor may first submit a written request for a feasibility review by the Engineer. The request should contain a description of the proposal together with a rough estimate of anticipated dollar and time savings. The Engineer will, within a reasonable time, advise the Contractor in writing whether or not the proposal would be considered by the Agency, should the Contractor elect to submit a detailed cost reduction proposal.

A detailed cost reduction proposal shall include without limitation the following information:

- A description of existing Contract requirements for performing the Work and the proposed change;
- The Contract items of Work affected by the proposed change, including any quantity variation caused by the proposed change;
- Pay Items affected by the proposed change including any quantity variations;
- A detailed cost estimate for performing the Work under the existing Contract and under the proposed change. Cost estimates shall be made according to Section 00197. Costs of

- re-design, which are incurred after the Agency has accepted the proposal, shall be included in the cost of proposed work; and
- A date by which the Engineer must accept the proposal in order to accept the proposed change without impacting the Contract Time or cost reduction amount.
- **(b) Continuing to Perform Work** The Contractor shall continue to perform the Work according to Contract requirements until the Engineer issues a Change Order incorporating the cost reduction proposal. If the Engineer fails to issue a Change Order by the date specified in the proposal, the proposal shall be deemed rejected.
- **(c) Consideration of Proposal** The Engineer is not obligated to consider any cost reduction proposal. The Agency will not be liable to the Contractor for failure to accept or act upon any cost reduction proposal submitted.

The Engineer will determine in its sole discretion whether to accept a cost reduction proposal as well as the estimated net savings in construction costs from the adoption of all or any part of the proposal. In determining the estimated net savings, the Engineer may disregard the Schedule of Items. The Engineer will establish prices that represent a fair measure of the value of Work to be performed or to be deleted as a result of the cost reduction proposal.

- (d) Sharing Investigation Costs As a condition for considering a Contractor's cost reduction proposal, the Agency reserves the right to require the Contractor to share in the Agency's costs of investigating the proposal. If the Agency exercises this right, the Contractor shall provide written acceptance of the condition to the Engineer. Such acceptance will authorize the Agency to deduct its share of investigation costs from payments due or that may become due to the Contractor under the Contract.
- **(e) Acceptance of Proposal Requirements** If the Contractor's cost reduction proposal is accepted in whole or in part, acceptance will be made by a Change Order that will include without limitation the following:
  - Statement that the Change Order is made according to 00140.70;
  - Revised Contract Documents that reflect all modifications necessary to implement the approved cost reduction measures;
  - Any conditions to which the Agency's approval is subject;
  - Estimated net savings in construction costs attributable to the approved cost reduction measures; and
  - A payment provision according to which the Contractor will be paid 50% of the estimated net savings amount as full and adequate consideration for performance of the Work of the Change Order.

The Contractor's cost of preparing the cost reduction proposal and the Agency's costs of investigating the proposal, including any portion paid by the Contractor, will be excluded from determination of the estimated net savings in construction costs. Costs of re-design, which are incurred after the Agency has accepted the proposal, will be included in the cost of the Work attributable to cost reduction measures.

If the Agency accepts the cost reduction proposal, the Change Order that authorizes the cost reduction measures will also address any Contract Time adjustment.

(f) Right to General Use - Once submitted, the cost reduction proposal becomes the property of the Agency. The Agency reserves the right to adopt the cost reduction proposal for general use

without additional compensation to the Contractor when it determines that a proposal is suitable for application to other contracts.

**00140.80 Use of Publicly Owned Equipment** - The Contractor is prohibited from using publicly-owned Equipment except in the case of emergency. In an emergency, the Contractor may rent publicly-owned Equipment provided that:

- The Engineer provides written approval that states that such rental is in the public interest; and
- · Rental does not increase the Project cost.

**00140.90 Final Trimming and Cleanup** - Before Final Inspection as described in 00150.90, the Contractor shall neatly trim and finish the Project and remove all remaining unincorporated Materials and debris. Final trimming and cleanup shall include without limitation the following:

- The Contractor shall retrim and reshape earthwork, and shall repair deteriorated portions of the Project Site.
- Where the Work has impacted existing facilities or devices, the Contractor shall restore or replace those facilities to their pre-existing condition.
- The Contractor shall clean all drainage facilities and sanitary sewers of excess Materials or debris resulting from the Work.
- The Contractor shall clean up and leave in a neat, orderly condition, Rights-of-Way, Materials sites, and other property occupied in connection with performance of the Work.
- The Contractor shall remove temporary buildings, construction plants, forms, falsework and scaffolding, surplus and discarded Materials, and rubbish.
- The Contractor shall dispose of Materials and debris, including, without limitation, forms, falsework, scaffolding, and rubbish resulting from clearing, grubbing, trimming, clean-up, removal, and other Work. These Materials and debris become the property of the Contractor. The Contractor shall dispose of these Materials and debris immediately.

Unless the Contract specifically provides for payment for this item, the Agency will make no separate or additional payment for final trimming and cleanup.

#### Section 00150 - Control of Work

**00150.00 Authority of the Engineer** - Except as indicated elsewhere in the Contract (e.g. Amendment approval by the BCC), the Engineer has full authority over the Work and its suspension. (See Section 00180.) The Contractor shall perform all Work to the complete satisfaction of the Engineer. The Engineer's determination shall be final on all matters, including, but not limited to, the following:

- · Quality and acceptability of Materials and workmanship
- Measurement of unit price Work
- Timely and proper prosecution of the Work
- · Interpretation of Contract Documents
- · Payments due under the Contract

The Engineer's decision is final and, except as provided in 00180.80 for adjustments of Contract Time and Section 00199 for claims for additional compensation, may be challenged only through litigation.

Work performed under the Contract will not be considered complete until it has passed Final Inspection by the Engineer and has been accepted in writing by the Agency.

Interim approvals issued by the Engineer, including, but not limited to, Third Notification, will not discharge the Contractor from responsibility for errors in prosecution of the Work, for improper fabrication, for failure to comply with Contract requirements, or for other deficiencies, the nature of which are within the Contractor's control.

**00150.01 Project Manager's Authority and Duties** - The Engineer may designate a Project Manager as its representative on the Project with authority to enforce the provisions of the Contract.

When the Engineer has designated a Project Manager, the Contractor should direct all requests for clarification or interpretation of the Contract, in writing, to the Project Manager. The Project Manager will respond within a reasonable time. Contract clarification or interpretation obtained from persons other than the Project Manager will not be binding on the Agency.

The Project Manager shall have the authority to appoint Inspectors and other personnel as required to assist in the administration of the Contract.

**00150.02** Inspector's Authority and Duties - To the extent delegated under 00150.01, Inspectors are authorized to represent the Engineer and Project Manager to perform the following:

- Inspect Work performed and Materials furnished, including, without limitation, the preparation, fabrication, or manufacture of Materials to be used:
- Orally reject defective Materials and to confirm such rejection in writing;
- By oral order, temporarily suspend the Work for improper prosecution pending the Engineer's decision; and
- · Exercise additional delegated authority.

Inspectors are not authorized to:

- · Accept Work or Materials.
- Alter or waive provisions of the Contract.

Give instructions or advice inconsistent with the Contract Documents.

**00150.10 Coordination of Contract Documents** - The Contract Documents, including, but not limited to, Amendments, the Special Provisions, the Plans, and the Standard Specifications are intended to collectively describe all of the items of Work necessary to complete the Project.

- (a) Order of Precedence The Engineer will resolve any discrepancies between these documents in the following order of precedence:
  - Approved Amendments
  - Schedule of Prices;
  - · Addenda:
  - · Special Provisions;
  - Stamped Agency-prepared drawings specifically applicable to the Project and bearing the Project title;
  - · Reviewed and accepted, stamped Working Drawings;
  - 3D Engineered Models and supplemental Agency-prepared line, grade and Cross Section data applicable to the Project;
  - · Standard Drawings;
  - · Approved unstamped Working Drawings and 3D Construction Models;
  - · Standard Specifications;
  - Agreement Form; and
  - All other Contract Documents not listed above, including permits from governmental agencies, and bid documents.

Notes on a drawing shall take precedence over drawing details.

Dimensions shown on the drawings, or that can be computed, shall take precedence over scaled dimensions.

- **(b) Immaterial Discrepancies** The Contract Documents specify details for the construction and completion of the Work. If Contract Documents describe portions of the Work in sufficient detail but are silent in some minor respect, the Contractor may proceed utilizing the current best industry practices.
- **(c) Material Discrepancies** If the Contractor identifies a discrepancy, error, or omission in the Contract Documents that cannot be resolved by the approach specified in (b) above, the Contractor shall immediately request clarification from the Engineer.

### 00150.15 Construction Stakes, Lines, and Grades:

- **(a) General** The Contractor shall perform no Work until the Engineer establishes field controls. Work performed without field controls will be subject to removal at the Contractor's expense.
- (b) Agency Responsibilities The Engineer will:
  - Lay out and set construction stakes and marks to establish the lines, grades, Slopes, Cross Sections, and curve super-elevations for roadwork;
  - Provide one set of construction stakes for line and grade for each additional phase of the Work:

- Set bench marks and stakes for centerline of Bridges and bents:
- Calculate and provide finish deck grades; and
- Deduct from payments due the Contractor all costs incurred to replace stakes and marks negligently or intentionally damaged, removed, or destroyed by the Contractor.

# (c) Contractor Responsibilities - The Contractor shall:

- Inform the Engineer of staking requirements at least 5 Calendar Days before the staking needs to begin;
- Coordinate construction to provide sufficient area for the Engineer to perform surveying work efficiently and safely;
- Accurately measure detailed dimensions, elevations, and Slopes from the Engineer's stakes and marks:
- · Perform the Work in such a manner as to preserve stakes and marks; and
- Set any reference lines for automatic control from the control stakes provided by the Engineer.

**00150.20 Inspection:** The Agency, through its designee shall at all times be allowed access to all parts of the operations and work locations of the Contractor, and shall be furnished such information and assistance by the Contractor, or the designated representative or representatives of the Contractor, as may be required to make a complete and detailed inspection.

(a) Inspection by the Engineer - The Engineer may test Materials furnished and inspect Work performed by the Contractor to ensure Contract compliance. The Contractor shall notify the Engineer 24 hours (one full Work Day) in advance for inspection of each portion of the Work.

Contractor shall not begin placing successive Courses or portions of Work until preceding Courses or portions of the Work have been inspected.

If the Contractor performs Work without the Engineer's inspection or uses Materials that the Engineer has not approved, the Engineer may order affected portions of the Work removed at the Contractor's expense. The foregoing sentence shall not apply if the Engineer fails to inspect the Work within a specific period of time required in the Contract or, in the absence of a specific period of time, within a reasonable period of time after receiving the Contractor's timely written request for inspection or testing.

At the Engineer's direction, any time before the Work is accepted, the Contractor shall uncover portions of the completed Work for inspection. After inspection, the Contractor shall restore these portions of Work to the standard required by the Contract. If the Engineer rejects Work due to Materials or workmanship, or if the Contractor performed such Work without providing sufficient advance request for inspection to the Engineer, the Contractor shall bear all costs of uncovering and restoring the Work. If the Engineer accepts the uncovered Work, and the Contractor performed the Work only after providing the Engineer with sufficient advance notice, the costs of uncovering and restoring the Work will be paid for by the Agency according to 00195.20.

- **(b) Inspection Facilities** The Contractor shall furnish walkways, railings, ladders, shoring, tunnels, platforms, and other facilities necessary to permit the Engineer to have safe access to the Work to be inspected. The Contractor shall require producers and fabricators to provide safe inspection access as requested by the Engineer.
- **(c) Sampling** The Contractor shall furnish the Engineer with samples of Materials that the Engineer will test. All of the Contractor's costs related to this required sampling are Incidental.

- **(d) Inspection by Third Parties** Where third parties have the right to inspect the Work, the Contractor shall coordinate with the Engineer and shall provide safe inspection access.
- **(e) Contractor's Duty to Make Corrections** The Contractor shall perform all Work according to the Contract Documents. The Contractor shall correct Work that does not comply with the Contract Documents at its own expense. Inspection of the Work by the Engineer does not relieve the Contractor of responsibility for improper prosecution of the Work.

**00150.25** Acceptability of Materials and Work - The Contractor shall furnish Materials and shall perform Work in Close Conformance to the Contract Documents. If the Engineer determines that the Materials furnished or the Work performed are not in Close Conformance with the Contract Documents, the Engineer may:

- Reject the Materials or Work and order the Contractor, at the Contractor's expense, to remove, replace, or otherwise correct any non-conformity; or
- Accept the Materials or Work as suitable for the intended purpose, adjust the amount paid for applicable Pay Items to account for diminished cost to the Contractor or diminished value to the Agency, document the adjustment, and provide written documentation to the Contractor regarding the basis of the adjustment.

The Engineer's decisions concerning acceptability of Materials or Work will be final.

**00150.30 Delivery of Notices** - Written notices to the Contractor by the Engineer or the Agency will be delivered:

- In person or via email to the email address provided by the Contractor at the Preconstruction Meeting;
- By U.S. Postal Service first class mail or priority mail (which at the sender's option may include certified or registered mail return receipt requested), to the current office address as shown in the records of the Agency; or
- By overnight delivery service of a private industry courier, to the current office address as shown in the records of the Agency.

Notices shall be considered as having been received by the Contractor:

- At the time of actual receipt when delivered in person or via email by the time which the email transmittal is electronically received by the Contractor's email inbox;
- At the time of actual receipt or seven Calendar Days after the postmarked date when deposited for delivery by first class or priority mail, whichever is earlier; or
- At the time of actual receipt or three Calendar Days after deposit with a private industry courier for overnight delivery service, whichever is earlier.

Written notices to the Engineer or the Agency by the Contractor shall be delivered to the Agency address shown in the Special Provisions, unless a different address is agreed to by the Engineer, and shall be delivered:

- In person
- Via email to the Agency Project Manager;
- By U.S. Postal Service first class mail or priority mail (which at the sender's option may include certified or registered mail return receipt requested); or
- By overnight delivery service of a private industry courier.

Notices will be considered as having been received by the Agency:

- At the time of actual receipt when delivered in person
- At the time of actual receipt via email to the Agency Project Manager;
- At the time of actual receipt or seven Calendar Days after the postmarked date, when deposited for delivery by first class or priority mail, whichever is earlier; or
- At the time of actual receipt or three Calendar Days after deposit with a private industry courier for overnight delivery service, whichever is earlier.

For purposes of this Subsection, the time zone is Pacific Standard Time (PST) to determine time of receipt of notices and other documents. For purposes of this Subsection, non-business days are Saturdays, Sundays and legal holidays as defined by ORS 187.010 and 187.020.

Claims must be submitted on paper documents according to Section 00199

# 00150.35 Plans, 3D Engineered Models, Working Drawings, and 3D Construction Models:

- (a) Plans and 3D Engineered Models The Agency-prepared Plans and 3D Engineered Models will show details of lines, grades, Cross Sections, and Typical Section of the Roadway, and locations and design details of Structures.
- **(b) Working Drawings and 3D Construction Models** The Contractor shall supplement the Agency-prepared Plans and 3D Engineered Models with stamped Working Drawings, unstamped Working Drawings, or 3D Construction Models that show all information necessary to complete the Work. The applicable Section or Subsection of the Standard Specifications will indicate the supplemental information required and whether the drawings are to be stamped or unstamped. Stamped Working Drawings, unstamped Working Drawings, and 3D Construction Models are defined as follows:
  - (1) Stamped Working Drawings Working Drawings, calculations, and other data which are prepared by or under the direction of a Professional Engineer licensed in the State of Oregon, and which bear the engineer's signature, seal, and expiration date.
  - **(2) Unstamped Working Drawings** Working Drawings, calculations, and other data that do not bear an engineering seal.
  - (3) 3D Construction Models See 00110.20.
- **(c) Number, Size, and Format of Working Drawings and 3D Construction Models** The Contractor shall submit Working Drawings and 3D Construction Models according to one of the following methods:
  - (1) Paper Submittal The Contractor shall submit to the Engineer seven copies of Working Drawings for steel Structures and six copies of Working Drawings for other Structures. The submitted copies shall be clear and readable. Drawing dimensions shall be 8 1/2 by 11 inches, 11 by 17 inches, or 22 by 36 inches in size. One copy of the submitted Working Drawings will be returned to the Contractor after processing. The Contractor shall submit such additional number of copies to the Engineer for processing that the Contractor would like to have returned.

The Contractor shall not submit 3D Construction Model data in paper format.

- **(2) Electronic Submittal** The Contractor shall submit electronic Working Drawings as directed by the Engineer. The Contractor shall submit 3D Construction Model data in LandXML format or as directed by the Engineer.
- **(d) Processing Working Drawings and 3D Construction Models** The Engineer will process Working Drawings and 3D Construction Models as follows:
  - (1) Stamped Working Drawings Stamped Working Drawings will be designated as "accepted", "accepted with comments", or "returned for correction" by the Engineer. If stamped Working Drawings are returned for correction by the Engineer, the Contractor shall address all comments and resubmit the stamped Working Drawings.
  - **(2) Unstamped Working Drawings** Unstamped Working Drawings will be designated as "approved", "approved as noted", or "returned for correction" by the Engineer. If unstamped Working Drawings are returned for correction by the Engineer, the Contractor shall address all comments and resubmit the unstamped Working Drawings.
  - (3) 3D Construction Models 3D Construction Models will be designated as "approved", "approved as noted", or "returned for correction" by the Engineer. If 3D Construction Models are returned for correction by the Engineer, the Contractor shall address all comments and resubmit the 3D Construction Models.

The Contractor shall not fabricate or construct any structural components until the stamped or unstamped Working Drawings are returned by the Engineer with a written designation of "accepted", "accepted with comments", "approved", or "approved as noted", as applicable for the Working Drawings.

The Contractor shall not begin construction activities that will utilize a 3D Construction Model until the Engineer has processed the model and designated it as "approved" or "approved as noted".

The Engineer's processing of the Working Drawings and 3D Construction Models does not amend any contractual obligations of the parties.

The Engineer will process and return Working Drawings and 3D Construction Models within 21 Calendar Days (65 Calendar Days if Railroad approval is required) after receipt by the Engineer. If the Engineer fails to return such drawings or models within this period of time, the Engineer will consider granting a Contract Time extension according to 00180.80. If the Contractor is required to resubmit Working Drawings or 3D Construction Models to the Engineer, the Engineer will process and return the Working Drawings or 3D Construction Models within 21 Calendar Days (65 Calendar Days if Railroad approval is required) after receipt of the resubmitted Working Drawings or 3D Construction Models by the Engineer.

**00150.37 Equipment Lists and Other Submittals** - The Contractor shall submit Equipment lists, and other required submittals for approval by the Engineer. The Engineer will respond to requests for approval within 21 Calendar Days (65 Calendar Days if Railroad approval is required) after receipt by the Engineer unless otherwise specified in the Section of the Specifications requiring such approval.

**00150.40** Cooperation and Superintendence by the Contractor - The Contractor is responsible for full management of all aspects of the Work, including superintendence of all Work by Subcontractors, Suppliers, and other providers. The Contractor shall appoint a single Superintendent and may also appoint alternate Superintendents as necessary to control the Work. The form of appointment of the alternate shall state, in writing, the alternate's name, duration of appointment in the absence of the Superintendent, and scope of authority. The Contractor shall:

- Provide for the cooperation and superintendence on the Project by:
  - Furnishing the Engineer all data necessary to determine the actual cost of all or any part of the Work, added Work, or Changed Work.
  - Allowing the Engineer reasonable access to the Contractor's books and records at all times.
     To the extent permitted by public records laws, the Engineer will make reasonable efforts to honor the Contractor's request for protection of confidential information.
  - Keeping one complete set of Contract Documents on the Project Site at all times, available for use by all the Contractor's own organization, and by the Engineer if necessary.
- Appoint a single Superintendent, and any alternate Superintendent, who shall meet the following qualifications:
  - Appointees shall be competent to manage all aspects of the Work.
  - · Appointees shall be from the Contractor's own organization.
  - Appointees shall have performed similar duties on at least one previous project of the size, scope and complexity as the current Contract.
  - Appointees shall be experienced in the types of Work being performed.
  - Appointees shall be capable of reading and thoroughly understanding the Contract Documents.
- The appointed single Superintendent, or any alternate Superintendent, shall:
  - Be present for all On-Site Work, regardless of the amount to be performed by the Contractor, Subcontractors, Suppliers, or other providers, unless the Engineer provides prior approval of the Superintendent's or alternate Superintendent's absence.
  - Be equipped with a two-way radio or cell phone capable of communicating throughout the Project during all the hours of Work on the Project Site and be available for communication with the Engineer.
  - Have full authority and responsibility to promptly execute orders or directions of the Engineer.
  - Have full authority and responsibility to promptly supply the Materials, Equipment, labor, and Incidentals required for performance of the Work.
  - Coordinate and control all Work performed under the Contract, including, without limitation, the Work performed by Subcontractors, Suppliers, and owner/operators.
  - Diligently pursue progress of the Work according to the schedule requirements of Section 00180.
  - Cooperate in good faith with the Engineer, Inspectors, and other contractors in performance of the Work.
  - Provide all assistance reasonably required by the Engineer to obtain information regarding the nature, quantity, and quality of any part of the Work.
  - Provide access, facilities and assistance to the Engineer in establishing such lines, grades and points as the Engineer requires.
  - Carefully protect and preserve the Engineer's marks and stakes.

Any Superintendent or alternate Superintendent who repeatedly fails to follow the Engineer's written or oral orders, directions, instructions, or determinations, shall be subject to removal from the Project.

If the Contractor fails or neglects to provide a Superintendent, or an alternate Superintendent, and no prior approval has been granted, the Engineer has the authority to suspend the Work according to 00180.70. Any continued Work by the Contractor, Subcontractors, Suppliers, or other providers may be subject to rejection and removal. The Contractor's repeated failure or neglect to provide the

superintendence required by these provisions constitutes a material breach of the Contract, and the Engineer may impose any remedies available under the Contract, including, but not limited to, Contract termination.

### 00150.50 Cooperation with Utilities:

- (a) General Unless otherwise specified in the Special Provisions or on the Plans, existing Utilities requiring adjustment may be adjusted by the Utility before, during, or after Project construction. "Adjustment of Utilities" shall mean the alteration, improvement, connection, disconnection, relocation, or removal of existing Utility lines, facilities, or systems in temporary or permanent manner.
- (b) Agency Responsibilities Before Bids are received, the Agency will make preliminary arrangements for planned Adjustment of Utilities. The Agency will list in the Special Provisions the estimated completion dates or times for adjustment work by the Utility owner, and will include a general statement describing any relocation. The Plans will not normally show the anticipated new location of Utilities that have been or will be adjusted.

# (c) Contractor's Responsibilities - The Contractor shall:

- Follow applicable rules adopted by the Oregon Utility Notification Center;
- Contact Utility owners during Bid preparation and after the Contract is awarded to verify all Utilities' involvement on the Project Site;
- Coordinate Project construction with the Utilities' planned adjustments, take all precautions necessary to prevent disruption of Utility service, and perform its Work in the manner that results in the least inconvenience to the Utility owners;
- Include all Utility adjustment work, whether to be performed by the Contractor or the Utilities, on the Contractor's Project Work schedule submitted under 00180.41;
- Protect from damage or disturbance any Utility that remains within the area in which Work is being performed. Maintain and re-establish location marks according to OAR 952-001-0090(3)(a). Coordinate re-establishment of the location marks with the associated Utility;
- Not disturb an existing Utility if it requires an unanticipated adjustment, but shall protect the Utility from damage or disturbance and promptly notify the Engineer;
- Determine the exact location before excavating within the tolerance zone according to OAR 952-001-0090(3)(c);
- Backfill any exposed Utilities as recommended and approved by the Utility representative.
   Obtain Utility locate warning tape from the Utility and replace damaged or removed warning tape. Utility locate warning tape may not be present at all existing Utilities;
- Stake, place warning tape, and maintain no work limits around critical Utility facilities as shown
  or directed by the Engineer and the Utility;
- In addition to the notification required in OAR 952-001-0090(6), notify the Engineer and the
  Utility as soon as the Contractor discovers any previously unknown Utility conflicts or issues.
  Contrary to the OAR, stop excavating until directed by the Engineer and allow the Utility a
  minimum of two weeks to relocate or resolve the previously unknown Utility issues; and
- Report to the Engineer any Utility owner who fails to cooperate or fails to follow the planned Utility adjustment.

Subject to the Engineer's approval, the Contractor may adjust the Utilities by asking the Utility owners to move, remove, or alter their facilities in ways other than as shown on the Plans or in the

Special Provisions. The Contractor shall conduct all negotiations, make all arrangements, and assume all costs that arise from such changes.

- (d) Delays If the Contractor complies with 00150.50(c), and if Utility adjustments are completed later than the date specified in the Special Provisions, thus causing Project completion to be delayed (provide notification under 00180.60), additional Contract Time will be considered under 00180.80, and additional compensation, if applicable, will be considered under 00195.40.
- **(e) Notification** Unless otherwise specified in the Special Provisions, the Project is located within the area served by the Oregon Utility Notification Center, which operates a Utilities notification system for notifying owners of Utilities about Work being performed in the vicinity of their facilities. The Contractor shall notify owners of Utilities prior to the performance of Work in the vicinity of their facilities. The Utilities notification system telephone number is 811 or 1-800-332-2344.

The Contractor shall comply with the rules of the Oregon Utility Notification Center, OAR 952-001-0010 through OAR 952-001-0090, and ORS 757.993. The Contractor may contact the Oregon Utility Notification Center at 503-232-1987 about these rules.

**00150.55** Cooperation with Other Contractors - The Agency reserves the right to perform other work on or near the Project Site, including, without limitation, any Materials site, with forces other than those of the Contractor.

If such work takes place on or near the Project Site, the Contractor shall have the following obligations:

- The Contractor shall coordinate Work with other contractors or forces.
- The Contractor shall cooperate in good faith with all other contractors or forces.
- The Contractor shall perform the Work specified in the Contract in a way that will minimize interference and delay for all forces involved.
- The Contractor shall place and dispose of the Materials being used so as not to interfere with the operations of other forces.
- The Contractor shall join the Work with that of other forces in a manner acceptable to the Engineer or the Agency, and shall perform it in the accepted sequence with the work of the other force.

The Engineer will resolve any disagreements under this Subsection that may arise among the Contractor and other work forces, or between the Contractor and the Agency. The Engineer's decision in these matters is final, as provided in 00150.00.

When the schedules for Work of the Contractor and the work of other forces overlap, each contractor involved shall submit a current, realistic progress schedule to the Engineer. Before the Engineer accepts the schedule, each party shall have the opportunity to review all schedules. After this review and any necessary consultations, the Engineer will determine acceptable schedules.

The Contractor waives any right it may have to make claims against the Agency for any damages or claims that may arise because of inconvenience, delay, or loss due solely to the presence of other contractors working on or near the Project Site.

If the Contract gives notice of work to be performed by other forces that may affect the Contractor's Work under the Contract, the Contractor shall include any costs associated with coordination of the Work in the appropriate Pay Item or as a portion of a Pay Item.

In an emergency, the Contractor most immediately able to respond may repair a facility or Utility of another contractor in order to prevent further damage to the facility, Utility, or other Structure as a result of the emergency.

### 00150.60 Construction Equipment Restrictions:

(a) Load and Speed Restrictions for Construction Vehicles and Equipment - The Contractor shall comply with legal weight and speed restrictions when moving Materials or Equipment beyond the limits of the Project Site.

The Contractor shall control vehicle and Equipment loads and speeds within the Project Site according to the following restrictions, unless the Special Provisions provide otherwise:

- The Contractor shall restrict loads and speeds as necessary to avoid displacement or loss of Materials on Subgrades and Aggregate Bases.
- The Contractor shall restrict weights to legal loads, and shall travel at speeds of no more than 45 mph or the posted construction speed, whichever is less, on treated Bases, Pavement, or wearing Courses.
- The Contractor shall not cross Bridges or other Structures with Equipment or vehicles
  exceeding the legal load limit without prior written permission of the Engineer. The Contractor
  shall make any such request in writing, describing the loading details and the arrangement,
  movement, and position of the Equipment on the Structure. The Contractor shall comply with
  any restrictions or conditions included in the Engineer's written permission.
- (b) Protection of Buried Items The Contractor shall use temporary fill or other methods to avoid overload of pipes, box culverts, and other items that are covered, or to be covered, by fill or backfill.
- **(c)** Responsibility for Damages The Contractor shall assume responsibility for damages caused by excessive Equipment speed or loads while performing the Work, both inside and outside the Project Site. The Engineer's permission to cross Bridges and other Structures, according to 00150.60(a), will not relieve the Contractor from responsibility for load-caused damages.

**00150.70 Detrimental Operations** - The Contractor shall avoid operations whose methods, conditions, or timing may injure people or damage property or the Work. Damage may include, without limitation, staining surfaces with mud or asphalt or damaging Utilities and foundations. (See also 00150.60, 00150.75, and Section 00170.)

When any such damage occurs, the Engineer will determine if it is to be corrected by repair, replacement, or compensatory payment by the Contractor. If compensatory payment is required, the Engineer will determine the amount. Compensatory payment may be deducted from monies due or to become due to the Contractor under the Contract.

Contractor is solely responsible for damages outside the Project limits. In addition, prior to construction, the Contractor shall provide to the Engineer videotape showing private property, if any, which may be disturbed during construction.

**00150.75 Protection and Maintenance of Work During Construction** - The Contractor shall protect and maintain the Work during construction and until Third Notification has been issued, unless otherwise provided in the Contract. For the purposes of this Subsection, "maintenance" shall include measures to prevent deterioration of Roadway and Structures at the Project Site, and to keep them in good condition at all times during the prosecution of the Work. The Contractor shall continuously allocate sufficient Equipment and workers to achieve such maintenance.

If the Contract requires the placement of a Course upon a previously constructed Course or Subgrade, the Contractor shall maintain the previous Course or Subgrade during all construction operations.

The Contractor shall include costs of protecting and maintaining the Work during construction in the unit prices bid for the various Pay Items. The Contractor will not be paid an additional amount for this Work, unless otherwise specified.

The Engineer will notify the Contractor of the Contractor's noncompliance with this Subsection. If the Contractor fails to remedy unsatisfactory protection or maintenance within 24 hours after receipt of such notice, the Engineer may proceed to remedy the deficiency, and deduct the entire cost from monies due or to become due the Contractor under the Contract.

**00150.80 Removal of Unacceptable and Unauthorized Work** - The Contractor shall correct or remove unacceptable Work and remove unauthorized work, as directed by the Engineer in writing. The Contractor shall replace such work with Work and Materials conforming to the requirements of the Contract.

For the purposes of this Subsection, "unauthorized work" shall include without limitation the following:

- Work that extends beyond lines shown on the Plans or otherwise established by the Engineer;
- Work that is contrary to the Engineer's instructions; and
- · Work that is conducted without the Engineer's written authorization.

The Agency will not pay the Contractor for unacceptable Work, except as provided in 00150.25, or for unauthorized work. The Engineer may issue a written order for the correction or removal of such work at the Contractor's sole expense.

If, when ordered by the Engineer, the Contractor fails to correct or remove unacceptable Work or remove unauthorized work, the Engineer may have the correction, removal or removal and replacement, done by others and deduct the entire cost from monies due or to become due the Contractor under the Contract.

### 00150.90 Final Inspection:

(a) On-site Construction Work - The Engineer will inspect the Project at a time close to the completion of On-Site Work.

When all On-Site Work on the Project is completed, including, but not limited to, Change Order Work and Extra Work, the Engineer will issue Second Notification as specified in 00180.50(g).

Within 15 Calendar Days after the Engineer receives the Contractor's written notification that all punch list items, final trimming and cleanup according to 00140.90 have been completed, the Engineer will review the Project and notify the Contractor that all Work is complete, or will give the Contractor written instruction regarding incomplete or unsatisfactory Work.

- **(b) All Contract Work** The Engineer will issue the Third Notification when the Contractor has satisfactorily accomplished all of the following:
  - The Contractor has completed all On-Site Work required under the Contract, including the punch list items from (a) above;
  - · The Contractor has removed all Equipment, other than that incorporated into the Work; and

 The Contractor has submitted all required certifications, bills, forms, warranties and other documents.

Upon completion of the requirements of all On-Site Work required under the Contract, Contractor is to promptly remove from the work location, and other property owned or controlled by the Agency, all equipment, materials and other property the Contractor has placed or caused to be placed thereon that is not to become the property of the Agency. It is further understood and agreed that any such equipment, materials and other property that are not removed within 30 days after the day this contract terminates, or within such longer time as may be agreed upon in writing between the Contractor and the Agency, shall become the property of the Agency and may be used or otherwise disposed of by the Agency without obligation to the Contractor or to any party to whom the Contractor may transfer title. Nothing in this section shall be construed as relieving the Contractor from an obligation to clean up, and to burn, remove, or dispose of debris, waste materials, and such, in accord with other provisions of the contract.

**00150.91 Post-Construction Review** - The Contractor or the Engineer may request a Post-Construction Review meeting, to be held at a time prior to issuance of Third Notification but not earlier than 45 Days following the date of Second Notification. The meeting may be held if agreed to by both parties. The party making the request will conduct the meeting, and will announce the time and place of the meeting at least 15 Days prior to the meeting date. The purpose of this meeting is to examine the Project for possible process improvements that may benefit future projects.

**00150.95 Final Acceptance** - After the Engineer completes Final Inspection of all Work and sends Third Notification to the Contractor, the Agency will acknowledge Final Acceptance. The Agency will notify the Contractor in writing of the date of Final Acceptance within 7 Calendar Days after Final Acceptance, or as soon thereafter as is practicable.

**00150.96 Maintenance Warranties and Guarantees** - Prior to Third Notification, the Contractor shall transfer to the Agency all unexpired manufacturers' warranties and guarantees for Materials and Equipment installed on the Project. Such warranties and guarantees shall recite that they are enforceable by the Agency.

### 00150.97 Responsibility for Materials and Workmanship:

- (a) The Contractor shall perform the Work according to the terms, conditions, and requirements of the Contract. Only materials, improvements and property free and clear of liens, claims and encumbrances shall be so furnished by the Contractor.
- **(b)** Whether before or after the Agency's acceptance of the Work, the Contractor shall be responsible for:
  - Correcting or repairing any defects in, or damage to, the Work that results from the use of improper or defective materials or workmanship; or
  - Replacing, in its entirety, the Work affected by the use of improper or defective materials or workmanship to the extent provided by law; and
  - Correcting or repairing any Work, Materials, Structures, Existing Surfacings, Pavement, Utilities, or sites, including, without limitation, Wetlands, damaged or disturbed in that correction, repair, or replacement. (See 00170.80 to 00170.85.)
- **(c)** Full or partial termination of the Contract under 00180.90 shall not relieve the Contractor of responsibility for completed or performed Work, or relieve the Contractor's Surety of the obligation for any just claims arising from the completed or performed Work.

### Section 00160 - Source of Materials

**00160.00 Definitions** - The following definitions apply to Section 00160:

- (a) Prospective Source Agency-furnished Materials source, use of which by the Contractor is optional. The Agency makes no guarantee or representation, by implication or otherwise, of the land use status, quantity, quality, or acceptability of Materials available from it, except as may be stated in the Special Provisions.
- **(b) Mandatory Source** Agency-furnished Materials source, use of which by the Contractor is required.
- (c) Blue Sheets Prequalified products and submittals for qualification of electrical equipment and materials.
- (d) Green Sheets Conditionally prequalified products and submittals for conditional qualification of controller equipment.
- **(e) Red Sheets** Statewide list of certification exempt traffic management systems components pursuant to ORS 479.540 and OAR 918-261-0037.

### 00160.01 Notification of Source of Supply and Materials:

- (a) All Materials The Contractor shall notify the Engineer in writing of all proposed Materials sources of supply, including, without limitation, any steel or other fabricators within the following time frames:
  - At least 15 Calendar Days before using or fabricating Materials, if the source is within the State; or
  - At least 45 Calendar Days before using or fabricating Materials, if the source is outside the State

The Contractor shall identify if the material source is a DBE or non-DBE. For DBE Suppliers, the Contractor shall identify an estimated value of the materials to be supplied. For each committed DBE Supplier, the Contractor shall submit a copy of the materials purchase order or supply agreement. For non-committed DBE suppliers, when the estimated value is over \$10,000, the Contractor shall submit a copy of the materials purchase order or supply agreement.

For this purpose, a committed DBE firm is one that was identified by the Contractor to meet an assigned DBE goal, including DBE firms substituting for DBE firms committed as a condition of Contract Award.

- **(b) Prospective Source Materials** When given an option to use Prospective Sources of Materials to be incorporated into the Work, the Contractor shall notify the Engineer in writing of the option selected within 15 Calendar Days from date of Notice to Proceed. Otherwise, such Materials sources may become unavailable.
- **(c) Approval Required** Before allowing production or delivery of Materials to begin from any source, the Contractor must obtain the Engineer's approval. Approval to use any source does not imply that Materials from that source will be accepted. If approved sources do not provide Materials that meet Specifications, the Materials will be rejected. The Contractor will then be responsible for locating other sources and obtaining the Engineer's approval.
- (d) Terms Required The Contractor shall comply with 00170.07.

**00160.05 Qualified Products List (QPL)** - The QPL is a listing of manufactured products available on the market (shelf items) that ODOT has evaluated and found suitable for a specified use in highway construction. The QPL is available from ODOT's Construction Section website (see 00110.05(e)).

The most current published PDF version of the QPL on ODOT's Construction Section website at the time of Advertisement is the version in effect for the Project. When the Contract specifies the use of the QPL, unless specified as the subject of an exemption per ORS 279C.345, the Agency may approve for use a conditionally qualified product, a product qualified for inclusion in a later edition of the QPL, or other equivalent product that meets the requirements of the QPL, following the Standard Guidelines for Product Review, if the Agency finds the product acceptable for use on the Project.

Use of listed products shall be restricted to the category of use for which they are listed. The Contractor shall install all products as recommended by the manufacturer. The Contractor shall replace qualified products not conforming to Specifications or not properly handled or installed at no additional cost to the Agency.

**00160.07 Electrical Equipment and Materials** - The Blue Sheets and Green Sheets are a listing of manufactured products available on the market (shelf items) that ODOT has evaluated and found suitable for use as electrical and controller equipment and materials for highway construction. The Blue Sheets and Green Sheets are available on the ODOT Traffic-Standards website (see 00110.05(e)). The most current version of the Blue Sheets and Green Sheets on the date of Advertisement is the version in effect for the Project.

When the Contract specifies the use of the Blue Sheets and Green Sheets, unless specified as the subject of an exemption per ORS 279C.345, the Agency may approve for use a product qualified for inclusion in a later edition of the Blue Sheets and Green Sheets or other equivalent product that meets the requirements of the Blue Sheets, following the Blue Sheet Qualification/Specification Information, or the Green Sheets, following the ODOT Standard Specification for Microcomputer Signal Controller and errata information, if the Agency finds the product acceptable for use on the Project.

Use of listed products shall be restricted to the category of use for which they are listed. The Contractor shall install all products as recommended by the manufacturer. The Contractor shall replace qualified products not conforming to the Specifications or not properly handled or installed at no additional cost to the Agency.

**00160.10 Ordering, Producing, and Furnishing Materials** - The Contractor shall not place orders for or produce full quantities of Materials anticipated to be required to complete the Work until the Work has advanced to a stage that allows the quantities to be determined with reasonable accuracy. Upon request, the Engineer will notify the Contractor in writing of the quantities required. Quantity estimates by the Engineer before this notification are only approximate.

- (a) Contractor's Duties In purchasing, producing, or delivering Materials, the Contractor shall take into account the following:
  - Kind of work involved;
  - · Amount of work involved:
  - Time required to obtain Materials; and
  - · Other relevant factors.
- **(b) Approval of Quantity of Materials Ordered** Materials quantities shown on the Plans, or indicated by quantities and Pay Items, are subject to change or elimination. Therefore, the Contractor is cautioned to order or produce Materials only after having received the approval of the

Engineer. The Contractor is responsible for payment for excess Materials delivered to the Project Site or storage sites without advance authorization from the Engineer. Unless otherwise specified in the Contract, the Agency will not be responsible for:

- Materials the Contractor may deliver or produce in excess of Contract requirements;
- Extra expense the Contractor may incur because Materials were not ordered or produced earlier; or
- The Contractor's expenses related to Materials ordered by the Contractor that are not subsequently approved for use.

Excess Materials ordered or produced by the Contractor without approval of the Engineer may be purchased by the Agency at the sole discretion of the Agency. (See 00195.80.)

#### 00160.20 Preferences for Materials:

(a) Buy America - If federal highway funds are involved on the Project, the Contractor shall limit the quantity of foreign Materials incorporated into the Work as follows. Section 635.410 of Title 23, Code of Federal Regulations, and the Intermodal Surface Transportation Efficiency Act require that all iron or steel manufacturing processes, including, without limitation, the casting of ingots, for iron or steel Materials permanently incorporated into the Project shall occur in the United States, unless the cost of foreign-origin iron or steel Materials does not exceed one-tenth of one percent (0.1%) of the Contract Amount or \$2,500, whichever is greater. The Contractor shall not incorporate foreign-origin iron or steel Materials in excess of this amount into the Project. All foreign-origin iron or steel Materials incorporated in the Project in excess of the amount indicated above shall be removed and replaced with domestic iron or steel Materials at the Contractor's expense. For purposes of this Specification, the cost of foreign-origin iron or steel Materials shall be the value of the iron or steel products as of the date they are delivered to the Project Site.

Manufacturing processes include without limitation the application of coatings to finished iron or steel products or components. Coatings include epoxy coating, galvanizing, painting, and any other coating that protects or enhances the value of the steel or iron product or component.

The Contractor shall provide the Engineer with a Certificate of Materials Origin, on a form furnished by the Engineer, before incorporating any iron or steel products into the Project. Unless a Certificate of Materials Origin has been provided to the Engineer, the Materials shall be considered of foreign origin.

The Contractor shall retain manufacturers' certificates verifying the origin of all domestic iron or steel Materials for 3 years after the date of final payment for the Project, and shall furnish copies to the Engineer upon request.

- **(b) Buy Oregon** According to ORS 279A.120, the Contractor shall give preference to goods or services produced in Oregon if price, fitness, availability, and quality are equal. This provision does not apply to contracts financed wholly or in part by federal funds.
- **(c) Recycled Materials** According to ORS 279A.010, ORS 279A.125, ORS 279A.145, ORS 279A.150, and ORS 279A.155, and subject to the approval of the Engineer, the Contractor shall use recycled products to the maximum extent economically feasible.
- (d) Build America Buy America Act Requirements If federal highway funds are involved on the Project, the Contractor shall comply with the Build America Buy America Act and implementing regulations (Infrastructure Investment and Jobs Act ("IIJA"), Pub. L. No. 117-58, which includes the Build America, Buy America Act ("the Act"). Pub. L. No. 117-58, Sections 70901-70941).

All of the manufacturing processes must occur in the United States for the applicable construction materials permanently incorporated in the Project as listed below.

Construction materials include an article, Material, or supply - that is or consists primarily of:

non-ferrous metals;

plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables);

glass;

lumber; or

drywall.

The Contractor shall provide the Engineer with a Certificate of Materials Origin, on a form furnished by the Engineer, before incorporating any applicable construction materials into the Project. Unless a Certificate of Materials Origin has been provided to the Engineer, the products and Materials shall be considered of foreign origin.

No de minimis amount has been established for applicable construction materials permanently incorporated into the Project. Strict compliance is required.

The Contractor shall retain manufacturers' certificates verifying the origin of all applicable construction materials for 3 years after the date of final payment for the Project, and shall furnish copies to the Engineer upon request.

Manufactured products assembled outside the Project Site are not subject to the Build America Buy America requirements. Manufactured products are items that consist of two or more of the listed construction materials that have been combined together through a manufacturing process, and items that include at least one of the listed construction materials combined with a Material that is not listed through a manufacturing process, and should be treated as manufactured products, rather than as construction materials.

Iron and steel Materials are subject to 00160.20(a).

The Contractor shall include this provision in all subcontracts.

**00160.21 Cargo Preference Act Requirements** - If federal highway funds are involved on the Project, the Contractor shall comply with the Cargo Preference Act and implementing regulations (46 CFR Part 381) for use of United States flag ocean vessels transporting materials or equipment acquired specifically for the Project. Strict compliance is required, including, but not limited to, the clauses in 46 CFR 381.7(a) and (b), which are incorporated by reference. The Contractor shall also include this provision in all subcontracts.

**00160.30 Agency-Furnished Materials** - Unless otherwise specified in the Special Provisions, Materials listed as Agency-furnished will be available to the Contractor free of charge.

The Contractor shall be responsible for all Materials furnished by the Agency and shall pay all demurrage and storage charges. The Contractor shall replace at its expense Agency-furnished Materials lost or damaged due to any cause.

The locations at which Agency-furnished Materials are available will be specified in the Special Provisions. If the locations are not listed in the Special Provisions, the Agency-furnished Materials will be furnished to the Contractor at the Project Site. In either case, all costs of handling, hauling,

unloading, and placing Agency-furnished Material shall be considered included in the price paid for the Pay Item involving such Material.

All Agency-furnished Materials not incorporated into the Work remain the property of the Agency. The Contractor shall deliver such Materials as directed by the Engineer.

- **00160.40** Agency-Furnished Sources The Agency may list in the Special Provisions, or show on the Plans, Borrow pits or Aggregate sources from which the Contractor may, or shall, obtain Materials. These sources will be identified and referred to as Prospective or Mandatory Sources. A development plan will be included in Section 00235 of the Special Provisions when such sources are shown on the Plans.
  - (a) Working in a Different Area of the Materials Source If the Contractor desires to work in a different area of the Materials source than that shown on the development plan, the Contractor must submit a written request stating the reasons for the requested change. If a new land use permit, development plan, or reclamation plan is needed, the Contractor must submit it and obtain approval from the Engineer before starting work in any area other than that shown on the Plans. Approval for work in a different area will not entitle the Contractor to any added compensation or adjustment of Contract Time.

The Agency will not be responsible for the availability of sources other than as stated in the Special Provisions. If the Contractor has given notice of intent to use, but does not use the source(s) on the Project, the Contractor shall reimburse the Agency for any costs the Agency incurs in making such source(s) available.

- **(b) Cost of Sources** Unless otherwise specified in the Special Provisions, any Prospective or Mandatory Source will be provided by the Agency for use without payment of royalty or other charge. (See 00160.50.)
- **(c)** Exhaustion of Sources If the Engineer determines that the quantities of specified Materials that can be produced from a Mandatory Source are insufficient for the Work, and it becomes necessary to move to another source, the Agency will pay for the reasonable cost of moving the plant to, and erecting it at, a new approved source from which specified Materials can be produced. Adjustment in hauling costs, other costs, and Contract Time will be determined as provided in 00140.30.

No allowance, reimbursement, compensation, or adjustment will be made for changes in the use of sources, or for moving from one source to another, except as provided above.

### 00160.50 Agency-Controlled Land; Limitations and Requirements:

**(a) General** - The Contractor shall have no property rights in, or right of occupancy on, Agency-Controlled Land. Nor shall the Contractor have the right to sell, use, remove, or otherwise dispose of any material from Agency-Controlled Land, areas, or property, except as specified or by the written authorization of the Engineer.

Unless authorized in the Contract, the Contractor shall not disturb any material within Rights-of-Way without written authorization from the Engineer. The Contractor shall not take, sell, use, remove or otherwise dispose of any sand, gravel, rock, earth, firewood, and/or other material obtained or produced from within the limits of rights-of-way, gravel pits, rock quarries or other property owned by or held by the Agency unless specially authorized by this contract or by written consent of the Agency.

Unless otherwise specified in the Contract, the ownership of all materials originating on Agency-Controlled Lands will at all times vest in, and remain within the control of, the Agency.

- **(b) Waste, Excess, and By-Product Materials** All waste, excess, and by-product materials, collectively referred to in this Subsection as "By-Products", from the manufacture or production of Aggregate Materials from Agency-Controlled Lands shall remain Agency property. Unless otherwise ordered by the Engineer in writing, By-Products shall be placed as required by the development plan:
  - · In stockpiles at designated locations;
  - · At locations and in shapes that are readily accessible; and
  - In such a manner as to avoid fouling areas containing useable materials, or interfering with future plant setups to use materials from the property.

The Agency will not compensate the Contractor for handling and stockpiling By-Products according to the development plan requirements. If by written order the Engineer directs the Contractor to stockpile or place designated By-Products at alternate sites, the By-Products designated shall be loaded, hauled, and placed as directed, and this work will be paid for according to 00195.20.

### 00160.60 Contractor-Furnished Materials and Sources:

- (a) General The Contractor shall furnish, at its own expense, all products and Materials required for the Project from sources of its own choosing, unless such sources have been specified in the Special Provisions or Plans as Prospective or Mandatory Sources.
- **(b) Acquisition of Sources** The Contractor shall acquire, at its own expense, the rights of access to, and the use of, all sources the Contractor chooses that are not Agency-controlled and made available by the Agency to the Contractor.
- **(c)** Additional Requirements Except for continuously-operated commercial sources, Work shall not begin, nor will any Materials be accepted by the Engineer, until the Contractor has:
  - (1) Given to the Engineer a copy of permits from, or proof that permits are not required from:
    - The Department of Geology and Mineral Industries, as required under ORS 517.790;
    - The Department of State Lands, as required under ORS 196.815 (when removing material from the bed or banks of any waters or from any Wetland); and
    - Local governmental authorities having jurisdiction over land use at the source location.
  - (2) Furnished to the Engineer written approval of the property owner, if other than the Contractor, for the Contractor's proposed plans of operation in, and reclamation of, the source. The Contractor shall include in the document containing the property owner's written approval a summary of the requirements of the permits described above, which shall be subject to the Engineer's approval.

**00160.70** Requirements for Plant Operations - Before operating mixing plants, Rock crushers, or other Equipment, the Contractor shall provide the Engineer copies of all applicable discharge permits for noise, air contaminants, and water pollutants from DEQ or applicable local jurisdictions, or a letter from DEQ or the local jurisdiction stating that no permits are required for the use of the Equipment and sites.

**00160.80** Requirements for Sources of Borrow and Aggregate - The Contractor shall conduct operations according to all applicable federal, State, and local laws (including, without limitation, ORS Chapter 517 and OAR 632-030) when developing, using, and reclaiming all sources of Borrow material and Aggregate. The Contractor shall provide erosion control at Borrow sources that are not within the Project Site. The Contractor shall not operate in Wetlands except as allowed by permit. The Contractor shall comply with all requirements for pollution and sediment control, including, without limitation, the National Pollutant Discharge Elimination System where applicable.

Except for continuously-operated commercial sources, the Contractor shall also conform to the following:

- (a) If a natural growth of trees or shrubs is present, preserve a border of such to conceal land scars.
- **(b)** Excavate Borrow sources and Aggregate sources, except for those in streams and rivers, to provide:
  - Reasonably uniform depths and widths;
  - Natural drainage so no water stands or collects in excavated areas, when practicable;
  - Slopes trimmed to blend with the adjacent terrain upon completion of operations;
  - Slopes covered with native Soil, or acceptable plant rejects to support plant growth, if required by Specifications, Plans, or permits; and
  - A vegetative cover that blends with the adjacent natural growth.
- (c) Excavate in quarries so that:
  - Faces will not be steeper than vertical (no overhang);
  - Vertical faces conform to Oregon OSHA standards, Division 3, and as shown on an approved development plan;
  - Floors or benches are excavated to a uniform Slope free of depressions and will drain and not interfere with the downland owner's property; and
  - Upon completion, the quarry is left appearing neat and compatible with surrounding terrain.
- **(d)** Obliterate haul roads specifically built for access to sources, and restore the areas disturbed by these roads as nearly as practicable to the conditions that existed before the roads were built, unless otherwise directed by the landowner or regulatory body.

# Section 00165 - Quality of Materials

### Description

**00165.00 General** - The Contractor shall incorporate into the Work only Materials conforming to the Specifications and approved by the Engineer. The Contractor shall incorporate into the Work only manufactured products made of new materials unless otherwise specified in the Contract. The Agency may require additional testing or retesting to determine whether the Materials or manufactured products meet Specifications.

Materials or manufactured products not meeting the Specifications at the time they are to be used are unacceptable and must be removed immediately from the Project Site, unless otherwise directed by the Engineer.

**00165.01 Rejected Materials** - The Engineer may reject any Materials that appear to be defective (see 00150.25) or that contain asbestos. The Contractor shall not incorporate any rejected Materials into the Work. Rejected Materials whose defects have been corrected may not be incorporated into the Work until the Engineer has approved their use. The Engineer may order the removal and replacement by the Contractor, at the Contractor's expense, of any defective Materials. (See also 00150.20.)

**00165.02 Materials Conformance and Quality Compliance Documents** - For purposes of this Section, "Materials Conformance Documents" means the Contractor's quality-control, the Agency's verification, and the independent assurance test results, and the identity of the testing facility, as specified in the ODOT *Manual of Field Test Procedures* (MFTP), unless otherwise specified in the Contract.

For purposes of this Section, "Quality Compliance Documents" means those documents specified in ODOT's *Nonfield-Tested Materials Acceptance Guide*, unless otherwise specified in the Contract.

**00165.03 Testing by Agency** - When testing Materials, the Agency will have tests conducted in laboratories designated by the Engineer, even though certain AASHTO, ASTM, and other materials specifications may require testing at the place of manufacture. Results of the Agency's tests will be made available to the Contractor.

**00165.04 Costs of Testing** - When the Contract requires that the Agency perform the testing, the testing will be at the Agency's expense. The Agency will pay the cost of Contractor-requested source-review tests on unprocessed Aggregates from no more than two sources for each Project, and on no more than three unprocessed samples from each source. Additional source-review tests performed at the Contractor's request shall be at the Contractor's expense.

Unless otherwise provided in the Contract, all testing required to be performed by the Contractor will be at the Contractor's expense.

### **Provisions and Requirements**

**00165.10 Materials Acceptance Guides** - Unless otherwise specified elsewhere in the Contract, Materials will be accepted according to the following guides:

(a) Field-Tested Materials - Field-tested Materials will be accepted according to the MFTP. The MFTP is published once per year and is available from the ODOT Construction Section; 800 Airport Road SE; Salem, OR 97301-4798; phone 503-986-3000. The MFTP is also available on the ODOT Construction Section website (see 00110.05(e)). The most current version of the MFTP on the date of Advertisement is the version in effect for the Project.

**(b) Nonfield-Tested Materials** - Nonfield-tested Materials will be accepted according to the ODOT *Nonfield Tested Materials Acceptance Guide* (NTMAG), unless otherwise specified in the Contract. The NTMAG is available on the ODOT Construction Section website (see 00110.05(e)). The most current version of the NTMAG on the date of Advertisement is the version in effect for the Project.

**00165.20 Materials Specifications and Test Method References** - References to materials specifications and test methods of ODOT, WAQTC, AASHTO, ASTM, other governmental agencies, or other recognized organizations mean those officially adopted and in current use by the agency or organization on the date of Advertisement.

If there are conflicting references, or if no reference is made to materials specifications, sampling and testing frequencies, or test method, the Engineer will resolve any discrepancies between these documents in the following orders of precedence:

### Field-Tested Materials:

- Contract Change Orders;
- Special Provisions;
- ODOT Laboratory Manual of Test Procedures;
- MFTP; and
- Standard Specifications.

### Nonfield-Tested Materials:

- Contract Change Orders:
- · Special Provisions;
- ODOT Laboratory Manual of Test Procedures; and
- Standard Specifications.

### Material test methods:

- ODOT:
- WAQTC:
- AASHTO:
- ASTM:
- Other recognized national organizations, such as ANSI, AWPA, IMSA, ISSA, and UL; and
- Industry standards in the location where the Work is being performed.

### Sampling and testing frequencies:

- Contract Change Orders;
- Special Provisions:
- MFTP; and
- Standard Specifications.

If the Contractor identifies conflicting references or if no reference is made, the Contractor shall immediately request a clarification from the Engineer.

### 00165.30 Field-Tested Materials:

- (a) Contractor's Duties The Contractor shall:
  - Furnish Materials of the quality specified in the Contract;
  - Provide and administer a quality control program as described in the Quality Assurance Program portion of the MFTP. Upon request, the Contractor shall provide to the Engineer the names, telephone numbers, and copies of certifications for all personnel performing field testing; and
  - Perform other testing as required by the Contract.
- **(b)** Types of Tests The types of tests and testing methods generally required by the Agency are described in the MFTP.
- (c) Acceptance of Field-Tested Materials The Contractor's test results for field-tested Materials will be verified by the Agency according to the Quality Assurance program outlined in the MFTP. If the Agency's QA test results verify the Contractor's results, the Materials will be analyzed for acceptance according to one of the following methods before the Engineer will accept them for incorporation into the Work:
  - Statistically, according to 00165.40, to determine "Pay Factors" for produced Aggregate;
  - · Statistically, according to 00165.40, to determine "Composite Pay Factors" for mixtures; or
  - Other methods determined by the Engineer.

If the Agency's verification test results do not verify the Contractor's test results, the Agency may require additional testing to determine whether the Materials meet Specifications. The Contractor shall perform additional testing or provide samples to the Agency for testing as directed. If the Materials do not meet Specifications, the Contractor shall reimburse the Agency for the cost of the additional testing, which may be deducted from monies due or to become due the Contractor under the Contract. Incorporated Materials that do not meet Specifications will be evaluated according to 00165.01 and 00150.25. If the Materials meet Specifications, the Agency will pay the cost for the additional testing.

**00165.35 Nonfield-Tested Materials** - The Contractor shall furnish Materials meeting Specifications, along with all Materials Conformance and Quality Compliance Documents.

- (a) Test Results Certificate The certificate shall:
  - Be from the manufacturer, verifying that the Material furnished has been sampled and tested and the test results meet the Specifications.
  - Include, or be accompanied by, a copy of the specified test results (ODOT, AASHTO, ASTM, UL or other).
  - Identify the testing agency and the representative responsible for the test results.
  - Permit positive determination that Material delivered to the Project is the same Material covered by the test results.
  - Be delivered to the Engineer with the shipment of the material.
- (b) Quality Compliance Certificate The certificate shall be from the manufacturer and shall:

- Verify that the Material meets the Specifications, and identify by number the specified test methods used, (ODOT, AASHTO, ASTM, UL, or other).
- Permit positive determination that Material delivered to the Project is the same Material covered by the certificate.
- Be delivered to the Engineer with the shipment of the Material, or be an identification plate or mark, decal, sticker, label, or tag attached to the container or Material.
- (c) Equipment List and Drawings These consist of lists of proposed Equipment and Materials, such as:
  - · Shop drawings
  - · Material lists
  - · Equipment lists
  - · Catalog description sheets
  - · Manufacturer's brochures

Submit these lists to the Engineer for review of conformance with the Specifications.

(d) Certificate of Origin of Steel Materials - When specified, complete this document (ODOT Form 734-2126) as required by 00160.20 for Federal-aid projects.

Materials will be subject to acceptance testing if the Engineer so elects. The Engineer may reject damaged or non-specification materials regardless of the Materials Conformance Documents furnished.

**00165.40 Statistical Analysis** - When 00165.30(c) or 00165.50 applies, the Contractor shall divide the Materials into lots and sublots, randomly sample and test them as required, and analyze the results statistically to determine whether the Materials conform to the Specifications.

All acceptance test results of lots and sublots will be analyzed collectively using the Quality Level Analysis procedure set out in this Subsection. This procedure shall not be used for a lot with less than three sublots. Sampling of Material for a lot that contains two or fewer sublots shall be increased to obtain at least three sublots. The Engineer has discretion to either accept or reject lots originating with two or fewer sublots, even after sampling is increased.

- (a) Lot A lot is the quantity of Materials produced by a single process or JMF that is sampled, tested, and statistically evaluated, as specified in this Subsection.
- (b) Sublot A sublot is a portion of a lot, for which a sample test value may be normally obtained.
- **(c) Quality Level Analysis** Quality Level Analysis is a statistical procedure to determine, for each lot:
  - The percentage of each constituent of the Materials meeting Specifications;
  - The Pay Factor for each constituent; and
  - The Composite Pay Factor, when specified.
- (d) Pay Factor and Composite Pay Factor Computation Procedures for determining the percent meeting Specifications, Pay Factors, and Composite Pay Factor for a lot of Materials are as follows:

(1) Compute lot arithmetic mean ( $\overline{X}$ ) for each constituent:

$$\overline{X} = \frac{\sum X}{n}$$

Where  $\Sigma X$  = summation of sample test values n = total number of samples

(2) Compute standard deviation (sd) for each constituent:

$$sd = \sqrt{\frac{\sum X^2 - n \overline{X}^2}{n - 1}}$$

Where  $\sum X^2$  = summation of the squares of each sample test value  $\overline{X}^2$  = square of the lot arithmetic mean

(3) Compute the upper quality index (Q<sub>U</sub>) for each constituent:

$$Q_U = \frac{USL - \overline{X}}{sd}$$

Where USL (upper specification limit) is the target value plus allowable tolerance

(4) Compute the lower quality index (Q<sub>L</sub>) for each constituent:

$$Q_{L} = \frac{\overline{X} - LSL}{sd}$$

Where LSL (lower specification limit) is the target value minus allowable tolerance

- (5) From Table 00165-1, for each constituent, determine the percent within the upper specification limit ( $P_U$ ) which corresponds to a given  $Q_U$ . If USL is 100% or is not specified,  $P_U$  will be 100.
- (6) From Table 00165-1, for each constituent, determine the percent within the lower specification limit ( $P_L$ ) which corresponds to a given  $Q_L$ . If LSL is 0 or not specified,  $P_L$  will be 100.
- (7) Compute the quality level, or total percent within specification limits (P<sub>T</sub>), for each constituent:

$$P_T = (P_U + P_L) - 100$$

(8) Using the  $P_T$  from Step 7, determine the Pay Factor (PF) from Table 00165-2 for each constituent tested. A minimum PF of 1.00 will be used when all sublot test values are within the upper and lower specification limits, regardless of the calculated PF.

(9) Compute the Weighted Pay Factor (WPF) for each constituent:

$$WPF = (PF) \times (f_i)$$

Where  $f_i$  = weighting factor listed in the Specifications for each constituent tested.

(10) Compute the Composite Pay Factor (CPF) for the lot and report the results to three decimal places.

$$\mathsf{CPF} \ = \ \frac{\sum \mathsf{WPF}}{\sum \mathsf{f}_{i}}$$

Where  $\Sigma^{WPF}$  = sum of the weighted pay factors for each constituent  $\Sigma^{f_i}$  = sum of the weighting factors listed in the Specifications

Table 00165-1								
QUALITY LEVEL ANALYSIS BY THE STANDARD DEVIATION METHOD								
Pu or PL PERCENT	U	PPER QU	ALITY IN	DEX Qu O	R LOWER	R QUALIT	Y INDEX (	QL
WITHIN LIMITS FOR								n = 10
POSITIVE VALUES								to
OF Q <sub>∪</sub> or Q <sub>L</sub>	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9	n = 11
100	1.16	1.50	1.79	2.03	2.23	2.39	2.53	2.65
99	-	1.47	1.67	1.80	1.89	1.95	2.00	2.04
98	1.15	1.44	1.60	1.70	1.76	1.81	1.84	1.86
97	-	1.41	1.54	1.62	1.67	1.70	1.72	1.74
96	1.14	1.38	1.49	1.55	1.59	1.61	1.63	1.65
95	-	1.35	1.44	1.49	1.52	1.54	1.55	1.56
94	1.13	1.32	1.39	1.43	1.46	1.47	1.48	1.49
93	-	1.29	1.35	1.38	1.40	1.41	1.42	1.43
92	1.12	1.26	1.31	1.33	1.35	1.36	1.36	1.37
91	1.11	1.23	1.27	1.29	1.30	1.30	1.31	1.31
90	1.10	1.20	1.23	1.24	1.25	1.25	1.26	1.26
89	1.09	1.17	1.19	1.20	1.20	1.21	1.21	1.21
88	1.07	1.14	1.15	1.16	1.16	1.16	1.16	1.17
87	1.06	1.11	1.12	1.12	1.12	1.12	1.12	1.12
86	1.04	1.08	1.08	1.08	1.08	1.08	1.08	1.08
85	1.03	1.05	1.05	1.04	1.04	1.04	1.04	1.04
84	1.01	1.02	1.01	1.01	1.00	1.00	1.00	1.00
83	1.00	0.99	0.98	0.97	0.97	0.96	0.96	0.96
82	0.97	0.96	0.95	0.94	0.93	0.93	0.93	0.92
81	0.96	0.93	0.91	0.90	0.90	0.89	0.89	0.89
80	0.93	0.90	0.88	0.87	0.86	0.86	0.86	0.85
79 70	0.91	0.87	0.85	0.84	0.83	0.82	0.82	0.82
78 77	0.89 0.87	0.84 0.81	0.82 0.78	0.80 0.77	0.80 0.76	0.79 0.76	0.79 0.76	0.79 0.75
76	0.84	0.78	0.75	0.74	0.73	0.73	0.70	0.73
76 75	0.82	0.75	0.73	0.74	0.73	0.73	0.72	0.72
74	0.79	0.73	0.72	0.71	0.70	0.76	0.66	0.66
73	0.76	0.69	0.66	0.65	0.64	0.63	0.63	0.62
72	0.74	0.66	0.63	0.62	0.61	0.60	0.60	0.59
71	0.74	0.63	0.60	0.59	0.58	0.57	0.57	0.57
70	0.68	0.60	0.57	0.56	0.55	0.55	0.54	0.54
69	0.65	0.57	0.54	0.53	0.52	0.52	0.51	0.51
68	0.62	0.54	0.51	0.50	0.49	0.49	0.48	0.48
67	0.59	0.51	0.47	0.47	0.46	0.46	0.46	0.45
66	0.56	0.48	0.45	0.44	0.44	0.43	0.43	0.43
65	0.52	0.45	0.43	0.41	0.41	0.40	0.40	0.40
64	0.49	0.42	0.40	0.39	0.38	0.38	0.37	0.37
63	0.46	0.39	0.37	0.36	0.35	0.35	0.35	0.34
62	0.43	0.36	0.34	0.33	0.32	0.32	0.32	0.32
61	0.39	0.33	0.31	0.30	0.30	0.29	0.29	0.29
60	0.36	0.30	0.28	0.27	0.27	0.27	0.26	0.26
59	0.32	0.27	0.25	0.25	0.25	0.24	0.24	0.24
58	0.29	0.24	0.23	0.22	0.21	0.21	0.21	0.21
57	0.25	0.21	0.20	0.19	0.19	0.19	0.18	0.18
56	0.22	0.18	0.17	0.16	0.16	0.16	0.16	0.16
55	0.18	0.15	0.14	0.14	0.13	0.13	0.13	0.13
54	0.14	0.12	0.11	0.11	0.11	0.11	0.10	0.10
53	0.11	0.09	0.08	0.08	0.08	0.08	0.08	0.08
52	0.07	0.06	0.06	0.05	0.05	0.05	0.05	0.05
51	0.04	0.03	0.03	0.03	0.03	0.03	0.03	0.03
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2.00							

NOTE: For negative values of  $Q_U$  or  $Q_L$ ,  $P_U$  or  $P_L$  is equal to 100 minus the table value for  $P_U$  or  $P_L$ . If the value of  $Q_U$  or  $Q_L$  does not correspond exactly to a figure in the table, use the next higher figure.

Table 00165-1

Table 00165-1							
QUALITY LEVEL ANALYSIS BY THE STANDARD DEVIATION METHOD							
Pu or PL PERCENT		PER QUAL	ITY INDEX	Qu OR LO	WER QUAL	ITY INDEX	QL
WITHIN LIMITS FOR	n = 12	n = 15	n = 19	n = 26	n = 38	n = 70	n = 201
POSITIVE VALUES	to						
OF Q <sub>U</sub> OR Q <sub>L</sub>	n = 14	n = 18	n = 25	n = 37	n = 69	n = 200	n = ∞
100	2.83	3.03	3.20	3.38	3.54	3.70	3.83
99	2.09	2.14	2.18	2.22	2.26	2.29	2.31
98	1.91	1.93	1.96	1.99	2.01	2.03	2.05
97	1.77	1.79	1.81	1.83	1.85	1.86	1.87
96	1.67	1.68	1.70	1.71	1.73	1.74	1.75
95	1.58	1.59	1.61	1.62	1.63	1.63	1.64
94	1.50	1.51	1.52	1.53	1.54	1.55	1.55
93	1.44	1.44	1.45	1.46	1.46	1.47	1.47
92	1.37	1.38	1.39	1.39	1.40	1.40	1.40
91	1.32	1.32	1.33	1.33	1.33	1.34	1.34
90	1.26	1.27	1.27	1.27	1.28	1.28	1.28
89	1.21	1.22	1.22	1.22	1.22	1.22	1.23
88	1.17	1.17	1.17	1.17	1.17	1.17	1.17
87	1.12	1.12	1.12	1.12	1.12	1.13	1.13
86	1.08	1.08	1.08	1.08	1.08	1.08	1.08
85	1.04	1.04	1.04	1.04	1.04	1.04	1.04
84	1.00	1.00	1.00	1.00	0.99	0.99	0.99
83	0.96	0.96	0.96	0.96	0.95	0.95	0.95
82	0.92	0.92	0.92	0.92	0.92	0.92	0.92
81	0.88	0.88	0.88	0.88	0.88	0.88	0.88
80	0.85	0.85	0.85	0.84	0.84	0.84	0.84
79	0.81	0.81	0.81	0.81	0.81	0.81	0.81
78 77	0.78 0.75	0.78 0.75	0.78 0.75	0.78 0.74	0.77 0.74	0.77 0.74	0.77 0.74
76	0.73	0.73	0.73	0.74	0.74	0.74	0.74
75	0.68	0.71	0.71	0.71	0.71	0.71	0.71
74	0.65	0.65	0.65	0.65	0.65	0.64	0.64
73	0.62	0.62	0.62	0.62	0.62	0.61	0.61
72	0.59	0.59	0.59	0.59	0.59	0.58	0.58
71	0.56	0.56	0.56	0.56	0.56	0.55	0.55
70	0.53	0.53	0.53	0.53	0.53	0.53	0.52
69	0.50	0.50	0.50	0.50	0.50	0.50	0.50
68	0.48	0.48	0.47	0.47	0.47	0.47	0.47
67	0.45	0.45	0.45	0.44	0.44	0.44	0.44
66	0.42	0.42	0.42	0.42	0.41	0.41	0.41
65	0.39	0.39	0.39	0.39	0.39	0.39	0.39
64	0.37	0.37	0.36	0.36	0.36	0.36	0.36
63	0.34	0.34	0.34	0.34	0.33	0.33	0.33
62	0.31	0.31	0.31	0.31	0.31	0.31	0.31
61	0.29	0.29	0.28	0.28	0.28	0.28	0.28
60	0.26	0.26	0.26	0.26	0.26	0.25	0.25
59	0.23	0.23	0.23	0.23	0.23	0.23	0.23
58	0.21	0.21	0.20	0.20	0.20	0.20	0.20
57	0.18	0.18	0.18	0.18	0.18	0.18	0.18
56	0.15	0.15	0.15	0.15	0.15	0.15	0.15
55	0.13	0.13	0.13	0.13	0.13	0.13	0.13
54	0.10	0.10	0.10	0.10	0.10	0.10	0.10
53	0.08	0.08	0.08	0.08	0.08	80.0	0.08
52	0.05	0.05	0.05	0.05	0.05	0.05	0.05
51	0.03	0.03	0.03	0.03	0.03	0.03	0.02
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00

NOTE: For negative values of  $Q_U$  or  $Q_L$ ,  $P_U$  or  $P_L$  is equal to 100 minus the table value for  $P_U$  or  $P_L$ . If the value of  $Q_U$  or  $Q_L$  does not correspond exactly to a figure in the table, use the next higher figure.

Table 00165-2

				0165-2				
	REQUIRED QUALITY LEVEL FOR A GIVEN SAMPLE SIZE (n) AND A GIVEN PAY FACTOR							
PAY FACTOR	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9	n = 10 to n = 11
1.05	100	100	100	100	100	100	100	100
1.04	90	91	92	93	93	93	94	94
1.03	80	85	87	88	89	90	91	91
1.02	75	80	83	85	86	87	88	88
1.01	71	77	80	82	84	85	85	86
1.00	68	74	78	80	81	82	83	84
0.99	66	72	75	77	79	80	81	82
0.98	64	70	73	75	77	78	79	80
0.97	62	68	71	74	75	77	78	78
0.96	60	66	69	72	73	75	76	77
0.95	59	64	68	70	72	73	74	75
0.94	57	63	66	68	70	72	73	74
0.93	56	61	65	67	69	70	71	72
0.92	55	60	63	65	67	69	70	71
0.91	53	58	62	64	66	67	68	69
0.90	52	57	60	63	64	66	67	68
0.89	51	55	59	61	63	64	66	67
0.88	50	54	57	60	62	63	64	65
0.87	48	53	56	58	60	62	63	64
0.86	47	51	55	57	59	60	62	63
0.85	46	50	53	56	58	59	60	61
0.84	45	49	52	55	56	58	59	60
0.83	44	48	51	53	55	57	58	59
0.82	42	46	50	52	54	55	57	58
0.81	41	45	48	51	53	54	56	57
0.80	40	44	47	50	52	53	54	55
0.79	38	43	46	48	50	52	53	54
0.78	37	41	45	47	49	51	52	53
0.77	36	40	43	46	48	50	51	52
0.76	34	39	42	45	47	48	50	51
0.75	33	38	41	44	46	47	49	50
REJECT	QUALITY LEVELS LESS THAN THOSE SPECIFIED FOR A 0.75							

NOTE: If the computed QUALITY LEVEL does not correspond exactly to a figure in the table, use the next lower value.

Table 00165-2

Table 00165-2							
	REQUIRED QUALITY LEVEL FOR A GIVEN SAMPLE SIZE (n) AND A GIVEN PAY FACTOR						
DAY FACTOR	n = 12	n = 15	n = 19	n = 26	n = 38	n = 70	n = 201
PAY FACTOR	to n = 14	to n = 18	to n = 25	to n = 37	to n = 69	to n = 200	to n = ∞
1.05	100	100	100	100	100	100	100
1.04	95	95	96	96	97	97	99
1.03	92	93	93	94	95	95	97
1.02	89	90	91	92	93	94	95
1.01	87	88	89	90	91	93	94
1.00	85	86	87	89	90	91	93
0.99	83	85	86	87	88	90	92
0.98	81	83	84	85	87	88	90
0.97	80	81	83	84	85	87	89
0.96	78	80	81	83	84	86	88
0.95	77	78	80	81	83	85	87
0.94	75	77	78	80	81	83	86
0.93	74	75	77	78	80	82	84
0.92	72	74	75	77	79	81	83
0.91	71	73	74	76	78	80	82
0.90	70	71	73	75	76	79	81
0.89	68	70	72	73	75	77	80
0.88	67	69	70	72	74	76	79
0.87	66	67	69	71	73	75	78
0.86	64	66	68	70	72	74	77
0.85	63	65	67	69	71	73	76
0.84	62	64	65	67	69	72	75
0.83	61	63	64	66	68	71	74
0.82	60	61	63	65	67	70	72
0.81	58	60	62	64	66	69	71
0.80	57	59	61	63	65	67	70
0.79	56	58	60	62	64	66	69
0.78	55	57	59	61	63	65	68
0.77	52	56	57	60	62	64	67
0.76	51	55	56	58	61	63	66
0.75	51	53	55	57	59	62	65
REJECT	Q	UALITY LEV	ELS LESS T	HAN THOSE	SPECIFIED	FOR A 0.75	5

NOTE: If the computed QUALITY LEVEL does not correspond exactly to a figure in the table, use the next lower value.

- **00165.50 Statistical Acceptance Sampling and Testing** The Contractor shall sample and test Materials for acceptance, as required by the Contract. The Contractor may statistically evaluate test results for purposes of quality control or to predict a Pay Factor or Composite Pay Factor. The following apply:
  - **(a) Statistical Acceptance** The Engineer will perform statistical analysis according to 00165.40 for acceptance and to determine a Pay Factor (PF) or Composite Pay Factor (CPF). The Engineer's determination of the PF or CPF shall be controlling.
  - **(b) Pay Adjustments** As an incentive to produce quality Materials, the Engineer's acceptance will be based upon the following:
    - (1) Specification Materials For Materials accepted by a PF, when all constituents of a Material have a PF of 1.00 or greater, that Material will be considered specification Materials. For Materials accepted by a CPF, all Materials with a CPF of 1.0000 or greater will be considered specification Materials. Materials with a CPF greater than 1.0000, when specified, may earn a CPF adjustment of greater than 1.0000, up to a maximum of 1.0500.
    - (2) Non-specification Materials For Materials accepted by a PF, when any constituent of a Material has a PF of less than 1.00, that Material will be considered non-specification Material. For Materials accepted by a CPF, all Materials with a CPF less than 1.0000 will be considered non-specification Materials. A lot containing non-specification Materials will be evaluated as described in 00165.50(c).

## (c) Non-specification Materials:

- (1) Isolation of a Partial Sublot The Engineer may isolate from a sublot or adjoining sublots any Material that the Contractor's test results show to be non-specification. The Contractor shall perform additional testing or provide samples to the Agency as directed. The Engineer will accept or reject the Material according to 00150.25.
- (2) Isolation of an Entire Sublot The Engineer may isolate a sublot or a series of sublots in which the Contractor's test results show the Material to be non-specification. The Contractor shall perform additional testing or provide samples to the Agency as directed. The isolated Material will be evaluated as a separate lot. The Engineer will accept or reject the Material according to 00150.25.
- (3) A Lot-in-Progress The Contractor shall shut down production when any of the following occurs:
  - The CPF for a lot-in-progress drops below 1.0000, and the Contractor is taking no corrective action;
  - · The CPF is less than 0.7500; or
  - Any constituent test is continually out of specification limits, regardless of whether or not the CPF is below 0.7500.

The Contractor shall not resume production until the Engineer has determined that Specification Materials can be produced, and has given approval to resume.

**(4) An Entire Lot** - The Engineer may reject an entire lot of Materials with a CPF between 0.7500 and 1.0000, or may take action according to 00150.25.

For a lot of Material with a CPF below 0.7500, the Engineer will take one or more of the following actions:

- **a. Remain in Place** Allow Materials to remain in place with an appropriate price reduction that may range from 25% to 100% (no payment);
- **b. Corrective Work** Require corrective work, at the Contractor's expense, with an appropriate price reduction that may range from zero (full payment) to 100% (no payment); or
- **c.** Remove and Replace Require complete removal and replacement with Specification Materials. No payment will be made for the rejected Materials, the cost of removal, or for the costs of sampling and testing.

#### 00165.70 Use of Materials without Acceptable Materials Conformance Documents:

- (a) General The Contractor shall not incorporate Materials into the Project prior to submittal of Materials Conformance Documents acceptable to the Engineer. The Engineer may waive this requirement temporarily if Materials are necessary for immediate traffic safety.
- **(b) Materials Incorporated for Immediate Traffic Safety** If Materials are incorporated into the Project for immediate traffic safety before acceptable Materials Conformance Documents are available, no payment will be made for the value of the Materials, or the costs of incorporating them, until Materials Conformance Documents have been submitted to and approved by the Engineer, or the Materials are otherwise found through testing to comply with Specifications.
- **(c) Contractor's Request for Testing Assistance** If acceptable Materials Conformance Documents are not available, the Contractor may either have the necessary tests performed at a private laboratory or request in writing that the Engineer:
  - Determine if the Agency or its agents can sample and test;
  - Estimate the cost to the Contractor for the testing service; and
  - · Estimate the time required to obtain the test results.

The Engineer will provide this information to the Contractor in writing. If the Contractor requests the Engineer, in writing, to proceed, the Engineer will arrange for the sampling and testing, at the Contractor's expense. If these tests determine the Material complies with the Specifications, the Materials may be incorporated into the Project, or for Materials previously incorporated according to (b) above, payment will be authorized.

**00165.75** Storage and Handling of Materials - The Contractor shall store and handle Materials so as to preserve their quality and fitness for incorporation into the Work. The Contractor shall restore all storage sites to their original condition according to 00140.90, or to comply with any applicable permits, orders, or agreements, at the Contractor's expense.

#### Stored Materials:

- Shall be readily accessible for inspection;
- · May be stored on approved parts of the Right-of-Way; and
- May be stored on private property if written permission of the owner or lessor is obtained.

#### Measurement

**00165.80 Measurement** - No separate measurement will be made of Work performed under this Section.

#### **Payment**

**00165.90 Incidental Basis** - No separate or additional payment will be made for sampling, testing, certification, or other associated Work performed under this Section, whether performed by the Contractor, manufacturer, producer or Supplier. No payment will be made for providing quality control personnel.

**00165.91 Fabrication Inspection Expense** - Fabrication of certain items outside of the State creates additional shop and plant inspection expense to the Agency. It is impractical, and extremely difficult, to determine the actual additional expenses incurred. Therefore, each time that inspection by or on behalf of the Agency is necessary, payment to the Contractor will be reduced by an amount computed at the following rates:

Zone 1	Place of Fabrication All of State of Oregon, and those portions of adjacent states within 50 airline miles of the Oregon border	Reduction in Payment \$0
2	Outside of Zone 1, and up to 300 airline miles from the Oregon border	\$200 per Calendar Day
3	Outside of Zone 2, up to 3,000 airline miles from the Oregon border, and within the continental United States.	Round trip coach airfare from Portland, Oregon plus \$200 per Calendar Day
4	Outside of Zone 3, or outside of the continental United States.	Round trip coach airfare from Portland, Oregon plus \$250 per Calendar Day

Calendar Day charges begin on the first day the Agency's Inspector begins travel to begin work at the fabrication site, and continue without interruption through the final day of travel back to the State. The Contractor will be notified in writing of the beginning and ending dates of the Calendar Days used in computing payment reduction.

This Subsection applies to all fabricated items or manufactured Materials that are inspected by or on behalf of the Agency, which include, but are not limited to:

- · Structural steel fabrication:
- · Prestressed concrete members:
- · Precast concrete;
- Signs:
- Preservative treatment of wood products;
- · Epoxy coating of reinforcing steel; and
- Other items specifically identified in the Specifications as requiring fabrication site or in-plant inspection by the Agency.

## Section 00170 - Legal Relations and Responsibilities

#### Description

**00170.00 General** - The Contractor shall comply with all laws, ordinances, codes, regulations, executive orders, and administrative rules (collectively referred to as "Laws" in this Section) that relate to the Work or to those engaged in the Work. Where the provisions of the Contract are inconsistent or in conflict, the Contractor shall comply with the more stringent standard.

The Contractor shall indemnify, defend, and hold harmless the Agency and its representatives from liability arising from or related to the violation of Laws by those engaged in any phase of the Work. This provision does not apply to Work performed by Agency employees.

In any litigation, the entire text of any order or permit issued by a governmental or regulatory authority, as well as any documents referenced or incorporated therein by reference, shall be admissible for the purpose of Contract interpretation.

The characterization of provisions of the Contract as material provisions or the failure to comply with certain provisions as a material breach of the Contract shall in no way be construed to mean that any other provisions of the Contract are not material or that failure to comply with any other provisions is not a material breach of the Contract.

All rights and remedies available to the Agency under applicable Laws are incorporated herein by reference and are cumulative with all rights and remedies under the Contract.

The Contract shall not be construed against either party regardless of which party drafted it. Other than as modified by the Contract, the applicable rules of contract construction and evidence shall apply. This Contract shall be governed by and construed and enforced according to the laws of the State of Oregon without regard to principles of conflict of laws.

Any dispute between the Agency and the Contractor that arises from or relates to this Contract and that is not resolved under the provisions of Section 00199 shall be brought and conducted solely and exclusively within the Clackamas County Circuit Court for the State of Oregon; provided, however, if a dispute must be brought in a federal forum, then it shall be brought and conducted solely and exclusively within the United States District Court for the District of Oregon. In no event shall this Subsection be construed as a waiver by the State of Oregon on any form of defense or immunity, whether sovereign immunity, governmental immunity, immunity based on the Eleventh Amendment to the Constitution of the United States, or otherwise, from any claim or from the jurisdiction of any court. CONTRACTOR BY EXECUTION OF THE CONTRACT HEREBY CONSENTS TO THE IN PERSONAM JURISDICTION OF THE COURTS REFERENCED IN THIS SECTION.

It is the Agency's intention to make all payments due under the Contract if funds are legally available for such purpose. The Agency reasonably believes that at the time of entering into the Contract sufficient funds are available and authorized for expenditure to finance the cost of the Contract within the Agency's appropriation or limitation, or other funding sources. Agency's payment of amounts under the Contract is contingent on the Agency receiving adequate appropriations, limitations or other expenditure authority or funds to allow the Agency to continue to make payments under the Contract. In the event the Agency becomes aware that sufficient funds are not available and authorized, the Agency will provide prompt written notice to the Contractor, and the Agency may terminate the Contract as provided in 00180.90(c).

## **Provisions and Requirements**

**00170.01 Other Agencies Affecting Agency Contracts** - Representatives of regulatory bodies or units of government whose Laws may apply to the Work shall have access to the Work according to 00150.20(d). These may include but are not limited to those in the following (a), (b), (c), and (d).

# (a) Federal Agencies:

Agriculture, Department of

Forest Service

Natural Resource Conservation Service

Army, Department of the

Corps of Engineers

Commerce, Department of

National Marine Fisheries Service

Defense, Department of

Energy, Department of

**Environmental Protection Agency** 

Federal Energy Regulatory Commission

Geology Survey

Health and Human Services, Department of

Homeland Security, Department of

U.S. Coast Guard

Housing and Urban Development, Department of

Interior, Department of

Heritage, Conservation, and Recreation Service

Bureau of Indian Affairs

Bureau of Land Management

**Bureau of Mines** 

Bureau of Reclamation

Geological Survey

Minerals Management Service

Office of Surface Mining, Reclamation, and Enforcement

Minerals Management Service

National Oceanic and Atmospheric Administration

Solar Energy and Energy Conservation Bank

U.S. Fish and Wildlife Service

Labor, Department of

Mine Safety and Health Administration

Occupational Safety and Health Administration

Transportation, Department of

Federal Highway Administration

Water Resources Council

## (b) State of Oregon Agencies:

Administrative Services, Department of

Agriculture, Department of

Natural Resources Division

Soil and Water Conservation District

Columbia River Gorge Commission

Consumer and Business Services, Department of

Insurance Division

Oregon Occupational Safety and Health Division

Energy, Office of

Environmental Quality, Department of

Fish and Wildlife, Department of

Forestry, Department of

Geology and Mineral Industries, Department of

Human Resources, Department of

Labor and Industries, Bureau of

Land Conservation and Development Department

Parks and Recreation, Department of

State Lands, Department of

Water Resources Department

# (c) Local Agencies:

City Councils

**County Courts** 

County Commissioners, Boards of

**Design Commissions** 

Historical Preservation Commissions

Lane Regional Air Pollution Authority

**Planning Commissions** 

Port Districts

**Special Districts** 

## (d) Oregon Federally Recognized Tribal Governments:

**Burns Paiute Tribe** 

Confederated Tribes of Coos, Lower Umpqua and Siuslaw Indians

Confederated Tribes of Grand Ronde

Confederated Tribes of Siletz

Confederated Tribes of Umatilla Indian Reservation

Confederated Tribes of Warm Springs

Coquille Tribe

Cow Creek Band of Umpqua Indians

Klamath Tribe

**00170.02 Permits, Licenses, and Taxes** - As required to accomplish the Work, the Contractor shall do the following:

- Obtain all necessary permits and licenses, except for those noted in 00170.03;
- Pay all applicable charges, fees and taxes, except for those noted in 00170.03;
- · Give all notices required by applicable Laws, or under the terms of the Contract;
- Comply with ORS 274.530 relating to lease of stream beds by Oregon Division of State Lands;
- · License, in the State of Oregon, all vehicles subject to licensing;
- Comply with ORS 477.625 and ORS 527.670 relating to clearing and fire hazards on forest lands; and
- Comply with all orders and permits issued by a governmental authority, whether local, State, or federal.

This project is to be constructed in Clackamas County rights of way. There are no separate permits required from Clackamas County to perform the work required under this contract.

**00170.03 Furnishing Right-of-Way and Permits** - Unless required to be obtained in the name of the Contractor, the Agency will obtain and pay for the following when they are required by the applicable Laws or by Plans or Specifications:

- · All necessary Rights-of-Way;
- Permits required for crossing or encroaching upon navigable streams;
- Permits required for removing materials from or depositing materials in waterways;
- Permits required for operating in Agency-controlled source of Materials or disposal area;
- · System development fees charged by local units of government;
- Building construction permits, not including specialty work such as heating, ventilation, air conditioning, or electrical;
- · Cost of referencing and replacing endangered survey monuments; and
- Environmental permits, including erosion control permits.

**00170.04 Patents, Copyrights, and Trademarks** - Prior to use of designs, devices, materials, or processes protected by patent, copyright, or trademark, the Contractor shall obtain from the Entity entitled to enforce the patent, copyright, or trademark all necessary evidence of Contractor's legal right to use such design, device, material, or process.

The Contractor shall indemnify, defend and hold harmless the Agency and all third parties and political subdivisions having a possessory or ownership interest or regulatory authority over the Project or Project Site from claims of patent, copyright or trademark infringement, and from costs, expenses and damages the Contractor or Agency may be obligated to pay as a result of such infringement during or after completing the Work.

**00170.05** Assignment of Antitrust Rights - The Contractor irrevocably assigns to the Agency any claim for relief or cause of action the Contractor acquires during the term of the Contract, or which may accrue thereafter, by reason of any violation of:

- Title 15 (Commerce and Trade), United States Code;
- ORS 646.725; or

#### ORS 646.730.

In connection with this assignment, it is an express obligation of the Contractor to take no action that would in any way impair or diminish the value of the rights assigned to the Agency according to the provisions of this Subsection. Further, it is the express obligation of the Contractor to take all action necessary to preserve the rights assigned. It is an express obligation of the Contractor to advise the Agency's legal counsel:

- In advance, of its intention to commence any action involving such claims for relief or causes of action:
- Immediately upon becoming aware of the fact that an action involving such claims for relief or causes of action has been commenced by some other person or persons;
- Of the date on which it notified the obligor(s) of any such claims for relief or causes of action of the fact of the Contractor's assignment to the Agency according to the provisions of this Subsection: and
- Immediately upon the discovery of any such antitrust claim for relief or cause of action.

In the event any payment is made to the Contractor under any such claims for relief, the Contractor shall promptly pay the full sum over to the Agency. In the event the Contractor fails to make such payment, the Agency may deduct the amount from monies due or to become due the Contractor under the Contract.

**00170.06 Federal-Aid Participation** - This Project is to be conducted according to the regulations applying to Federal-Aid Highway Projects.

**00170.07 Record Requirements** - For purposes of this Subsection, the term "Contractor" includes the Contractor, all Subcontractors, Material Suppliers, and providers of rented operated Equipment (except non-DBE truck drivers), at all tiers, for all subcontracts with first-tier Subcontractors, all subcontracts between the first-tier Subcontractors and their Subcontractors and any other lower-tier subcontracts, and "Related Entities" as that term is defined in OAR 734-010-0400. The Material Suppliers included in this definition are those for Aggregates, asphalt cement concrete, Portland Cement Concrete and the supply and fabrication of structural steel items, and Material Suppliers that provide quotes.

- (a) Records Required The Contractor shall maintain all records, whether created before or after execution of the Contract, or during Contract performance, or after Contract completion, to clearly document:
  - The Contractor's performance of the Contract or a subcontract;
  - · The Contractor's ability to continue performance of the Contract or a subcontract; and
  - All claims arising from or relating to performance under the Contract or a subcontract.

These records shall include all records, including fiscal records, regardless of when created for the Contractor's business. The records for the Contractor's business include, without limitation:

- Bidding estimates and records, worksheets, tabulations or similar documents.
- Job cost detail reports, including monthly totals.
- Payroll records (including, without limitation, the ledger or register, and tax forms) and all
  documents that establish the periods, individuals involved, the hours for the individuals, and
  the rates for the individuals.

- Records that identify the Equipment used by the Contractor and Subcontractors in the
  performance of the Contract or subcontracts, including, without limitation, Equipment lists,
  rental contracts and any records used in setting rental rates.
- Invoices from vendors, rental agencies, and Subcontractors.
- · Material quotes, invoices, purchase orders and requisitions.
- Contracts with Subcontractors and contracts with Material Suppliers, Suppliers and providers
  of rented equipment.
- Contracts or documents of other arrangements with any Related Entity as defined in OAR 734-010-0400.
- · General ledger.
- · Trial Balance.
- Financial statements (including, without limitation, the balance sheet, income statement, statement of cash flows, and financial statement notes).
- · Income tax returns.
- All worksheets used to prepare bids or claims, or to establish the cost components for the Pay Items, including, without limitation, the labor, benefits and insurance, Materials, Equipment, and Subcontractors.

The following are examples, but not an exhaustive list, of records that would be included, if generated by the Contractor. If the Contractor generates such records, or equivalent records, they are included among the records subject to 00170.07.

- · Daily time sheets and supervisors' daily reports.
- · Collective bargaining agreements.
- Earnings records.
- · Journal entries and supporting schedules.
- · Insurance, welfare, and benefits records.
- · Material cost distribution worksheet.
- Subcontractors' and lower-tier Subcontractors' payment certificates.
- · Payroll and vendor's cancelled checks.
- · Cash disbursements journal.
- All documents related to each and every claim together with all documents that support the amount of damages as to each claim.
- Additional financial statements (including, without limitation, the balance sheet, income statement, statement of cash flows, and financial notes) preceding the execution of the Contract and following final payment of the Contract.
- Depreciation records on all business Equipment maintained by the business involved, its accountant, or other Entity. (If a source other than depreciation records is used to develop cost for the Contractor's internal purposes in establishing the actual cost of owning and operating Equipment, all such other source documents.)

The Contractor shall maintain all fiscal records in material compliance with generally accepted accounting principles, or other accounting principles that are accepted accounting principles and practices for the subject industry and adequate for the nature of the Contractor's business, and in such a manner that providing a complete copy is neither unreasonably time-consuming nor

unreasonably burdensome for the Contractor or the Agency. Failure to maintain the records in this manner shall not be an excuse for not providing the records.

The Contractor shall include in its subcontracts, purchase orders, and all other written agreements, a provision requiring all Subcontractors, Material Suppliers and providers of rented operated Equipment (except non-DBE truck drivers), at all tiers, to comply with 00170.07. The Contractor shall also require all Subcontractors, Material Suppliers, and providers of rented operated Equipment (except non-DBE truck drivers), at all tiers, and Related Entities to include in their contracts, purchase orders, and all other written agreements, a provision requiring all lower-tier Subcontractors, Material Suppliers and providers of rented operated Equipment (except non-DBE truck drivers) to comply with 00170.07. The Material Suppliers to which this applies are those for Aggregates, asphalt cement concrete, Portland Cement Concrete and the supply and fabrication of structural steel items and Material Suppliers that provide Material quotes and Related Entities as defined in OAR 734-010-0400.

- (b) Access to Records The Contractor shall provide the Engineer access to or a copy of all Contractor records upon request. A Project Manager's authority to request or access records is subject to OAR 734-010-0400(9). During the record retention period the Engineer, employees of the Agency, representatives of the Agency, or representatives of regulatory bodies or units of government may:
  - Inspect, examine and copy or be provided a copy of all Contractor records;
    - Audit the records, a Contract or the performance of a Contract;
  - Inspect, examine and audit the records when, in the Agency's sole discretion, the records
    may be helpful in the resolution of any claim, litigation, administrative proceeding or
    controversy arising out of or related to a Contract.

Reasons for access to audit, inspect, examine and copy records include without limitation, general auditing, reviewing claims, checking for collusive bidding, reviewing or checking payment of required wages, performance and contract compliance, workplace safety compliance, evaluating Related Entities, environmental compliance, and qualifications for performance of the Contract, including the ability to perform and the integrity of the Contractor.

Where such records are stored in a computer or in other digital media, the Engineer may request, and the Contractor shall provide, a copy of the data files and such other information or access to software to allow the Engineer review of the records.

Nothing in 00170.07 is intended to operate as a waiver of the confidentiality of any communications privileged under the Oregon Evidence Code. Nothing in 00170.07 limits the records or documents that can be obtained by legal process.

- **(c) Record Retention Period** The Contractor shall maintain the records and keep the records accessible and available at reasonable times and places for at least 3 years from the date of final payment under the Contract, or until the conclusion of all audits, litigation, administrative proceedings, disputes and claims arising out of or related to the Contract, whichever date is later.
- (d) Public Records Requests If records provided under this section contain any information that may be considered exempt from disclosure as a trade secret under either ORS 192.345(2) or ORS 646.461(4), or under other grounds specified in Oregon Public Records Law, ORS 192.311 through ORS 192.478, the Contractor shall clearly designate on or with the records the portions which the Contractor claims are exempt from disclosure, along with a justification and citation to the authority relied upon. Entire records or documents should not be designated as a trade secret

or otherwise exempt from disclosure. Only specific information within a record or document should be so designated.

To the extent allowed by the Oregon Public Records Law or other applicable law related to the disclosure of public records, the Agency will not disclose records or portions of records the Contractor has designated as trade secrets to a third party, who is not a representative of the Agency, to the extent the records are exempt from disclosure as trade secrets under the Oregon Public Records Law or other applicable law, except to the extent the Agency is ordered to disclose in accordance with the Oregon Public Records Law or by a court of competent jurisdiction. Application of the Oregon Public Records Law or other applicable law shall determine whether any record, document or information is actually exempt from disclosure.

In addition, in response to a public records request, the Agency will not produce or disclose records so identified as exempt by the Contractor to any person other than representatives of the Agency, and others with authorized access under 00170.07(b), without providing the Contractor a copy of the public records request, unless:

- The Contractor consents to such disclosure; or
- The Agency is prohibited by applicable law or court order from providing a copy of the public records request to the Contractor.

**00170.10 Required Payments by Contractors** - The Contractor shall comply with ORS 279C.505 and ORS 279C.515 during the term of the Contract.

- (a) Prompt Payment by Contractor for Labor and Materials As required by ORS 279C.505, the Contractor shall:
  - Make payment promptly, as due, to all Entities supplying labor or Materials under the Contract:
  - Pay all contributions or amounts due the Industrial Accident Fund, whether from the Contractor or a Subcontractor, incurred in the performance of the Contract;
  - Not permit any lien or claim to be filed against the State or any political subdivision thereof, on account of any labor or Material furnished in performance of the Contract; and
  - Pay to the Department of Revenue all sums withheld from employees according to ORS 316.167.
- **(b) Prompt Payment by Contractor to First-Tier Subcontractor(s)** According to ORS 279C.580(3)(a), after the Contractor has determined and certified to the Agency that one or more of its Subcontractors has satisfactorily performed subcontracted Work, the Contractor may request payment from the Agency for the Work, and shall pay the Subcontractor(s) within 10 Calendar Days out of such amounts as the Agency has paid to the Contractor for the subcontracted Work.
- (c) Interest on Unpaid Amount If the Contractor or a first-tier Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract within 30 Days after the Contractor's receipt of payment, the Contractor or first-tier Subcontractor shall owe the Entity the amount due plus interest charges that begin at the end of the 10 day period within which payment is due under ORS 279C.580(3) and that end upon final payment, unless payment is subject to a good-faith dispute as defined in ORS 279C.580(5)(b). As required by ORS 279C.515(2), the rate of interest on the amount due shall be 9 percent per annum. The amount of interest shall not be waived.

(d) Agency's Payment of the Contractor's Prompt Payment Obligations - If the Contractor fails, neglects or refuses to make prompt payment of any invoice or other demand for payment for labor or services furnished to the Contractor or a Subcontractor by any Entity in connection with the Contract as such payment becomes due, the Agency may pay the Entity furnishing the labor or services and charge the amount of the payment against monies due or to become due the Contractor under the Contract. (The Agency has no obligation to pay these Entities, and the Agency will not normally do so, but will refer them to the Contractor and the Contractor's Surety.)

The payment of a claim by the Agency in the manner authorized in this Subsection shall not relieve the Contractor or the Contractor's Surety from obligations with respect to any such claims.

- **(e)** Right to Complain to the Construction Contractors Board If the Contractor or a Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract, the Entity may file a complaint with the Construction Contractors Board, unless payment is subject to a good-faith dispute as defined in ORS 279C.580(5)(b).
- **(f) Notice of Claim Against Bond** An Entity (which by definition includes a natural person) claiming not to have been paid in full for labor or Materials supplied for the prosecution of the Work may have a right of action on the Contractor's Payment Bond as provided in ORS 279C.600 and ORS 279C.605.

The Commissioner of the Bureau of Labor and Industries (BOLI) may have a right of action on the Contractor's and Subcontractors' public works bonds and Payment Bonds for workers who have not been paid in full, as provided in ORS 279C.600 and ORS 279C.605.

- **(g) Paid Summary Report** The Contractor shall submit a "Paid Summary Report", form 734-2882, to the Engineer certifying payments made to all of the following:
  - · All Subcontractors
    - Committed DBE suppliers
    - Non-committed DBE suppliers and service providers with estimated total payments for the Project over \$10,000.

For this purpose, a committed DBE firm is one that was identified by the Contractor to meet an assigned DBE goal including DBE firms substituting for DBE firms committed as a condition of Contract Award.

Submit the completed and signed Paid Summary Report to the Engineer within 20 Calendar Days of receipt of payment from the Agency for each month in which payments were made to each Subcontractor, each committed DBE Supplier, and each non-committed DBE Supplier or service provider with estimated total payments for the Project over \$10,000. At the completion of the Project, submit form 734-2882 recapping the total amounts paid to each Subcontractor, each committed DBE Supplier, and each non committed DBE Supplier or service provider with estimated total payments for the Project over \$10,000.

The Contractor shall require each Subcontractor at every tier to comply with the requirement to submit form 734-2882 within 20 Calendar Days of receipt of payment from its controlling contractor and provide a recap of the total amounts paid at the completion of the Project or completion of their Work.

Forms shall be submitted to an email address provided to the Contractor at the preconstruction conference.

**00170.20 Public Works Bond** - Before starting Work, the Contractor and Subcontractors shall each file with the Construction Contractors Board, and maintain in full force and effect, a separate public works bond, in the amount of \$30,000 unless otherwise exempt, as required by ORS 279C.830(2) and ORS 279C.836. The Contractor shall verify Subcontractors have filed a public works bond before the Subcontractor begins Work.

**00170.32 Protection of Navigable Waters** - The Contractor shall comply with all applicable Laws, including, without limitation, the Federal River and Harbor Act of March 3, 1899 and its amendments.

The Contractor shall not interfere with waterway navigation or impair navigable depths or clearances, except as U.S. Coast Guard or Corps of Engineer permits allow.

**00170.60 Safety, Health, and Sanitation Provisions** - The Contractor shall comply with all Laws concerning safety, health, and sanitation standards. The Contractor shall not require workers to perform Work under conditions that are hazardous, dangerous, or unsanitary.

Workers exposed to traffic shall wear upper body garments or safety vests that are highly visible and meet the requirements of 00221.20.

Workers exposed to falling or flying objects or electrical shock shall wear hard hats.

Upon their presentation of proper credentials, the Contractor shall allow inspectors of the U.S. Occupational Safety and Health Administration (OSHA) and the Oregon Occupational Safety and Health Division (OR-OSHA) to inspect the Work and Project Site without delay and without an inspection warrant.

According to ORS 468A.715 and ORS 468A.720, the Contractor or a Subcontractor who performs Project Work involving asbestos abatement shall possess a valid DEQ asbestos abatement license.

#### 00170.61 Industrial Accident Protection:

- (a) Workers' Compensation The Contractor shall provide workers' compensation coverage for on-the-job injuries as required by 00170.70(d).
- **(b)** Longshoremen's and Harbor Workers' Compensation If Work to be performed is over or adjacent to navigable waters, the Longshoremen's and Harbor Workers' Compensation Act, (Chapter 18, Title 33 of the USC) may apply, and the Contractor shall be responsible for complying with its provisions (which may include the provision of additional workers' compensation benefits to employees).

**00170.62 Labor Nondiscrimination** - The Contractor shall comply with all Laws concerning equal employment opportunity, including, without limitation, those prohibiting discrimination because of race, religion, color, sex, disability, or national origin.

It is a material term of this Contract that the Contractor certifies by entering into this Contract that the Contractor has a written policy and practice that meets the requirements described in ORS 279A.112 (House Bill 3060, 2017) for preventing sexual harassment, sexual assault and discrimination against employees who are members of a protected class and that the Contractor shall maintain the policy and practice in force during the entire term of this Contract.

**00170.63** Payment for Medical Care - According to ORS 279C.530, the Contractor shall promptly, as due, make payment to any person, copartnership, association or corporation furnishing medical, surgical and hospital care services or other needed care and attention, incident to sickness or injury, to the employees of the Contractor, of all sums that the Contractor agrees to pay for the services and

all moneys and sums that the Contractor has collected or deducted from the wages of employees under any law, contract or agreement for the purpose of providing or paying for the services.

# 00170.65 Minimum Wage and Overtime Rates for Public Works Projects:

(a) General - The Contractor is responsible for investigating local labor conditions. The Agency does not imply that labor can be obtained at the minimum hourly wage rates specified in State or federal wage rate publications, and no increase in the Contract Amount will be made if wage rates paid are more than those listed.

As required by ORS 279C.520, the Contractor shall comply with ORS 652.220 and shall not unlawfully discriminate against any of the Contractor's employees in the payment of wages or other compensation for work of comparable character on the basis of an employee's membership in a protected class. "Protected class" means a group of persons distinguished by race, color, religion, sex, sexual orientation, national origin, marital status, veteran status, disability, or age. Contractor's compliance with this provision constitutes a material element of the Contract and failure to comply constitutes a material breach that entitles the Agency to exercise any remedies available under the Contract, including, but not limited to, termination for default.

As required by ORS 279C.520, the Contractor shall not prohibit any of the Contractor's employees from discussing the employee's rate of wage, salary, benefits or other compensation with another employee or another person and shall not retaliate against an employee who discusses the employee's rate of wage, salary, benefits or other compensation with another employee or another person.

- **(b) State Prevailing Wage Requirements** The Contractor shall comply with the prevailing wage provisions of ORS 279C.800 through ORS 279C.870.
  - (1) Minimum Wage Rates The Bureau of Labor and Industries (BOLI) determines and publishes the existing State prevailing wage rates in the publication *Prevailing Wage Rates for Public Works Contracts in Oregon.* The Contractor shall pay workers not less than the specified minimum hourly wage rate according to ORS 279C.838 and ORS 279C.840, and shall include this requirement in all subcontracts.

See the Project Wage Rates page included with the Special Provisions for additional information about which wage rates apply to the Project and how to access the applicable wage rates.

The applicable BOLI wage rates will be included in the Contract.

(2) Payroll and Certified Statements - As required in ORS 279C.845, the Contractor and every Subcontractor shall submit written certified statements to the Engineer on the form prescribed by the Commissioner of BOLI in OAR 839-025-0010 certifying compliance with wage payment requirements and accurately setting out the Contractor's or Subcontractor's weekly payroll records for each worker employed on the Project.

The Contractor and Subcontractors shall preserve the certified statements for a period of 6 years from the date of completion of the Contract.

## (3) Additional Retainage:

**a.** Agency - As required in ORS 279C.845(7) the Agency will retain 25% of any amount earned by the Contractor on the Project until the Contractor has filed the certified statements required in ORS 279C.845 and in FHWA Form 1273, if applicable. The Agency will pay to the Contractor the amount retained within 14 Days after the Contractor files the required

certified statements, regardless of whether a Subcontractor has failed to file certified statements.

- **b.** Contractor As required in ORS 279C.845(8) the Contractor shall retain 25% of any amount earned by a first-tier Subcontractor on the Project until the first-tier Subcontractor has filed with the Agency the certified statements required in ORS 279C.845 and in FHWA Form 1273, if applicable. Before paying any amount retained, the Contractor shall verify that the first-tier Subcontractor has filed the certified statement. Within 14 Days after the first-tier Subcontractor files the required certified statement, the Contractor shall pay the first-tier Subcontractor any amount retained.
- (4) Owner/Operator Data For a project funded by the FHWA, the Contractor shall furnish data to the Engineer for each owner/operator providing trucking services. Furnish the data before the time the services are performed and include without limitation for each owner/operator:
  - Driver's name:
  - · Present driver license upon request;
  - · Vehicle identification number;
  - · Present vehicle registration upon request;
  - · Motor vehicle license plate number;
  - · Motor Carrier account number:
  - Present ODOT Motor Carrier 1A Permit upon request; and
  - Name of owner/operator from the side of the truck.
- **(c) State Overtime Requirements** As a condition of the Contract, the Contractor shall comply with the pertinent provisions of ORS 279C.520 and ORS 279C.540.
  - (1) Maximum Hours of Labor and Overtime Pay According to ORS 279C.540, no person shall be employed to perform Work under this Contract for more than 10 hours in any 1 Day, or 40 hours in any 1 week, except in cases of necessity, emergency, or where public policy absolutely requires it. In such instances, the Contractor shall pay the employee at least time and a half pay:
    - For all overtime in excess of 8 hours a day or 40 hours in any 1 week when the work week is 5 consecutive days, Monday through Friday; or
    - For all overtime in excess of 10 hours a day or 40 hours in any 1 week when the work week is 4 consecutive days, Monday through Friday; and
    - For all Work performed on Saturday and on any legal holiday specified in ORS 279C.540.

For additional information on requirements for overtime and establishing a work schedule see OAR 839-025-0050 and OAR 839-025-0034.

- **(2) Notice of Hours of Labor** The Contractor shall give written notice to employees of the number of hours per day and days per week the employees may be required to work. Provide the notice either at the time of hire or before commencement of work on this Contract, or by posting a notice in a location frequented by employees.
- (3) Exception The maximum hours of labor and overtime requirements under ORS 279C.540 will not apply to the Contractor's Work under this Contract if the Contractor is a party to a collective bargaining agreement in effect with any labor organization. For a collective bargaining

agreement to be in effect it shall be enforceable within the geographic area of the Project, and its terms shall extend to workers who are working on the Project (see OAR 839-025-0054).

- (d) State Time Limitation on Claim for Overtime According to ORS 279C.545, any worker employed by the Contractor is foreclosed from the right to collect any overtime provided in ORS 279C.540 unless a claim for payment is filed with the Contractor within 90 Days from the completion of the Contract, provided the Contractor posted and maintained a circular as specified in this provision. Accordingly, the Contractor shall:
  - Cause a circular, clearly printed in boldfaced 12-point type and containing a copy of ORS 279C.545, to be posted in a prominent place alongside the door of the timekeeper's office or in a similar place that is readily available and freely visible to any or all workers employed to perform Work; and
  - Maintain such circular continuously posted from the inception to the completion of the Contract on which workers are or have been employed.
- **(e) Additional Requirements When Federal Funds are Involved** When federal funds are involved, the following requirements shall apply in addition to the requirements of 00170.65(a) through 00170.65(d). The Contractor shall include these provisions in all subcontracts as well as ensure that all Subcontractors include these provisions in their lower-tier subcontracts.
  - (1) FHWA Requirements For Federal-aid projects, the Contractor shall comply with the provisions of FHWA Form 1273, Required Contract Provisions Federal-aid Construction Contracts.
  - (2) Minimum Wage Rates The Contractor shall pay each worker in each trade or occupation employed to perform any work under the Contract not less than the existing State (BOLI) prevailing wage rate or the applicable federal prevailing wage rate required under the Davis-Bacon Act (40 U.S.C. 3141 et seq.), whichever is higher. The Contractor shall include this provision in all subcontracts.

See the Project Wage Rates page included with the Special Provisions for additional information about which wage rates apply to the Project and how to access the applicable wage rates.

The applicable Davis-Bacon and BOLI wage rates will be included in the Contract.

- (3) Payroll and Certified Statements In addition to providing the payroll information and certified statements required under ORS 279C.845 (see 00170.65(b)(2)), the Contractor and every Subcontractor shall submit written certified statements that also meet the requirements in Section IV of FHWA Form 1273, except the Contractor and every Subcontractor shall preserve the certified statements for a period of 6 years from the date of completion of the Contract.
- **(4) Overtime** With regard to overtime pay, the Contractor shall comply with the overtime provision affording the greatest compensation required under FHWA Form 1273 and ORS 279C.540.

**00170.67 Fees** - The fee required by ORS 279C.825(1) will be paid by the Agency to the Commissioner of the Oregon Bureau of Labor and Industries under the administrative rules of the Commissioner.

#### 00170.70 Insurance:

(a) Insurance Coverages -

**Contractor** - The Contractor shall obtain the insurance specified below prior to the execution of the Contract. The Contractor shall maintain the insurance in full force at the Contractor's expense throughout the duration of the Contract and all warranty periods that apply.

**Subcontracting** - If the Contractor specifies prior to the execution of the Contract that a Subcontractor will satisfy an insurance requirement that is permitted to be satisfied by a Subcontractor, the Contractor shall obtain Agency approval of Subcontractor and Subcontractor's insurance coverage(s), as required by 00180.21, prior to commencement of Subcontracted work. After the Contractor receives Agency approval of the Subcontractor, the Contractor may contractually obligate the Subcontractor to obtain and maintain, at the Subcontractor's expense or at the Contractor's expense, the insurance permitted.

The Contractor shall require that all Subcontractors carry insurance coverage that the Contractor deems appropriate based on the risks of the subcontracted work. The Contractor shall obtain proof of the required insurance coverages, as applicable, from any Subcontractor providing Services related to the Contract.

Neither the insurance provided by Subcontractor(s) nor any agreements Contractor or Subcontractor(s) may enter into shall place any limitation on the liability or indemnification obligations of the Contractor under applicable law or the Contract.

**Insurance Provisions** - The Contractor and Subcontractor(s), if any, shall obtain insurance from insurance companies or entities that are authorized to transact the business of insurance and issue coverage in the State and that are acceptable to the Agency. Insurance coverage shall be primary and noncontributory with any other insurance and self-insurance, with the exception of Workers' Compensation. The Contractor, or appropriate Subcontractor, but not the Agency, shall pay for all deductibles, self-insurance retentions and self-insurance, if any.

• Commercial General Liability – The Contractor shall provide Commercial General Liability Insurance written on an occurrence basis and covering the Contractor's liability for bodily injury and property damage. This insurance shall include personal and advertising injury liability, products and completed operations coverage, and contractual liability coverage. Coverage may be written in combination with Commercial Automobile Liability Insurance with separate limits for Commercial General Liability and Commercial Automobile Liability. Combined single limit per occurrence shall not be less than the dollar amount specified in the Special Provisions. The annual aggregate limit shall not be less than the dollar amount specified in the Special Provisions. The policy shall be endorsed to state that the annual aggregate limit of liability shall apply separately to the Contract.

When Work to be performed includes operations or activity within 50 feet of any railroad property, bridge, trestle, track, roadbed, tunnel, underpass or crossing, the Contractor shall provide the Contractual Liability – Railroads CG 24 17 endorsement, or equivalent, on the Commercial General Liability policy.

• Commercial Automobile Liability – The Contractor shall provide Commercial Automobile Liability Insurance covering all owned, non-owned, and hired vehicles for bodily injury and property damage. This coverage may be written in combination with the Commercial General Liability Insurance with separate limits for Commercial Automobile Liability and Commercial General Liability. Combined single limit per occurrence shall not be less than the dollar amount specified in the Special Provisions. If this coverage is written in combination with the Commercial General Liability, the policy shall be endorsed to state that the Commercial General Liability annual aggregate limit shall apply separately to the Contract.

- Pollution Liability If indicated by Special Provision, the Contractor or Subcontractor, whichever is performing the pollution related Work, shall provide Pollution Liability Insurance written on an occurrence or claims made basis and covering the Contractor's or Subcontractor's liability, for bodily injury, property damage, and environmental damage resulting from sudden, accidental, and gradual pollution, and related clean-up costs. If the coverage is obtained by the Contractor, the coverage may be written in combination with the Commercial General Liability Insurance with separate limits for Pollution Liability and Commercial General Liability. Combined single limit per occurrence shall not be less than the dollar amount specified in the Special Provisions. The annual aggregate limit shall not be less than the dollar amount specified in the Special Provisions. The policy shall be endorsed to state that the annual aggregate limit of liability shall apply separately to the Contract.
- Asbestos Liability If indicated by Special Provision, the Contractor, or Subcontractor, whichever is performing asbestos related Work, shall provide the Pollution Liability coverage with an Asbestos Liability endorsement. If an endorsement cannot be obtained, the Contractor or Subcontractor shall provide separate Asbestos Liability Insurance at the same combined single limit per occurrence and annual aggregate limit as the Pollution Liability Insurance with the policy endorsed to state that the annual aggregate limit of liability shall apply separately to the Contract.
- Lead Liability If indicated by Special Provision, the Contractor or Subcontractor, whichever
  is performing lead related Work, shall provide the Pollution Liability coverage with a Lead
  Liability endorsement. If an endorsement cannot be obtained, the Contractor or
  Subcontractor shall provide separate Lead Liability Insurance at the same combined single
  limit per occurrence and annual aggregate limit as the Pollution Liability Insurance with the
  separate policy endorsed to state that the annual aggregate limit of liability shall apply
  separately to the Contract.
- Commercial Automobile Liability with Pollution Coverage If indicated by Special Provision, the Contractor or Subcontractor, whichever is performing the pollution related Work, shall provide Commercial Automobile Liability Insurance with Pollution coverage covering the Contractor's or Subcontractor's liability for bodily injury, property damage, natural resource damage, and environmental damage arising out of the use of all owned, non-owned, or hired vehicles while performing Work under the Contract. Combined single limit per occurrence shall not be less than the dollar amount specified in the Contract. If the coverage is obtained by the Contractor, the coverage may be written in combination with the Commercial General Liability Insurance with separate limits for Commercial Automobile Liability with Pollution Coverage and Commercial General Liability. If this coverage is written in combination with the Commercial General Liability, the policy shall be endorsed to state that the Commercial General Liability annual aggregate limit shall apply separately to the Contract.
- Marine Insurance (watercraft) If indicated by Special Provision, the Contractor or Subcontractor, whichever is performing watercraft related Work, entails the use of watercraft, including but not limited to barges, tug boats, work boats, and supply boats, shall provide the following insurance:
  - Marine Liability Insurance For the performance of the Work that requires the use of any watercraft, whether owned, non-owned, leased, rented, or chartered by Contractor or any Subcontractors, Marine Liability insurance shall not be less than the dollar amount specified in the Special Provisions per occurrence for bodily injury and property damage. Such insurance shall also include coverage for collision liability, tower's liability, marine contractual liability, wreck/debris removal, and liability for seepage, pollution, containment and cleanup.

- Hull and Machinery Insurance Including collision liability, with sister-ship clause un-amended, with limits of liability at least equal to the full value of all vessels used in connection with performance of the Work required under this Contract and with navigational limitations adequate for the Contractor to perform the specified Work. Where vessels engage in towing operations, said insurance shall include full towers' liability with the sister-ship clause un-amended.
- Protection and Indemnity Insurance To be evidenced through a full entry with a Group P&I Club, including collision liability, towers' liability, marine contractual liability, tankermans' liability, and specialist operations. Alternatively, if a full entry in a Group P&I Club is not available or applicable, Protection and Indemnity Insurance coverage shall be evidenced on the SP-23 form or equivalent, including, by endorsement or otherwise, collision liability, tower's liability, specialist operations, and liability for seepage, pollution, containment and cleanup, with extensions for marine contractual liability, shall not be less than the dollar amount specified in the Special Provisions.
- Pollution Liability Insurance If pollution coverage is provided outside of a P&I Club
  entry or outside of Protection and Indemnity Insurance coverage evidenced on the SP23 form or equivalent, the amount shall not be less than the dollar amount specified in
  the Special Provisions. Pollution liability coverage shall cover bodily injury, property
  damage, including cleanup costs and defense costs resulting from sudden and gradual
  pollution conditions of contaminants or pollutants into or upon the land, the atmosphere
  or any water course or body of water.

With respect to the aforementioned Hull & Machinery Insurance, Protection and Indemnity Insurance and Pollution Insurance, the policy or policies shall be endorsed as follows:

- Other than owner provisions of all policies shall be deleted with respect to the naming of Company as an Additional Assured/Insured;
- Delete any as owner clause and any other language, which limits or purports to limit the coverage afforded to an insured or an additional insured who is not a ship-owner, with coverage to be afforded to all additional insureds in any capacity in which they may be held liable; and
- Operator warrants that COFR's are on file with the U.S. Coast Guard as per Federal requirements.

If Subcontractor(s) are utilized to perform any Work that requires the use of watercraft under the Contract, all such Subcontractor(s) shall maintain insurance including limits, coverages, terms and conditions as required herein unless said Subcontractor(s) are insured by Contractor. Where Contractor provides coverage for a Subcontractor, the Contractor shall issue a Certificate of Insurance, along with related endorsement(s) required to effect coverage, evidencing Subcontractor's "Additional Insured/Assured" status under Contractor's coverage.

An Excess Marine Liability insurance policy may be used to meet the required limits of insurance. Excess coverage must follow form and be as broad as that provided by the underlying primary liability insurance policies.

ORS 15.320 provides that Oregon law applies to the Contract. The parties also agree that Oregon law applies to the Contract, even if ORS 15.320 is determined to be inapplicable or invalid.

- **(b) Extended Reporting** If any of the required insurance is permitted to be and is on a "claims made" basis, the Contractor or Subcontractor who provided the insurance coverage, shall obtain an extended reporting period on the claims made policy or maintain the claims made policy, for a duration of at least 24 months from the date the applicable work has been completed and accepted by the Agency or the date of Final Acceptance. This extended reporting requirement shall be satisfied with documentation of one of the following:
  - Extended Reporting Endorsement;
  - Tail Coverage; or
  - Maintaining the applicable continuous claims made policy with liability coverage.

The Contractor or Subcontractor shall furnish certification of this extended reporting requirement as a condition to receive Third Notice under 00150.90(b) and 00180.50(g).

- **(c)** Excess/Umbrella Liability A combination of primary and Excess/Umbrella Insurance may be used to meet the required limits of insurance. Excess/Umbrella coverage must be at least as broad as that provided by the underlying primary insurance policies. In addition, the limits of the underlying primary insurance must be sufficient to prevent any gap between such minimum limits and the attachment point of the coverage provided by the Excess/Umbrella Liability policy.
- (d) Additional Insured The liability insurance coverages of 00170.70(a) shall include the Agency, the Agency's governing body, board, or Commission and its members, and their respective officers, agents, and employees as Additional Insureds, but only with respect to the Contractor's activities to be performed under the Contract. When federal transportation funding is involved, the liability coverages of 00170.70(a) shall also include the State of Oregon, the Oregon Transportation Commission and the Oregon Department of Transportation and their respective officers, members and employees as additional insureds, but only with respect to the Contractor's activities to be performed under the Contract. Coverage shall be primary and non-contributory with any other insurance and self-insurance. The liability coverages of 00170.70(a) that are permitted by the Agency to be obtained by an appropriate Subcontractor shall include all of the foregoing as Additional Insureds and shall also include the Contractor and its officers and employees as Additional Insureds.

Additional Insured Endorsements on the Commercial General Liability shall be written on ISO Form CG 20 10 07 04, or equivalent, with respect to liability arising out of ongoing operations and ISO Form CG 20 37 07 04, or equivalent, with respect to liability arising out of completed operations. Additional Insured Endorsements shall be submitted with the Certificate(s) of Insurance and must be acceptable to the Agency.

(e) Workers' Compensation - All employers, including the Contractor and Subcontractor(s), if any, that employ subject workers, as defined in ORS 656.027, shall comply with ORS 656.017 and shall provide Workers' Compensation Insurance coverage, unless such employers meet the requirement for an exemption under ORS 656.126(2). The coverage shall include Employer's Liability Insurance with limits not less than \$500,000 each accident.

The Contractor shall certify in the Contract that the Contractor is registered by the Oregon Workers' Compensation Division either as a carrier-insured employer, a self-insured employer, an exempt employer, or is an independent contractor who will perform the Work without the assistance of others.

The Contractor shall require and verify that its insurance carrier files a guaranty contract with the Oregon Workers' Compensation Division before performing any Work.

All employers, including the Contractor and Subcontractor(s), if any, exempt under ORS 656.126(2) and subject to any other state's Workers' Compensation law, shall provide Workers' Compensation Insurance coverage as required by applicable Workers' Compensation laws. The coverage shall also include Employer's Liability Insurance with limits not less than \$500,000 each accident.

If the Contractor's and Subcontractor's, if any, operations include use of watercraft on navigable waters and employ persons in applicable positions, a Maritime Coverage Endorsement must be added to the Workers' Compensation policy, unless coverage for captain and crew is provided in a Protection and Indemnity policy.

If the Contractor and Subcontractor, if any, conducts its operations in proximity to navigable waters and employ persons in applicable positions, United States Longshore and Harbor Workers' Compensation Act coverage must be endorsed onto the Workers' Compensation policy.

The Contractor shall require compliance with these requirements in all Subcontractor contracts.

- (f) Notice of Cancellation or Change The Contractor shall provide at least 30 Days' written notice to the Agency before cancellation of, material change to, potential exhaustion of aggregate limits, or non-renewal of the required insurance coverages. If a Subcontractor is providing insurance to meet the contract requirements, the Contractor shall provide at least 30 Days' written notice to the Agency before cancellation of, material change to, potential exhaustion of aggregate limits, or non-renewal of the required insurance coverage(s). Any failure to comply with the reporting provisions of this insurance shall not affect the coverage(s) provided to the State, Agency, County, City, or other applicable political jurisdiction or to the Agency's governing body, board, or Commission and its members, and the Agency's officers, agents, and employees.
- **(g) Certificate(s) of Insurance** As evidence of the insurance coverages required by the Contract, the Contractor shall furnish Certificate(s) of Insurance to the Agency at the time(s) provided in 00130.50(a). As evidence of insurance coverages required by the Contract but permitted by the Agency under 00170.70(a) to be obtained by an appropriate Subcontractor, the Contractor shall furnish Certificate(s) of Insurance to the Agency for such coverages together with the Contractor's request under 00180.21 for approval of the subcontract with that Subcontractor. The Certificate(s) shall:
  - List Clackamas County and when federal transportation funding is involved, shall also include "State of Oregon, the Oregon Transportation Commission and the Department of Transportation, and their respective officers, members, agents and employees" as a Certificate holder and endorse as an Additional Insured:
  - Include all required endorsements or copies of the applicable policy language effecting coverage required by the Contract;
  - Specify that all liability insurance coverages shall be primary and non-contributory with any
    other insurance and self-insurance, with exception of Workers' Compensation;
  - Include a list of all policies that fall under the Excess/Umbrella Insurance if Excess or Umbrella Insurance is used to meet the minimum insurance requirement.
- **(h) Agency Acceptance** All insurance and insurance providers are subject to Agency acceptance. In addition, all of the following are subject to Agency acceptance and, if requested by Agency, the Contractor shall provide complete copies of the following to Agency's representatives responsible for verification of the insurance coverages required by the Contract: insurance policies, endorsements, self-insurance documents and related insurance documents.

- (i) Insurance Requirement Review The Contractor agrees to periodic review of insurance requirements by Agency under the Contract and to provide updated requirements as mutually agreed upon by the Contractor and Agency.
- (j) Builders' Risk If specified by Special Provision, the Contractor shall obtain, at its expense, and keep in effect during the term of the Contract, Builders' Risk Insurance on an all risks of direct physical loss basis, including, without limitation, earthquake and flood damage, for an amount equal to at least the value specified in the Special Provisions. The policy shall not contain a coinsurance clause or any collapse exclusions. Any deductible shall not exceed \$50,000 for each loss, except that the earthquake and flood deductible shall not exceed 5% of each loss or \$50,000, whichever is greater. The policy shall include the Agency, State of Oregon, and building or structure owner as loss payees.
- **(k)** Builder's Risk Installation Floater If specified by Special Provision, the Contractor shall obtain, at its expense, and keep in effect during the term of the Contract, Builder's Risk Installation Floater Insurance covering the Contractor's Materials and Equipment to be used for completion of the Work performed under the Contract. The minimum amount of coverage to be carried shall be equal to the full amount of the Contractor's Equipment, Materials, or fixtures to be installed, intransit, or stored off-site during the performance of the Contract. This insurance shall include as loss payees the Agency, State of Oregon, the building or structure owner, the Contractor and Subcontractors as their interests may appear.
- **00170.71 Independent Contractor Status** The service or services to be rendered and the Work to be completed under this Contract are those of an independent contractor as defined in ORS 670.600. The Contractor is not an officer, employee, or agent of the Agency or the State as those terms are used in ORS 30.265.
- **00170.72** Indemnity/Hold Harmless To the fullest extent permitted by law, and except to the extent otherwise void under ORS 30.140, the Contractor shall indemnify, defend (with counsel approved by the Agency) and hold harmless the Agency, Agency's Authorized Representative, Architect/Engineer, Architect/Engineer's consultants, and their respective officers, directors, agents, employees, partners, members, stockholders and affiliated companies (collectively "Indemnitees") from and against all liabilities, damages, losses, claims, expenses (including reasonable attorney fees), demands and actions of any nature whatsoever that arise out of, result from or are related to the following:
  - Any damage, injury, loss, expense, inconvenience or delay described in this Subsection.
  - Any accident or occurrence that happens or is alleged to have happened in or about the Project Site or any place where the Work is being performed, or in the vicinity of either, at any time prior to the time the Work is fully completed in all respects.
  - Any failure of the Contractor to observe or perform any duty or obligation under the Contract
    Documents that is to be observed or performed by the Contractor, or any breach of any
    agreement, duty, obligation, responsibility, covenant, provision, requirement, representation or
    warranty of the Contractor contained in the Contract Documents or in any subcontract.
  - The negligent acts, omissions, or the improper conduct of the Contractor, a Subcontractor or anyone directly or indirectly employed by them or any one of them or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss or expense is caused in part by a party indemnified hereunder.
  - Any failure to comply with all applicable Laws by the Contractor or any Subcontractor, or anyone
    employed by any one of them, or anyone for whose acts they may be liable.
  - · Any lien filed upon the Project or bond claim in connection with the Work.

Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity which would otherwise exist as to a party, person, or Entity described in this Subsection.

In claims against any person or Entity indemnified under this Subsection by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, the indemnification obligation under this Subsection shall not be limited by a limitation on amount or type of damages, compensation or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts or other employee benefit acts.

Notwithstanding the Contractor's foregoing defense obligations, neither the Contractor nor any attorney engaged by the Contractor shall defend any claim in the name of the Agency, nor purport to act as legal representative of the Agency, without the prior written consent of the Agency's legal counsel. The Agency may, at any time at its election, assume its own defense and settlement in the event that it determines that the Contractor is prohibited from defending the Agency, or that the Contractor is not adequately defending the Agency's interests, or that an important governmental principle is at issue or that it is in the best interests of the Agency to do so. The Agency reserves all rights to pursue any claims it may have against the Contractor.

When federal transportation funding is involved, the following additional requirements apply:

- The State of Oregon, the Oregon Transportation Commission and the Oregon Department of Transportation and their respective officers and members and employees (for purposes of this Subsection 00170.72 collectively "State") are additional Indemnitees.
- Neither Contractor nor Subcontractors nor any attorney engaged by the Contractor or Subcontractors shall defend any claim in the name of the State or purport to act as legal representative of the State or any of its agencies, without the prior written consent of the State's legal counsel, the Oregon Attorney General. State may, at any time at its election, assume its own defense and settlement in the event that it determines that the Contractor or Subcontractors are prohibited from defending the State, or that the Contractor or Subcontractors are not adequately defending the State's interests, or that an important governmental principle is at issue or that it is in the best interests of the State to do so. The State reserves all rights to pursue any claims it may have against the Contractor or Subcontractors.
- Contractor shall include a provision in each subcontract requiring Subcontractors to indemnify, defend (with counsel approved by the State) and hold harmless the State in accordance with this Subsection 00170.72.

**00170.74 Employee Drug Testing Program** - As required by ORS 279C.505(2), the Contractor shall have in place, and maintain during the period of the Contract, an employee drug-testing program. The Agency retains the right to audit and/or monitor the program. On request by the Engineer, the Contractor shall furnish a copy of the employee drug-testing program.

**00170.78** Conflict of Interest - The Contractor shall not give or offer any gift, loan, or other thing of value to any member of the Agency's governing body or employee of the Agency in connection with the award or performance of any Contract.

The Contractor shall not rent, lease, or purchase Materials, supplies, or Equipment, with or through any Agency employee or member of the Agency's governing body.

No ex-employee of the Agency who has worked for the Agency on any phase of the Project within the prior 2 years may be employed by the Contractor to perform Work on the Project.

The Contractor shall also be and remain in compliance with the Agency's Conflict of Interest Guidelines. (See 00120.40(g) and 00180.21(b).)

**00170.79 Third Party Beneficiary** - There are no third-party beneficiaries of the Contract, unless federal transportation funding is involved then the State of Oregon, the Oregon Transportation Commission and the Oregon Department of Transportation and their respective officers and members and employees, are third-party beneficiaries of the Contract.

00170.80 Responsibility for Damage to Work:

- (a) Responsibility for Damage in General The Contractor shall perform Work, and furnish Materials and Equipment for incorporation into the Work, at the Contractor's own risk, until the entire Project has been completed and accepted by the Agency. The Contractor shall repair all damages to Work performed, Materials supplied, and Equipment incorporated into the Work, except as otherwise provided in this Section.
- (b) Repair of Damage to Work Until Final Acceptance, the Contractor shall promptly rebuild, repair, restore, and make good damages to all portions of the permanent or temporary Work, except to the extent the Agency has assumed responsibility according to the provisions of (c) below. The Contractor shall perform all repairs of damage to Work at no additional cost to the Agency, except for repairs necessitated by damage caused by:
  - · Acts of God or Nature, as defined in Section 00110; or
  - · Actions of governmental authorities.
- **(c)** Responsibility for Damage to Work Caused by Public Traffic The Contractor may apply for relief of responsibility for damage to Work caused by Public Traffic by submitting a signed Contractor's Request for Relief of Responsibility, form 734-2768, to the Engineer by mail, personal delivery, courier, FAX, scanned and submitted via email, or other agreed-upon method.

The Engineer will process a maximum of two forms per month and return the forms within 7 Calendar Days indicating each item as "approved" or "denied".

The approval of the Engineer is limited, and is made only for the purposes of determining relief of responsibility for damage to completed portions of the Work caused by Public Traffic. The completed portions of the Work are not considered complete, and are not finally accepted for any other purposes under the Contract.

If the Contractor disagrees with the Engineer's findings, the Contractor may request a Step 1 review according to 00199.40(b).

- (1) Request for Relief The Agency will only accept a request for relief from and will only assume responsibility for damages caused by Public Traffic, to the following completed portions of the Work:
  - A segment of Roadway, drainage facilities, Slopes, lighting, traffic control devices and access facilities;
  - · A Bridge or other Structure within a segment of Roadway;
  - Traffic signals and appurtenances at an intersection;
  - Permanent, passive traffic control devices;
  - · Complete circuits of a highway lighting system; and
  - Portions of a building open to public use.

The Agency will approve a request for the Agency to assume responsibility for damages to the completed portions of the Work caused by Public Traffic only under the following conditions:

- The completed portions of the Work are completed according to Contract Change Orders, the Plans or approved stage construction Plans;
- The traffic control complies with approved traffic control Plans; and
- All required Materials conformance and quality compliance documents pertaining to the completed portions of the Work are on file with the Engineer (see Section 00165).
- **(2) Scope of Relief** When the Agency assumes responsibility for damage to completed portions of the Work caused by Public Traffic, any damages will be repaired by the Contractor on a Changed Work basis, or by Agency forces, or by other means as determined by the Engineer. If completed portions of the Work are damaged by Public Traffic before Final Inspection, and the Agency requires the Contractor to repair the damages, the Engineer will reimburse the Contractor for the Changed Work at 75% of the total amount calculated according to Section 00197.

If completed portions of the Work are damaged by Public Traffic after Final Inspection, and the Agency requires the Contractor to repair the damages, the Engineer will reimburse the Contractor for the Work at 100% of the total amount calculated according to Section 00197.

If any additional Work is performed by the Contractor on completed portions of the Work for which the Agency has assumed responsibility for damages caused by Public Traffic, and the Work is performed outside of the approved stage construction Plans or approved traffic control Plans, the Contractor shall become fully responsible and liable, and shall make good all damages caused by Public Traffic at no additional cost to the Agency.

**(d) Vandalism and Theft** - Vandalism includes damage to or destruction of Work or portions of Work that remain on the Project Site resulting from vandalism, criminal mischief, arson, or other criminal or illegal behavior.

The Contractor shall provide reasonable protection of the Work from vandalism until Third Notification.

Theft includes the loss of Work or portions of Work that are lost or stolen or otherwise unaccounted for from the Project Site or from Materials or fabrication locations. The Contractor shall remain solely responsible for all losses caused by theft, including, without limitation, theft that occurs in conjunction with vandalism.

## 00170.82 Responsibility for Damage to Property and Facilities:

(a) In General - As used in this Subsection, the term "Contractor" shall include the Contractor's agents, Subcontractors, and all workers performing Work under the Contract; and the term "damage" shall include without limitation soiling or staining surfaces by tracking or splashing mud, asphalt, and other materials, as well as damage of a more serious nature.

The Contractor shall be solely responsible for damages arising from:

- The Contractor's operations;
- · The Contractor's negligence, gross negligence, or intentional wrongful acts; and
- The Contractor's failure to comply with any Contract provision.

The Agency may withhold funds due the Contractor or the Contractor's Surety until all lawsuits, actions, and claims for injuries or damages are resolved, and satisfactory evidence of resolution is furnished to the Agency.

- **(b) Protection and Restoration of Agency Property and Facilities** The following requirements apply to Highways, Highway Structures and other improvements that are existing, under construction, or completed. The Contractor shall:
  - · Provide adequate protection to avoid damaging Agency property and facilities;
  - Be responsible for damage to Agency property and facilities caused by or resulting from the Contractor's operations; and
  - Clean up and restore such damage by repair, rebuilding, replacement, or compensation, as determined by the Engineer.
- (c) Protection and Restoration of Non-Agency Property and Facilities The Contractor shall determine the location of properties and facilities that could be damaged by the Contractor's operations, and shall protect them from damage. The Contractor shall protect monuments and property marks until the Engineer has referenced their location and authorized their removal. The Contractor shall restore property or facilities damaged by its operations to the condition that existed before the damage, at no additional compensation.

The Contractor shall provide temporary facilities when needed, (e.g., to maintain normal service or as directed by the Engineer), until the required repair, rebuilding, or replacement is accomplished.

The Contractor shall protect specific service signs, (e.g., business logos, and tourist-oriented directional signs (TODS)) from damage, whether the signs are to remain in place or be placed on temporary supports. The Contractor shall repair or replace damaged signs at no cost to the Agency. Liquidated damages will be assessed against the Contractor in the amount of \$200 per Day for each sign out of service for more than 5 Calendar Days because of the Contractor's operations.

**00170.85** Responsibility for Defective Work - The Contractor shall make good any defective Work, Materials or Equipment incorporated into the Work, according to the provisions of Section 00150.

(a) Latent Defects - The Contractor shall remain liable for all latent defects resulting from causes other than fraud or gross mistakes that amount to fraud until the expiration of all applicable statutes of limitation and ultimate repose, the Performance Bond, Warranty Bond, or warranty period, whichever expires last. The Contractor shall remain liable for all latent defects resulting from fraud or gross mistakes that amount to fraud regardless of when those latent defects may be discovered, and regardless of whether such discovery occurs outside any applicable statutes of limitation or ultimate repose or any applicable Performance Bond, Warranty Bond, or warranty period.

## (b) Contractor Furnished Warranties:

(1) Contractor Warranty for Specific Items - For those Items with Specifications referencing this 00170.85(b)(1) warranty, the Contractor warrants that the Work for those Items, including Changed Work, Additional Work, Incidental Work, On-Site Work, and Extra Work, and Materials and Equipment incorporated into the Work, shall meet the technical and performance Specifications required under the Contract. The warranty period will be identified in each applicable Specification or elsewhere in the Contract and will begin on the date of Second Notification. The Contractor shall be responsible for making good the Work, and for all repairs of damage to the Work and other improvements, natural and artificial structures, systems, equipment, and vegetation caused by, or resulting in whole or in part from, defects in warranted

Materials, Equipment, and workmanship. The Contractor shall be responsible for all costs caused by, or resulting in whole or in part from, defects in warranted Materials, Equipment, or workmanship.

When the Agency makes written notification of failure of an item covered by this warranty, the warranty period will stop for the effected item or the portion of the effected item that failed, as applicable, until the required repairs or replacements are made and accepted. All repaired or replaced items shall meet current Specifications, unless otherwise specified in the Contract, and will be warranted for the remaining warranty period.

This warranty provision shall survive expiration or termination of the Contract.

(2) General Warranty for Local Public Agency Projects - For those Contracts that are developed, advertised, awarded, and administered by Local Public Agencies, and are not on the National Highway System or do not contain federal funding, this 00170.85(b)(2) warranty applies.

The Contractor shall warrant all Work and workmanship, including Changed Work, Additional Work, Incidental Work, On-Site Work, and Extra Work, and Materials and Equipment incorporated in the Work, for 1 year from the date of Second Notification, except that warranties according to 00170.85(b)(1) and manufacturers' warranties and extended warranties according to 00170.85(c) shall not be abridged.

The Contractor shall be responsible for meeting the technical and performance Specifications required, making good the Work, and for all repairs of damage to the Work and other improvements, natural and artificial structures, systems, equipment, and vegetation caused by, or resulting in whole or in part from, occurrences beginning during the warranty period and are the result of defects in Materials, Equipment, and workmanship. The Contractor shall be responsible for all costs associated with completing the repair of the defects and for associated Work including, but not limited to, permitting, mobilization, traffic control, erosion control, surface restoration, site cleanup and remediation caused by, or resulting in whole or in part from, defects in Materials, Equipment, or workmanship, and other Work determined by the Engineer to be necessary to complete the repair of the defects.

Within 10 Calendar Days of the Agency's written notice of defects, the Contractor, or the Contractor's Surety, shall vigorously and continuously correct and repair the defects and all related damage. If the Contractor or the Contractor's Surety fails to correct and repair the defects, the Agency may have the correction and repair done by others. The Contractor or Contractor's Surety shall promptly reimburse the Agency for all expenses incurred to correct and repair the defects.

In the event of an emergency, where delay could result in serious loss or damage, the Agency may make emergency corrections and repairs without written notice. The Contractor or Contractor's Surety shall promptly reimburse the Agency for all expenses incurred to correct and repair the defects.

Corrections, repairs, replacements or changes shall be warranted for an additional 1 year period beginning on the date of the Agency's acceptance of the corrections, repairs, replacements or changes.

Without limiting the general applicability of other survival clauses under the Contract, this warranty provision shall survive expiration or termination of the Contract.

#### (c) Manufacturer Warranties and Guarantees:

(1) Manufacturer Warranties - For those Specification Sections referencing 00170.85(c)(1), the Contractor shall furnish Warranties from the Manufacturer and signed by a Manufacturer's Representative.

The warranty period will be specified in the applicable Specification Section for which it applies.

The warranty period will begin on the date of Second Notification unless otherwise specified in the Contract.

When the Agency makes written notification to the Manufacturer of failure of an item covered by this warranty, the warranty period will stop for the effected item or the portion of the effected item that failed, as applicable, until the required repairs or replacements are made and accepted. All repaired or replaced items shall meet current Specifications, unless otherwise specified in the Contract, and will be warranted for the remaining warranty period.

If, in the opinion of the Engineer, temporary repairs are necessary, the temporary repairs will be made by the Agency or an independent contractor at the Manufacturer's expense. The Manufacturer shall replace all temporary repairs at no additional cost to the Agency.

The Manufacturer shall provide all required traffic control during repair or replacement of failed items at no additional cost to the Agency.

Warranty work shall be performed when weather permits.

(2) Trade Practice Guarantees - For those Items installed on the Project that have customary trade practice guarantees, the Contractor shall furnish the guarantees to the Engineer at the completion of the Contract.

This 00170.85 provision shall survive expiration or termination of the Contract.

# 00170.89 Protection of Utility, Fire-control, and Railroad Property and Services; Repair; Roadway Restoration:

(a) Protection of Utility, Fire-Control, and Railroad Property and Services; Coordination - The Contractor shall avoid damaging the properties of Utilities, Railroads, railways, and fire-control authorities during performance of the Work. The Contractor shall cooperate with and facilitate the relocation or repair of all Utilities and Utility services, as required under 00150.50, and of Railroad and fire-control property and railways.

The Contractor shall conduct no activities of any kind around fire hydrants until the local fire-control authority has approved provisions for continued service.

The Contractor shall immediately notify any Utility, Railroad, or fire-control authority whose facilities have been damaged.

If an Entity has a valid permit from the proper authority to construct, reconstruct, or repair Utility, Railroad, or fire-control service in the Roadway, the Contractor shall allow the permit holder to perform the work.

**(b) Restoration of Roadway after Repair Work** - The Contractor shall restore the Roadway to a condition at least equal to that which existed before the repair work addressed under this Subsection was performed, as directed by the Engineer, at no additional cost to the Agency.

- **00170.92 Fencing, Protecting Stock, and Safeguarding Excavations** The Contractor shall be responsible for loss, injury, or damage that results from its failure to restrain stock and persons.
  - (a) At the Contractor's Expense The Contractor shall restrain stock to lands on which they are confined using temporary fences or other adequate means. The Contractor shall provide adequate temporary fences or other protection around excavations to prevent animals and unauthorized persons from entering.

The Contractor shall repair, at Contractor's expense and to the Engineer's satisfaction, fences damaged by the Contractor's operations and the operations of the Contractor's agents, employees and Subcontractors.

- **(b)** At the Agency's Expense The Contractor shall construct fences, or move and reconstruct fences, as shown on the Contract Documents or as directed by the Engineer. The Contractor shall tear down and remove fencing within the Right-of-Way when no longer needed, as part of the removal Work described in and paid for according to Section 00310.
- **00170.93 Trespass** The Contractor shall be responsible for its own, its agents' and employees', and its Subcontractors' trespass or encroachment upon, or damage to, property during performance of the Contract.
- **00170.94** Use of Explosives The Contractor shall comply with all Laws pertaining to the use of explosives. The Contractor shall notify anyone having facilities near the Contractor's operations of the Contractor's intended use or storage of explosives. The Contractor shall be responsible for all damage resulting from its own, its agents' and employees', and its Subcontractors' use of explosives. (See 00330.41(e) and Section 00335.)

## Section 00180 - Prosecution and Progress

**00180.00 Scope** - This Section consists of requirements for assignment of the Contract, subcontracting, time for performance, Contract responsibility, suspensions, terminations, and related provisions.

**00180.05** Assignment/Delegation of Contract - Unless the Agency gives prior written consent, which will not be unreasonably withheld, the Contractor shall not assign, delegate, sell, or otherwise transfer or dispose of any rights or obligations under the Contract, whether voluntarily or involuntarily, and whether by merger, consolidation, dissolution, operation of law, or any other manner, including, without limitation:

- The power to execute or duty to perform the Contract; or
- Any of its right, title or interest in the Contract.

Any purported or attempted assignment, delegation, sale, transfer or disposition without prior Agency consent shall be voidable.

If written Agency consent is given to assign, delegate, sell, or otherwise transfer or dispose of any rights or obligations under the Contract, such consent shall not relieve the Contractor or its Surety of any part of their duties, obligations, responsibilities, or liabilities under or pursuant to the Contract.

**00180.06** Assignment of Funds Due under the Contract - Assignment of funds due or to become due under the Contract to the Contractor will not be permitted unless:

- The assignment request is made on the form provided by the Agency;
- The Contractor secures the written consent of the Contractor's Surety to the assignment; and
- The Engineer gives prior written consent to the assignment, which will not be unreasonably withheld.

**00180.10** Responsibility for Contract - The Contractor shall direct and coordinate the operations of its employees, Subcontractors and agents performing Work, and see that the Engineer's orders are carried out promptly. The Contractor's failure to direct, supervise and control its employees, Subcontractors and agents performing Work will result in one or more of the following actions, as the Engineer deems appropriate:

- Suspension of the Work;
- · Withholding of Contract payments, as necessary to protect the Agency;
- Ordering removal of individuals from the Project Site; or
- · Termination of the Contract.

**00180.15** Agency's Right to Do Work at Contractor's Expense - Except as otherwise provided in 00150.75 and 00220.60, if the Contractor neglects to prosecute the Work properly or fails to perform any provision of the Contract, the Agency may, after 2 Calendar Days' written notice, correct the deficiencies at the Contractor's expense. In situations where the Engineer reasonably believes there is danger to life or property, the Agency may immediately and without notice correct the deficiencies at the Contractor's expense.

Action by the Agency under this provision will not prejudice any other remedy it may have.

## 00180.20 Subcontracting Limitations:

- (a) General The Contractor's own organization shall perform Work amounting to at least 30% of the original Contract Amount. The value of subcontracted Work is the full compensation to be paid to the Subcontractor(s) for all pay items in the subcontract(s).
- **(b) Own Organization** The term "own organization", as used in Section 00180, includes only employees of the Contractor, Equipment owned or rented by the Contractor, Incidental rental of operated Equipment, truck hauling of Materials not included in or requiring a subcontract, and Materials and Equipment to be incorporated into the Work purchased or produced by the Contractor.
- (c) Rental of Operated Equipment The use of Equipment rented with operators, except truck hauling of materials which is addressed in 00180.20(e), will be allowed without a subcontract only when the following requirements are met:
  - (1) Written Request The Contractor has submitted to the Engineer a written request describing the work or service to be provided, its estimated cost, and its estimated duration. The Engineer must approve the request before the work or service is provided.
  - (2) Limitations The use of Equipment rented with operators is limited to performing minor, Incidental, short-duration work or services under the direct supervision of the Contractor or Subcontractor, with Equipment not customarily owned, rented, leased, or operated by a Contractor, or with Equipment that is temporarily unavailable to the Contractor.
  - (3) Submittals The Contractor shall provide the Engineer with a copy of the rental agreement or purchase order covering the work or service to be provided. The Contractor shall make certain that the provider of approved work or services submits payrolls required under Section 00170 and complies with applicable Contract provisions, including, without limitation, 00170.07. The work or service provider will not be considered a Subcontractor under the Contract, but the work or services will be considered to have been performed by the Contractor's own organization for the purposes of determining compliance with 00180.20(a).
  - (4) Revocation of Approval The Engineer may revoke approval for the work or services provided through rented, operated Equipment at any time the Engineer determines that the work is outside that authorized under 00180.20(c)(2). Unless the Contractor promptly submits to the Engineer a subcontract agreement for consent under 00180.21, the work or service provider shall be immediately removed from the Project Site.
- (d) Disadvantaged Business Enterprise (DBE) Every agreement to perform Work, including, without limitation, subcontracts, trucking services agreements, purchase orders, and rental agreements, shall indicate whether the Work will be performed by a DBE or non-DBE.
- **(e) Trucking** This Section does not apply to delivery of Materials by or for or from a Supplier. This Subsection applies to all truck hauling of Materials not performed with trucks owned (or rented) and operated by the Contractor. If the services under Rental of Operated Equipment or Trucking are provided by a committed DBE firm, a subcontract is required under 00180.21. For this purpose a committed DBE firm is one that was identified by the Contractor to meet an assigned DBE goal including DBE firms substituting for DBE firms committed as a condition of Contract Award.
  - (1) Trucking Services Agreement The Contractor shall submit at the preconstruction conference one or more proposed trucking services agreements for all trucking services for hauling materials. The proposed agreements shall include:

- Statement specifying whether the services will be provided by a DBE;
- Statement specifying whether the services will be provided by an owner/operator;
- · Prompt payment clause (10 days) (ORS 279C.580);
- Interest penalty clause (ORS 279C.580);
- Lower-tier clause (ORS 279C.580);
- Statement about the provider's ability to file a complaint with the Construction Contractors Board (ORS 279C.515);
- Statement that workers shall be paid not less than the specified minimum hourly rate of wage (ORS 279C.830) as applicable;
- Provision requiring the provider to have a public works bond filed with the Construction Contractors Board before starting work on the Project, unless exempt under ORS 279C.836(4) or (9), or has elected to not file a bond under ORS 279C.836(7) or (8), or is otherwise not applicable;
- Insurance clauses that include Commercial Automobile Liability and Workers Compensation (ORS 656.017 unless exempt under ORS 656.126);
- Provision requiring the provider to comply with applicable Contract provisions, including, without limitation, Record Requirements in 00170.07; and
- Construction Contractors Board License Number if applicable.

The Agency must review and consent to the proposed trucking services agreements prior to use.

- (2) Limitations The approved trucking services agreements shall be used for all trucking services for hauling Materials not provided by trucks owned (or rented) and operated by the Contractor except for trucking services provided by committed DBEs that require a subcontract under 00180.21. The Contractor shall execute a trucking services agreement with every trucking services provider for hauling Materials prior to the trucking services provider doing any Work on the Project Site.
- (3) Submittals The Contractor shall provide the Engineer with an executed copy of the trucking services agreement not later than 2 Days after the trucking services provider for hauling Materials has started work. The Contractor shall make certain that the provider of approved trucking services submits payrolls required under Section 00170, complies with applicable Contract provisions, including, without limitation, 00170.07, and complies with applicable trucking services agreement provisions. The work or service provider will not be considered a Subcontractor under the Contract, but the work or services will be considered to have been performed by the Contractor's own organization for the purposes of determining compliance with 00180.20(a). If the trucking services are provided by an owner/operator:
  - Attach a copy of the data required under 00170.65(b)(4) to the trucking services agreement; and
  - Each truck shall have the name of the owner/operator clearly displayed on the side of the truck.
- (4) Revocation of Approval The Engineer may revoke approval for trucking services provided under the trucking services agreement at any time the Engineer determines that the work or service is outside that authorized under 00180.20(e). Upon revocation of approval, the service provider shall be immediately removed from the Project Site.

## 00180.21 Subcontracting:

(a) General - The Contractor shall not subcontract or perform any portion of the Contract by other than the Contractor's own organization without the Agency's prior written consent. A request for consent to subcontract, at any tier, solely for the furnishing of a labor force will not be considered.

A written request for consent to subcontract any portion of the Contract at any tier shall be submitted to the Engineer, and when required by the Engineer, shall be accompanied by background information showing that the organization proposed to perform the Work is experienced and equipped for such Work. The Agency will review the Contractor's submission to verify compliance with Contract requirements, confirm the percentage of Work subcontracted, and evaluate the proposed Subcontractor's ability to perform the Work. If the Agency approves the Contractor's request to subcontract, the Agency will provide its consent to the Contractor's request as follows:

- If the Subcontractor is not providing any of the insurance coverages as permitted under 00170.70(a), the Agency will respond within 7 Calendar Days after the Engineer's receipt of the request.
- If the Subcontractor is providing any of the insurance coverages as permitted under 00170.70(a), the Agency will respond within 35 Calendar Days after the Engineer's receipt of the request. (28 Calendar Days for the Agency to review and approve the Certificates of Insurance required by 00170.70(f) plus 7 Calendar Days to review and approve the subcontract request.)

The Engineer may revoke consent to subcontract. If the Engineer revokes consent to subcontract, the Subcontractor shall be immediately removed from the Project Site.

**(b) Submittal of Requests** - The Contractor must submit requests for consent to subcontract any portion of the Contract, at any tier, on the Agency's form, available from the Engineer. The Contractor shall attach a duplicate original subcontract agreement. The Contractor must also submit in writing any amendments or modifications proposed to Agency-approved subcontract agreements, at any tier, before the affected Work begins. The Agency's written consent will be required before such amendments or modifications become effective.

The Contractor and proposed Subcontractors shall review the Agency's Conflict of Interest Guidelines, and if any disclosures are required, they shall complete the Conflict of Interest Disclosure Form(s) and submit them with the request for consent to subcontract. The Conflict of Interest Guidelines and Conflict of Interest Disclosure Form are available on the ODOT Procurement Office website (see 00110.05(e)).

If disclosures are not required under the Agency's Conflict of Interest Guidelines, no disclosures need be submitted.

The Subcontractors shall also otherwise be and remain in compliance with the Agency's Conflict of Interest Guidelines. (See 00170.78.)

- **(c)** Substitution of Disclosed Subcontractors The Contractor may only substitute a previously undisclosed first-tier Subcontractor according to the provisions of ORS 279C.585. The Contractor shall provide the Engineer with a written notification that identifies the name of the proposed new Subcontractor and the reason for the substitution. Authorized reasons for substitution are limited to the following circumstances (see ORS 279C.585(1) through ORS 279C.585(10)):
  - The disclosed Subcontractor fails or refuses to execute a written contract that is reasonably based either upon the Project Plans and Specifications, or the terms of the Subcontractor's written Bid, after having had a reasonable opportunity to do so;

- The disclosed Subcontractor becomes bankrupt or insolvent;
- The disclosed Subcontractor fails or refuses to perform the contract;
- The disclosed Subcontractor fails or refuses to meet the bond requirements of the prime Contractor that had been identified prior to the Bid submittal;
- The Contractor demonstrates to the Agency that the Subcontractor was disclosed as the result of an inadvertent clerical error;
- The disclosed Subcontractor does not hold a license from the Construction Contractors Board and is required to be licensed by the board;
- The Contractor determines that the Work performed by the disclosed Subcontractor is not in substantial compliance with the Plans and Specifications, or that the Subcontractor is substantially delaying or disrupting the progress of the Work;
- The disclosed Subcontractor is ineligible to work on a public improvement according to the applicable statutory provisions;
- The substitution is for "good cause" as defined by State Construction Contractors Board rule; or
- The substitution is reasonably based on the Contract alternates chosen by the Agency.
- (d) Terms of Subcontracts All subcontracts shall provide that Work performed under the subcontract shall be conducted and performed according to, and shall include, the pertinent requirements, provisions, terms, and conditions of the Contract, including but not limited to the requirements of Subsection 00170.72. Compliance with 00170.07 is required. All subcontracts, including Contractor's with the first-tier Subcontractors and those of the first-tier Subcontractors with their Subcontractors, and any other lower-tier subcontracts shall contain a clause or condition that if the Contractor or a Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract, the Entity may file a complaint with the Construction Contractors Board, unless payment is subject to a good-faith dispute as defined in ORS 279C.580. Additionally, according to the provisions of ORS 279C.580, subcontracts shall include:
  - (1) A payment clause that obligates the Contractor to pay the first-tier Subcontractor for satisfactory performance under the subcontract within 10 Calendar Days out of amounts the Agency pays to the Contractor under the Contract.
  - (2) A clause that requires the Contractor to provide the first-tier Subcontractor with a standard form that the first-tier Subcontractor may use as an application for payment or as another method by which the Subcontractor may claim a payment due from the Contractor.
  - **(3)** A clause that requires the Contractor, except as otherwise provided in this Subsection, to use the same form and regular administrative procedures for processing payments during the entire term of the subcontract. The Contractor may change the form or the regular administrative procedures the Contractor uses for processing payments if the Contractor:
    - Notifies the Subcontractor in writing at least 45 Calendar days before the date on which the Contractor makes the change; and
    - Includes with the written notice a copy of the new or changed form or a description of the new or changed procedure.
  - (4) An interest penalty clause that obligates the Contractor, if the Contractor does not pay the first-tier Subcontractor within 30 Calendar Days after receiving payment from the Agency, to pay the first-tier Subcontractor an interest penalty on amounts due in each payment the Contractor

does not make in accordance with the payment clause included in the subcontract under 00180.21(d)(1). The Contractor or first-tier Subcontractor is not obligated to pay an interest penalty if the only reason that the Contractor or first-tier Subcontractor did not make payment when payment was due is that the Contractor or first-tier Subcontractor did not receive payment from the Agency or the Contractor when payment was due. The interest penalty applies to the period that begins on the day after the required payment date and ends on the date on which the amount due is paid; and shall be computed at the rate specified in 00170.10(c).

(5) A clause that requires the Contractor's first-tier Subcontractor to include a payment clause and an interest penalty clause that conform to the standards of ORS 279C.580 (see 00180.21(d)(1) and 00180.21(d)(4)) in each of the first-tier Subcontractor's subcontracts and to require each of the first-tier Subcontractor's Subcontractors to include such clauses in its subcontracts with each lower-tier Subcontractor or Material supplier.

These payment clauses shall require the Contractor to return all retainage withheld from the Subcontractor, whether held by the Contractor or the Agency, as specified in 00195.50(d).

As required by ORS 279C.800 through ORS 279C.870, subcontracts shall include:

- A provision requiring the Subcontractor to have a public works bond filed with the Construction Contractors Board before starting Work on the Project, unless exempt.
- A provision requiring that the workers shall be paid not less than the specified minimum hourly rate of wage.

As and when applicable, the Contractor shall require in its subcontracts that Subcontractors maintain the certifications required by ORS 279A.107.

- **(e) Contractor's Responsibilities** Under the provisions of ORS 279C.505 and as a condition of the Agency's grant of consent to subcontract, whether or not stated in the subcontract agreement itself, the Contractor shall remain solely responsible for administration of the subcontract, including but not limited to:
  - Performance of subcontracted Work;
  - · Progress of subcontracted Work;
  - Payments for accepted subcontracted Work;
  - Not permit any lien or claim to be filed or prosecuted against the state, county, district, municipality, municipal corporation or subdivision thereof, on account of or material furnished:
  - Pay to the Revenue Department all sums withheld from the employees pursuant to ORS 316.197; and
  - Disputes and claims for additional compensation regarding subcontracted Work.

The Engineer's consent to subcontract will not create a contract between the Agency and the Subcontractor, will not convey to the Subcontractor any rights against the Agency, and will not relieve the Contractor or the Contractor's Surety of any of their responsibilities under the Contract.

- (f) Failure to Comply Failure to comply with 00180.21 will be cause for the Engineer to take action reasonably necessary to obtain compliance. This action may include, but is not limited to:
  - · Suspension of the Work;
  - · Withholding of Contract payments as necessary to protect the Agency; and

· Termination of the Contract.

**00180.22** Payments to Subcontractors and Agents of the Contractor - To the extent practicable, the Contractor shall pay in the same units and on the same basis of measurement as listed in the Schedule of Items for subcontracted Work or other Work not done by the Contractor's own organization. The Agency will not be responsible for any overpayment or losses resulting from overpayment by the Contractor to Subcontractors and to its other agents, work providers, service providers, and trucking services providers.

If requested, the Engineer will make estimates of the Work quantities performed by Subcontractors or by others on the Project, and of Materials eligible for advances on Materials in the progress payments. These estimates are approximate only, and will be made in units of measure as listed in the Schedule of Items. The Agency does not guarantee the accuracy of these estimates, and an incorrect estimate will not bind the Agency in final settlement.

If requested in writing by a first-tier Subcontractor, the Contractor shall send to the Subcontractor, within 10 Calendar Days of receiving the request, a copy of that portion of any invoice or request for payment submitted to the Agency, or pay document provided by the Agency to the Contractor, specifically related to any labor, Equipment, or Materials supplied by the first-tier Subcontractor.

**00180.30 Materials, Equipment, and Work Force** - The Contractor shall furnish suitable and sufficient Materials, Equipment, and personnel to properly prosecute and complete the Work. The Contractor shall use only Equipment of adequate size and condition to meet the requirements of the Work and Specifications, and to produce a satisfactory quality of Work. Upon receipt of the Engineer's written order, the Contractor shall immediately remove, and not use again on the Project without the Engineer's prior written approval, Equipment that, in the Engineer's opinion, fails to meet Specifications or produce a satisfactory product or result.

The work force shall be trained and experienced for the Work to be performed. Upon receipt of the Engineer's written order, the Contractor shall immediately remove from the Project Site, and shall not employ again on the Project without the Engineer's prior written approval, any supervisor or employee of the Contractor or any Subcontractor who, in the Engineer's opinion, does not perform satisfactory Work or whose conduct interferes with the progress of the Work.

If the Contractor fails to remove Equipment or persons as ordered, or fails to furnish suitable and sufficient Materials, Equipment and personnel for the proper prosecution of the Work, the Engineer may suspend the Work by written notice until such orders are complied with and such deficiencies are corrected, or the Engineer may terminate the Contract under the provisions of 00180.90(a).

**00180.31 Required Materials, Equipment, Products, and Methods** - The Engineer's decisions under this Section are final. Substitutions after Award will be considered as provided below unless specified as the subject of an exemption per ORS 279C.345. See 00120.16 for possible substitutions before Bid Opening.

(a) General - When the Equipment and methods to be used are not specified in the Contract, any Equipment or methods that accomplish the Work as required by the Contract will be permitted.

When the Contract specifies certain Equipment or methods, the Contractor shall use the Equipment or methods specified unless otherwise authorized by the Engineer in writing.

**(b)** Substitution of Materials, Products, and Equipment to be Incorporated into the Work - After execution of the Contract, the Engineer may approve substitution of Materials, products, and Equipment to be incorporated into the Work as follows:

- (1) Reasons for Substitution The Engineer will consider substitution only if:
  - The proposed Materials, products, or Equipment are equal to or superior to the specified items in construction, efficiency and utility; or
  - Due to reasons beyond the control of the Contractor, the specified Materials, products, or Equipment cannot be delivered to the Project in sufficient time to complete the Work in proper sequence.
- (2) Submittal of Request The Contractor shall submit requests for substitution to the Engineer, including manufacturers' brochures and other information needed to verify equality of the proposed item(s).
- **(c) Substitution of Equipment Specified to Perform Work** The Agency encourages development of new or improved Equipment and innovative use of Equipment. When the Specifications require Equipment of a particular size or type to be used to perform certain portions of the Work, the Contractor may submit a request to the Engineer to use Equipment of a different size or type. The request will not be considered as a cost reduction proposal under 00140.70. The request shall:
  - Be in writing and include a full description of the Equipment proposed and its intended use;
  - · Include the reasons for requesting the substitution; and
  - Include evidence, obtained at the Contractor's expense and satisfactory to the Engineer, that
    the proposed Equipment is capable of functioning as well as or better than the specified
    Equipment.

The Engineer will consider the Contractor's request and will provide a written response to the Contractor, either permitting or denying use of the proposed Equipment.

Permission may be granted on a trial basis to test the quality of Work actually produced, subject to the following:

- There will be no cost to the Agency, either in Contract Amount or in Contract Time;
- The permission may be withdrawn by the Engineer at any time if, in the Engineer's opinion, the Equipment is not performing in all respects equivalent to the Equipment specified in the Contract;
- If permission is withdrawn, the Contractor shall perform the remaining Work with the originally-specified Equipment; and
- The Contractor shall remove and replace non-specification work resulting from the use of the Contractor's proposed Equipment, or otherwise correct it as the Engineer directs, at no additional compensation.
- **(d) Substitution of Methods** The Agency encourages development of new, improved, and innovative construction methods. When the Plans or Specifications require a certain construction method for a portion of the Work, the Contractor may submit a request for a change by following the provisions of 00140.70, "Cost Reduction Proposals".
- **00180.32** Alternative Materials, Equipment, and Methods Whenever the Contract authorizes certain alternative Materials, Equipment, or methods of construction for the Contractor's use to perform portions of the Work, and leaves the selection to the Contractor, the Agency does not guarantee that all listed alternative Materials, Equipment, or methods of construction can be used successfully throughout all or any part of the Work.

The Contractor shall employ only those alternatives that can be used to satisfactorily perform the Work. No additional compensation will be paid for corrective work necessitated by the Contractor's use of an inappropriate alternative.

### 00180.40 Limitation of Operations:

- (a) In General The Contractor shall comply with all Contract provisions and shall:
  - · Conduct the Work at all times so as to cause the least interference with traffic, and
  - Not begin Work that may allow damage to Work already started.

The Contractor must provide, at a minimum, a 24-hour notice to the Clackamas County Engineer or Project Manager in order to perform any work on Saturdays.

- (b) On-Site Work The Contractor shall not begin On-Site Work until the Contractor has:
  - Received Notice to Proceed;
  - Filed with the Construction Contractors Board the public works bond as required in 00170.20;
  - · An approved Project Work schedule;
  - · An approved Traffic Control Plan;
  - · An approved Pollution Control Plan;
  - An approved Erosion and Sediment Control Plan;
  - · Met with the Engineer at the required preconstruction conference; and
  - Assembled all Materials, Equipment, and labor on the Project Site, or has reasonably assured that they will arrive on the Project Site, so the Work can proceed according to the Project Work schedule.

**00180.41 Project Work Schedules** - The Contractor shall submit a Project Work schedule meeting the requirements of this Subsection to the Engineer. The Project Work schedule is intended to identify the sequencing of activities and time required for prosecution of the Work. The schedule is used to plan, coordinate, and control the progress of construction. Therefore, the Project Work schedule shall provide for orderly, timely, and efficient prosecution of the Work, and shall contain sufficient detail to enable both the Contractor and the Engineer to plan, coordinate, analyze, document, and control their respective Contract responsibilities. Sufficient detail shall also include all required double shifts, overtime work, or combination of both necessary to complete Contract Work within the Contract Time.

Contractor's activity related to developing, furnishing, monitoring, and updating these required schedules is Incidental.

The Contractor shall submit a supplemental "look ahead" Project Work schedule each week to the Engineer. The "look ahead" Project Work schedule is supplemental to the Type A, B, or C schedule specified below. The supplemental "look ahead" Project Work schedule shall:

- Identify the sequencing of activities and time required for prosecution of the Work.
- Provide for orderly, timely, and efficient prosecution of the Work.
- Contain sufficient detail to enable both the Contractor and the Engineer to plan, coordinate, analyze, document, and control their respective Contract responsibilities.

The supplemental "look ahead" Project Work schedule shall be written in common terminology and show the planned Work activities broken down into logical, separate activities by area, stage, and size and include the following information:

- The resources the Contractor, Subcontractors, or services will use.
- The locations of each activity that will be done including the limits of the Work by mile posts, stations, or other indicators.
- The time frames of each activity by Calendar Days, shifts, and hours.
- All anticipated Shoulder, lane, and road closures.

At a minimum, the Contractor shall prepare a bar chart that:

- Shows at least 3 weeks of activity including the week the bar chart is issued.
- Uses a largest time scale unit of 1 Calendar Day. Smaller time scale units may be used if needed.
- · Is appropriate to the activities.
- · Identifies each Calendar Day by month and day.

Include the Contract name, Contract number, Contractor's name, and date of issue on each page of the bar chart.

The Contractor shall submit the supplemental "look ahead" Project Work schedule starting at First Notification and continuing each week until Second Notification has been issued and all punch list items and final trimming and clean-up has been completed. The Contractor shall meet with the Engineer each week to review the supplemental "look ahead" Project Work schedule. If the Engineer or the Contractor determines that the current supplemental "look ahead" Project Work schedule requires changes or additions, either notations can be made on the current schedule or the Engineer may require the submittal of a revised supplemental "look ahead" Project Work schedule. Review of the current and subsequent supplemental "look ahead" Project Work schedules does not relieve the Contractor of responsibility for timely and efficient execution of the Contract.

One of the following Type "A", "B", or "C" schedules will be required under the Contract. The type of schedule will be identified in the Special Provisions.

- (a) Type "A" Schedule When a Type "A" schedule is required, the Contractor shall do the following:
  - (1) **Schedule** At least 7 Calendar Days prior to the preconstruction conference, the Contractor shall provide to the Engineer four copies of a Project Work schedule, including a time-scaled bar chart and narrative, showing:
    - · Expected beginning and completion dates of each activity, including all staging; and
    - Elements of the Traffic Control Plan as required under 00221.06.

The schedule shall show detailed Work activities as follows:

- · Construction activities:
- The time needed for completion of the Utility relocation work;
- · Submittal and approval of Materials samples and shop drawings;
- Fabrication, installation, and testing of special Materials and Equipment; and
- Duration of Work, including completion times of all stages and their sub phases.

For each activity, the Project Work schedule shall list the following information:

- A description in common terminology;
- The quantity of Work, where appropriate, in common units of measure:
- The activity duration in Calendar Days; and
- Scheduled start, completion, and time frame shown graphically using a time-scaled bar chart.

The schedule shall show the Work broken down into logical, separate activities by area, stage, or size. The duration of each activity shall be verifiable by manpower and Equipment allocation, in common units of measure, or by delivery dates.

The bar chart shall be prepared as follows:

- · The length of bar shall represent the number of workdays scheduled.
- The time scale shall be appropriate for the duration of the Contract.
- · The time scale shall be in Calendar Days.
- The smallest unit shown shall be 1 Calendar Day.
- The first day and midpoint of each month shall be identified by date.
- · Distinct symbols shall be used to denote multiple shift, holiday, and weekend Work.

Each page of the bar chart shall include a title block showing the Contract name and number, Contractor's name, date of original schedule, and all update dates; and a legend containing the symbols used, their definitions, and the time scale, shown graphically. To ensure readability the bar chart shall be drawn on a reasonable size of paper up to a maximum of 36 inch by 36 inch, using multiple sheets when needed.

Within 7 Calendar Days after the preconstruction conference, the Engineer and the Contractor shall meet to review the Project Work schedule as submitted. The Engineer will review the schedule for compliance with all Contract Time limitations and other restraints. Review of this and subsequent schedules by the Engineer shall not relieve the Contractor of responsibility for timely and efficient execution of the Contract. Within 10 Calendar Days of this meeting, the Contractor shall resubmit to the Engineer four copies of the Project Work schedule, including required revisions.

(2) Review by the Engineer - The Project Work schedule may need revision as the Work progresses. Therefore, the Contractor shall periodically review the Project Work schedule and progress of the Work with the Engineer. If the Engineer or the Contractor determines that the Project Work schedule no longer represents the Contractor's own plans or expected time for the Work, a meeting shall be held between the Engineer and the Contractor. At this meeting, the Contractor and the Engineer shall review Project events and any changes for their effect on the Project Work schedule.

The Contractor shall compile an updated Project Work schedule incorporating any changes to the Project completion time(s). The bar chart shall reflect the updated information. The Contractor shall submit four copies of the updated Project Work schedule to the Engineer within 7 Calendar Days after the meeting. The report shall include without limitation the following:

- Sufficient narrative to describe the past progress, anticipated activities, and stage Work;
- A description of any current and expected changes or delaying factors and their effect on the construction schedule; and

- · Proposed corrective actions.
- **(b) Type "B" Schedule** When a Type "B Schedule is required, the Contractor shall do the following:
  - (1) Initial Schedule At least 7 Calendar Days prior to the preconstruction conference, the Contractor shall provide to the Engineer four copies of a time-scaled bar chart Project Work schedule showing:
    - Expected beginning and completion date of each activity, including all staging; and
    - Elements of the Traffic Control Plan as required under 00221.06.

The initial schedule shall show all Work intended for the first 60 Days of the Contract to the level of detail described in (2) below, and shall show the priority and interdependence (sequencing and network logic) of all major segments of the remainder of the Work.

(2) Detailed Schedule - In addition to the above requirements, and within 30 Calendar Days after the Notice to Proceed, the Contractor shall provide the Engineer one digital copy and four paper copies of a detailed time-scaled bar chart Project Work schedule indicating the critical course of the Work. The digital copy shall be compatible with Microsoft Project 2016 or another scheduling program approved by the Engineer.

Detailed work schedule activities shall include the following:

- · Construction activities:
- The time needed for completion of the Utility relocation work;
- Submittal and approval of Material samples and shop drawings;
- Procurement of critical Materials;
- · Fabrication, installation, and testing of special Material and Equipment; and
- Duration of Work, including completion times of all stages and their sub phases.

For each activity, the Project Work schedule shall list the following information:

- A description in common terminology:
- The quantity of Work, where appropriate, in common units of measure:
- · The activity duration in normal workdays; and
- Scheduled start, completion, and time frame shown graphically using a time-scaled bar chart.

The schedule shall show the Work broken down into logical, separate activities by area, stage, or size. The duration of each activity shall be verifiable by manpower and Equipment allocation, in common units of measure, or by delivery dates.

The bar chart shall be prepared as follows:

- The length of bar shall represent the number of normal workdays scheduled.
- The time scale shall be appropriate for the duration of the Contract.
- The time scale shall be in normal workdays (every day except Saturday, Sunday, and legal holidays).

- · The smallest unit shown shall be 1 Calendar Day.
- · The first day and midpoint of each month shall be identified by date.
- Distinct symbols shall be used to denote multiple shift, holiday, and weekend Work.

The bar chart drawing(s) shall include a title block showing the Contract name and number, Contractor's name, date of original schedule, and all update dates; and a legend containing the symbols used, their definitions, and the time scale, shown graphically. To ensure readability the bar chart shall be drawn on a reasonable size of paper up to a maximum of 36 inch x 36 inch, using multiple sheets when needed.

Within 10 Calendar Days after submission of the Project schedule the Engineer and the Contractor shall meet to review the Project schedule as submitted. Within 10 Days of the review meeting, the Contractor shall resubmit to the Engineer one digital and four paper copies of the Project schedule, including required revisions.

The accepted Project schedule shall represent all Work, as well as the planned sequence and time for the Work. Review of this and subsequent schedules by the Engineer shall not relieve the Contractor of responsibility for timely and efficient execution of the Contract.

- **(3) Review and Reporting** The Project Work schedule may require revision as the Work progresses. Therefore, the Contractor shall monitor and when necessary revise the Project Work schedule as follows:
  - **a.** Review with the Engineer The Contractor shall perform ongoing review of the Project Work schedule and progress of the Work with the Engineer. If the Engineer or the Contractor determines that the Project Work schedule no longer represents the Contractor's own plans or expected time for the Work, a meeting shall be held between the Engineer and the Contractor. At this meeting, the Contractor and the Engineer shall review Project events and any changes for their effect on the Project Work schedule. After any necessary action has been agreed upon, the Contractor shall make required changes to the Project Work schedule.

The Contractor shall collect information on all activities worked on or scheduled to be worked on during the previous report period, including shop drawings, Material procurement, and Contract Change Orders that have been issued. Information shall include commencement and completion dates on activities started or completed, or if still in progress, the remaining time duration.

The Contractor shall develop detailed sub-networks to incorporate changes, Additional Work, and Extra Work into the Project Work schedule. Detailed sub-networks shall include all necessary activities and logic connectors to describe the Work and all restrictions on it. The restraints shall include those activities from the Project Work schedule that initiated the sub-network as well as those restrained by it.

The Contractor shall evaluate this information and compare it with the Contractor's Project schedule. If necessary, the Contractor shall make an updated bar chart schedule to incorporate the effect changes may have on the Project completion time(s). For any activity that has started, the Contractor shall add a symbol to show the actual date the activity started and the number of normal workdays remaining until completion. For activities that are finished, a symbol shall be added to show the actual date. The Contractor shall submit one digital and four paper copies of the updated bar chart to the Engineer within 7 Days after the progress meeting, along with a progress report as required by "b." below.

- **b. Progress Report** The Contractor shall submit a progress report to the Engineer each month. The report shall include the following:
  - Sufficient narrative to describe the past progress, anticipated activities, and stage Work;
  - A description of any current and expected changes or delaying factors and their effect on the construction schedule; and
  - · Proposed corrective actions.
- (c) Type "C" Schedule When a Type "C" Schedule is required, the Contractor shall do the following:
  - (1) Initial Schedule At least 7 Calendar Days prior to the preconstruction conference, the Contractor shall provide to the Engineer one digital copy and four paper copies of a time-scaled bar chart Project Work schedule. The digital copy shall be compatible with Microsoft Project2016, or another scheduling program approved by the Engineer. The initial schedule shall show:
    - The expected beginning and completion date of each activity, including all stages and phases;
    - · The time needed for completion of the Utility relocation work; and
    - The elements of the traffic control plan as required under 00221.06.

A logic diagram and a time-scaled bar chart will be acceptable in lieu of a time-scaled logic diagram.

The initial schedule shall show all Work intended for the first 60 Days of the Contract to the level of detail described in (2) below, and shall show the priority and interdependence (sequencing and network logic) of all major segments of the remainder of the Work.

**(2) Detailed Project Work Schedule** - In addition to the above requirements, and within 30 Calendar Days after First Notification, the Contractor shall provide the Engineer one digital copy and four paper copies of a detailed time-scaled critical path method (CPM) network Project Work schedule and computer analysis printout, both clearly indicating the critical path. The digital copy shall be compatible with the current version of Microsoft Project 2016 or another scheduling program approved by the Engineer. The first submitted detailed time-scaled critical path method (CPM) network Project Work schedule shall also contain a listing of the quantity of Work for each activity, when appropriate, in common units of measure.

Detailed work schedule activities shall include the following:

- Construction activities:
- Any limitations of operation specified in 00180.40;
- The time needed for completion of the Utility relocation work;
- Implementation of TCP for each stage and phase;
- Submittal and approval of Material samples, mix designs, and shop drawings;
- Agency timeframes to process and return Contractor submitted plans, Working Drawings, Equipment lists and other submittals;
- · Procurement of critical Materials;
- Fabrication, installation, and testing of special Material and Equipment:

- · Duration of Work, including completion times of all stages and their sub-phases; and
- · Specified cure times for all concrete elements.

The activities shall be separately identifiable by coding or use of sub-networks or both. The duration of each activity shall be verifiable and consistent with the description in the Project narrative required in (3) below.

Detailed sub-networks shall include all necessary activities and logic connectors to describe the Work and all restrictions on it. In the restraints, include those activities from any Project Work schedule that initiated the sub-network as well as those restrained by it.

The time scale used on the Contractor's detailed time-scaled critical path method (CPM) network Project Work schedule shall be appropriate for the duration of the activities and the Project duration. The time scale shall be in normal workdays, defined as every day except Saturday, Sunday and legal holidays, with calendar dates identified no less than the first and midpoint of each calendar month. The smallest unit shown shall be 1 Day. The network shall show the length of the activity or part scaled to accurately represent the number of normal workdays scheduled. Distinct symbols or graphics shall be used to show multiple shift, holiday, or weekend work.

The schedule network drawing(s) shall include a title block showing the Contract name and number, Contractor's name, date of original schedule, and all update dates; and a legend containing the symbols used, their definitions, and the time scale, shown graphically. To ensure readability the drawings shall be on a reasonable size of paper up to a maximum of 36 inch x 36 inch, using multiple sheets when needed.

The Contractor shall include a tabulation of each activity in the computer mathematical analysis of the network diagram. The following information represents the minimum required for each activity:

- Event (node) number(s) for each activity;
- · Maintain event (node) numbers throughout the Project;
- · Activity description;
- Original duration of activities (in normal workdays);
- · Estimated remaining duration of activities (in normal workdays);
- Earliest start date and actual start date (by calendar date);
- Earliest finish date and actual finish date (by calendar date);
- · Latest start date (by calendar date);
- Latest finish date (by calendar date); and
- · Slack or float time (in workdays).

Computer print-outs shall consist of at least a node sort and an "early start/total-float" sort.

Within 14 Calendar Days after submission of the detailed time-scaled critical path method (CPM) network Project Work schedule, the Engineer and the Contractor shall meet to review the detailed time-scaled critical path method (CPM) network Project Work schedule as submitted. Within 7 Calendar Days of the meeting, the Contractor shall resubmit to the Engineer one digital and four paper copies of the detailed time-scaled critical path method (CPM) network Project Work schedule, including required revisions.

This first accepted detailed time-scaled critical path method (CPM) network Project Work schedule, also called the accepted Project Work schedule, shall represent all Work, as well as the planned sequence and time for the Work. Review and acceptance of any Project Work schedules and Project narratives by the Engineer shall not relieve the Contractor of responsibility for timely and efficient execution of the Contract.

- **(3) Project Narrative** In addition to the above requirements, and within 30 Calendar Days after First Notification, the Contractor shall provide to the Engineer a final written Project narrative that discusses the planning, coordinating, scheduling and resourcing of the Work. The Project narrative shall include the following written description:
  - Plans for staging the Project.
  - · All critical activities.
  - · All near critical activities defined as those with less than 30 Days of float.
  - All Subcontractor activities that are critical, near critical, and those that are greater than two weeks in duration.
  - Labor resourcing, by stage and phase, to include the number of crews, average crew size and planned night/weekend shifts including that of Subcontractors.
  - Equipment allocation, by stage and phase to include mobilization, demobilization and planned activities including that of Subcontractors.
  - Notifications required under the Contract during each stage and phase which may include but is not limited to road closures, lanes closures, night work, cold plane Pavement removal, and pile driving.
  - Provide discussion on addressing reasonably predictable weather conditions and their impact on all weather sensitive activities. Also, provide discussion on other weather limitations that may affect the Project schedule.
  - Submittal and approval of material samples, mix designs, and shop drawings.
  - · Procurement of critical materials.
  - Plans for dealing with "unique" construction items.
  - Coordination of utilities and any immediate concerns for impacts/delays.
  - · Constructability issues.
  - Cost Reduction Proposals and/or immediate requests for changes to the Specifications.
  - Concerns/issues that need to be addressed within the first 90 Days following First Notification.

The accepted Project narrative shall represent all critical and near critical Work, as well as the planned sequence and time for the Work.

- **(4) Review and Reporting** The Project Work schedule may require revision as the Work progresses. Therefore, the Contractor shall monitor and when necessary revise the Project Work schedule as follows:
  - a. Review with the Engineer The Contractor shall perform ongoing review of the accepted Project Work schedule and progress of the Work with the Engineer. If the Engineer or the Contractor determines that the accepted Project Work schedule no longer represents the Contractor's own plans or expected time for the Work, a meeting shall be held between the Engineer and the Contractor. At this meeting, the Contractor and the Engineer shall review Project events and any changes for their effect on the accepted Project Work schedule. After

any necessary action has been agreed upon, the Contractor shall make required changes to the accepted Project Work schedule and associated Project narrative. Upon acceptance by the Engineer, this will become the new accepted Project Work schedule and associated Project narrative.

The Contractor shall collect information on all activities worked on or scheduled to be worked on during the previous report period, including shop drawings, Material procurement, and Contract Change Orders that have been issued. Information shall include actual start and completion dates on activities started or completed, or if still in progress, the remaining time duration.

The Contractor shall develop detailed sub-networks to incorporate changes, Additional Work, and Extra Work into the Project Work schedule. Detailed sub-networks shall include all necessary activities and logic connectors to describe the Work and all restrictions on it. The restraints shall include those activities from the Project Work schedule that initiated the sub-network as well as those restrained by it. The procedure for acceptance of the revised or updated Project Work schedule as the new accepted Project Work schedule will be as provided above.

The Contractor shall evaluate this information each month and compare it with the accepted Project Work schedule. The Contractor shall make an updated bar chart schedule to incorporate the effect changes may have on the Project completion time(s). For any activity that has started, the Contractor shall add a symbol to show the actual date the activity started and the number of normal workdays remaining until completion. For activities that are finished, a symbol shall be added to show the actual date. The Contractor shall submit, digitally and in paper, copies of the updated bar chart to the Engineer within 7 Days after the progress meeting, along with a progress report as required by "b." below.

- **b. Progress Report** Each month the Contractor shall submit a progress report and an update of the Project Work schedule to the Engineer. The report and updated schedule shall be submitted both digitally and in paper copy and shall include the following:
  - A sufficient description, in narrative form, to describe the past progress, anticipated activities, and stage Work;
  - A description of any current and expected changes or delaying factors and their effect on the construction schedule:
  - Proposed corrective actions;
  - · Proposals to keep the Project on schedule in the event of a delay; and
  - · Any changes to the logic as compared to the accepted Project Work schedule.
- (d) Substitution of Schedules When a Type "A" schedule is required, a Type "B" or Type "C" schedule may be substituted for the Type "A" schedule.

When a Type "B" schedule is required, a Type "C" schedule may be substituted for the Type "B" schedule.

(e) Specified Contract Time Not Superseded by Schedule Revisions - The completion dates in any Project Work schedule and any revised or updated Project Work schedules shall be within the Contract Time(s) specified for the Project, or within adjusted Contract Times approved according to 00180.80(c). Acceptance of any Project Work schedule or any revised or updated Project Work schedules shall not constitute approval of any completion dates that exceed such Contract Time(s). If the Contractor believes that additional Contract Time is due, the Contractor

shall submit, with a revised Project Work schedule, a request for adjustment of Contract Time according to 00180.80(c). A request for an adjustment of Contract Time will be evaluated using the most recently accepted Project Work schedule.

- **(f) Float Time** Float time shown on the Project Work schedule, including any time between a Contractor's scheduled completion date and the specified Contract Time(s), does not exist for the exclusive use of either party to the Contract and belongs to the Project.
- **(g)** Schedules Do Not Constitute Notice Submittal of a Project Work schedule, with supporting Project narrative, does not constitute or substitute for any notice the Contractor is required under the terms of the Contract to give the Agency.
- **(h) Failure to Provide Schedule** The Project Work schedule is essential to the Agency. The Contractor's failure to provide the schedule, schedule information, progress reports, Project narratives, or schedule updates when required will be cause to suspend the Work, or to withhold Contract payments as necessary to protect the Agency, until the Contractor provides the required information to the Engineer.

**00180.42 Preconstruction Conference** - Unless otherwise approved in writing by the Engineer, before any Work is performed and within 30 Calendar Days of the Notice to Proceed, the Contractor shall meet with the Engineer for a preconstruction conference at a time mutually agreed upon.

Submit the following during the preconstruction conference unless otherwise directed:

- The names, addresses, and telephone numbers of two or more persons employed by the Contractor who can be reached day or night to handle emergency matters.
- Subcontractor's list including contact list for each subcontractor with phone numbers and addresses and work to be performed.
- List of personnel authorized to sign change orders and receive progress payment warrants.

A representative of each subcontractor shall be required to attend the pre-construction conference.

**00180.43 Commencement and Performance of Work** - From the time of commencement of the Work to the time of Final Acceptance the Contractor shall:

- Provide adequate Materials, Equipment, labor, and supervision to perform and complete the Work within the Contract Time or the adjusted Contract Time;
- Perform the Work as vigorously and as continuously as conditions permit, and according to a Project Work schedule that ensures completion within the Contract Time or the adjusted Contract Time:
- Not voluntarily suspend or slow down operations without prior written approval from the Engineer, and if approved submit an updated Project Work schedule according to 00180.41 that ensures completion within the Contract Time or the adjusted Contract Time; and
- Not resume suspended Work without the Engineer's written authorization.
- Conduct the work at all times in a manner and sequence that will ensure minimal interference
  with traffic. The Contractor shall not begin work that will interfere with work already started. If it
  is in the County's best interest to do so, the County may require the Contractor to finish a portion
  or unit of the project on which work is in progress or to finish a construction operation before
  work is started on an additional portion or unit of the project.

## 00180.50 Contract Time to Complete Work:

- **(a) General** The time allowed to complete the Work or Pay Item is stipulated in the Solicitation Documents, and will be known as the "Contract Time". (See 00110.20.)
- (b) Kinds of Contract Time The Contract Time will be expressed in one or more of the following ways:
  - (1) Fixed Date Calculation The calendar date on which the Work or Pay Item shall be completed; or
  - **(2) Calendar Day Calculation** The number of Calendar Days from a specified beginning point in which the Work or Pay Item shall be completed.
  - (3) Work Day Calculation The number of Work Days from a specified beginning point in which the Work or Pay item shall be completed.
- (c) Beginning of Contract Time When the Contract Time is stated in Calendar Days, counting of Contract Calendar Days will begin on the day the Contractor begins On-Site Work as defined in 00110.20.
- (d) Recording Contract Time All Contract Time will be recorded and charged to the nearest one-half Day.

On Contracts with Calendar Day or Work Day counts, the Engineer will furnish the Contractor a weekly statement of Contract Time charges. The statement will show the number of Calendar Days counted for the preceding week and the number of Calendar Days remaining prior to the established completion date for the specified Work in 00180.50(h).

For Contracts with fixed completion dates for Pay Items, the Engineer will furnish the Contractor a weekly statement of Contract Time charges only after expiration of the Contract Time. The statement will show the number of Calendar Days of liquidated damages that have been assessed, if any.

These statements will include any exclusions from, or adjustments to, Contract Time.

- **(e) Exclusions from Contract Time** Regardless of the way Contract Time is expressed in the Contract, certain Calendar Days will not be charged against Contract Time. These exclusions will be allowed when the Contractor is prevented from performing Work due to one of the following reasons, resulting in delay:
  - · Acts of God or Nature:
  - · Court orders enjoining prosecution of the Work;
  - Strikes, labor disputes or freight embargoes that, despite the Contractor's reasonable efforts
    to avoid them, cause a shutdown of the entire Project or one or more major operations.
     "Strike" and "labor dispute" may include union action against the Contractor, a Subcontractor,
    a materials Supplier, or the Agency; or
  - Suspension of the Work by written order of the Engineer for reasons other than the Contractor's failure or neglect.
- (f) Time Calculation Protest In the event the Contractor disputes the accuracy of the statement of Contract Time charges, it shall immediately contact the Engineer and attempt to resolve the dispute. If the dispute cannot be resolved informally, the Contractor shall submit a formal written

protest to the Engineer within 7 Calendar Days of the date the Engineer mailed or delivered the statement. Failure to submit a formal written protest within the 7 Calendar Day period constitutes the Contractor's approval of the time charges, or adjusted time charges, itemized in the statement.

**(g) End of Contract Time** - When the Engineer determines that the On-Site Work has been completed, except for the items listed below, the Engineer will issue a Second Notification.

The Second Notification will list:

- The date the time charges stopped;
- Final trimming and cleanup tasks (see 00140.90);
- Equipment to be removed from the Project Site;
- · Minor corrective work not involving additional payment to be completed; and
- Submittals, including, without limitation, all required certifications, bills, forms, warranties, certificate of insurance coverage (00170.70(b)), and other documents, required to be provided to the Engineer before Third Notification will issue.

The Contractor shall complete all tasks listed in the Second Notification in an expeditious manner within the time frame proposed by the Contractor and accepted by the Engineer. Unless otherwise agreed by the Agency, failure of the Contractor to complete all tasks listed in the Second Notification within the time frame accepted, will result in the Agency rescinding the Second Notification. Counting of time charges will resume upon expiration of the accepted time frame.

**00180.60 Notice of Delay** - The Contractor shall notify the Engineer of any delay that will likely prevent completion of the Work or a Pay Item by the date specified in the Project Work schedule. The notice shall be in writing and shall be submitted within 7 Calendar Days of when the Contractor knew or should have known of the delay. The notice shall include, to the extent available, the following:

- · The reasons or causes for the delay;
- The estimated duration of the delay and the estimated resulting cumulative delay in Contract completion;
- Except for 00180.50(e) and 00180.65 delays, whether or not the Contractor expects to request an adjustment of Contract Time due to the delay;
- · Whether or not the Contractor expects to accelerate due to the delay; and
- Whether or not the Contractor expects to request additional compensation due to the delay.
   Except for 00180.50(e) and 00180.65 delays, failure to include this information will constitute waiver of the Contractor's right to later make such a request.

**00180.65** Right-of-Way and Access Delays - Right-of-Way and access delays will be taken into consideration in adjusting Contract Time, and in approving additional compensation if the performance of the Work is delayed because of the Agency's failure to make available to the Contractor:

- · Necessary Rights-of-Way;
- Agency-owned or Agency-controlled Materials sources that are offered in the Contract for the Contractor's use; or
- Access to, or rights of occupancy of, buildings and other properties the Contractor is required to enter or to disturb according to Contract requirements.

If the ending date of an anticipated delay is stated in the Special Provisions, only the delay occurring after that date will be considered for adjusting Contract Time or providing additional compensation.

## 00180.70 Suspension of Work:

- (a) General The Engineer has authority to suspend the Work, or part of the Work, for any of the following causes:
  - · Failure of the Contractor to correct unsafe conditions:
  - Failure of the Contractor to carry out any provision of the Contract;
  - Failure of the Contractor to carry out orders issued by the Engineer, the Agency, or any regulatory authority;
  - Existence of conditions unsuitable to proper or safe performance of the Work;
  - · Due to a fire hazard; or
  - Any reason considered by the Agency to be in the public interest.

When Work has been suspended for any reason, the Contractor shall not resume Work without the Engineer's written authorization.

**(b) Contractor's Responsibilities during and after Suspension** - During periods of suspension of the Work, the Contractor shall continue to be responsible for protecting and repairing the Work according to 00170.80, and for ensuring that a single designated representative responsible for the Project remains available according to 00150.40.

When Work is resumed after suspension, unless otherwise specified in the Contract, the Contractor shall perform the following at no additional compensation:

- Replace or repair any Work, Materials, and Equipment to be incorporated into the Work that was lost or damaged because of the temporary use of the Project Site by the public; and
- Remove Materials, Equipment, and temporary construction necessitated by temporary maintenance during the suspension, as directed by the Engineer.
- **(c) Compensation and Allowances for Suspension** Compensation and allowance of additional Contract Time due to suspension of any portion of the Work will be authorized only for Agency-initiated suspensions for reasons other than the Contractor's failure or neglect. (See 00180.50(e), 00180.65, and 00195.40.)

#### 00180.80 Adjustment of Contract Time:

- (a) General Contract Time established for the Work will be subject to adjustment, either by increase or decrease, for causes beyond the control of the Contractor, according to the terms of this Subsection. After adjustment, the Contract Time will become, and be designated as, the "Adjusted Contract Time". Except as provided in 00180.65 and 00195.40, an adjustment of Contract Time shall be the Contractor's only remedy for any delay arising from causes beyond the control of the Contractor.
- **(b) Contractor's Request Not Required** The Engineer may increase or decrease the Contract Time or the Adjusted Contract Time if Change Orders or Extra Work orders issued actually increase or decrease the amount of time required to perform the Work. The Engineer may also increase Contract Time in the event of Right-of-Way and Access delays (see 00180.65), and those delays due to causes beyond the Contractor's control specified in 00180.50(e). The Engineer will promptly inform the Contractor of adjustments made to Contract Time according to this Subsection, and will include the reasons for adjustment.

If the Agency anticipates delay during performance of the Contract, and specifies its expected duration in the Special Provisions, the Engineer will only consider additional delay beyond the stipulated duration in determining whether to adjust Contract Time.

- **(c)** Contractor's Request Required In the event the Contractor believes that additional Contract Time is due, the Contractor shall submit to the Engineer a timely request for adjustment of Contract Time. The Engineer will not consider untimely requests. The Agency regards as timely only those requests for adjustment of Contract Time that:
  - Accompany a proposed revised Project Work schedule submitted according to 00180.41, for comparison with the last revision of the Project Work schedule; or
  - Are not otherwise deemed waived and are submitted within 45 Days after the date of Second Notification, if Second Notification has been issued.

The Engineer will not grant an adjustment of Contract Time for events that occurred prior to the date of the last revision of the Project Work schedule. The Engineer will not authorize, nor the Agency pay, acceleration costs incurred by the Contractor prior to its submittal of a request for adjustment of Contract Time to which the acceleration costs relate.

The Contractor's request for adjustment of Contract Time shall be submitted to the Engineer on a form provided by, or in a format acceptable to, the Engineer, and shall include a copy of the written notice required under 00180.60. The request shall include without limitation:

- Consent of the Contractor's Surety if the request totals more than 30 Calendar Days of additional Contract Time;
- Sufficient detail for the Engineer to evaluate the asserted justification for the amount of additional Contract Time requested;
- The cause of each delay for which additional Contract Time is requested, together with supporting analysis and data;
- Reference to the Contract provision allowing Contract Time adjustment for each cause of delay;
- The actual or expected duration of delay resulting from each cause of delay, expressed in Calendar Days; and
- A schedule analysis based on the current approved Project Work schedule for each cause of delay, indicating which activities are involved and their impact on Contract completion.
- (d) Basis for Adjustment of Contract Time In the adjustment of Contract Time, the Engineer will consider causes that include, but are not limited to:
  - Failure of the Agency to submit the Contract and bond forms to the Contractor for execution within the time stated in 00130.50, or to submit the Notice to Proceed within the time stated in 00130.90;
  - Errors, changes, or omissions in the Supplemental Drawings, quantities, or Specifications;
  - Performance of Extra Work;
  - Failure of the Agency or Entities acting for the Agency to act promptly in carrying out Contract duties and obligations;
  - Acts or omissions of the Agency or Entities acting for the Agency that result in unreasonable delay referenced in 00195.40;
  - Causes cited in 00180.50(e); and

Right-of-way and access delays referenced in 00180.65.

The Engineer will not consider requests for adjustment of Contract Time based on any of the following:

- Contentions that insufficient Contract Time was originally specified in the Contract;
- Delays that do not affect the specified or Adjusted Contract Time;
- Delays that affect the Contractor's planned early completion, but that do not affect the specified or adjusted Contract Time;
- Shortage or inadequacy of Materials, Equipment or labor;
- · Work stoppage required by the Engineer to determine the extent of Work defects;
- Time for the Contractor to correct the Work defects from date of notification of the defects until the correction work is completed and has been approved by the Engineer;
- Late delivery of Materials and Equipment to be incorporated into the Work, except under those conditions referenced in 00180.50(e);
- Different area of Material source in 00160.40(a);
- Substitution of Equipment in 00180.31(c);
- Reasonably predictable weather conditions: For Fixed Date Contracts, normally expected inclement weather conditions are considered in the Engineer's selection of the completion date, and time extensions will only be considered for reasons shown in 00180.50(e) and for weather conditions which in the opinion of the Engineer have an extraordinarily low statistical probability. Low statistical probability will be determined using historical weather data from a government website for the previous 10 years in which weather that occurs within 7 years of the 10-year period is considered reasonable and predictable; or
- Other matters within the Contractor's control or Contract responsibility.
- **(e) Consideration and Response by Agency** The Engineer will only consider a Contractor's request for Contract Time adjustment submitted according to the requirements of 00180.80(c). The Engineer may elect not to consider claimed delays that do not affect the specified or adjusted Contract Time required to complete the Work.

The Engineer may adjust Contract Time for causes not specifically identified by the Contractor in its request.

The Engineer will review a properly submitted request for Contract Time adjustment, and within a reasonable time will advise the Contractor of the Engineer's findings. If the Contractor disagrees with the Engineer's findings, the Contractor may request review according to the procedure specified in 00199.40.

## 00180.85 Failure to Complete on Time; Liquidated Damages:

(a) Time is of the Essence - Time is of the essence in the Contractor's performance of the Contract. It is essential and in the public interest that the Contractor prosecute the Work vigorously to Contract completion and within Contract Time or adjusted Contract Time.

The Agency does not waive any rights under the Contract by permitting the Contractor to continue to perform the Contract, or any part of it, after the Contract Time or adjusted Contract Time has expired.

**(b)** Liquidated Damages - Delays in the Contractor's performance of the Work will cause the Agency to sustain damages; increase risk to, inconvenience, and interfere with the traveling public and commerce; and increase costs to taxpayers. Because the Agency finds it is unduly burdensome and difficult to demonstrate the exact dollar value of such damages, the Contractor agrees to pay to the Agency, not as a penalty but as liquidated damages, the amount(s) determined as specified below for each Calendar Day the Work remains incomplete after the expiration of the Contract Time or adjusted Contract Time applicable to that Work. The liquidated damages shall constitute payment in full only of damages incurred by the Agency due to the Contractor's failure to complete the Work on time.

Payment by the Contractor of liquidated damages does not release the Contractor from its obligation to fully and timely perform the Contract according to its terms. Nor does acceptance of liquidated damages by the Agency constitute a waiver of the Agency's right to collect any additional damages it may sustain by reason of the Contractor's failure to fully perform the Contract according to its terms.

If the Contract is terminated according to 00180.90(a), and if the Work has not been completed by other means on or before the expiration of Contract Time or adjusted Contract Time, liquidated damages will be assessed against the Contractor for the duration of time reasonably required to complete the Work.

#### 00180.90 Termination of Contract and Substituted Performance:

- (a) Termination for Default Termination of the Contract for default may result if the Contractor:
  - Fails to comply with the requirements for records;
  - · Violates any material provision of the Contract;
  - Disregards applicable laws and regulations or the Engineer's instructions;
  - Refuses or fails to supply enough Materials, Equipment or skilled workers for prosecution of the Work in compliance with the Contract;
  - Fails to make prompt payment to Subcontractors;
  - Makes an unauthorized general assignment for the benefit of the Contractor's creditors;
  - Has a receiver appointed because of the Contractor's insolvency;
  - · Is adjudged bankrupt and the court consents to the Contract termination; or
  - Otherwise fails or refuses to faithfully perform the Contract according to its terms and conditions.

If the Contract is terminated by the Agency, upon demand the Contractor and the Contractor's Surety shall provide the Engineer with immediate and peaceful possession of the Project Site, and of all Materials and Equipment to be incorporated into the Work, whether located on and off the Project Site, for which the Contractor received progress payments under 00195.50.

If the Contract is terminated for default, neither the Contractor nor its Surety shall be:

- Relieved of liability for damages or losses suffered by the Agency because of the Contractor's breach of Contract; or
- Entitled to receive any further progress payments until the Work is completed. However, progress payments for completed Work that remain due and owing at the time of Contract termination may be made according to the terms of 00195.50, except that the Engineer will be entitled to withhold sufficient funds to cover costs incurred by the Agency as a result of the

termination. Final payment to the Contractor will be made according to the provisions of Section 00195.

If a termination under this provision is determined by a court of competent jurisdiction to be unjustified, the termination shall be deemed a termination for public convenience.

- **(b)** Substituted Performance According to the Agency's procedures, and upon the Engineer's recommendation that sufficient cause exists, the Agency, without prejudice to any of its other rights or remedies and after giving the Contractor and the Contractor's Surety at least 10 Calendar Days' written notice, may:
  - · Terminate the Contract;
  - Substitute the Contractor with another Entity to complete the Contract;
  - · Take possession of the Project Site;
  - · Take possession of Materials on the Project Site;
  - Take possession of Materials not on the Project Site, for which the Contractor received progress payments under 00195.50;
  - Take possession of Equipment on the Project Site that is to be incorporated into the Work;
  - Take possession of Equipment not on the Project Site that is to be incorporated into the Work, and for which the Contractor received progress payments under 00195.50; and
  - Finish the Work by whatever method the Agency deems expedient.

If, within the 10 Calendar Day notice period provided above, the Contractor and/or its Surety corrects the basis for declaration of default to the satisfaction of the Engineer, or if the Contractor's Surety submits a proposal for correction that is acceptable to the Engineer, the Contract will not be terminated.

**(c) Termination for Public Convenience** - The Engineer may terminate the Contract for convenience in whole or in part whenever the Engineer determines that termination of the Contract is in the best interest of the public.

The Engineer will provide the Contractor and the Contractor's Surety 7 Calendar Days' written notice of termination for public convenience. After such notice, the Contractor and the Contractor's Surety shall provide the Engineer with immediate and peaceful possession of the Project Site, and of Materials and Equipment to be incorporated into the Work, whether located on and off the Project Site, for which the Contractor received progress payments under 00195.50.

If the Contract is terminated for public convenience, neither the Contractor nor its Surety shall be relieved of liability for damages or losses suffered by the Agency as a result of defective, unacceptable or unauthorized Work completed or performed.

Compensation for Work terminated by the Engineer under this provision will be determined according to the provisions of 00195.70(b).

### Section 00190 - Measurement of Pay Quantities

#### Description

**00190.00 Scope** - The Engineer will measure pay quantities for accepted Work according to the United States standard measure unless otherwise provided in the Contract. Unless otherwise specified in the Contract, the Engineer will round off all quantity computations using the following convention:

- The final significant digit will not be changed when the succeeding digit is less than 5.
- The final significant digit will be increased by one when the succeeding digit is 5 or greater.

The measurement provisions contained in the Specifications for each Pay Item will supplement or modify the above convention by:

- Imposing measurement limitations
- Describing measurement or computation procedures
- · Giving conversion factors or adjustment conditions
- Providing for determination of reasonably accurate and representative Pay Item quantities

Measurements required or allowed to be made by the Contractor will be subject to the Engineer's verification. The Engineer's decision about measurement is final.

**00190.10 Measurement Guidelines** - Measurement of quantities will be made on the following bases, unless otherwise specified in the Contract:

- (a) Unit Basis Unit will be each, unless otherwise specified in the Contract and will be determined by actual count of units in place.
- **(b)** Length Basis Length will be feet or mile, unless otherwise specified in the Contract and will be determined by measuring the length at least to the nearest 0.1 foot or at least to the nearest 0.1 mile, as applicable, unless otherwise specified in the Contract. Measurements will be limited to the dimensions shown or specified, or as directed by the Engineer.
- **(c)** Area Basis Area will be square foot, square yard, or acre, unless otherwise specified in the Contract and will be determined by measuring the width and the length (or height) at least to the nearest 0.1 foot and computed at least to the nearest 0.1 square foot, nearest 0.1 square yard, or nearest 0.1 acre, as applicable, unless otherwise specified in the Contract.
- (d) Weight Basis Weight will be pound or ton, unless otherwise specified in the Contract and will be determined as follows:
  - (1) Pound Pound weight will be determined by the net weight identified on the manufacturer's packaged labels, subject to periodic check weighing. Weight by pound will be measured at least to the nearest 1.0 pound unless otherwise specified in the Contract.

Provide a certificate with each shipment together with a certified copy of the weight of each delivery. If the check weight is less than the manufacturer weight by more than 0.4%, the discrepancy will be resolved by the Engineer.

**(2)** Ton - Ton weight will be determined on Contractor-provided scales as required under 00190.20 unless otherwise allowed by the Specifications. Weight by ton will be measured at least to the nearest 0.01 ton unless otherwise specified in the Contract.

If bituminous materials, portland cement, lime, and similar bulk Materials are shipped by truck or rail, the supplier's shipping invoice with net scale weights, or volumes converted to weights, may be used for Pay Item quantity determination in place of weights determined on the Contractor-provided vehicle scales.

Shipping invoice weights of the supplier's truck or transport shall be subject to periodic check weighing on the Contractor's vehicle scales, or other scales designated, according to 00190.20. If the check weight is less than the supplier weight by more than 0.4%, the discrepancy will be resolved by the Engineer.

No payment will be made:

- · For quantities in excess of the supplier weight
- When Materials have been lost, wasted, or otherwise not incorporated into the Work
- For additional hauling costs resulting from the check weighing
- **(e) Volume Basis** Volume will be cubic yard truck measure or in-place measure, gallons, foot board measure (FBM), or thousand foot board measure (MFBM), unless otherwise specified in the Contract and will be measured at least to the nearest 0.1 cubic yard, nearest 1.0 gallon, nearest 0.1 FBM, or nearest 0.1 MFBM, as applicable, unless otherwise specified in the Contract.

Truck measure will be the measured and calculated maximum "water level" capacity of the vehicle. Quantities will be determined at the point of delivery, with no allowance for settlement of Material during transit. When required to facilitate measurement, the vehicle load shall be leveled at the point of delivery. Payment will not be made for Material in excess of the maximum "water level" capacity. Deductions will be made for loads below the maximum "water level" capacity.

When bituminous materials are measured by volume, the volume will be measured at 60 °F or will be corrected to the volume at 60 °F using the correction factors found in the MFTP (ODOT TM 321).

- (f) Time Basis Time will be hour, Day, or year, unless otherwise specified in the Contract, and will be measured to at least the nearest 0.5 hour, nearest 1.0 Day, or nearest 1.0 year, as applicable, unless otherwise specified in the Contract.
- (g) Standard Manufactured Items If standard manufactured items, such as fence, wire, plates, rolled shapes, pipe, conduit and other similar items are specified in the Contract by properties such as gauge, unit weight, or section dimensions, the manufacturing tolerances established by the industry involved will be accepted unless more stringent tolerances are cited in the Contract.
- (h) Lump Sum Basis Lump sum, when used, means the Work described shall be completed and accepted without measurement unless changes are ordered in writing by the Engineer. If estimated quantities of the Work to be performed are listed in the Special Provisions, they provide only a basis for adjusting payment amounts. Estimated quantities are approximate only, and are made from a reasonable interpretation of the Contract Documents. Computations based on the details and dimensions shown on the Contract Documents are not guaranteed to equal estimated quantities.

If the Agency issues no Change Order, the Agency will make no pay adjustment for quantities based on the Contractor's computations that overrun or underrun the estimated quantities.

If the Agency issues Change Orders for changes in the Work, the Engineer will measure such changes according to the standards set by 00195.20 to determine adjustment of payment.

# 00190.20 Contractor to Provide Vehicle Weigh Scales:

(a) General - If the Specifications require measurement by weighing on vehicle weigh scales, the Contractor shall provide vehicle weigh scales and shall transport Materials to the scales. Subject to the Engineer's approval, weights may be determined by plant or hopper scales according to 00190.30.

Contractor-provided scales shall be furnished, installed and maintained by the Contractor or its supplier, or, subject to the Engineer's approval, may be commercial scales located in the vicinity of the Project.

Unless otherwise provided in the Contract, Pay Items to be measured by weight shall include all Contractor costs for providing, maintaining, inspecting, and testing scales; for furnishing appropriate weigh tickets; for self-printing scales; for electronic weigh memo system(s); and for transporting Materials to the scales or to check weighing.

- **(b) Requirements** The scales shall conform to ORS Chapter 618, or the laws of the state in which they are located, and NIST *Handbook 44*, and shall be:
  - Licensed by the Oregon Department of Agriculture, or by the analogous regulatory body for scales located outside the State;
  - Technically suitable for weighing the Materials;
  - · Properly installed and maintained; and
  - Accurate to the required tolerances.

The weight of any Materials weighed by anyone other than the Engineer will be subject to check weighing as the Engineer directs.

- (c) Approaches Vehicle scale approaches shall be:
  - · At each end of the scale platform;
  - · Straight and in line with the platform; and
  - Long enough to accommodate combination vehicles longer than the scale platform so that
    they are level and allow release of brakes before weighing.
- (d) Inspections Contractor shall have all scales certified, that is inspected and their accuracy tested, by the Oregon Department of Agriculture, an analogous regulatory body for scales located outside the State, or a scale service company, as follows:
  - · Before use if installed at a new site:
  - 60 Calendar Days after initial inspection;
    - As otherwise required by the Oregon Department of Agriculture, or an analogous regulatory body for scales located outside the State; and
  - · When the Engineer directs additional inspections.

No Materials weighed on scales without current certifications according to this Subsection will be accepted. The Contractor shall provide a copy of all required certifications to the Engineer.

Testing by a scale service company within the State of Oregon shall comply with ORS Chapter 618.

If additional inspections directed by the Engineer confirm that the scale accuracy is within the required tolerances, the Agency will pay the cost for inspecting and testing the scales. If the scale accuracy is not within these tolerances, the Contractor shall pay the cost for inspecting and testing the scales.

**(e) Inspection Results** - If an inspection indicates the scales have been under-weighing (indicating less than the true weight), the Agency will make no additional payment to the Contractor for Materials previously weighed.

If an inspection indicates the scales have been over-weighing (indicating more than the true weight), the weights will be reduced for Materials received after the time the Engineer determines the overweighing began or, if that is not possible, after the last acceptable certification of the scales. The reduction will be the amount of error in excess of the 0.2% maintenance tolerance allowed in the Contract.

- **(f)** Contractor-Provided Weigh Technician The Contractor shall provide a technician to operate Contractor-provided vehicle weigh scales. The Agency may observe procedures and require check weighing according to the following:
  - (1) Scale with Automatic Printer If the scales have an automatic weigh memo printer or an approved electronic weigh memo system that does not require manual entry of gross weight information, the Agency may periodically have a representative at the scales to observe the weighing procedures. In addition, the Engineer may periodically check the weight for a load of Materials by directing the haul vehicle to reweigh on a different scale that has been inspected and certified according to 00190.20(b) and 00190.20(d).

If a different scale is not available within a 30-mile round trip from the regular haul route, the Agency will allow check weighing on an approved alternate basis. Check weights within 0.4% of the Contractor-provided weight are acceptable.

The Engineer will resolve discrepancies found by check weighing. Agency employee costs will be paid by the Agency. The Contractor shall pay all other costs resulting from the check weighings, including, without limitation, the use of other scales.

When 2,000 tons or less of all types of Materials are received from a scale, check weighing will be at the discretion of the Engineer.

The Contractor shall make at least one check weighing on projects where more than 2,000 Tons of all types of Materials are received from a scale. If more than 50 Tons per Day of all types of Materials are received from a scale, the Contractor shall make random check weighings at least once every ten Days on which more than 50 Tons is received or at each interval that 10,000 Tons has been weighed, whichever occurs first, or as directed by the Engineer. The check weighing frequency does not apply to total quantities less than 2,000 Tons of all types of Materials from a scale. The Contractor shall provide the Engineer with the results of the check weighing.

(2) Scale Without Automatic Printer - If the scales require manual entry of gross weight information, the Agency may periodically have a representative weigh witness at the scales to observe the weighing procedures. The Contractor shall inform the Engineer of his intent to use a scale without an automatic printer at least 3 working days before weighing begins or before the Contractor changes to a scale that does not have an automatic printer. The Contractor shall pay costs for the weigh witness. The hourly cost of the weigh witness will be as stated in the

Special Provisions. In addition, the Engineer may periodically check the weight for a load of Materials by directing the haul vehicle to reweigh on a different scale that has been inspected and certified according to 00190.20(b) and 00190.20(d).

If a different scale is not available within a 30-mile round trip from the regular haul route, the Agency will allow check weighing on an approved alternate basis. Check weights within 0.4% of the Contractor-provided weight are acceptable.

The Engineer will resolve discrepancies found by check weighing. Agency employee costs for check weighings will be paid by the Agency. The Contractor shall pay all other costs resulting from the check weighings, including, without limitation, the use of other scales.

If more than 50 tons per Day of all types of Materials are received from a scale, the Contractor shall make random check weighings at least every tenth day on which more than 50 tons is received or at each interval that 10,000 tons has been weighed, whichever occurs first, or as directed by the Engineer. The Contractor shall make at least one check weighing on all projects where materials are received from a scale without an automatic printer. The Contractor shall provide the Engineer with the results of the check weighing.

### (3) Duties of Weigh Technician - The Contractor's weigh technician shall:

- Determine twice a Day, or as otherwise directed by the Engineer, the empty haul weights (tare weights) of hauling vehicles, unless vehicles are tared before each load;
- Furnish daily a listing of the tare weights if 10 or more loads are hauled during that Day;
- · Furnish a note listing the net weight for each consecutive ten loads with the following load;
- Furnish a daily listing of the net weights and total weight for each type of Material hauled during that Day; and
- Furnish a legible, serially numbered weigh memo for each load of Materials to the Agency's Materials receiver at the point of delivery, or as directed by the Engineer. The memo shall identify the Project, the Materials, the date, net weight (gross and tare as appropriate), and identification of the vehicle and weigh technician. If approved by the Engineer an electronic weigh memo system may be used. Requests to use an electronic weigh memo system shall be submitted to the Engineer according to 00150.37, providing sufficient detail for the Engineer to perform an evaluation. If approved, the Contractor shall provide training, technical support, reports, and weigh memo information to the Engineer at no additional cost to the Agency. The electronic weigh memo system shall be:
- Capable of recording and securely retaining the same required "weigh memo" information identified above. For retention see 00170.07(c).
- Fully integrated with the provided weigh scale system.
- Designed in such a way that the data electronically read from scales cannot be altered by the Contractor, Subcontractor, Supplier, Engineer, or other system users.
- Designed to allow the Engineer remote access to all the weigh memo data in real-time and allow the Engineer to add comments to the individual weigh memo regarding waste, temperature, stations, yield or other information. The system shall identify the system user or individual that adds comments to the electronic weigh memo or otherwise access the system. The Contractor shall provide the Engineer a means to access the data if the Engineer cannot use an Agency provided hand held device for access.
- Capable of providing all the weigh memo information, including any added comments, in an electronic data file the Engineer can easily access without proprietary software.

**(g) No Agency-Provided Weigh Technician** - The Contractor must provide a weigh technician. The Agency will not provide one for the Contractor.

**00190.30 Plant Scales** - The Contractor, with the Engineer's written approval, may weigh plant-mixed Materials on scales that have either:

- An automatic weight batching and mixing control printer system; or
- · A weigh hopper printer system.

If approved by the Engineer an electronic weigh memo system may be used in place of a printer system. See 00190.20(f)(3).

Any additional costs resulting from the use of these scales shall be borne by the Contractor. Check weighing will be done according to 00190.20(f).

Except for 00190.20(c) regarding approaches, the Contractor's use of plant scales shall comply with all provisions of 00190.20.

The Engineer's approval for the Contractor's use of plant scales to determine pay weights will be rescinded if check weighing or scale inspections indicate the scales do not consistently determine weights within the tolerances allowed by state law.

### Section 00195 - Payment

### Description

### 00195.00 Scope and Limit:

(a) General - The Agency will pay only for measured Pay Item quantities incorporated into the Work or performed according to the terms of the Contract. The Contractor understands and agrees that Pay Item quantities listed in the Schedule of Items do not govern payment.

Payment constitutes full compensation to the Contractor for furnishing all Materials, Equipment, labor, and Incidentals necessary to complete the Work; and for risk, loss, damage, and expense arising from the nature or prosecution of the Work or from the action of the elements, subject to the provisions of 00170.80. The Contractor shall include the costs of bonds and insurance for the Project in the unit price for each Pay Item of Work to be performed.

**(b) Essential or Incidental Materials or Work** - When the Specifications state that the unit price for a Pay Item is compensation for certain Materials or Work essential or Incidental to the Pay Item, the same Materials or Work will not be measured or paid under any other Pay Item.

### **Provisions and Requirements**

**00195.10 Payment For Changes in Materials Costs** - On certain projects, as identified in the Special Provisions, an escalation/de-escalation clause with respect to certain materials will be in effect during the life of the Contract.

**00195.12 Steel Material Price Escalation/De-Escalation Clause** - Subsections 00195.12, 00195.12(a), 00195.12(b), 00195.12(c), and 00195.12(d) contain the price escalation/de-escalation clause relating to steel materials (as defined in 00195.12(d)) that is included in this Contract. This exclusive steel material price escalation/de-escalation clause, and the steel escalation/de-escalation program described in 00195.12 through 00195.12(d), are in effect for the life of this Contract regardless of the number of steel material Pay Items, if any, that are included, and whether or not the Contractor elects to participate in the steel escalation/de-escalation program according to 00195.12(d).

(a) Steel Material Price Escalation/De-Escalation Participation - The Contractor may select individual Pay Items to include in the steel escalation/de-escalation program from those Pay Items listed for this Project under 00195.12(d) by following the directions provided in 00195.12(d). The Contractor is not obligated to select any Pay Items. Before or within seven Calendar Days after the date of the preconstruction conference, the Contractor shall submit in writing to the Project Manager the Pay Items selected by the Contractor to be included in the steel escalation/de-escalation program, in the manner required under 00195.12(d). If the Contractor elects to not participate in the steel escalation/de-escalation program for the Project, no response from the Contractor is required. If the Contractor fails to inform the Project Manager of Pay Items to include in the steel escalation/de-escalation program in the manner and within the time limits stated in 00195.12(d) (or the Contractor otherwise elects not to participate in the program), the Contractor thereby elects not to participate in the program for this Project.

The Agency reserves all of its rights under the Contract, including, but not limited to, its rights for suspension of the Work under 00180.70 and its rights for termination of the Contract under 00180.90, and this steel material price escalation/de-escalation provision will not limit those rights. Adjustment for fluctuations in the cost of steel material will apply only to the Pay Items

individually selected by the Contractor from the Pay Items listed under 00195.12(d), and will be made using the respective steel cost basis (CB) listed.

(b) Monthly Steel Materials Value (MV) and Base Steel Materials Value (BV) - The Monthly Steel Materials Value (MV) will be established by the Agency from the IDWPUSISTEEL1 Bureau of Labor Statistics (BLS), Producer Price Indexes (PPI) using non-seasonally adjusted indexes only. Preliminary numbers may be referenced on the IDWPUSISTEEL1 BLS PPI for 6 months or more before IDWPUSISTEEL1 BLS PPI determines they are final numbers.

The Base Steel Materials Value (BV) for this Project will be the MV published on the ODOT Estimating website (see 00110.05(e)) for the month of the Bid Opening for this Project. The Agency will only publish values on the ODOT Estimating website for use after the IDWPUSISTEEL1 BLS PPI establishes the numbers as final numbers. The final values of MV and BV will be available at the ODOT Estimating website.

The Agency has no control of when the IDWPUSISTEEL1 BLS PPI establishes final values. The Agency steel material price escalation/de-escalation adjustments made under 00195.12 through 00195.12(d) may not be reflected on payments made to the Contractor for up to 2 months after the IDWPUSISTEEL1 BLS PPI applicable values become final. This timing for steel material price escalation/de-escalation adjustments is an agreed term of this Contract and shall not constitute late payment under ORS 279C.570, nor shall the Agency be responsible to pay interest on any such steel material price adjustments.

If the Agency-selected index ceases to be available for any reason, the Agency in its discretion will select and begin using a substitute price source or index to establish the MV each month. The MV will only apply to Pay Items selected by the Contractor and provided in writing to the Project Manager from the Pay Item list contained under, and in the manner and within the time limits required by, 00195.12(d). The Agency does not guarantee that steel material will be available at any stated or implied materials price.

(c) Monthly Steel Materials Price Adjustment - If the Contractor has properly informed the Project Manager of Pay Items to include in the steel escalation/de-escalation program as required by 00195.12(a) and 00195.12(d), a price adjustment evaluation will be made for the Pay Items individually selected. No adjustments will be made using the BV or MV until such time as they are listed as final values by the IDWPUSISTEEL1 BLS PPI. The price adjustment as calculated in this provision for a given Pay Item will use the MV for the month the Work associated with that Pay Item is performed and added to the monthly progress estimate. A price adjustment for that Pay Item will only be made if the MV for the month the Work associated with the Pay Item is performed and added to the monthly progress estimate differs by more than 10% from the BV. A price adjustment will be made, as and when required by 00195.12 through 00195.12(d), only for the Pay Items, if any, that were selected by the Contractor in the manner and within the time limits required under 00195.12(a) and 00195.12(d).

The Monthly Steel Materials Price Adjustment will be determined as follows:

- If the MV is within 10%  $\pm$  of the BV, there will be no adjustment.
  - If the MV is more than 110% of the BV, then:
     PA = (((MV-BV) ÷ BV) 0.10) x (CB x PIP)
  - If the MV is less than 90% of the BV, then:
     PA = (((MV-BV) ÷ BV) + 0.10) x (CB x PIP)

#### Where:

PA = Price Adjustment, dollars

- MV = Monthly Steel Materials Value from BLS PPI for the month determined above (after becomes final)
- BV = Base Steel Materials Value from month of the Bid Opening (after becomes final)
- PIP = Amount paid for the Pay Item for the month for which the adjustment is made
- CB = Cost Basis for the applicable steel material, in percent (see 00195.12(d))
- (d) Steel Materials Pay Item Selection The Agency has a process using estimated quantities to determine which Pay Items containing steel material qualify for the steel escalation/de-escalation program by meeting a minimum threshold, and are therefore included in the eligible Pay Items listed in the Special Provisions.

For purposes of 00195.12 through 00195.12(d), "steel material" means structural and reinforcing steel, steel studs, sheet piling, guardrail, ductile iron pipe and other steel products used for the construction, reconstruction or major renovation of a road or Highway.

The Contractor may elect to participate in the steel escalation/de-escalation program for this Project by marking the list in the Special Provisions, checking each box next to each Pay Item the Contractor wants included in the program and submitting this information in writing, signed and dated by the Contractor, to the Project Manager before or within 7 Calendar Days after the date of the preconstruction conference. The steel material price escalation/de-escalation clause for price adjustments for fluctuations in the cost of steel material will apply only to the Pay Items selected by the Contractor, from the Pay Item list included in the Special Provisions, and provided in writing to the Project Manager in the manner and within the time limits stated above.

If the Contractor fails to inform the Project Manager of Pay Items to include in the steel escalation/de-escalation program in the manner and within the time limits stated above (or the Contractor otherwise elects not to participate in the program), the Contractor thereby elects not to participate in the program and forfeits all present and future rights to participate in the program for this Contract and this Project.

#### 00195.20 Changes to Plans or Character of Work:

(a) Insignificant Changed Work - If the changes made under 00140.30 do not significantly change the character or unit cost of the Work to be performed under the Contract, the Agency will pay for such Work at the Pay Item price.

If the Work involved in the change is measured on a lump sum basis and its character is not significantly changed, payment for the Changed Work will be determined:

- As described in the applicable Section of the Specifications;
- If not described there, on a theoretical unit price determined by dividing the Contractor's lump sum price by the estimated quantity of the Pay Item listed in the Special Provisions; or
- If neither of the above apply, the Engineer will make an equitable adjustment.
- **(b) Significant Changed Work** If the changes made under 00140.30 significantly alter the character, unit cost, or lump sum cost of the Work, the Agency will adjust the Contract. Adjustments will exclude any loss of anticipated profits. The parties shall agree upon the basis for payment and the amount of adjustment prior to the Contractor commencing the Changed Work. If the basis and amount cannot be agreed upon, the Engineer will make an equitable adjustment, which may increase or decrease the Contract Amount and Contract Time.

Any such adjustments may be less than, but will not be more than the amount justified by the Engineer on the basis of the established procedures set out in Section 00197 for determining rates. This does not limit the application of Section 00199.

The term "Significant Changed Work" shall apply only to that circumstance in which the character of the Work, as changed, differs materially in kind, nature, or unit cost from that involved or included in the originally proposed construction.

**00195.30 Differing Site Conditions** - Upon written notification, as required in 00140.40, the Engineer will investigate the identified conditions. If the Engineer determines that the conditions materially differ and cause an increase or decrease in the cost or time required to perform any Work under the Contract, an adjustment in the Contract Amount or Contract Time, excluding loss of anticipated profits, will be made, and the Contract modified accordingly, in writing. The Engineer will notify the Contractor as to whether or not an adjustment of the Contract is warranted.

No Contract adjustment which benefits the Contractor will be allowed unless the Contractor has provided the required written notice. Any such adjustments will be made according to 00195.20.

**00195.40 Unreasonable Delay by the Agency** - If the Contractor believes that performance of all or any portion of the Work is suspended, delayed, or interrupted for an unreasonable period of time in excess of that originally anticipated or customary in the construction industry, due to acts or omissions of the Agency, or persons acting for the Agency, and that additional compensation, Contract Time, or both, are due the Contractor because of the suspension, delay or interruption, the Contractor shall immediately file a written notice of delay according to 00180.60. The Contractor shall then promptly submit a properly supported request for any additional compensation, Contract Time, or both, according to the applicable provisions in 00180.60 through 00180.80 and Section 00199.

The Engineer will promptly evaluate a properly submitted request for additional compensation. If the Engineer determines that the delay was unreasonable, and that the cost required for the Contractor to perform the Contract has increased as a result of the unreasonable suspension, delay or interruption, the Engineer will make an equitable adjustment, excluding profit, and modify the Contract in writing accordingly. The Engineer will notify the Contractor of the determination and whether an adjustment to the Contract is warranted.

Under this provision, no Contract adjustment will be allowed:

- Unless the Contractor has provided the written notice required by 00180.60;
- For costs incurred more than 10 Calendar Days before the Engineer receives the Contractor's properly submitted written request;
- For any portion of a delay that the Engineer deems to be a reasonable delay, or for which an
  adjustment is provided for or excluded under other terms of the Contract; or
- To the extent that performance would nevertheless have been suspended, delayed or interrupted by causes other than those described in this Subsection.

### 00195.50 Progress Payments and Retained Amounts:

(a) Progress Payments - The Agency's payment of progress payments, or determination of satisfactory completion of Pay Items or Work or release of retainage under 00195.50(d), shall not be construed as Final Acceptance or approval of any part of the Work, and shall not relieve the Contractor of responsibility for defective Materials or workmanship or for latent defects and warranty obligations.

The estimates upon which progress payments are based are not represented to be accurate estimates. All estimated quantities are subject to correction in the final estimate. If the Contractor uses these estimates as a basis for making payments to Subcontractors and Suppliers, the Contractor assumes all risk and bears any losses that result.

If the estimated amount due the Contractor for any given month is less than \$1,000, the Agency will make no payment for that month unless requested by the Contractor.

(1) Progress Estimates - At a regular period each month to be determined at the Preconstruction Conference, the Contractor will make an estimate of the amount and value of pay item work completed and in place. This estimate shall indicate pertinent County contract and purchase order numbers, be signed and shall be submitted to the Engineer or Project Manager for review and approval. The amount of Work completed will be documented and will be the sum of the estimated number of units completed for unit price Pay Items plus the estimated percentage completed of lump sum Pay Items.

The estimated value of the Work completed will then be determined by using the Contract unit price for unit price Pay Items, and by using one of the following methods to determine the value of the lump sum Pay Items:

- The "theoretical unit price", when the Special Provisions contain an estimated number of units;
- A Contractor-submitted, Engineer-approved Schedule of Values, when there is no theoretical unit price available; or
- Engineer's determination, when there is neither an available theoretical unit price, nor an approved, Contractor-submitted Schedule of Values.

The amounts to be allowed for lump sum Pay Items in progress payments will not exceed the reasonable value of the Work performed, as determined by the Engineer.

Incidentals such as formwork, falsework, shoring, and cribbing shall be included in the unit prices for the various Pay Items requiring their use, unless specified as a separate Pay Item. No payment will be made for Pay Items that include Incidentals until units or portions of such Pay Item Work are in place and completed. The costs of Incidentals will be paid in proportion to the percentage of Pay Item Work completed.

- (2) Value of Materials on Hand The Contractor will make an estimate of the amount and value of acceptable material to be incorporated in the completed work which has been delivered and stored as given in 00195.60(a) for review and approval.
- (3) Value of Work Accomplished The sum of the values in (1) and (2) above will be collectively referred to in this Subsection as the "value of Work accomplished", subject to (4) below.
- (4) Limitations on Value of Work Accomplished In determining the "value of Work accomplished", the Contractor's reviewed estimate will be based on the unit prices for the various Pay Items. Any amounts not included in progress payments due to substantial mathematical unbalancing of Pay Item prices will be included in the final payment issued according to 00195.90(b).
- **(5) Reductions to Progress Payments** With each progress payment, the Contractor will receive a Contract payment voucher and summary setting forth the value of Work accomplished reduced by the following:

- Amounts previously paid;
- Amounts deductible or owed to the Agency for any cause specified in the Contract;
- Additional amounts retained to protect the Agency's interests according to Subsection (e) below.
- **(b)** Retainage The Agency reserves the right in its sole discretion to not withhold retainage from progress payments or to begin withholding retainage at any time. If the Agency withholds retainage from progress payments, the amount to be retained from progress payments will be 5.0% of the value of Work accomplished, and will be retained in one of the forms specified in Subsection (c) below. No retainage will be withheld from Work performed as Force Account Work, escalation/deescalation, bonuses, or other items decided by the Agency.

As provided in 00170.65(b)(3) in addition to any retainage, a withholding of 25% of amounts earned will be withheld and released according to ORS 279C.845 when the Contractor fails to file the certified statements required in ORS 279C.845, FHWA Form 1273, and 00170.65.

- (c) Forms of Retainage If the Agency withholds retainage, forms of acceptable retainage are specified below in Subsections (1) through (3). Unless the Contractor requests and the Agency accepts a form of retainage under Subsections (2) or (3), the Agency will use the "Cash, Alternate A" in this Subsection. If the Agency incurs additional costs as a result of the Contractor's election to use a form of retainage other than Cash, Alternate A, the Agency may recover such costs from the Contractor by a reduction of the final payment.
  - (1) Cash, Alternate A Retainage will be deducted from progress payments and held by the Agency until final payment is made according to 00195.90, unless otherwise specified in the Contract.

Except as otherwise provided, the Agency will deposit the cash retainage withheld in an interest-bearing escrow account as required by ORS 279C.570(2). The Contractor shall execute such documentation and instructions respecting the interest-bearing escrow account as the Agency may require to protect its interests, including but not limited to a provision that no funds may be paid from the account to anyone without the Agency's advance written authorization. Interest earned on the account shall accrue to the Contractor. Amounts retained and interest earned will be included in the final payment made according to 00195.90, unless otherwise specified in the Contract.

For a contract over \$500,000, if the Contractor requests that the Agency deposit the retainage in an interest-bearing account under ORS 279C.560(5), the Agency will use the "Cash, Alternate A" in this Subsection. For a contract \$500,000 or less, if the Contractor requests that the Agency deposit the retainage in an interest-bearing account under ORS 279C.560(5), the Agency will use an interest-bearing account (in a bank, savings bank, trust company, or savings association) as provided under ORS 279C.560(5).

Any retainage withheld on Work performed by a Subcontractor will be released to the Contractor according to 00195.50(d).

(2) Cash, Alternate B (Retainage Surety Bond) - Upon receipt of an approved retainage surety bond, the Agency will limit the amount of cash retainage withheld to \$10,000, which will be deposited in an interest-bearing escrow account as described in (1) above. The surety bond must be in the bond form provided by the Agency. The bond must be provided by the same Surety that provides the Performance and Payment Bonds.

If the Contractor elects this form of retainage, the Agency will withhold from progress payments up to 5% of the value of the Work accomplished as cash retainage until the retained amount equals \$10,000. After that amount is retained, no further cash retainage will be withheld until the additional required retainage that would have been withheld exceeds the face amount of the retainage surety bond provided. Thereafter, retainage will be withheld from progress payments according to these Specifications. According to 00195.50(b), if at any time the Agency determines that satisfactory progress is not being made on the Work, the Agency may withhold up to 5% of the value of the Work accomplished from subsequent progress payments.

If an acceptable retainage surety bond is provided, the Contractor shall notify all Subcontractors of the existence of the retainage surety bond and shall advise them of their rights under ORS 279C.560(7) and ORS 701.435.

Amounts retained and interest earned will be included in the final payment made according to 00195.90, unless otherwise specified in the Contract.

Any retainage withheld on Work performed by a Subcontractor shall be released to the Contractor according to 00195.50(d).

(3) Bonds, Securities, and Other Instruments - In accordance with ORS 279C.560, unless the Agency finds in writing that accepting a bond, security or other instrument poses an extraordinary risk that is not typically associated with the bond, security or other instrument, the Agency will approve the Contractor's written request to deposit bonds, securities or other instruments with the Agency or in a custodial account or other account satisfactory to the Agency with an approved bank or trust company, to be held instead of cash retainage for the benefit of the Agency. In such event, the Agency will reduce the cash retainage by an amount equal to the value of the bonds, securities and other instruments. Interest or earnings on the bonds, securities and other instruments shall accrue to the Contractor.

Bonds, securities and other instruments deposited instead of cash retainage shall be assigned to or made payable to the Agency and shall be of a kind approved by the Director of the Oregon Department of Administrative Services, including, but not limited to:

- · Bills, certificates, notes or bonds of the United States;
- Other obligations of the United States or agencies of the United States:
- Obligations of a corporation wholly owned by the federal government;
- · Indebtedness of the Federal National Mortgage Association;
- General obligation bonds of the State of Oregon or a political subdivision of the State of Oregon;
- Irrevocable letters of credit issued by an insured institution, as defined in ORS 706.008.

The Contractor shall execute and provide such documentation and instructions respecting the bonds, securities and other instruments as the Agency may require to protect its interests. When the Engineer determines that all requirements for the protection of the Agency's interest have been fulfilled, the bonds and securities deposited instead of cash retainage will be released to the Contractor.

(d) Release of Retainage - As the Work progresses, release of the amounts to be retained under (b) of this Subsection will only be considered for Pay Items that have been satisfactorily completed. For purposes of this Subsection, a Pay Item will be considered satisfactorily completed only if all of the Work for the Pay Item is complete and all contractual requirements pertaining to the Pay Item and Work have been satisfied. Work not included in a Pay Item, or which constitutes part of an

uncompleted Pay Item, will not be regarded as satisfactorily completed Work for the purposes of this Subsection.

When the Work is 50% completed and upon written application of the Contractor and written approval of the Surety, the Engineer or Project Manager may reduce or eliminate retainage on remaining progress payments if the Work is progressing satisfactorily. If retainage has been reduced or eliminated, the Agency reserves the right to protect its interests by retaining amounts from further progress payments at the rates provided in 00195.50(b).

A determination of satisfactory completion of Pay Items or Work or release of retainage shall not be construed as acceptance or approval of the Work and shall not relieve the Contractor of responsibility for defective Materials or workmanship or for latent defects and warranty obligations.

The Contractor shall comply with all applicable legal requirements for withholding and releasing retainage and for prompt payments, including but not limited to those in ORS Chapters 279C and 701, and 49 CFR 26.29.

- **(e) Withholding Payments** The Engineer may withhold such amounts from progress payments or final payment as may reasonably protect the Agency's interests until the Contractor has:
  - Complied with all orders and directives issued by the Engineer under or pursuant to the Contract;
    - Corrected or cured its failure to comply with the Contract;
  - Satisfied all legal actions filed against the Agency, the Agency's governing body and its members, and Agency employees that the Contractor is obliged to defend. (See 00170.72.)

Notwithstanding ORS 279C.555 or ORS 279C.570 or 00195.50(d), if a Contractor is required to file statements on the prevailing rate of wages, but fails to do so, the Agency will withhold 25% of any amount earned as required in 00170.65.

**(f) Prompt Payment Policy** - Payments shall be made promptly according to ORS 279C.570, ORS 279C.580 and other applicable legal requirements.

#### 00195.60 Advance Allowance for Materials on Hand:

- (a) General If the total value of Materials on hand is at least \$1,000, or the total value of a single class of Materials on hand is at least \$500, the Engineer may authorize an advance allowance for the Materials in the progress payments. The Agency will not make advance allowances on the Materials unless the following three conditions are satisfied:
  - (1) Request for Advance Allowance If Materials on hand meet the requirement of (2) below, an advance allowance will be made if:
    - A written request for advance allowance for Materials on hand has been received by the Engineer at least 5 Calendar Days before the pay period cutoff date; and
    - The request is accompanied by written consent of the Contractor's Surety, if required by the Agency.
  - **(2) Stored or Stockpiled Conditions** The Materials shall have been delivered and/or acceptably stored or stockpiled according to the Specifications and as follows:
    - · At the Project Site;

- On Agency-owned property;
- On property in the State of Oregon on which the property owner has authorized storage in writing. The written authorization must allow the Agency to enter upon the property and remove Materials for at least 6 months after completion of the Project. The Contractor shall furnish a copy of the written permission to the Agency; or
- On property outside the State of Oregon on which the property owner has authorized storage in writing, provided that such storage location is allowed by the Special Provisions or authorized in writing by the Engineer. The permit must allow the Agency to enter upon the property and remove Materials for at least 6 months after completion of the Project. The Contractor shall furnish a copy of the written permission to the Agency.

To be eligible for advance allowance, the Materials shall:

- Meet Specification requirements;
- Have the required Materials conformance and quality compliance documents on file with the Engineer (see Section 00165);
- · Be in a form ready for incorporation into the permanent Work; and
- Be clearly marked and identified as being specifically fabricated, or produced, and reserved for use on the Project.
- (3) Responsibility for Protection The Contractor has full control and responsibility for the protection of Materials on hand from the elements and against damage, loss, theft, or other impairment until the entire Project has been completed and accepted by the Agency.

If Materials are damaged, lost, stolen, or otherwise impaired while stored, the monetary value advanced for them, if any, will be deducted from the next progress payment.

If these conditions in 00195.60(a)(1) through 00195.60(a)(3) have been satisfied, the amount of advance allowance, less the retainage described in 00195.50, will be determined by one of the following methods as elected by the Engineer:

- Net cost to the Contractor of the Materials, f.o.b. the Project Site or other approved site; or
- Price (or portion of it attributable to the Materials), less the cost of incorporating the Materials into the Project, as estimated by the Engineer.
- **(b) Proof of Payment** The Contractor shall provide the Engineer with proof of payment to the materials Suppliers for purchased Materials within 30 Calendar Days of the date of the progress payment that includes the advance allowance.

If proof of payment is not provided, sums advanced will be deducted from future progress payments, and the Engineer will not approve further prepayment advance allowance requests.

**(c) Terminated Contract** - If the Contract is terminated, the Contractor shall provide the Agency immediate possession of all Materials for which advance allowances have been received, as provided above. If, for any reason, immediate possession of the Materials cannot be provided, the Contractor shall immediately refund to the Agency the total amount advanced for the Materials. The Agency may deduct any amount not so refunded from final payment.

**00195.70 Payment under Terminated Contract** - Payment for Work performed under a Contract that is terminated according to the provisions of 00180.90 will be determined under (a) or (b) of this Subsection.

(a) Termination for Default - Upon termination of the Contract for the Contractor's default, the Agency will make no further payment until the Project has been completed. The Agency will make progress payments to the party to whom the Contract is assigned, but may withhold an amount sufficient to cover anticipated Agency costs, as determined by the Engineer, to complete the Project.

Upon completion of the Project, the Engineer will determine the total amount that the defaulting Contractor would have been entitled to receive for the Work, under the terms of the Contract, had the Contractor completed the Work (the "cost of the completed Work").

If the cost of the completed Work, less the sum of all amounts previously paid to the Contractor, exceeds the expense incurred by the Agency in completing the Work, including, without limitation, expense for additional managerial and administrative services, the Agency will pay the excess to the Contractor, subject to the consent of the Contractor's Surety.

If the expense incurred by the Agency in completing the Work exceeds the Contract Amount, the Contractor or the Contractor's Surety shall pay to the Agency the amount of the excess expense.

The Engineer will determine the expense incurred by the Agency and the total amount of Agency damage resulting from the Contractor's default. That determination will be final as provided in 00150.00.

If a termination for default is determined by a court of competent jurisdiction to be unjustified, it shall be deemed a termination for public convenience, and payment to the Contractor will be made as provided in Subsection (b) below.

## (b) Termination for Public Convenience:

- (1) General Full or partial termination of the Contract shall not relieve the Contractor of responsibility for completed or performed Work, or relieve the Contractor's Surety of the obligation for any just claims arising from the completed or performed Work.
- **(2) Mobilization** If mobilization is not a separate Pay Item, and payment is not otherwise provided for under the Contract, the Agency may pay the Contractor for mobilization expenses, including moving Equipment to and from the Project Site. If allowed, payment of mobilization expenses will be based on cost documentation submitted by the Contractor to the Engineer.
- (3) All Other Work The Agency will pay the Contractor at the unit price for the number of Pay Item units of completed, accepted Work. For units of Pay Items partially completed, payment will be as mutually agreed, or, if not agreed, as the Engineer determines to be fair and equitable. No claim for loss of anticipated profits will be allowed. The Agency will purchase Materials left on hand according to 00195.80.

#### 00195.80 Allowance for Materials Left on Hand:

(a) Purchase of Unused Materials - If Materials are delivered to the Project Site, or otherwise acceptably stored at the order of the Engineer, but not incorporated into the Work due to complete or partial elimination of Pay Items, changes in Plans, or termination of the Contract for public convenience according to 00180.90, and it is not commercially feasible for the Contractor to return them for credit or otherwise dispose of them on the open market; the Agency will purchase them according to the formula and conditions specified in Subsection (b) below.

#### (b) Purchase Formula and Conditions:

(1) Formula - The Agency will apply the following formula in determining the Contractor's allowance for Materials left on hand:

Contractor's Actual Cost, plus 5% Overhead Allowance, minus Advance Allowances under 00195.60, but no markup or profit.

- **(2) Conditions** The Agency will not purchase the Contractor's Materials left on hand unless the Contractor satisfies the following conditions:
  - Requests the Agency's purchase of unused Materials;
  - Shows acquisition of the Materials according to 00160.10;
  - Shows that the Materials were acquired prior to the Agency change or termination;
  - · Shows that the Materials meet Specifications; and
  - Provides receipts, bills and other records of actual cost of Materials delivered to the designated delivery points.

#### 00195.90 Final Payment:

- (a) Final Estimate As soon as practicable after Final Inspection of the Project, as provided in 00150.90, the Engineer will prepare a final estimate of the quantities of the Pay Items completed. With this estimate of quantities as a base, the total amount due the Contractor will be determined according to the terms of the Contract, including, without limitation, any amounts due for Extra Work performed.
- **(b) Final Payment** The amount of final payment will be the difference between the total amount due the Contractor and the sum of all payments previously made. All prior partial estimates and payments shall be subject to correction in the final estimate and payment.

After computation of the final amount due, and after Final Acceptance of the Project, final payment will be mailed to the Contractor's last known address as shown in the records of the Agency.

Beginning 30 Calendar Days after the date of Third Notification, interest will begin to accrue at the rate established by ORS 279C.570 on any money due and payable to the Contractor as final payment, determined as described above. No interest will be paid on money withheld due to outstanding amounts owed by the Contractor under the provisions of 00170.10.

- **(c) No Waiver of Right to Make Adjustment** The fact that the Agency has made any measurement, estimate, determination or certification either before or after completion of the Project, Final Acceptance, Agency assumption of possession of the Project Site, determination of satisfactory completion of Pay Items or Work or release of retainage under 00195.50(d) or payment for any part of the Work, shall not prevent either party from:
  - Showing the true amount and character of the Work;
  - Showing that any measurement, estimate, determination or certification is incorrect;
  - Recovering from the other party damages that may have been suffered because the other party failed to comply with the Contract.

#### 00195.95 Error in Final Quantities and Amounts:

(a) Request for Correction of Compensation - If the Contractor believes the quantities and amounts detailed in the final Contract payment youcher, prepared by the Engineer according

to 00195.90, to be incorrect, the Contractor shall submit an itemized statement to the Engineer detailing all proposed corrections.

This statement must be submitted to the Engineer within 90 Calendar Days from the date the voucher was mailed to the Contractor, according to 00195.90(b). Any request for compensation not submitted and supported by an itemized statement within the 90 Calendar Day period will not be paid by the Agency. This does not limit the application of Section 00199.

## (b) Acceptance or Rejection of Request:

- (1) Consideration of Request The Engineer will consider and investigate the Contractor's request for correction of compensation submitted according to 00195.95(a), and will promptly advise the Contractor of acceptance or rejection of the request in full or in part.
- (2) Acceptance of Request If the Engineer accepts the Contractor's request(s) in full or in part, the Engineer will prepare a post-final Contract payment voucher, including all accepted corrections, and will forward it to the Contractor.
- (3) Rejection of Request If the Engineer rejects the request(s) in full, the Engineer will issue a written notice of rejection and mail it to the Contractor.
- (4) Contractor Objection to Revised Voucher or Notice of Rejection If the Contractor disagrees with the revised voucher or notice of rejection, the Contractor may request review according to the procedure specified in 00199.40. If the Contractor fails to submit a request for 00199.40 review within 30 Calendar Days after the Engineer mails a post-final Contract payment voucher or notice of rejection, the Contractor waives all rights to a claim based on errors in quantities and amounts.

If the Engineer rejects the Contractor's request on the basis that the issue was not one that qualified for treatment under this Section, no review according to 00199.40 will be allowed.

#### Section 00196 - Payment for Extra Work

#### Description

**00196.00 General** - Only work not included in the Contract as awarded but deemed by the Engineer or Project Manager to be necessary to complete the Project (see 00140.60) will be paid as Extra Work. Regardless of alterations and changes, any item of Work provided for in the Contract will not constitute Extra Work. Payment for alterations and changes to Work will be made according to 00195.20.

Compensation for Extra Work will be paid only for Work authorized in writing by the Engineer or Project Manager and performed as specified. Work performed before issuance of the Engineer's written authorization shall be at the Contractor's risk. Extra Work will be paid as determined by the Engineer, according to 00196.10 and 00196.20.

## **Provisions and Requirements**

**00196.10 Negotiated Price** - If the Engineer or Project Manager can reasonably determine a price estimate for Extra Work, the Engineer may then give written authorization to the Contractor to begin the Extra Work. As soon as practicable, but within 10 Calendar Days after that authorization, the Contractor shall respond in writing to the Engineer's Extra Work price estimate by submitting to the Engineer an Extra Work price quote. The price quote shall detail the following items related to the Extra Work:

- Types and amounts of Materials
- · Hours of Equipment use and hours of labor
- Travel
- · Overhead and profit
- Other costs associated with the proposed Extra Work

Pending approval of the price quote, the Engineer will maintain force account records of the Extra Work. As soon as practicable, but within 10 Calendar Days of receipt of a properly supported price quote, the Engineer will review the price quote and advise the Contractor if it is accepted or rejected. The Engineer will not accept a price quote that cannot be justified on a Force Account basis. If the Contractor's price is accepted, the Engineer will issue a Change Order, and the Extra Work will be paid at the accepted price.

**00196.20 Force Account** - If the Engineer and the Contractor cannot agree on a price for the Extra Work, the Engineer may issue a Force Account Work order requiring the Extra Work to be paid as Force Account Work. Force Account Work records and payment will be made according to Section 00197.

#### Section 00197 - Payment for Force Account Work

#### **Force Account Work**

**00197.00** Scope - The Materials, Equipment and labor rates and procedures established in this Section apply to Extra Work ordered by the Engineer to be performed as Force Account Work. With the exceptions identified in 00197.01(b), these rates and procedures also apply to other Work when according to other Sections this Section 00197 applies, including, without limitation, the following:

- 00140.70 Cost Reduction Proposals
- 00195.20 Changes to Plans or Character of Work
- 00195.30 Differing Site Conditions
- 00199.30(b) Claims Requirements

#### 00197.01 General:

- (a) Extra Work on a Force Account Basis Before ordering Force Account Work, the Engineer will discuss the proposed work with the Contractor, and will seek the Contractor's comments and advice concerning the formulation of Force Account Work specifications. The Engineer is not bound by the Contractor's comments and advice, and has final authority to:
  - Determine and direct the Materials, Equipment and labor to be used on the approved Force Account Work; and
  - Determine the time of the Contractor's performance of the ordered Force Account Work.

If the Engineer orders the performance of Extra Work as Force Account Work, the Engineer will record, on a daily basis, the Materials, Equipment, labor, and Special Services used for the Force Account Work during that day. The Engineer and the Contractor shall sign the record daily to indicate agreement on the Materials, Equipment, labor, and Special Services used for the Force Account Work performed on that day.

The following shall be reflected on the daily record:

- Materials used in the Force Account Work as directed by the Engineer, except those furnished and paid under rental rates for use of Equipment;
- Equipment that the Engineer considers necessary to perform the Force Account Work. Equipment hours will be recorded to the nearest quarter hour;
- Labor costs, including that of Equipment operators and supervisors in direct charge of the specific operations while engaged in the Force Account Work;
- · Special Services; and
- The Engineer's and Contractor's signatures confirming its accuracy.
- **(b)** Other Work When according to other Sections this Section 00197 applies, the following exceptions apply to the Work under those other Sections, except for Extra Work ordered by the Engineer to be performed as Force Account Work.
  - 00197.01(a) does not apply.
  - Cost Efficiency The Agency will not be responsible for additional costs that are a direct or indirect result of the Contractor's inefficient means and methods or that reasonably could have

been avoided if the Materials, Equipment, labor or services had been obtained at a more commercially reasonable cost.

Standby Time - Equipment that is necessary for the Work but is not being operated to
progress the Work will be considered to be on standby and will be limited to the standby rates
and hour limitations in 00197.20(e). Equipment costs will be limited to a combination of
operating time and standby time of not more than 8 hours in a 24 hour period or 40 hours in
a 1 week period. The Equipment must be onsite and available for use to be eligible for
standby time.

For a period of 7 or fewer Calendar Days: If a continuous period of standby time for a piece of Equipment does not exceed 7 Calendar Days, the accumulated standby cost for that continuous period of standby time shall be limited to the standby rates and hour limitations in 00197.20(e).

For a period of more than 7 Calendar Days: Unless the Engineer has otherwise agreed in advance in writing, if a continuous period of standby time for a piece of Equipment exceeds 7 Calendar Days, the accumulated standby cost shall be limited to:

- For the first 7 Calendar Days, the standby rates and hour limitations in 00197.20(e), and
- For the portion of the continuous period of standby time after the first 7 Calendar Days, the lesser of:
  - The standby rates and hour limitations in 00197.20(e); or
  - The cost for moving that piece of Equipment to and from the Project Site according to 00197.20(d).

#### 00197.10 Materials:

- (a) General The Contractor will be paid for Materials actually used in the Force Account Work as directed by the Engineer, except for those furnished and paid for under rental rates included with the use of Equipment. Payments will be at actual cost, including transportation costs to the specified location, from the supplier to the purchaser, whether the purchaser is the Contractor, a Subcontractor, or other forces. All costs are subject to the provisions of this Subsection.
- **(b) Trade Discount** If a commercial trade discount is offered or available to the purchaser, it shall be credited to the Agency, even though the discount may not have actually been taken. The Agency will not take any discounts for prompt or early payment, whether or not offered or taken.
- **(c) Not Directly Purchased From Supplier** If Materials cannot be obtained by direct purchase from and direct billing by the supplier, the cost shall be considered to be the price billed to the purchaser less commercial trade discounts, as determined by the Engineer, but not more than the purchaser paid for the Materials. No markup other than actual handling costs will be permitted.
- (d) Purchaser-Owned Source If Materials are obtained from a supply or source wholly or partly owned by the purchaser, the cost shall not exceed the price paid by the purchaser for similar Materials furnished from that source on Pay Items, or the current wholesale price for the Materials delivered to the Project Site, whichever is lower.

#### 00197.20 Equipment:

(a) General - Equipment approved by the Engineer to perform the Force Account Work will be eligible for payment at the established rates only during the hours it is operated or on standby if so

ordered by the Engineer. Equipment hours will be recorded on the daily record to the nearest quarter hour.

Except as modified by these provisions, Equipment use approved by the Engineer will be paid at the rental rates given in the most current edition of the EquipmentWatch Cost Recovery (Blue Book) published by EquipmentWatch, a division of Penton Business Media, Inc., and available from EquipmentWatch (phone 1-800-669-3282) (see 00110.05(e) for website).

**(b) Equipment Description** - On the billing form for Equipment costs, the Contractor shall submit to the Engineer sufficient information for each piece of Equipment and its attachments to enable the Engineer to determine the proper rental rate from the Blue Book.

## (c) Rental Rates (without Operator):

(1) Rental Rate Formula - Rental rates for Equipment will be paid on an hourly basis for Equipment and for attachments according to the following formula:

Some attachments are considered "standard Equipment" and are already included in the monthly base rate for the Equipment. That information can be obtained from EquipmentWatch.

- **(2) Monthly Base Rate** The monthly base rate used above for the machinery and for attachments represents the major costs of Equipment ownership, such as depreciation, interest, taxes, insurance, storage, and major repairs.
- (3) Rate Adjustment Factor The rate adjustment factor used above will be determined by applying only the Model Year Adjustment to the Blue Book Rates. The Regional and User Defined Ownership/Operating Adjustments shall not apply.
- **(4) Hourly Operating Rate** The hourly operating rate used above for the machinery and for attachments represents the major costs of Equipment operations, such as fuel and oil, lubrications, field repairs, tires or ground engaging components, and expendable parts.
- (5) Limitations If multiple attachments are included with the rental Equipment, and are not considered "standard Equipment", only the attachment having the higher rental rate will be eligible for payment, provided the attachment has been approved by the Engineer as necessary to the Force Account Work.

Rental will not be allowed for small tools that have a daily rental rate of less than \$5, or for unlisted Equipment that has a fair market value of \$400 or less.

The above rates apply to approved Equipment in good working condition. Equipment not in good working condition, or larger than required to efficiently perform the work, may be rejected by the Engineer or accepted and paid for at reduced rates.

(d) Moving Equipment - If it is necessary to transport Equipment located beyond the Project Site exclusively for Force Account Work, the actual cost to transport the Equipment to, and return it from, its On-Site Work location will be allowed as an additional item of expense. However, the return cost will not exceed the original delivery cost. These costs will not be allowed for Equipment that is brought to the Project Site for Force Account Work if the Equipment is also used on Pay Item or related Work.

If transportation of such Equipment is by common carrier, payment will be made in the amount paid for the freight. No markups will be allowed on common carrier transportation costs. If the Equipment is hauled with the Contractor's own forces, transportation costs will include the rental rate of the hauling unit and the hauling unit operator's wage. If Equipment is transferred under its own power, the rental rate allowed for transportation time will be 75% of the appropriate hourly rate for the Equipment, without attachments, plus the Equipment operator's wage.

- **(e) Standby Time** If ordered by the Engineer, standby time will be paid at 40% of the hourly rental rate calculated according to this Subsection, excluding the hourly operating rate. Rates for standby time that are calculated at less than \$1 per hour will not be paid. Payment will be limited to not more than 8 hours in a 24-hour period or 40 hours in a 1 week period.
- **(f) Blue Book Omissions** If a rental rate has not been established in the Blue Book, the Contractor may:
  - If approved by the Engineer, use the rate of the most similar model found in the Blue Book, considering such characteristics as manufacturer, capacity, horsepower, age and fuel type;
  - Request EquipmentWatch to furnish a written response for a rental rate on the Equipment, which shall be presented to the Engineer for approval; or
  - · Request that the Engineer establish a rental rate.
- (g) Outside Rental Equipment If Contractor-owned or Subcontractor-owned Equipment is not available, and Equipment is rented from outside sources, payment will be based on the actual paid invoice.

If the invoice specifies that rental rate does not include fuel, lubricants, field repairs, and servicing, an amount equal to the Blue Book hourly operating cost may be added for those items that were excluded.

The Agency may reduce the payment when the invoice amount plus allowance is higher than the amount authorized under (c) through (f) of this Subsection.

The provisions of 00180.20(c) apply to owner-operated Equipment.

**00197.30 Labor** - The Contractor will be paid for all labor engaged directly on Force Account Work, including Equipment operators and supervisors in direct charge of the specific force account operations, as follows:

- (a) Wages The actual wages paid to laborers and supervisors, if those wages are paid at rates not more than those for comparable labor currently employed on the Project, or at the recognized, current, prevailing rates in the locality of the Project.
- **(b) Required Contributions** The actual cost of industrial accident insurance, unemployment compensation contributions, payroll transit district taxes, and social security for old age assistance contributions incurred or required under statutory law and these Specifications. The actual cost of industrial accident insurance is the National Council on Compensation Insurance (NCCI) rate for the assigned risk pool for the appropriate work class multiplied by the experience modification factor for the Contractor.
- **(c)** Required Benefits The actual amount paid to, or on behalf of, workers as per diem and travel allowances, health and welfare benefits, pension fund benefits, or other benefits when such other benefits are required by a collective bargaining agreement or other employment contract generally applicable to the classes of labor employed on the Project.

**00197.40 Invoices for Special Services** - Invoices for Special Services that reflect current market pricing may be accepted without complete itemization of Materials, Equipment, and labor costs, if the itemization is impractical or not customary. The invoice for Special Services shall show credit for commercial trade discounts offered or available.

No percentage markup will be allowed other than that specified in 00197.80.

**00197.80 Percentage Allowances** - To the Contractor's actual costs incurred, as limited in this Section 00197, amounts equal to a percentage markup of such costs will be allowed and paid to the Contractor as follows:

Subsection	Percent
00197.10 Materials	17
00197.20 Equipment	17
00197.30 Labor	22
00197.40 Special Services	17

When a Subcontractor performs ordered Force Account Work, the Contractor will be allowed a supplemental markup of 8% on each Force Account Work order.

These allowances made to the Contractor will constitute complete compensation for overhead, general and administrative expense, profit, and all other Force Account Work costs that were incurred by the Contractor, or by other forces that the Contractor furnished. No other reimbursement, compensation, or payment will be made.

**00197.90 Billings** - Billings for Force Account Work by the Contractor shall be submitted for the Engineer's approval on forms provided by the Agency or approved by the Engineer. Billings for Materials (other than Incidental items out of the inventory of the Contractor or Subcontractors), rental Equipment from sources other than the Contractor or Subcontractors, and Special Services, shall be accompanied by copies of invoices for the goods and services. The invoices shall be fully itemized showing dates, quantities, unit prices, and complete descriptions of goods and services provided. Invoices for amounts of \$10 or less per invoice are not required, unless requested by the Engineer.

Costs included on the billings shall comply with 00197.01(a) and 00197.10 through 00197.40.

When a billing for Force Account Work has been paid at the Project level, no further corrections will be made because of further review if those corrections amount to less than \$10.

#### Section 00199 - Disagreements, Protests, and Claims

#### Description

**00199.00 General** - This Section details the process through which the parties agree to resolve any disagreement concerning additional compensation or concerning a combination of additional compensation and Contract Time. (See 00180.80 for disagreements and claims concerning additional Contract Time only, and 00195.95 for disagreements and claims concerning correction of final compensation.) The Agency will not consider direct disagreements, protests, or claims from Subcontractors, Suppliers, or any other Entity not a party to the Contract.

## **Provisions and Requirements**

**00199.10 Procedure** for Resolving Disagreements - When disagreements occur concerning additional compensation or a combination of additional compensation and Contract Time, the Contractor shall first pursue resolution through the Engineer of all issues in the dispute, including, without limitation, the items to be included in the written notice in 00199.20. If the discussion fails to provide satisfactory resolution of the disagreement, the Contractor shall follow the protest procedures outlined in 00199.20. If the Engineer denies all or part of the Contractor's protest, and the Contractor desires to further pursue the issues, the Contractor shall submit a claim for processing according to 00199.30.

**Inappropriate Protest or Claim -** It shall be presumed that the Contractor submits a protest or claim for additional compensation in good faith, based upon facts which reasonably support the Contractor's position and with full knowledge and understanding of the injury done to the Agency when notice of differing Project Site conditions or claims for additional compensation are not submitted in a timely manner as required under the Contract. Accordingly, the submission of a protest or claim without the concurrent submission of evidence that reasonably supports the protest or claim, or the submission of a protest or claim in an untimely manner will constitute a waiver of the protest or claim.

**00199.20 Protest Procedure** - If the Contractor disagrees with anything required in a Change Order or other written or oral order from the Engineer, including any direction, instruction, interpretation, or determination, or if the Contractor asserts a disagreement or dispute on any other basis, except 0195.95, that, in the Contractor's opinion, entitles or would entitle the Contractor to additional compensation or a combination of compensation and Contract Time, the Contractor shall do all of the following in order to pursue a protest and preserve its claim:

- (a) Oral Notice Give oral notice of protest to the Engineer and outline the areas of disagreement before starting or continuing the protested Work.
- **(b)** Written Confirmation of Oral Notice Not later than the end of the next business day following the day that oral notice of protest is given, deliver written documentation to the Engineer of the oral notice that includes the notice of protest and the areas of disagreement.
- (c) Written Notice File a proper written notice of protest with the Engineer within 7 Calendar Days after receiving the protested order. In the notice the Contractor shall:
  - Describe the acts or omissions of the Agency or its agents that allegedly caused or may cause damage to the Contractor or to the Project, citing specific facts, persons, dates and Work involved;
  - Describe the Contractor's proposed alternative to the Work ordered, if any, which will avoid damage to Contractor or to the Project;
  - · Describe the nature of the damages;
  - Cite the specific Contract provision(s), if any, that support the protest;
  - Include the estimated dollar cost, if any, of the protested Work, and furnish a list of estimated Materials,
     Equipment and labor for which the Contractor might request additional compensation; and
  - If additional compensation is estimated to be due, include the estimated amount of additional time required, if any.

FAILURE TO COMPLY WITH THIS NOTICE REQUIREMENT RENDERS THE NOTICE IMPROPER AND SHALL CONSTITUTE A WAIVER OF ANY CLAIM FOR ADDITIONAL COMPENSATION OR A COMBINATION OF ADDITIONAL COMPENSATION AND CONTRACT TIME FOR ANY PART OF THE PROTESTED WORK.

(d) Engineer's Record and Response – The Engineer will file a copy of each written notice of protest in the Project records and will issue a written response to the protest within fourteen (14) business days of receipt of a

timely filed written notice of protest. The Engineer has no responsibility to evaluate the protest unless the Contractor has timely filed a proper notice submitting all of the above information.

- **(e) Final Documentation of Claim -** Within 45 Calendar Days following completion of the protested work, Contractor shall provide the Engineer with complete documentation of protested work, listing exact materials, equipment and labor used for the work and the dollar amount requested for each. If the claim is accepted, no additional compensation will be awarded based on documentation submitted after this deadline. If the claim is denied or if the Contractor is not satisfied with the decision by the Engineer, the amount claimed by the Contractor in any subsequent Step or proceeding may not exceed the dollar amount requested under this subsection.
- **(f)** Records Contractor must keep complete records of all costs and time incurred throughout the protested Work, and allow the Engineer access to those and other supporting records. Provide daily records of protested Work, on a weekly basis, on a schedule to be set by agreement with the Engineer.
- (g) Comparison of Records Provide the Engineer adequate facilities for keeping cost and time records of the protested Work. The Contractor and the Engineer will compare records and either bring them into agreement at the end of each day, or record and attempt to explain any differences.
- (h) Work to Proceed In spite of any protest, proceed promptly with the Work ordered by the Engineer.
- (i) Evaluation of Protest The Engineer has no responsibility for evaluating a protest that is not timely filed, or for which adequate supporting documentation has not been made available to the Engineer. Provided the procedures above are followed, the Engineer will promptly evaluate all protests, after the Contractor has fully complied with the requirements described in 00199.20(c), Written Notice. If the protest is denied, the Engineer will notify the Contractor in writing of the reasons for full or partial denial. If a protest is found to be valid, the Engineer will, within a reasonable time, make an equitable adjustment of the Contract. Adjustment of time will be evaluated according to 00180.80.

The Engineer has no responsibility for evaluating and may reject a protest that does not comply with 00199.20(b). If the protest is rejected, the Engineer will notify the Contractor in writing of the reasons for rejection.

(j) Protest Evaluation by Third Party Neutral - If the Engineer agrees that the Contractor has fully complied with the requirements described in 00199.20(b), and if the Engineer fully or partially denies, in writing, the Contractor's protest according to 00199.20(f), the Contractor may request that a mutually selected Third Party Neutral review the protest. Procedures for selecting, using, and paying for the cost of the Third Party Neutral will be specified by Change Order.

If the Contractor does not accept the Engineer's evaluation of the protest, or either the Contractor or Engineer disagrees with the resolution recommended by the Third Party Neutral, the Contractor may pursue a claim as described in 00199.30.

## 00199.30 Claims Procedure:

**(a) General** - If the Contractor believes that additional compensation is due, or a combination of additional compensation and Contract Time, and has pursued and exhausted all the procedures provided in 00199.10 and 00199.20 to resolve a disagreement and protest, the Contractor may file a claim.

The Agency's Contract is with the Contractor. There is no contractual relationship between the Agency and any Subcontractors, Suppliers or any Entity other than the Contractor. It is the Contractor's responsibility to fully evaluate any claim before presenting it to the Agency. In addition, when a claim includes Work done or costs incurred by any Subcontractors, Suppliers, or any Entity other than the Contractor, the Contractor remains solely responsible for presenting the claim to the Agency.

Claims that include Work done or costs incurred by any Subcontractors, Suppliers, or any Entity other than the Contractor will not be considered by the Agency unless the Contractor has:

- Completed and provided its own written evaluation of the claim;
- · Verified by its own independent review and evaluation of the amount of compensation sought; and
- · Certified the claim according to 00199.30(b) (Part 10).
- **(b) Claims Requirements** At any time during the progress of the Work, but not later than 45 Calendar Days following the date of the Second Notification, the Contractor shall submit to the Engineer in writing, claims for

additional compensation or a combination of additional compensation and Contract Time additional to that specified in the Contract. For a claim not submitted within the 45-day limit, that has not met the requirements of 00199.20, or is not filed as provided in 00199.30, the Contractor waives any claim for additional compensation or for additional compensation and Contract Time, and the Agency may reject the claim.

Written claims to the Engineer or the Agency by the Contractor shall be delivered to the Agency address shown in the Special Provisions, unless a different address is agreed to by the Engineer, and shall be delivered:

- By U.S. Postal Service first class mail or priority mail (which at the sender's option may include certified or registered mail return receipt requested); or
- By overnight delivery service of a private industry courier.

Claims will be considered as having been received by the Agency:

- At the time of actual receipt or 7 Calendar Days after the postmarked date when deposited for delivery by first class or priority mail, whichever is earlier; or
- At the time of actual receipt or 3 Calendar Days after deposit with a private industry courier for overnight delivery service, whichever is earlier.

The Agency reserves the right at any time and at any step in the claim decision or review process to request additional information, records or documentation related to the claim or the Contract either directly or through agents working toward resolution of the disputed or claimed events and issues.

Claims shall be made in writing, and shall include all information, records and documentation necessary for the Agency to properly and completely evaluate the claim.

To be considered, claims for additional compensation, or for additional compensation and Contract Time, shall be completed according to 00199.30 and shall be submitted with the required information and in the format below and labeled as required below for each claimed issue:

(Part 1) Summary (label page 1.1 through page 1.X) - In the summary, include a detailed, factual statement of the claim for additional compensation and Contract Time, if any, with necessary dates and locations of Work involved in the claim and the dates of when the event arose. Also include detailed facts supporting the Contractor's position relative to the Engineer's decision (see 00199.20(f));

(Part 2) Proof of notice (label page 2.1 through page 2.X) - Submit a copy of the written notice, with all attachments, that was given to the Agency. Include the date when that written notice and the date when oral notice was given:

(Part 3) Copies of the Contract Specifications that support the Contractor's claim (label page 3.1 through page 3.X);

(Part 4) Theory of entitlement supporting the claim (label page 4.1 through page 4.X) - Include a narrative of how or why the specific Contract Specifications support the claim and a statement of the reasons why such Specifications support the claim;

(Part 5) Itemized list of claimed amounts (label page 5.1 through page 5.X) - Claimed damages that resulted from the event with a narrative of the theories and records and documents used to arrive at the value of the damages;

(Part 6) Additional Contract Time requests (label page 6.1 through page 6.X) - If the claim is for a combination of additional compensation and Contract Time, submit a copy of the schedule that was in effect when the event occurred and a detailed narrative which explains how the event impacted Contract Time. In addition, if an Agency-caused delay is claimed:

- Include the specific days and dates under claim;
- Provide detailed facts about the specific acts or omissions of the Agency that allegedly caused the delay, and the specific reasons why the resulting delay was unreasonable; and
- · Provide a schedule evaluation that accurately describes the impacts of the claimed delay.

Also see 00180.80 for additional requirements regarding claims for Contract Time and causes that are eligible and ineligible for consideration;

(Part 7) Copies of actual expense records (label page 7.1 through page 7.X) - Include documents that contain the detailed records and which support and total to the exact amount of additional compensation sought. Include the information and calculations necessary to support that amount. That amount may be calculated on the basis of Section 00197, if applicable, or may be calculated using direct and indirect costs presented in the following categories:

- Direct Materials;
- Direct Equipment. The rate claimed for each piece of Equipment shall not exceed the actual cost. In the
  absence of actual Equipment costs, the Equipment rates shall not exceed 75 percent of those calculated
  under the provisions of 00197.20. For each piece of Equipment, the Contractor shall include a detailed
  description of the Equipment and attachments, specific days and dates of use or standby, and specific hours
  of use or standby;
- · Direct labor:
- · Job overhead:
- General and administrative overhead; and
- · Other categories as specified by the Contractor or the Agency;

(Part 8) Supporting records and documents (label page 8.1 through page 8.X) - Include copies of, or excerpts from the following:

- Any documents that support the claim, such as manuals standard to the industry and used by the Contractor; and
- Any daily reports or diaries related to the event, photographs or media that help explain the issue or event (optional), or all other information the Contractor chooses to provide (optional);

(Part 9) Certification (label page 9.1 through 9.X) - A certified statement, signed by a person authorized to execute Change Orders, by the Contractor, Subcontractor, Supplier, or Entity, originating the claim, as to the validity of facts and costs with the following certification:

Under penalty of law for perjury or falsification, the undersigned, (Name), (Title), (Company) certifies that this

claim for additional compensation for Work on the Contrathe amount of \$, exclusive of interest) and is followween the parties.	•
Signature:	
Date:, 20	
Subscribed and sworn before me this day of	, 20
Notary Public	
My commission expires	

(Part 10) Contractor evaluation of a lower-tier claim (label page 10.1 through 10.X) - If the claim includes Work done or costs incurred by any Subcontractors, Suppliers, or any Entity other than the Contractor, the following are required:

- Data required by the other Subsections of 00199.30(b);
- Copies of the Contractor's, Subcontractor's, Supplier's and Entity's, at all tiers above the level of which the claim originates, separate evaluation of entitlement;
- Copies of the Contractor's, Subcontractor's, Supplier's and Entity's, at all tiers above the level of which the claim originates, independent verification and evaluation of the amount of damages sought; and
- A person authorized to execute Change Orders on behalf of the Contractor, Subcontractor, Supplier and Entity, at all tiers above the level of which the claim originates, must sign a statement with the following certification:

Under	penalty	ot law	tor	perjury	or	talsification,	the	undersigned,
(Name)	(Title), (Co	ompany) c	ertifies th	at this clain	n origin	ating from the	Subcontr	actor, Supplier
or Entity_	(Company)	for additiona	al compen	sation for W	ork on	the Contract is	a reasona	able statement,
independ	dently verifie	d, of the cos	sts incurre	ed (in the an	nount c	of \$, e	exclusive o	of interest) and
is fully do	ocumented a	and supporte	ed under t	he Contract	betwe	en the parties.		
Signatur	e:							
Date:		. 2	0					
		,						
Subscrib	ed and swor	rn before me	e this	_ day of		, 20_	_	
Noton, D	Dublia							
Notary P	rublic							
My comr	mission expii	'es						

If the Engineer determines that additional information, records or documentation is needed to allow proper evaluation of the claim submittal, the Engineer will request the information, records or documentation. The Contractor shall submit to the Engineer within 14 Calendar Days, or as otherwise agreed by the parties, the required additional information, records and documentation.

If the Engineer determines that the claim submittal with the additional information, records and documentation submitted is incomplete and not accepted as a claim, the Engineer will notify the Contractor in writing and the submittal will be rejected and will not be considered under 00199.40.

- (c) Records Requirements The Contractor shall comply with 00170.07.
- **(d) Compliance Required** Full compliance by the Contractor with the provisions of this Section is a condition precedent to the commencement of any lawsuit by the Contractor to enforce any claim.

#### 00199.40 Claim Review Procedure

(a) Engineer Claim Review - The Engineer or Project Manager will, as soon as practicable, consider and investigate a Contractor's properly submitted claim for additional compensation, Contract Time, or for a combination of additional compensation and Contract Time. Once the Engineer or Project Manager determines the Agency is in receipt of a properly submitted claim, the Engineer or Project Manager will arrange a meeting, within 28 Calendar Days, or as otherwise agreed by the parties, with the Contractor in order to present the claim for formal review and discussion. A person authorized by the Contractor to execute Change Orders on behalf of the Contractor must be present and attend all claim meetings.

If the Engineer or Project Manager determines that the Contractor must furnish additional information, records, or documentation to allow proper evaluation of the claim, the Engineer will schedule a second meeting, to be held within 14 calendar days, or as otherwise agreed by the parties, at which the Contractor shall present the requested information, records and documentation.

The Engineer or Project Manager will advise the Contractor of the decision to accept or reject the claim. If the Engineer or Project Manager finds the claim has merit, an equitable adjustment will be offered. If the Engineer or Project Manager finds the claim has no merit, no offer of adjustment will be made and the claim will be denied. The County intends to resolve claims at the lowest possible level.

If, at any step in the claim decision or review process, the Contractor fails to promptly submit requested information or documentation that the Agency deems necessary to analyze the claim, the Contractor is deemed to have waived its right to further review, and the claim will not be considered properly filed and preserved.

If the Engineer or Project Manager has denied a claim, in full or in part, for Contract Time only according to 00180.80, or has denied a claim, in full or in part, for correction of final compensation according to 00195.95, those disputed claims may then be resolved, in full or in part, at either of the two progressive steps of claim review procedure as specified in this Subsection. For all claims, all of the actions and review under each step of the review process shall occur before the review can be advanced to the next higher step.

(b) Director Claim Review - Upon request by the Contractor, the Department Director will review the Engineer or Project Manager's decision on the claim and advise the Contractor of the decision in writing. If the Director finds

the claim has merit, and equitable adjustment will be offered. If the Director finds the claim has no merit, no offer of adjustment will be made and the claim will be denied.

Once the Engineer determines the Agency is in receipt of a properly submitted claim, the Engineer will arrange a meeting, within 21 Calendar Days or as otherwise agreed by the parties, with the Contractor in order to present the claim for formal review and discussion.

If the Engineer determines that the Contractor must furnish additional information, records or documentation to allow proper evaluation of the claim, the Engineer will schedule a second meeting, to be held within 14 Calendar Days or as otherwise agreed by the parties, at which the Contractor shall present the requested information, records and documentation.

The Director shall evaluate the claim based on the information provided by the Contractor to the Engineer or Project Manager. However, if the Department Director (or designee) determines that the Contractor must furnish additional information, records or documentation to allow proper evaluation of the claim, the Department Director (or designee) will schedule a meeting, to be held within 14 Calendar Days, or as otherwise agreed by the parties, at which the Contractor shall present the requested information, records and documentation.

The claim is subject to records review, if not all of the records requested by the Department Director (or designee) were furnished. If applicable, advancement of the claim is subject to the provisions regarding waiver and dismissal of the claim or portions of the claim.

The decision of the Department Director shall be the final decision of the Agency.

(c) Commencement of Litigation - If the Contractor does not accept the Director's decision, then the Contractor shall commence any suit or action to collect or enforce any claim filed in accordance with 00199.30 within a period of one (1) year following the mailing of the decision or within one (1) year following the date of "Second Notification", whichever is later. If said suit or action is not commenced in said one (1) year period, the Contractor expressly waives any and all claims for additional compensation and any and all causes of suit or action for the enforcement thereof that he might have had.

The Contractor must follow each step in order, and exhaust all available administrative remedies before resorting to litigation. Litigation of a claim that cannot be resolved through the process described above shall be initiated by filing a complaint in the Clackamas County Circuit Court for the State of Oregon.

In any litigation, the entire text of any order or permit issued by the County or any other governmental or regulatory authority, as well as any documents referenced or incorporated therein by reference, shall be admissible for purposes of Contract interpretation.

The Contract shall not be construed against either party regardless of which party drafted it. Other than as modified by the Contract, the applicable rules of contract construction and evidence shall apply. This Contract shall be governed by and construed according to the laws of the State of Oregon without regard to principles of conflict of laws.

The Contractor shall comply with 00170.00.

# **SECTION 13**

# **SECTION 13**

# Disadvantaged Business Enterprise (DBE) Commitment Requirements DBE Information Page

**DBE Commitment Certification and Utilization Form** 

**Assigned DBE Contract Goal** 

**ODOT DBE Policy Statement** 

**Disadvantaged Business Enterprise Provisions** 

**Equal Employment Opportunity Provisions** 

**Equal Employment Opportunity-Aspirational Target Provisions** 

On-Site Workforce Affirmative Action Requirements for Women and Minorities on Federal-Aid Contracts

Required Contract Provision Federal-Aid Construction Contracts (FHWA 1273)

Reimbursable Federal On-the-Job and Apprenticeship Training

# DISADVANTAGED BUSINESS ENTERPRISE (DBE) COMMITMENT REQUIREMENTS

## 1. DBE Policies, Obligations, Applicabilities, and Authorities

According to 49 CFR Part 26, all ODOT, all Bidders, and all Contractors shall agree to abide by and take all necessary and reasonable steps to comply with the DBE policies, obligations, applicabilities and authorities listed in the Disadvantaged Business Enterprise (DBE) Supplemental Required Contract Provisions.

The "assigned DBE contract goal" for this project is referred to in the project Special Provisions.

## 2. Eligibility Requirements for DBE Participation on Projects

Participation shall be accomplished by including certified DBEs in any part of the Contract work that is necessary to complete the Contract obligation. A certified DBE may participate as a prime Contractor, subcontractor, joint venture, material supplier, material manufacturer, or professional service provider.

Only those firms certified by the State of Oregon Certification Office of Business Inclusion and Diversity (COBID) as a DBE in the types of work selected shall be eligible to fulfill required DBE participation Contract obligations.

## 3. Crediting of DBE Participation Toward Meeting the Assigned DBE Contract Goal

## (a) Crediting of DBE Participation in Bid Submission

Credit toward meeting the assigned DBE contract goal shall be granted only when a listed firm is currently certified by COBID as a DBE. Bidders should not assume that a minority-owned or a woman-owned firm is currently certified by COBID as a DBE firm or that a firm is certified to perform any particular type of work. Bidders are encouraged to verify each DBE firm's certification by:

- 1) requesting a copy of the DBE certification letter from the committed DBE firm and contacting COBID at 503-986-0075 to confirm the firm's current certification status; or
- 2) accessing information on certification and the updated Certification Directory of DBEs by going to the COBID website at <a href="https://www.oregon4biz.com/How-We-Can-Help/COBID/">https://www.oregon4biz.com/How-We-Can-Help/COBID/</a>

For joint ventures, the percentage of DBE participation to be credited toward the assigned DBE contract goal will be determined and approved by ODOT prior to Bid Opening on the basis of information submitted in the joint venture application according to Item No. 6 DBE Participation through Joint Venture.

## (b) Crediting of DBE Participation Subsequent to Contract Award

The total dollar value of and the scope of work for the DBE commitment as shown on the DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM shall be credited toward meeting the assigned DBE contract goal, provided the DBE performs a Commercially Useful Function according to 49 CFR 26.55(c)(1).

## (c) Crediting of DBE Participation through the Use of DBE Manufacturers

The Bidder may count 100% of its expenditure to a DBE manufacturer. According to 49 CFR 26.55(e)(1)(i), a DBE manufacturer is a firm that operates or maintains a factory or establishment that produces on the premises the materials or supplies obtained by the Contractor.

The Bidder may count 100% of its expenditures for a DBE firm that furnishes and places these materials **only if** the DBE firm is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The DBE shall negotiate the cost, arrange delivery of, and pay for the materials and supplies required for the work of its contract. Invoices for materials must be invoiced to the DBE firm and not to the Contractor.

# (d) <u>Crediting of DBE Participation Through Use of DBE Regular Dealers</u>

The Bidder may count only 60% of the committed amount for the cost of supplies and materials from regular dealers toward meeting the assigned DBE contract goal. According to 49 CFR 26.55(e)(2)(i) a DBE regular dealer owns, operates, or maintains a store, warehouse, or other establishment in which the materials or supplies required for the performance of the Contract are bought, kept in stock, and regularly sold to the public in the usual course of business.

No credit will be granted if the Contractor makes a direct payment to a material supplier. However, it will be permissible for a material supplier to invoice the Contractor and the DBE jointly and be paid by the Contractor making remittance to the DBE firm and material supplier jointly, provided such joint payment arrangements received prior written approval from ODOT.

No credit will be granted if the Contractor deducts from the amounts owed to DBE firms for work performed the costs for: (1) materials and service ordered by the DBE firm and used by the DBE in performing its work, (2) purchase price of supplies or materials acquired from the Contractor by the DBE firm and used by the DBE in performing its work, and (3) cost of equipment leased or rented from the Contractor by the DBE firm and used by the DBE in performing its work. Credit shall be withheld where such costs have been deducted from dollar amounts paid to DBE firms for work performed.

## (e) Crediting of DBE Participation through Use of DBE Service Providers

Credit toward meeting the assigned DBE contract goal through use of DBE service providers shall be granted for:

- (1) The fees or commissions charged for providing a BONA FIDE service, such as professional, technical, consultant, or managerial services and assistance in the procurement of essential personnel, facilities, equipment, materials, or supplies required for performance of the Contract, provided that the fee or commission is determined by ODOT to be reasonable and not excessive as compared with fees customarily allowed for similar services.
- (2) The fees charged for delivery of materials and supplies required on a job site (but not the cost of materials and supplies themselves) when the hauler, trucker, or delivery service is not also the manufacturer of or a regular dealer in the materials or supplies. The fee must be reasonable and not excessive as compared with fees customarily allowed for similar services.
- (3) The fees or commissions charged for providing any bonds or insurance specifically required for the performance of the Contract, provided that the fee or commission is determined by ODOT to be reasonable and not excessive as compared with fees customarily allowed for similar services.
- (4) The total dollar value of payments to the DBE for which a Commercially Useful Function was performed in delivering a professional, technical and/or expert service.

# (f) Crediting of DBE Participation Through Use of DBE Owner/Operator Trucking

A DBE owner/operator must own and operate at least one truck and be certified by COBID.

In order for the Contractor or subcontractor to be credited and receive payment for DBE owner/operator trucking participation, a valid agreement that includes or has attached the following information must be submitted to the Engineer:

- (1) Driver's name;
- (2) Copy of driver's license;
- (3) Vehicle identification number;
- (4) Copy of vehicle registration;
- (5) Motor vehicle license plate number;
- (6) Motor Carrier Plate Number;
- (7) Copy of ODOT Motor Carrier 1A Permit;
- (8) Name of owner/operator from the side of the truck; and
- (9) Method of payment (hour, ton or load)

## (g) Crediting of DBE Participation Through Use of DBE Trucking Firms

In order for the Contractor to receive credit and payment for the use of a DBE trucking firm, the trucking firm must be covered by a subcontract or written agreement, and the Engineer must have granted consent to that subcontract or agreement prior to the beginning of the work.

# 4. Documentation of Bidders' Proposed DBE Participation

## (a) DBE Commitment Certification and Utilization Form

DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM shall become a part of the resulting Contract. This certification and utilization form shall be used to determine the Bidder's responsiveness to the DBE requirements.

If the assigned DBE contract goal is greater than zero, the Bidder must complete and sign the DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM. The form must be completed and signed by the Bidder's authorized representative. In Part I of the form, the Bidder shall fill in each committed DBE firm and its corresponding type of work, its capacity, and the subcontract amount, expenditure, fee, or commission. Should the Bidder fail to completely fill out, sign, and submit the form with the bid when the assigned DBE contract goal is greater than zero, the Bidder will be considered non-responsive. The Agency will calculate each DBE amount, total the amount to be applied to the assigned DBE contract goal and calculate the DBE commitment as a percentage of the total bid.

# (b) DBEs Bidding as Prime Contractors

The requirements of section 4(a) will apply to DBE Bidders for a Contract. In determining whether a DBE Bidder for a Contract has met an assigned DBE contract goal, only the work the DBE has committed with its own forces as well as the work that it has committed to be performed by DBE subcontractors, suppliers, or service providers will be counted.

DBEs bidding as prime Contractors shall complete the DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM indicating the percentage of work to be performed by its own forces as well as the work to be performed by other committed DBEs to meet the assigned DBE contract goal.

## (c) DBE Commitment Certification Form Part II - Good Faith Efforts

Should bidders not meet the assigned DBE contract goal for DBE participation, they must demonstrate good faith efforts at the time of bid. ODOT must decide whether the efforts made to obtain DBE participation constituted good faith efforts. ODOT will review the quality and intensity of those efforts. Efforts that are merely superficial are not good faith efforts to meet the assigned DBE contract goal.

The Bidder shall provide additional information regarding good faith efforts per the requirements Part II of the DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM. The Bidder must document the steps taken to obtain DBE participation, which demonstrate good faith efforts, such as those outlined below:

- (1) Evidence that the Bidders attended any pre-solicitation or prebid meetings that were scheduled by ODOT to inform DBEs of contracting and subcontracting or material supply opportunities available on the project;
- (2) Evidence that the Bidder identified and selected specific economically feasible units of the project to be performed by DBEs in order to increase the likelihood of participation by DBEs;
- (3) Evidence that the Bidder advertised in general circulation, trade association, minority and trade oriented, women-focus publication, concerning the subcontracting or supply opportunities;
- (4) Evidence that the Bidder provided written notice to a reasonable number of specific DBEs, identified from the Certification Directory of DBEs for the selected subcontracting of material supply work, in sufficient time to allow the enterprises to participate effectively;
- (5) Evidence that the Bidder followed up initial solicitations of interest by contacting the enterprises to determine with certainty whether the enterprises were interested. This may include the information outlined below:
  - (a) The names, addresses, and telephone numbers of DBEs who were contacted, the dates of initial contact and whether initial solicitations of interest were followed up by contacting the DBEs to determine with certainty whether the DBEs were interested;
  - (b) A description of the information provided to the DBEs regarding the plans and specifications and estimated quantities for portions of the work to be performed;
  - (c) Documentation of each DBE contacted but rejected and the reasons for the rejection.
- (6) Evidence that the Bidder provided interested DBEs with adequate information about the plans, specifications and requirements for the selected subcontracting or material supply work;
- (7) Evidence that the Bidder negotiated in good faith with the enterprises, and did not without justifiable reason reject as unsatisfactory bids prepared by any DBE;
- (8) Evidence that the Bidder advised and made efforts to assist interested DBEs in obtaining bonding, lines of credit, or insurance required by ODOT or contractor;
- (9) Evidence that the Bidder's efforts to obtain DBE participation were reasonably expected to produce a level of participation sufficient to meet the assigned DBE contract goal or requirements of ODOT;
- (10) Evidence that the Bidder used the services of minority community organizations, minority contractor groups, local, state and federal minority business assistance offices and other

organizations identified by the Advocate for Minority, Women, and Emerging Small Business that provide assistance in the recruitment and placement of disadvantaged, minority, or women business enterprises; and

(11) Evidence that the Bidder used the services of ODOT's Supportive Services contractor(s).

## (d) Failure to Comply

All Bidders, including certified DBE prime Bidders, shall submit a completed and signed DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM with its bid when the assigned DBE contract goal is greater than zero.

If the Bidder fails to properly and completely fill out the DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM and/or to provide sufficient evidence of compliance with good faith effort requirements, the bid shall be considered non-responsive and the bid shall be rejected.

#### 5. Contract Award Selection Procedure

In addition to the provisions of Sections 00120 and 00130 of the bid documents, the following items will be considered in determining Contract Award:

- (a) The Award of the Contract will be in the best interest of the State of Oregon and will assure that ODOT meets its commitment to its overall DBE goal.
- (b) If the low Bidder offering a reasonable bid meets or exceeds the assigned DBE contract goal, that Bidder will be considered responsive to the DBE requirement.
- (c) If a DBE's type of work listed on the DBE COMMITMENT CERTIFICATION AND UTILIZATION FORM does not match the type of work for which the DBE is certified by COBID, then the firm's participation on that Contract cannot count toward the assigned DBE contract goal or overall DBE goals. The Bidder will be determined non-responsive unless the Bidder meets or exceeds the assigned DBE contract goal by committing sufficient other work to one or more certified DBE firms with matching types of work, or the Bidder has established sufficient good faith efforts.
- (d) If the low Bidder has not met the assigned DBE contract goal, ODOT will review the documentation regarding its good faith effort activities to determine if the steps taken are satisfactory. If the steps taken are found satisfactory during the review process, that Bidder will be considered responsive to the DBE requirement. If the steps taken are not found satisfactory, the bid will be considered non-responsive to the DBE requirement.
- (e) If the low Bidder is determined to be non-responsive, ODOT, before awarding the Contract, will notify the Bidder in writing within 15 Calendar Days of the Bid Opening. The notification will include the reason for the determination and provide the Bidder an opportunity for administrative reconsideration.

#### Administrative Reconsideration includes:

- (1) The Bidder will have the opportunity to provide written documentation or argument to the Review Committee, consisting of personnel knowledgeable with DBE Program requirements, concerning the issue of whether it met the assigned DBE contract goal or made adequate good faith efforts to do so, within four Calendar Days of the receipt of notification.
- (2) Upon request, the Bidder will have the opportunity to meet in person with the Review Committee, to discuss the issue of whether it met the assigned DBE contract goal or made adequate good faith efforts to do so.

- (3) The Review Committee will make a decision on reconsideration within four Calendar Days after reviewing evidence of Good Faith Efforts.
- (4) The Bidder will be notified in writing by the Review Committee regarding the decision of reconsideration within five Calendar Days of the decision. This notice will explain the basis for finding that the Bidder did or did not meet the assigned DBE contract goal or make adequate good faith efforts to do so.
- (5) The result of the reconsideration process is not administratively appealable to the U.S. Department of Transportation.

## 6. DBE Participation Through Joint Venture

Bidders who plan to bid as a joint venture with a DBE partner must be pre-qualified with the ODOT Procurement Office under the provisions of ORS 279C.430 and Oregon Administrative Rule 731-007-0520 through 731-007-0540. The requirements of 49 CFR 26.55(b) also apply to Bidders bidding as joint ventures. The pre-qualification application must be received by ODOT Procurement Office - Construction Contracts Unit at least 10 days prior to the date of Bid Opening for each individual Contract, and approval given prior to Bid Opening.

## 7. DBE Contract Compliance After Award and Before Contract Execution

ODOT will send the successful Bidder written notice of acceptance and Award, including a request for further breakdown of the DBE information. Within 10 Calendar Days after Award and prior to Contract execution, the successful Bidder shall provide ODOT with a completed Committed DBE Breakdown and Certification Form describing the work to be performed by each DBE firm.

The successful Bidder shall submit the following breakdown information: bid item, type of work, bid quantity and unit, unit price, and total price. Furthermore, the successful Bidder shall indicate partial work on a bid item and explain the partial item work. If trucking is a DBE committed work

item, the successful Bidder shall indicate if the DBE firm is an owner/operator trucking firm. The Contractor and the Committed DBE Contractor shall sign the form.

FAILURE TO PROVIDE DETAILED DBE INFORMATION TO ODOT WITHIN TEN CALENDAR DAYS AFTER AWARD SHALL BE CAUSE FOR CANCELLATION OF THE AWARD AND WITHDRAWAL OF THE CONTRACT AND MAY BE CAUSE FOR FORFEITURE OF THE BID GUARANTY.

## 8. Information Relating to Contractors Soliciting Project Participation (Bidders List)

Within ten Calendar Days after Bid Opening, all Bidders shall provide information requested in the Subcontractor Solicitation and Utilization Report, (see appendix), listing bona fide bids or quotes received on this project. The information provided will be used to construct a Bidders List required by 49 CFR 26.11(c).

# 9. Information Relating to the DBE Requirements on this Project

For further information concerning Disadvantaged Business Enterprise participation, including confirmation of certification for type of work, contact in writing, the DBE Program Manager no later than one week prior to the project Bid Opening at ocrinforequest@odot.state.or.us.

Other requests may be directed to:

Oregon Department of Transportation Office of Civil Rights MS 23 3930 Fairview Industrial Dr., S.E. Salem, OR 97302

Phone: 503-986-4350 Fax: 503-986-6382

ocrinforequest@odot.state.or.us

[BLANK PAGE]

#### **DBE INFORMATION**

#### **GENERAL INFORMATION**

It is the policy of the Oregon Department of Transportation (ODOT) that Disadvantaged Business Enterprises (DBE) as defined in 49 CFR Part 26 shall have the opportunity to participate in the performance of contracts financed in whole or in part with USDOT funds under this agreement.

A full explanation of DBE Participation Goals and Requirements is in Sections 03.00 and 04.00 of the DBE Supplemental Required Contract Provisions.

Firms certified by the State of Oregon Certification Office of Business Inclusion and Diversity (COBID) as DBE in the state of Oregon shall be used to meet the assigned DBE contract goals for DBE participation on contracts funded in whole or in part with U.S. Department of Transportation (USDOT) funds.

Responsiveness is based on the DBE firm's certification status at time of Bid Opening. Contractors should not rely upon past experiences and verbal assurances of firms listed or non-listed.

Services and Commodity Codes reflect information provided by the certified DBE Firms and is not used as a pre-qualification factor by ODOT.

All Bidders, including DBE prime Bidders, are required to submit a Subcontractor Solicitation and Utilization Report form to ODOT Office of Civil Rights, DBE Program, within 10 Calendar Days after the Bid Opening date.

## **WEBSITES**

**DBE Directory** - A Certification Directory of DBEs is available from COBID at:

https://oregon4biz.diversitysoftware.com/FrontEnd/VendorSearchPublic.asp

**Subcontractor Solicitation And Utilization Report** - The Subcontractor Solicitation and Utilization Report form is available from the Office of Civil Rights at:

https://www.oregon.gov/ODOT/Business/OCR/Pages/Forms.aspx

Project Name	Bid Opening Date
D	BE COMMITMENT CERTIFICATION AND UTILIZATION FORM  Are you a DBE prime contractor?
	_ ' _
	□ Yes □ No
This DBE Certification	and Utilization Form applies solely to meeting the assigned DBE contract goal for

This DBE Certification and Utilization Form applies solely to meeting the assigned DBE contract goal for DBE participation. If the assigned DBE contract goal is greater than zero, each Bidder, including DBE prime Bidders, shall complete and submit this form with their Bid. SHOULD THE BIDDER FAIL TO COMPLETELY FILL OUT, SIGN, AND SUBMIT THIS FORM WITH THE BID WHEN THE ASSIGNED DBE CONTRACT GOAL IS GREATER THAN ZERO, THE BIDDER WILL BE CONSIDERED NON-RESPONSIVE. This certification shall be deemed a part of the resulting contract.

The Bidder acknowledges and certifies that this form accurately represents receipt of and consent from the listed DBE firm as to the use of the referenced itemized quote below for the performance of this project. Bidder certifies that it had direct contact with the named DBE firms regarding participation of this project. Bidder certifies, if awarded this project, that it shall award subcontracts to or enter into agreements with the named DBE. DBE Prime Contractor will receive a minimum 30% credit to be applied to the DBE goal. Part I of the form is not required if the Bidder is a DBE, the DBE contract goal is greater than zero, and the DBE meets the goal by self-performing the minimum required 30% of the work. If the DBE is self-performing more than 30%, it must include any additional work to receive appropriate DBE credit for the goal.

If the Bidder is submitting evidence of good faith efforts to secure participation, Bidder certifies that the good faith efforts documentation is true, accurate and correctly reports the actions taken by the Bidder.

Bidder's Authorized Representative (PRINT)		
Bidder's Authorized Representative (SIGN)	Date	Name of Contractor (Company Name)

## <u>PART I</u>

These columns to be completed by Bidder				These columns to be completed by Agency	
Name of DBE Firm	Type of Work *	Function ** (examples: Sub., Supp., DBE Man., Serv., Brok.)	(or expenditure amount or	Goal Participation % ***	DBE Amount ****

<sup>\*</sup> From " Certification Office of Business Inclusion and Diversity " \*\* From "Function" column below. \*\*\* From "Goal Participation %" column below. \*\*\*\* (Subcontract Amount x Goal Participation %)

Function	Goal Participation %	This section to be completed by Agency		
Subcontractor	100% (of subcontract amount)	ASSIGNED DBE CONTRACT GOAL		
Supplier (Regular Dealer)	60% (of supply expenditure amount)	TOTAL DBE AMOUNT	\$	
DBE Manufacturer	100% (of material expenditure amount)	TOTAL BID AMOUNT	\$	
Service Provider	100% (of fee or commission)	DBE COMMITMENT	%	
Broker	100%	(TOTAL DBE AMOUNT + TOTAL BID AMOUNT) (calculated to two decimal places (0.01))	70	

ſ	(of brokerage fee only)	
П		

Additional sheets may be used by copying this form. Bidder must sign each additional sheet to certify its content and completion of form.


# **PART II**

If Bidder's participation commitment to eligible DBEs is less than the assigned DBE contract goal, Bidder shall submit documentation of "good faith efforts" as evidence of actions to secure DBE participation. This may not be applicable to a DBE prime contractor.

Bidder's documentation of "good faith efforts" shall meet the requirements provided in the Disadvantaged Business Enterprise (DBE) Commitment Requirements, item no. 4(c) DBE Commitment Certification Form Part II - Good Faith Efforts, which outlines the activities considered for good faith efforts.

# Jennings Ave: OR99E to Oatfield Rd Earthwork and Drainage, Bridges and Structures, Asphalt Concrete Paving and Oiling

# **ASSIGNED DBE CONTRACT GOAL**



# Oregon Department of Transportation Policy Statement Disadvantaged Business Enterprise (DBE) Program

The Oregon Department of Transportation (ODOT) is committed to a Civil Rights Program that includes participation of Disadvantaged Business Enterprises (DBEs) in ODOT contracting opportunities. ODOT has established a DBE program in accordance with U.S. Department of Transportation (USDOT) regulations 49 CFR Part 26, as amended in 2014 and effective as of November 3, 2014.

It is ODOT's policy never to exclude any person from participation in, deny any person the benefits of, or otherwise discriminate on the basis of race, color, sex, national origin, or disability in the award and administration of USDOT-assisted contracts. It is ODOT's policy to ensure DBEs, as defined in 49 CFR Part 26, have an equal opportunity to receive and participate in USDOT-assisted contracts. It is also our policy to:

- 1. Ensure nondiscrimination in the award and administration of USDOT-assisted contracts;
- 2. Create a level playing field on which DBEs can compete fairly for USDOT-assisted contracts;
- 3. Ensure the DBE program is narrowly tailored in accordance with applicable law;
- 4. Ensure only firms that fully meet 49 CFR Part 26 eligibility standards are permitted to participate as DBEs:
- 5. Help remove barriers to the participation of DBEs in USDOT-assisted contracts;
- 6. Promote the use of DBEs in all types of federally-assisted contracts and procurement activities conducted by recipients
- 7. Assist the development of firms that can compete successfully in the marketplace outside the DBE program; and
- 8. Provide appropriate flexibility to recipients of Federal financial assistance in establishing and providing opportunities for DBEs.

The Director of ODOT establishes the DBE policy for the department. The Manager of the Office of Civil Rights (OCR) is delegated as the DBE Liaison Officer. In that capacity, the Manager of OCR, in coordination with all ODOT personnel, is responsible for implementing all aspects of the DBE program. Implementation of the DBE program is accorded the same priority as compliance with all other legal obligations incurred by ODOT in its financial assistance agreements with the USDOT. It is the expectation of the Director that all ODOT personnel shall adhere to the intent as well as the provisions and procedures of the DBE Program.

ODOT circulates this policy to the following in accordance with the DBE program: (1) The Oregon Transportation Commission, (2) ODOT personnel involved with USDOT-assisted work, (3) Members of the DBE and non-DBE business communities that perform or are interested in performing work on ODOT contracts. The complete DBE Program and the overall goal calculation reports are available for review at:

ODOT Office of Civil Rights 800 Airport Road SE Salem, OR 97301

https://www.oregon.gov/odot/Business/OCR/Pages/Disadvantaged-Business-

Enterprise.aspx

For questions or further information, please contact:

Angela M. Crain, Manager Office of Civil Rights (T) 503-931-2575

(F) 503-986-6382

Angela.M.Crain@odot.oregon.gov

Kristopher Strickler, Director
Oregon Department of Transportation

June 10, 2022

Date

## DISADVANTAGED BUSINESS ENTERPRISE (DBE) SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS

#### 01.00 DBE Policy and Authorities:

- (a) DBE Policy, Required Assurance, and Applicability As required by 49 CFR Part 26, the Oregon Department of Transportation (ODOT) and the Contractor agree to abide by and take all necessary and reasonable steps to comply with the policy set out below:
  - (1) **DBE Policy** It is the policy of the United States Department of Transportation (USDOT) to practice nondiscrimination on the basis of race, color, sex and/or national origin in the award and administration of USDOT assisted contracts. Consequently, the Disadvantaged Business Enterprise (DBE) requirements of 49 CFR part 26 apply to this agreement.
  - (2) DBE Required Assurance The Contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of USDOT-assisted contracts. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as ODOT deems appropriate. Each subcontract the Contractor signs with a subcontractor must include the assurance in this paragraph (see 49 CFR 26.13(b)).
  - (3) DBE Applicability This applies to all public improvement projects financed in whole or in part with federal funds received from FHWA, FTA and FAA through ODOT. ODOT and its Contractors shall conform to all applicable civil rights laws, orders, and regulations. ODOT and its Contractors shall not discriminate on the basis of race, age, sex, color, religion, national origin, mental or physical disability, political affiliation, or marital status in the award and performance of ODOT contracts.
- **(b) Authorities** These DBE Supplemental Required Contract Provisions are authorized by the following laws, rules, regulations and guidelines, which, in conjunction with any pertinent policy memoranda or procedures issued by the FHWA, all of which are incorporated by reference into the provisions, govern ODOT's administration of the DBE Program.
  - (1) The USDOT Regulations (49 CFR Part 26) published in the Federal Register, effective March 4, 1999, established a requirement that all recipients of USDOT funds establish a DBE Program. The regulations are applicable both to ODOT's Federal-aid construction and to its non-construction activities.
  - **(2)** The USDOT's legal authority for its DBE regulations includes Executive Order 11625 (October 13, 1971), which required that federal executive agencies develop comprehensive plans and programs to encourage minority business participation. USDOT requires ODOT to establish a DBE Program as a condition for receiving USDOT federal funds.

- **(3)** Title VI, Civil Rights Act of 1964. This Act concerns non-discrimination in federally assisted programs or activities on the grounds of race, color, sex or national origin.
- **(4)** The Program is also subject to the following laws: Section 30 of the Airport and Airway Development Act of 1970 and Section 520 of the Airport and Airway Improvement Act of 1982, as amended by the Airport and Airway Safety Capacity Expansion Act of 1987; Section 905 of the Railroad Act of 1978 (45 USC 903); and Section 19 of the Urban Mass Transportation Act of 1964, as amended (Public Law 95-599).
- (5) Oregon Revised Statutes, Chapters 200 and 279.
- (6) Oregon Administrative Rules, Chapter 123, Division 200, Certification Procedures.
- (7) The Contractor agrees that these Disadvantaged Business Enterprise (DBE) Supplemental Required Contract Provisions (including all references) shall be incorporated into all subcontracts, regardless of tier, and into any agreements with Committed DBEs, regardless of form of agreement.
- **02.00 Abbreviations and Definitions** Abbreviations and definitions of words and phrases used in connection with the DBE Program are as follows:

#### (a) Abbreviations:

**COBID** - State of Oregon Certification Office of Business Inclusion and Diversity, which is authorized to certify DBE firms according to federal regulations

**DBE** - Disadvantaged Business Enterprise

FAA - Federal Aviation Administration

**FHWA** - Federal Highway Administration

FTA - Federal Transit Administration

**ODOT** - Oregon Department of Transportation (also referred to as 'Agency')

**USDOT** - United States Department of Transportation

#### (b) Definitions:

**Assigned DBE Contract Goal** - An assigned numerical percentage value of the total dollar amount of a Contract Award that is allocated solely for DBE participation. For a DBE to count towards participation it must be certified by COBID under the commodity codes of the work it is contracted to perform.

**Broker** - A business firm that provides a bona fide service, such as professional, technical, consultant or managerial services and assistance in the procurement of essential personnel, facilities, equipment, materials, or supplies required for the performance of the contract.

**Certification Directory of DBEs** - A publication (available in paper or Internet) listing all DBEs which are currently certified by the COBID. The Directory is provided to the Contractor for use in identifying DBE firms whose participation on a contract may be counted toward achievement of the assigned DBE contract goal.

**Certified Disadvantaged Business Enterprise (DBE)** - A business firm certified by the COBID, indicating that it:

- Meets the criteria outlined in 49 CFR part 26 regarding certification as a DBE; and
- Possesses the required resources and expertise to perform designated types of work.

**Commercially Useful Function (CUF)** - The definition is consistent with 49 CFR 26.55(c) and describes how ODOT counts DBE participation towards DBE goals:

A DBE performs a commercially useful function when it is responsible for execution of the work of the contract and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. To perform a commercially useful function, the DBE must also be responsible, with respect to materials and supplies used on the contract, for negotiating price, determining quality and quantity, ordering the material, and installing (where applicable) and paying for the material itself. To determine whether a DBE is performing a commercially useful function, you must evaluate the amount of work subcontracted, industry practices, whether the amount the firm is to be paid under the contract is commensurate with the work it is actually performing and the DBE credit claimed for its performance of the work, and other relevant factors.

**Committed DBE** - A Committed DBE firm is one that was identified by the Contractor to meet an assigned DBE contract goal as a condition of Contract Award, and includes any substitute DBE that has been approved by ODOT in accordance with 49 CFR 26.53(f) and section 10.00 of the Disadvantaged Business Enterprise (DBE) Supplemental Required contract Provisions in exhibit C-5 that has subsequently been committed work to meet the assigned DBE contract goal. A non-Committed DBE is one that was hired on a race- and gender-neutral basis and has not been identified as a substitute Committed DBE.

**Commodity Codes** - Codes assigned by the COBID to indicate the standard types of services, labor, materials, or work the DBE provides. Services and commodity codes reflect information provided by the certified DBE firms and are not used as prequalification factors by ODOT.

**Contractor's DBE Liaison Officer** - The individual designated by the Contractor to assist the Contractor in meeting the Contractor's responsibility of compliance with the legal requirements of the DBE program and with the contractual obligations imposed by these supplementary provisions including but not limited to assuring that the DBE subcontractors on this project perform a commercially useful function.

**DBE Eligibility** - A firm is eligible to participate as a DBE if it meets the criteria as established by the federal DBE regulations in 49 CFR part 26 and enforced by the certifying agency, which in Oregon is COBID, applies these regulations to make

certification decisions. A firm will no longer be able to participate as a DBE on current or future contracts when it receives notification of decertification, denial of recertification, or notice of graduation by the certifying agency.

**Equipment** - All machinery, tools, and apparatus needed to complete the contract.

**Federal-Aid Contract** - For the purposes of these Disadvantaged Business Enterprise (DBE) Supplemental Required Contract Provisions, any contract including consultant agreements or modifications of a contract between ODOT and a Contractor which is paid for in whole or in part with USDOT financial assistance from FHWA, FTA or FAA.

**Good Faith Efforts** - Efforts required to obtain and support DBE participation that could reasonably be expected to produce and maintain a level of DBE participation sufficient to meet the assigned DBE contract goal. Good faith efforts are required before Bid Opening, upon Contract Award, and continue throughout the performance of the contract to maximize DBE participation. See 49 CFR 26.53 and 49 CFR Part 26, Appendix A.

**Joint Venture DBE** - An ODOT certified enterprise consisting of one or more firms of which at least one is a certified DBE, formed to carry out a single, for-profit business enterprise, for which the parties combine their property, capital, efforts, skills and knowledge, and in which the DBE is responsible for a distinct, clearly defined portion of the work of the contract and whose share in the capital contribution, control, management, risks and profits of the joint venture are commensurate with its ownership interest of the business. (see Section 8.00).

**Managerial Control** - Consistent with normal industry practice, management shall include scheduling work operations, ordering equipment and materials (if materials are part of the contract), preparing and submitting payrolls and all other required reports and forms, and hiring and firing employees, including supervisory employees.

**Manufacturer** - A firm that operates or maintains a factory or establishment that produces on the premises the materials or supplies obtained by the Contractor.

**Operational Control** - Consistent with normal industry practice, the DBE shall supervise the daily operations of the work contracted. There are only two acceptable ways for the DBE to supervise the daily operations. The DBE owner shall act as superintendent and directly supervise the work or the DBE owner shall supervise the work of and employ a skilled and knowledgeable superintendent. If the latter is used, the DBE owner shall be actively involved in making the operational and managerial decisions of the firm; wherein the DBE owner can continue operations should the skilled and knowledgeable superintendent's employment be discontinued.

**Regular Dealer** - A DBE firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials or supplies required for the performance of a contract are bought, kept in stock, and regularly sold to the public in the usual course of business. To be a regular dealer, the DBE firm shall engage in, as its principal business and in its own name, the purchase and sale of the products in question. A regular dealer in such items as steel, cement, gravel, stone, and petroleum products need not keep such products in stock if it owns and operates distribution equipment. Any supplementing of a regular dealer's own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis, and such equipment shall be operated by

the DBE's own employees. Brokers and packagers shall not be regarded as regular dealers within the meaning of this definition.

**Subcontract** - A subcontracting arrangement is generally considered to exist when a person or firm assumes an obligation to perform a part of the contract work and the following conditions are present:

- Compensation for performance of work is on a unit price or lump sum basis.
- The subcontractor exercises full control and authority over the subcontracted work, including the furnishing of labor and equipment and choice of work methods, with only general supervision being exercised by the Contractor.
- Personnel involved in the operation are under the direct supervision of the subcontractor and are included on the subcontractor's payroll.
- ODOT has provided written consent to the subcontract arrangement, regardless of tier.

All conditions involved should be considered and no one condition alone will normally determine whether a subcontract actually exists. (See 00180.21.)

**Type of Work** - Specific descriptions of work which the DBE is certified in the Certification Directory of DBEs as having the expertise and resources necessary to perform.

**03.00 Assigned DBE Contract Goal** - For any project with an assigned DBE contract goal for DBE participation, the Contractor is required to select a portion of work available on the project for DBE participation. The Contractor may use DBE subcontractors, suppliers, manufacturers or professional service providers to fulfill the assigned DBE contract goal as long as the DBE is certified in the types of work selected. The assigned DBE contract goal on a project remains in effect throughout the life of the contract. Dollar values of participation shall be credited toward meeting the assigned DBE contract goal based on DBE gross earnings.

According to 49 CFR 26.87(j)(2), if a Contractor has executed a subcontract with a firm before COBID notifies the firm of its ineligibility, the Contractor may continue to use the firm on the contract and may continue to receive credit toward its assigned DBE contract goal for the firm's work. If ODOT awards the contract to a DBE prime Contractor that is later ruled ineligible, the portion of the ineligible firm's performance of the contract remaining after COBID issued the notice of ineligibility shall not count toward the ODOT overall goal, but may count toward the assigned DBE contract goal. There is an exception under 49 CFR 26.87(j)(3) if the DBE's ineligibility is caused solely by its having exceeded the size standard during the performance of the contract, ODOT may continue to count its participation on the contract toward overall and assigned DBE contract goals.

In determining whether a DBE Contractor has met an assigned DBE contract goal, only the work the DBE has committed with its own forces as well as the work that it has committed to be performed by DBE subcontractors and DBE suppliers will be counted.

According to 49 CFR 26.71(n), DBE firms are certified only for specific types of work. If a DBE firm has not been certified prior to Bid Opening, for the type of work it is intending to

perform on a given contract, then the firm's participation on that contract cannot count toward assigned DBE contract or overall goals.

The assigned DBE contract goal for the project is listed on the "Assigned DBE Contract Goal" sheet at the end of these provisions.

#### 04.00 Subcontracting Limitations:

- (a) DBE Subcontractors All DBE subcontractors committed to perform a function or service as a condition of contract award, or for replacing the performance of a Committed DBE, shall perform a commercially useful function according to Section 09.00. If it is determined by ODOT that the DBE subcontractor is unable to perform a commercially useful function, ODOT will notify the Contractor prior to subcontract approval. The Contractor shall either provide evidence that the DBE subcontractor is able to perform a commercially useful function, or replace the DBE subcontractor with another DBE who has been certified to perform the bid item subcontracted according to Section 10.00(c). If the Contractor cannot provide sufficient evidence that the DBE subcontractor has the ability to perform a CUF, and/or refuses to replace the DBE, the Contractor may be declared in default and the contract could be terminated according to the Oregon Standard Specifications for Construction subsection 00180.90(a).
- **(b) Second Tier DBE Subcontracts** Second tier DBE subcontracts may be counted toward the Contractor's assigned DBE contract goal provided the subcontract was listed in the original DBE commitment prior to bid award. The proportion of participation or work performed by a second-tier DBE subcontract may not be double counted and may only be counted towards the DBE goal in accordance with 49 CFR Part 26.

#### 05.00 DBE Subcontract, Sub-Subcontract(s), and Other Agreement Documents:

- (a) Committed DBEs All work committed to a DBE toward meeting an assigned DBE contract goal, including work to be performed by a substitute Committed DBE, shall be performed under a written agreement according to 00160.01 and 00180.21. The agreement shall fully describe any partial pay item work committed to be performed by DBE firms.
- **(b) Non-Committed DBEs** Work to be performed by a non-Committed DBE shall be in accordance with 00160.01, 00180.20, and 00180.21.
- **06.00 Good Faith Efforts Requirements** The Contractor is required to exercise good faith efforts during the entire life of the contract to meet the assigned DBE contract goal. Good faith efforts shall be made to secure DBE participation sufficient to meet the assigned DBE contract goal. The Contractor shall also make every reasonable effort during the course of the project to enable DBE firms to perform those portions of the contract work for which they have been committed.

If the Contractor determines that the committed DBE is unable or unwilling to perform under the subcontract, unable to perform a commercially useful function, or has changed its ownership and/or control, the Contractor shall make good faith efforts to replace with another DBE. Section 10.00 discusses the procedures that shall be followed to terminate a Committed DBE and replace the firm with a substitute.

The Engineer may request the Contractor to submit evidence of Good Faith Efforts at any time during the course of the contract and the Contractor shall promptly submit such evidence.

**07.00 DBE Work Plan Proposal Form** - The Contractor shall require each DBE participating on the project as a subcontractor and each Committed DBE, regardless of work type or form of agreement, to complete the "Disadvantaged Business Enterprise Work Plan Proposal - Form 3A" (Form 734-2165A). The form shall be filled-in electronically, then printed, and signed by an authorized representative of the DBE and of the Contractor. The Contractor shall submit the completed form to the Engineer. Form 734-2165A is available on the ODOT Office of Civil Rights website at:

https://www.oregon.gov/ODOT/Business/OCR/Pages/Forms.aspx

For Committed DBEs, the Contractor shall submit the completed DBE Work Plan Proposals to the Engineer at or before the pre-construction conference. For non-Committed DBE subcontractors, the Contractor shall submit the completed forms to the Engineer in time for review of the Contractor's request for consent to use the DBE subcontractor on the project.

The purpose of the DBE Work Plan Proposal is to preview whether the proposed activities and type of work identified will comply with DBE program regulations, particularly with respect to commercially useful function and crediting rules. The Contractor shall ensure the form is completed with sufficient information about the DBE's intended work, personnel, equipment, materials, and performance to allow the Agency to determine whether the DBE's proposed performance will meet commercially useful function requirements. Additional information and documentation may be requested by the Agency as needed to alleviate program compliance concerns and must be provided promptly according to 49 CFR 26.109.

The DBE Work Plan Proposal specifically solicits information regarding the following:

- (a) Type of Work List the types of work the DBE will perform.
- **(b) Personnel Required** List the names and/or craft classifications for personnel who will perform. Indicate whether the individual is regularly employed by the DBE, or the source from which the individual was or is to be recruited.
- **(c) Equipment Required** List the items of equipment that will be used on the project. Indicate whether the equipment is owned, rented or leased. If rented or leased, consent to the rental or lease shall be obtained from the Agency prior to beginning of the work.
- (d) Supplies and Materials Required List the supplies and materials that will be used on the project. Indicate the source, by name, address, and phone number, from which supplies and materials will be obtained. For a DBE supplier committed to meet an assigned DBE contract goal, attach documentation showing how the DBE meets manufacturer, regular dealer, or broker requirements, as applicable to the credit being claimed and provide any additional explanation needed regarding ordering, scheduling, and delivery according to subsection (f) below.

- **(e) Prime Contractor Resources** Discuss any plans for the DBE to share any resources of the Contractor, e.g. personnel, equipment, tools, or facilities.
- **(f) Additional Information** Provide comments or explanation of any of the information provided above. Include information related to joint check arrangements or any plans the DBE has to subcontract work to a lower tier or perform work through a specialty contractor.

The Engineer and Office of Civil Rights (OCR) Field Coordinator will review the proposals and may provide written comments as to whether the activities and type of work identified in the proposals complies with program regulations. In those instances where proposed activity and type of work violates applicable regulations, written comments will be offered as to corrective action required in order to comply with the regulations.

**08.00 Contractor Pre-construction Conference Reporting** - The Contractor shall deliver the following information to the Engineer at or before the Pre-construction Conference:

- The name of the DBE liaison officer who will administer the Contractor's DBE program.
   Said officer or the officer's designee shall attend the conference.
- Contractor's project schedule showing the work commencement date and estimated completion date for each DBE that will perform work on the project.
- "Disadvantaged Business Enterprise Work Plan Proposal Form 3A" for all Committed DBEs that are performing work on the project regardless of contracting tier.

**09.00 Commercially Useful Function** - The Contractor is responsible for ensuring that DBE firms working on the project perform a commercially useful function (CUF). The Contractor shall receive credit toward meeting the assigned DBE contract goal and payment for DBE commercially useful function performed work only.

ODOT may perform an on-site review to ascertain whether the DBE is actively performing, managing, and supervising the work. All DBEs shall employ a labor force which is separate and apart from that employed by the Contractor, and which is independently recruited by the DBE according to standard industry practice. The DBE shall supervise and manage the work or independently hire a supervisor, who may not be a supervisor employed by the Contractor or any other subcontractor on the project.

With regard to the Federal-aid share, if an investigation reveals that there has been a violation of the CUF provisions, that portion of the work found to be in violation would not be counted toward goal achievement for either the Contractor or the Agency.

When a DBE is presumed not to be performing a CUF as described in this section, the DBE may present evidence through the Contractor to the Agency to rebut that presumption.

(a) The DBE (Not Some Other Business Entity) Shall Actually Perform the Subcontract - The DBE's utilization of labor, supervisory personnel, equipment and material in the performance of the subcontract shall be consistent with industry standards and shall demonstrate that the DBE and not some other business entity is actually performing the subcontract. For example, when a DBE associates itself too closely with

another business entity or entities, in acquiring a labor force, supervisors, equipment or materials to an extent inconsistent with industry standards, the DBE can no longer be said to be actually performing the subcontract because a partnership or joint venture, of which the DBE is a member, is the actual performer of the subcontract.

- **(b) DBE's Work Force** The DBE shall solicit, hire, place on its payroll, direct, and control all workers performing work under its contract. The DBE owner or its superintendent shall, on a full-time basis, supervise and control the work of the contract. The DBE may with the prior written consent of the Engineer augment its work force with personnel of another firm. The Engineer shall approve the request only when:
  - · Specialized skills are required, and
  - The use of such personnel is for a limited time period.
- (c) DBE Equipment The DBE is expected to perform the work with equipment that is owned, being purchased, or leased by the DBE under a written lease agreement that has been consented to by the Engineer prior to the DBE starting work. No credit will be given, nor payment made for the cost of equipment leased or rented and used in the DBE firm's work when payment for those costs is made by a deduction from the Contractor's payment(s) to the DBE firm.

The DBE may lease specialized equipment, provided a written rental agreement, separate from the subcontract specifying the terms of the lease arrangement, is consented to by the Engineer prior to the DBE starting work. The Engineer will consent to the lease agreement only when:

- The equipment is of a specialized nature,
- The equipment is readily available at the job site,
- The operation of the equipment is under the full control of the DBE,
- The lease arrangement is for a short term,
- The lease arrangement for the specialized equipment in question is a normal industry practice, and
- The DBE shall hire, direct, supervise, control and carry the operator of the equipment on the DBE payroll.
- (d) DBE Trucking Firms Whenever a DBE trucking firm has been committed to meet an assigned DBE contract goal, the Contractor shall ensure that the Committed DBE individually identifies each truck intended for use on the Project on its "Disadvantaged Business Enterprise Work Plan Proposal Form 3A" or an attached list.

The Contractor shall furnish a daily log of all trucking work performed under the Committed DBE's subcontract. The "Daily DBE Trucking Log" (Form 734-2916), (or an approved equal that contains all the information on the ODOT form, including the certification) shall be completed for each day work is performed under the DBE's subcontract. The Daily DBE Trucking Log shall identify all trucks under the management and supervision of the DBE subcontractor used on the Project.

The Contractor shall submit the Daily DBE Trucking Log to the Engineer on a weekly basis and no later than 14 Calendar Days after the first recorded date in the logs. For owner-operator trucks, the Contractor shall comply with 00170.65(b-4).

The following factors will be used to determine if a DBE Trucking firm is performing a CUF:

- The DBE shall be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract, and there cannot be a contrived arrangement for the purpose of meeting DBE goals.
- The DBE shall itself own and operate at least one fully licensed, insured and operational truck used on the contract.
- The DBE receives credit for the total value of the transportation services it provides on the contract using trucks it owns, insures, and operates using drivers it employs.
- The DBE may lease trucks from another DBE firm, including an owner-operator who
  is certified as a DBE. The DBE who leases trucks from another DBE receives credit
  for the total value of the transportation services the lessee DBE provides on the
  contract.
- According to 49 CFR 26.55(d)(5) the DBE may also lease trucks from a non-DBE firm, including an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit for the total value of the transportation services provided by the non-DBE lessees not to exceed the value of transportation services provided by DBE-owned trucks on the contract. Additional participation by non-DBE lessees receives credit only for the fee or commission it receives as a result of the lease arrangements.
- For the purposes of this paragraph, a lease shall indicate that the DBE has exclusive
  use of and control over the truck. This does not preclude the leased truck from
  working for others during the term of the lease with the consent of the DBE, so long
  as the lease gives the DBE absolute priority for use of the leased truck. Leased
  trucks shall display the name and identification number of the DBE.
- **(e) DBE Flagging Firms** DBE flagging firms shall be responsible for ensuring all their dispatched employees meet the required certification and licensing requirements and for furnishing their employees with equipment (in this case, paddles and radios) to perform the committed work. This does not preclude the DBE's employees from supplementing with their own equipment.
- **10.00 Termination and Substitution of DBEs** The Contractor must comply with the requirements and procedures under 49 CFR 26.53(f). The Contractor shall use the specific DBEs listed in response to a contract goal to perform the work and supply the materials for which each is listed unless the contractor obtains ODOT's prior written consent, coordinated with the ODOT Office of Civil Rights. Without ODOT consent, the Contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE. Contractor must provide the DBE with written notice and supporting documentation of its good cause reasons they wish to terminate and/or substitute the DBE with a copy to the Engineer and the ODOT Office of Civil Rights. The DBE must be given 5 days to respond to the termination request, copying the ODOT Office of Civil Rights.

ODOT may provide such written consent only if it agrees, for reasons stated in its concurrence document, that the prime contractor has good cause to terminate the DBE firm because the DBE is unable, unwilling or ineligible to perform. To initiate the termination, substitution, removal or replacement process with a Committed DBE contractor/supplier (regardless of the tier), the Contractor or lower tier contractor/subcontractor must do the following:

- (a) Contractor Notice of Termination of a Non-Committed DBE The Contractor shall notify the Agency in writing of plans to terminate a non-Committed DBE. Include the name of the non-Committed DBE to be terminated, a brief explanation of the reason for termination, and the adjusted DBE subcontract or agreement amount.
- **(b) Contractor Written Request to Terminate a Committed DBE** All Contractor requests to terminate, substitute or replace a Committed DBE, including a partial termination or substitution of work committed to a DBE, shall be in writing and shall include the following information:
  - Date the Contractor determined the DBE to be unwilling, unable or ineligible to perform.
  - Projected date Contractor will require substitution or replacement DBE to commence work if consent is granted to the request.
  - Brief statement of facts describing and citing specific actions or inaction by the DBE giving rise to the Contractor's assertion that the DBE is unwilling, unable or ineligible to perform.
  - Brief statement of the affected DBE's capacity and ability to perform the work as determined by Contractor.
  - Brief statement of facts regarding actions taken by Contractor that are believed to constitute good faith efforts toward enabling the DBE to perform.
  - To date percentage of work completed on each bid item by the DBE.
  - The total dollar amount paid, per bid item, to date for work performed by the DBE.
  - The total dollar amount, per bid item, remaining to be paid to the Committed DBE for work completed, but for which the DBE has not received payment and with which the Contractor has no dispute.
  - The total dollar amount, per bid item, remaining to be paid to the DBE for work completed, but for which the DBE has not received payment and over which the Contractor and/or the DBE have dispute.
  - A written, signed statement from the DBE, provided the DBE concurs with request to terminate, indicating its unwillingness or inability to perform.
- (c) Contractor Written Notice to Committed DBE of Pending Request to Terminate and Substitute with Another DBE The Contractor shall send a copy of the request to terminate and substitute letter to the affected Committed DBE in conjunction to submitting the request to the Engineer. The affected DBE firm may submit a response letter to the Engineer within five Calendar Days of receiving the notice from the Contractor. The affected DBE firm may explain its position concerning performance on the committed work. The Engineer will consider both the Contractor's request and DBE's response and explanation before approving the Contractor's termination and substitution request. If the Contractor is unsuccessful in notifying the affected DBE firm, after trying its best to deliver

a copy of its request letter, the Agency may determine that the affected Committed DBE is unable or unwilling to continue the contract and a substitution will be immediately approved by the Engineer. Contractor must provide the DBE with written notice and supporting documentation of its good cause reasons they wish to terminate and/or substitute the DBE with a copy to the Engineer and the ODOT Office of Civil Rights. The DBE must be given 5 days to respond to the termination request, copying the ODOT Office of Civil Rights.

- (d) Proposed Substitution of Another Certified DBE When a Committed DBE substitution shall occur, the Contractor may submit another eligible DBE firm to replace the original committed firm in writing. The Contractor shall submit the name of the DBE firm, the proposed work to be performed, and the dollar amount of the work. The Contractor shall give pertinent information including bid item, item description, bid quantity and unit, unit price, and total price. In addition, the Contractor shall submit a written DBE Work Plan for the requested substitute DBE according to Section 07.00. The dollar value of work to be performed by the substitute DBE shall be in an amount equal to the dollar value of the amount committed to the terminated DBE, minus the value of work performed to date by the DBE, prior to the request for substitution. Should the Contractor be unable to commit the required dollar value to the substitute DBE, the Contractor shall provide written evidence of good faith efforts made to obtain the substitute value requirement. The Agency will review the quality and intensity of those efforts. Efforts that are merely superficial are not good faith efforts to meet the assigned DBE contract goal. The Contractor shall document the steps taken to obtain participation which demonstrate the good faith efforts outlined below:
  - Evidence that the Contractor attended any pre-solicitation or prebid meetings that were scheduled by ODOT to inform DBE firms of contracting and subcontracting or material supply opportunities available on the project;
  - Evidence that the Contractor identified and selected specific economically feasible units of the project to be performed by DBE firms in order to increase the likelihood of participation by DBE firms;
  - Evidence that the Contractor advertised in general circulation, trade association, minority and trade oriented, women-focus publications, concerning the subcontracting or supply opportunities;
  - Evidence that the Contractor provided written notice to a reasonable number of specific DBE firms, identified from the DBE Directory of Certified Firms for the selected subcontracting or material supply work, in sufficient time to allow the enterprises to participate effectively;
  - Evidence that the Contractor followed up initial solicitations of interest by contacting the enterprises to determine with certainty whether the enterprises were interested. The Contractor should provide the following information as evidence:
    - The names, addresses, and telephone numbers of DBE firms who were contacted, the dates of initial contact and whether initial solicitations of interest were followed up by contacting the DBE firms to determine with certainty whether the DBE firms were interested;
    - A description of the information provided to the DBE firms regarding the plans and specifications and estimated quantities for portions of the work to be performed;

- Documentation of each DBE contacted, but rejected and the reasons for the rejection.
- Evidence that the Contractor provided interested DBE firms with adequate information about the plans, specifications and requirements for the selected subcontracting or material supply work;
- Evidence that the Contractor negotiated in good faith with the enterprises, and did not without justifiable reason reject as unsatisfactory bids prepared by any DBE;
- Evidence that the Contractor advised and made efforts to assist interested DBE firms in obtaining bonding, lines of credit, or insurance required by ODOT or Contractor;
- Evidence that the Contractor's efforts to obtain DBE participation were reasonably expected to produce a level of participation sufficient to meet the assigned DBE contract goal or requirements of ODOT; and
- Evidence that the Contractor used the services of minority community organizations or minority organizations that provide assistance in the recruitment and placement of disadvantaged, minority, or women business enterprises.
- **11.00** Changes in Work Committed to DBEs The Agency will consider the impact on DBE participation in instances where the Agency changes, reduces, or deletes work committed to a DBE at the time of contract award. In such instances, the Contractor shall not be required to replace the work but is encouraged to do so. If the prime Contractor proposes any changes that involve a Committed DBE, the Contractor shall notify the affected DBE of the proposed change, reduction, or deletion of any work committed at the time of contract award prior to executing the change order. The Contractor shall enable the affected DBE to participate in the change order request and will make every effort to maintain the Committed DBE percentage that was the condition of contract award. Documentation of this effort and a letter from the DBE agreeing to the change shall be included with the request.

#### 12.00 Contractor Payments to Subcontractors and Suppliers:

- (a) DBE-Related Records The Contractor shall maintain records of all subcontracts or other agreements entered into with DBE firms and records of materials purchased from DBE suppliers. Such records shall show the name and business address of each DBE subcontractor or vendor and the total dollar amount actually paid to each DBE subcontractor or vendor.
- (b) Prompt Payment and Release of Retainage The Contractor shall pay each subcontractor for satisfactory performance of its contract no later than 10 Calendar Days from receipt of each payment the Contractor receives from ODOT. If retainage is withheld the Contractor shall also return retainage payments to each subcontractor within 10 Calendar Days after the subcontractor's work is satisfactorily completed. Any delay or postponement of payment from the above referenced time frame may occur only for good cause following written approval of the Engineer. This policy applies to both DBE and non-DBE contractors.
- **(c) Paid Summary Reports** The Contractor shall submit a "Paid Summary Report" (Form 734-2882) to the Engineer certifying payments made to all of the following:

- All subcontractors
- Committed DBE suppliers
- Non-Committed DBE suppliers and service providers with estimated total payments for the Project over \$10,000.

The Contractor shall submit the completed and signed Paid Summary Report to the Engineer within 20 days of receipt of payment from the Agency for each month in which payments were made to each subcontractor, each Committed DBE supplier, and each non-Committed DBE supplier or service provider with estimated total payments for the Project over \$10,000. At the completion of the project, submit Form 734-2882 recapping the total amounts paid to each subcontractor, and each Committed DBE supplier, and each non-Committed DBE supplier or service provider with estimated total payments for the Project over \$10,000.

The Contractor shall require each subcontractor at every tier to comply with the requirement to submit Form 734-2882 within 20 days of receipt of payment from its controlling contractor and provide a recap of the total amounts paid at the completion of the project or completion of their Work.

Forms shall be submitted to an email address provided to the Contractor at the Preconstruction Conference.

The participation of a DBE subcontractor will not be credited towards the Contractor's assigned DBE contract goal, or the overall goal, until the amount being counted toward the goal, and any retainage held by the Contractor has been paid to the DBE.

**13.00 Remedies** - Failure of any Contractor to meet the requirements cited in Section 01.00(b) constitutes a breach of contract for which the imposition of the following sanctions could occur:

- Temporarily withholding progress payments until the Contractor complies with these provisions through future performance.
- Permanently withholding payment for work already performed in a manner that constitutes a breach of contract.
- Suspension of work according to the Oregon Standard Specifications for Construction, subsections 00150.00 and 00180.70.

Any Bidder or Contractor or subcontractor on a public contract that violates the provisions of ORS 200.075 shall have its right to bid on or participate in any public contract suspended for up to 90 days for a first violation, up to one year for a second violation and up to five years for a third violation.

Each violation shall remain on record for five years. After five years, the violation shall no longer be considered in reviewing future violations.

Failure of a Bidder, Contractor, or subcontractor to comply with the requirements cited in Section 01.00(b) when there appears to be evidence of criminal conduct, shall be referred to the Oregon Department of Justice and/or the FHWA Inspector General for criminal investigation, and if warranted, prosecution.

**14.00 Records and Reports** - The Contractor shall keep such project records as are necessary to determine compliance with these DBE Supplemental Required Contract Provisions, including but not limited to records on equipment usage, fuel consumption, invoicing, and payments. Such records shall include written reports from the DBE Liaison Officer to the Contractor as to the performance of the committed DBE and its performance of a commercially useful function. Contractor shall provide the Engineer with records on equipment and fuel logs and other records needed to verify compliance with commercially useful function and DBE crediting requirements.

**15.00 Further Information** - The Disadvantaged Business Enterprise Supplemental Required Contract Provisions shall be incorporated into and attached to all agreements and contracts on projects financed in whole or in part with federal funds.

For further information concerning Disadvantaged Business Enterprise participation, including confirmation of certification for type of work, contact, in writing, the DBE Program Manager not later than one week prior to the project Bid Opening at ocrinforeguest@odot.oregon.gov.

Other requests may be directed to:

Oregon Department of Transportation Office of Civil Rights 800 Airport Road SE Salem, OR 97301 Phone: 503-986-4350

Fax: 503-986-6382

ocrinforequest@odot.oregon.gov

#### **EQUAL EMPLOYMENT OPPORTUNITY PROVISIONS**

As used in these provisions, "Engineer" means the Chief Engineer of the Oregon Department of Transportation acting either directly or through authorized representatives. "Good Faith Efforts" means "affirmative action measures designed to implement the established objectives of an Affirmative Action Plan" 23 CFR 230.407(o).

Section 140 of Title 23, United States Code, EQUAL EMPLOYMENT OPPORTUNITY, as in effect on May 1, 1982, is incorporated by this reference and made a part of these provisions.

#### **Written Notification**

The Contractor shall provide to the Engineer within two weeks of award of any construction subcontract in excess of \$10,000 at any tier for construction work under the Contract resulting from this solicitation written notification with the following information: the name, address and telephone number of the Subcontractor; employer identification number; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.

The Contractor shall provide immediate written notification to the Engineer when (1) the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor minorities or women that the Contractor sent to the union, or (2) the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its equal opportunity obligations. This is in addition to the notification required in item 7d in the "On-Site Workforce Affirmative Action Requirements for Women and Minorities on Federal-Aid Contracts".

#### **Monthly Report**

The Contractor and each Subcontractor (on contracts that require certified payrolls) shall submit each month to the Engineer a "Monthly Employment Utilization Report" (Form 731-0668). The electronic form is available at:

https://www.oregon.gov/ODOT/Business/OCR/Pages/Forms.aspx

#### **Annual Report**

Each July for the duration of the Project, each Contractor and Subcontractor shall submit Form FHWA-1391. This report shall be sent directly to the ODOT Office of Civil Rights.

PURSUANT TO 23 CFR PART 230, SUBPART D, THE STATE HIGHWAY AGENCY HAS A RESPONSIBILITY TO ASSURE COMPLIANCE BY CONTRACTORS WITH THE REQUIREMENTS OF FEDERAL-AID CONSTRUCTION CONTRACTS, 23 CFR 230.405(b). THEREFORE, THE STATE HIGHWAY AGENCY HAS THE FOLLOWING OBLIGATIONS CONCERNING MONITORING AND COMPLIANCE, INCLUDING SHOW CAUSE NOTICE REQUIREMENTS.

#### **Monitoring and Compliance**

The Agency will maintain a vigorous monitoring process to ensure nondiscrimination and affirmative action on all federally funded Projects. Monitoring shall include at a minimum, monthly meetings to review the "Monthly Employment Utilization Report" (Form 731-0668) with the Contractor's Equal Employment Opportunity (EEO) Officer and quarterly reviews of the Contractor's Good Faith Efforts as outlined in FHWA 1273.

The Agency shall determine the Contractor's compliance with equal opportunity requirements including:

- Non-discrimination in selection and retention of subcontractors, material suppliers and vendors;
- Maintenance of non-segregated facilities;
- Adequate representation and utilization of minorities and women (by craft and trade) in the Contractor's workforce;
- Good Faith Efforts in meeting on-the-job training and training special provisions contained in FHWA 1273:
- Fair treatment in all terms and conditions of employment; and,
- Adherence (where applicable) to Indian preference provisions.

If the Agency or the FHWA becomes aware of any possible violations of Executive Order 11246 or 41 CFR 60, each has the authority and the responsibility to notify the Office of Federal Contract Compliance Programs. The Contractor has the responsibility either to meet all the craft goals set forth in the applicable "Covered Area" of "On-Site Workforce Affirmative Action Requirements for Women and Minorities on Federal-Aid Contracts" or demonstrate Good Faith Efforts to meet these goals (as specified in paragraphs 7a through 7p of the "On-Site Workforce Affirmative Action Requirements for Women and Minorities on Federal-Aid Contracts").

#### **Show Cause Notice**

If an investigation or review reveals that a Contractor or Subcontractor has not complied with these EEO Provisions, the Agency shall issue a Show Cause Notice to initiate efforts to bring the Contractor or Subcontractor into compliance. This written notice shall state the deficiencies found during the review, and shall advise the Contractor or Subcontractor to show cause within 30 Calendar Days why the Agency shall not impose administrative

sanctions. The Contractor or Subcontractor must then show good cause or must provide an acceptable agreement for corrective action within 30 Calendar Days.

If the Contractor or Subcontractor does not provide this information by the end of the 30 Calendar Days, the Engineer shall withhold all project progress payments in process as of the date the Show Cause Notice was issued and will continue to withhold project progress payments until the Contractor or Subcontractor responds in an acceptable manner. If the Contractor or Subcontractor fails to meet the conditions of the corrective action agreement, no further Show Cause Notice is required; the Agency shall immediately initiate enforcement proceedings.

If a Contractor's prequalification certification is revoked or disqualified because the Contractor has been found on at least two occasions to be in breach of these EEO Provisions of Federal-Aid highway construction contracts, the Contractor must be determined to be in compliance with these EEO Provisions prior to the Contractor's prequalification certificate being reinstated.

#### **EQUAL EMPLOYMENT OPPORTUNITY-ASPIRATIONAL TARGET PROVISIONS**

See the EQUAL EMPLOYMENT OPPORTUNITY PROVISIONS incorporated in this Contract for notifying the Engineer, monthly and annual reporting, monitoring, and compliance.

#### **Aspirational Diversity Targets**

**ODOT Aspirational Diversity Targets** - While Aspirational Diversity Targets are not requirements for this Contract and are not binding on the Contractor, ODOT desires to encourage the highest possible participation of minorities and women in the work force. Therefore, ODOT has established aspirational targets on all federally funded Projects:

#### **Covered Areas**

Area Aspirational

ODOT Region 1 ODOT Region 2, 3, 4, & 5 Women 14% - Minority 20% Women 14% - Minority 14%

Neither the Contractor nor its subcontractors are under any obligation to meet any aspirational targets.

### ON-SITE WORKFORCE AFFIRMATIVE ACTION REQUIREMENTS FOR WOMEN AND MINORITIES ON FEDERAL-AID CONTRACTS

Pursuant to 41 CFR 60-4.6 (see also 41 CFR 60-4.2(a)) the following notice concerning Affirmative Action Requirements for Women and Minorities shall be included in, and shall be a part of, all solicitations for offers and bids on all Federal and federally assisted construction contracts or subcontracts in excess of \$10,000 to be performed in geographical areas designated by the United States Department of Labor (USDOL) Director. The USDOL, Office of Federal Contract Compliance Programs (OFCCP) has made the following statement concerning Goals, Timetables and Good Faith Efforts:

"Numerical goals are established based on the availability of qualified applicants in the job market or qualified candidates in the employer's work force. Executive Order [E.O. 11246] numerical goals do not create set-asides for specific groups, nor are they designed to achieve proportional representation or equal results. Rather, the goal-setting process in affirmative action planning is used to target and measure the effectiveness of affirmative action efforts to eradicate and prevent discrimination. The Executive Order and its supporting regulations do not authorize OFCCP to penalize contractors for not meeting goals. The regulations at 41 CFR 60-2.12(e), 60-2.30 and 60-2.15, specifically prohibit quota and preferential hiring and promotions under the guise of affirmative action numerical goals. In other words, discrimination in the selection decision is prohibited."

For purposes of these "On-Site Workforce Affirmative Action Requirements for Women and Minorities on Federal-Aid Contracts", "Good Faith Effort" means affirmative action measures designed to implement the established objectives of an Affirmative Action Plan 23 CFR 230.407(o).

#### A. AFFIRMATIVE ACTION REQUIREMENTS

Notice of Requirement for Affirmative Action To Ensure Equal Employment Opportunity (Executive Order 11246)

1. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

#### **Goal and Timetable for Female Utilization Statewide**

#### **Goals for Minority Utilization by County**

#### Goal (Percent)

Clackamas, Multnomah, and Washington Counties 4.5
Marion and Polk Counties2.9
Benton, Clatsop, Columbia, Crook, Deschutes, Hood River, Jefferson, Lincoln, Linn, Sherman, Tillamook, Wasco, and Yamhill Counties
Lane, Coos, Curry, Douglas, Jackson, Josephine, Klamath, and Lake Counties2.4
Baker, Gilliam, Grant, Morrow, Umatilla, Union, Wallowa, and Wheeler Counties
Harney and Malheur Counties4.4

These goals are applicable to all the Contractor's construction work (whether or not it is Federal or federally assisted) performed in the covered area. If the contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and non-federally involved construction.

The Contractor's compliance with the Executive Order and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, the Executive Order and the regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

- 2. The Contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within 10 business days of award of any construction subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor; employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.
- **3.** As used in this Notice, and in the contract resulting from this solicitation, the "covered area" is the county or counties shown in the Solicitation Documents. In cases where the work is two or more counties covered by different percentage goals, the highest percentage will govern.

### B. STANDARD FEDERAL EQUAL EMPLOYMENT OPPORTUNITY CONSTRUCTION CONTRACT SPECIFICATIONS (EXECUTIVE ORDER 11246)

- **1.** As used in these specifications:
  - **a.** "Covered area" means the geographical area, described in the solicitation from which this contract resulted:
  - **b.** "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority;
  - **c.** "Employer identification number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.
  - **d.** "Minority" includes:
    - (i) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);
    - (ii) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American or other Spanish Culture or origin, regardless of race);
    - (iii) Asian American and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and
    - (iv) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).
- 2. Whenever the Contractor, or any Subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000 the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitation from which this contract resulted.
- **3.** A contractor participating, either individually or through an association, in an approved Hometown Plan (including heavy highway affirmative action plans) shall comply with its affirmative action obligations under Executive Order 11246 by complying with its obligations under the plan; provided, that each contractor or subcontractor participating in an approved plan is individually required to comply with the equal opportunity clause set forth in 41 CFR 60-1.4; to make a good faith effort to achieve the goals for each trade participating in the plan in which it has employees; and that the overall good performance by other contractors or subcontractors toward a goal in an approved plan does not excuse any covered contractor's or subcontractor's failure to take good faith efforts to achieve the plan's goals and timetables.
- **4.** The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through 7p of these specifications. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minorities and female utilization the Contractor should

reasonably be able to achieve in each construction trade in which it has employees in the covered area. Covered construction contractors performing construction work in geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical area where the work is performed. Goals are published periodically in the Federal Register in notice form, and such notices maybe obtained from any Federal Contract Compliance Programs office or from Federal procurement contracting officers. The Contractor is expected to make substantially uniform progress toward its goals in each craft during the period specified.

- **5.** Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.
- **6.** In order for the non-working training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.
- **7.** The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:
  - **a.** Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minorities and female individuals working at such sites or in such facilities.
  - **b.** Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organization's responses.
  - **c.** Maintain a current file of the names, addresses and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source, or a community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefore, along with whatever additional actions the Contractor may have taken.
  - **d.** Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the

Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

- **e.** Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.
- **f.** Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreement; by publicizing it in the company newspaper, annual report, etc., by specific review of the policy with all management personnel and with all minority and female employees at least once a year, and by posting the Contractor's EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.
- **g.** Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination or other employment decisions including specific review of these items with on-site supervisory personnel such as Superintendents, General Foremen, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject manner.
- **h.** Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractors and Subcontractors with whom the Contractor does or anticipates doing business.
- i. Direct its recruitment efforts, both oral and written, to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.
- **j.** Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer and vacation employment to minority and female youth both on the site and in other areas of a Contractor's work force.
- **k.** Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.

- **I.** Conduct, at least annually, an inventory and evaluation at least of all minority and female employees for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.
- **m.** Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
- **n.** Ensure that all facilities and Contractor's activities are non-segregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
- **o.** Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.
- **p.** Conduct a review, at least annually, of all supervisor's adherence to and performance under the Contractor's EEO policies and affirmative action obligations.
- **8.** Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through 7p). The efforts of a contractor association, joint contractor union, contractor-community; or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under 7a through 7p of these specifications provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female work force participation, makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.
- **9.** A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specific minority group of women is underutilized).
- **10.** The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex or national origin.
- **11.** The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.

- **12.** The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termination and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.
- **13.** The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.8.
- 14. The contractor will designate an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so. Additionally, the contractor EEO Officer shall ensure that the company EEO policy is being carried out, to submit reports relating to the specifications hereof as may be required by the Agency and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, Contractors shall not be required to maintain separate records.
- **15.** Nothing herein provided shall be construed as a limitation upon the application of other laws, which establish different standards of compliance, or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).
- 16. The Office of Federal Contract Compliance Programs (OFCCP) may conduct compliance evaluations to determine if the contractor maintains nondiscriminatory hiring and employment practices and is taking affirmative action to ensure that applicants are employed and that employees are placed, trained, upgraded, promoted, and otherwise treated during employment without regard to race, color, religion, sex, or national origin. In the event of the contractor's non-compliance with the nondiscrimination clauses of this contract or with any of such rules, regulations, or orders, this contract may be canceled, terminated or suspended in whole or in part and the contractor may be declared ineligible for further Government contracts in accordance with procedures authorized in Executive Order 11246 of September 24, 1965, and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law.

### REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I General
- II. Nondiscrimination
- III. Non-segregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion
- XI. Certification Regarding Use of Contract Funds for Lobbying
- XII. Use of United States-Flag Vessels:

#### **ATTACHMENTS**

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

#### I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under title 23, United States Code, as required in 23 CFR 633.102(b) (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services). 23 CFR 633.102(e).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider. 23 CFR 633.102(e).

Form FHWA-1273 must be included in all Federal-aid designbuild contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services) in accordance with 23 CFR 633.102. The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in solicitation-for-bids or request-for-proposals documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract). 23 CFR 633.102(b).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work

performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract. 23 CFR 633.102(d).

- 3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.
- 4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. 23 U.S.C. 114(b). The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors. 23 U.S.C. 101(a).
- II. NONDISCRIMINATION (23 CFR 230.107(a); 23 CFR Part 230, Subpart A, Appendix A; EO 11246)

The provisions of this section related to 23 CFR Part 230, Subpart A, Appendix A are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR Part 60, 29 CFR Parts 1625-1627, 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR Part 60, and 29 CFR Parts 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), and Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR Part 230, Subpart A, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

- 1. Equal Employment Opportunity: Equal Employment Opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (see 28 CFR Part 35, 29 CFR Part 1630, 29 CFR Parts 1625-1627, 41 CFR Part 60 and 49 CFR Part 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140, shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR Part 35 and 29 CFR Part 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
- a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract. 23 CFR 230.409 (g)(4) & (5).
- b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, sexual orientation, gender identity, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

- 2. **EEO Officer:** The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.
- 3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action or are substantially involved in such action, will be made fully cognizant of and will implement the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer or other knowledgeable company official.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women

- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
- **4. Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.
- a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.
- b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.
- c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.
- **5. Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, sexual orientation, gender identity, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to ensure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
- b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action

within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

#### 6. Training and Promotion:

- a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.
- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs (i.e., apprenticeship and on-the-job training programs for the geographical area of contract performance). In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.
- 7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. 23 CFR 230.409. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:
- a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.
- b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability.
- c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.
- d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide

sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

- 8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established thereunder. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.
- 9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.
- a. The contractor shall notify all potential subcontractors, suppliers, and lessors of their EEO obligations under this contract.
- b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

#### 10. Assurances Required:

- a. The requirements of 49 CFR Part 26 and the State DOT's FHWA-approved Disadvantaged Business Enterprise (DBE) program are incorporated by reference.
- b. The contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:
  - (1) Withholding monthly progress payments;
  - (2) Assessing sanctions;
  - (3) Liquidated damages; and/or
- (4) Disqualifying the contractor from future bidding as non-responsible.
- c. The Title VI and nondiscrimination provisions of U.S. DOT Order 1050.2A at Appendixes A and E are incorporated by reference. 49 CFR Part 21.
- 11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.
- a. The records kept by the contractor shall document the following:

- (1) The number and work hours of minority and nonminority group members and women employed in each work classification on the project;
- (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and
- (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women.
- b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on <a href="Form FHWA-1391">Form FHWA-1391</a>. The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

#### **III. NONSEGREGATED FACILITIES**

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of more than \$10,000. 41 CFR 60-1.5.

As prescribed by 41 CFR 60-1.8, the contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, sexual orientation, gender identity, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location under the contractor's control where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

#### IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size), in accordance with 29 CFR 5.5. The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. 23 U.S.C. 113. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. 23 U.S.C. 101. Where applicable law requires that projects be treated as a project on a Federal-aid highway, the provisions of this subpart will apply regardless of the location of the project. Examples include: Surface Transportation Block Grant Program projects funded under 23 U.S.C. 133 [excluding recreational trails projects], the Nationally Significant Freight and Highway

Projects funded under 23 U.S.C. 117, and National Highway Freight Program projects funded under 23 U.S.C. 167.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

#### 1. Minimum wages (29 CFR 5.5)

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

- b.(1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:
  - (i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and
  - (ii) The classification is utilized in the area by the construction industry; and

- (iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
- (2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

#### 2. Withholding (29 CFR 5.5)

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics,

including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

#### 3. Payrolls and basic records (29 CFR 5.5)

- a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.
- b.(1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency.
- (2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or

subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

- (i) That the payroll for the payroll period contains the information required to be provided under 29 CFR 5.5(a)(3)(ii), the appropriate information is being maintained under 29 CFR 5.5(a)(3)(i), and that such information is correct and complete;
- (ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in 29 CFR part 3;
- (iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- (3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.
- (4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.
- c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

#### 4. Apprentices and trainees (29 CFR 5.5)

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State

Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the

corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

- c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.
  - d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. 23 CFR 230.111(e)(2). The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

- **5. Compliance with Copeland Act requirements.** The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract as provided in 29 CFR 5.5.
- **6. Subcontracts.** The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.
- **7. Contract termination: debarment.** A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.
- 8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract as provided in 29 CFR 5.5.
- **9. Disputes concerning labor standards.** As provided in 29 CFR 5.5, disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor

set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

#### 10. Certification of eligibility (29 CFR 5.5)

- a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- c. The penalty for making false statements is prescribed in the U.S. Criminal Code,  $18\,U.S.C.\,1001.$

# V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

Pursuant to 29 CFR 5.5(b), the following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

- 1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek. 29 CFR 5.5.
- 2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph 1 of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph 1 of this section, in the sum currently provided in 29 CFR 5.5(b)(2)\* for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph 1 of this section. 29 CFR 5.5.
- \* \$27 as of January 23, 2019 (See 84 FR 213-01, 218) as may be adjusted annually by the Department of Labor; pursuant to the Federal Civil Penalties Inflation Adjustment Act of 1990).

- 3. Withholding for unpaid wages and liquidated damages. The FHWA or the contacting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 2 of this section.
- **4. Subcontracts.** The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraphs 1 through 4 of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs 1 through 4 of this section. 29 CFR 5.5.

#### VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System pursuant to 23 CFR 635.116.

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).
- a. The term "perform work with its own organization" in paragraph 1 of Section VI refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions: (based on longstanding interpretation)
- (1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
  - (2) the prime contractor remains responsible for the quality of the work of the leased employees;
- (3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
  - (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.
- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or

- equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract. 23 CFR 635.102.
- 2. Pursuant to 23 CFR 635.116(a), the contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. Pursuant to 23 CFR 635.116(c), the contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract. (based on long-standing interpretation of 23 CFR 635.116).
- 5. The 30-percent self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements. 23 CFR 635.116(d).

#### **VII. SAFETY: ACCIDENT PREVENTION**

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR Part 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract. 23 CFR 635.108.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR Part 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704). 29 CFR 1926.10.
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance

with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

## VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR Part 635) in one or more places where it is readily available to all persons concerned with the project:

#### 18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 11, 1916, (39 Stat. 355), as amended and supplemented:

Shall be fined under this title or imprisoned not more than 5 years or both."

# IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT (42 U.S.C. 7606; 2 CFR 200.88; EO 11738)

This provision is applicable to all Federal-aid construction contracts in excess of \$150,000 and to all related subcontracts. 48 CFR 2.101; 2 CFR 200.326.

By submission of this bid/proposal or the execution of this contract or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, subcontractor, supplier, or vendor agrees to comply with all applicable standards, orders

or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal Highway Administration and the Regional Office of the Environmental Protection Agency. 2 CFR Part 200, Appendix II.

The contractor agrees to include or cause to be included the requirements of this Section in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements. 2 CFR 200.326.

# X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200. 2 CFR 180.220 and 1200.220

#### 1. Instructions for Certification – First Tier Participants:

- a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction. 2 CFR 180.320.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default. 2 CFR 180.325.
- d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances. 2 CFR 180.345 and 180.350.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900-180.1020, and 1200. "First Tier Covered Transactions" refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant

who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

- f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction. 2 CFR 180.330.
- g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold. 2 CFR 180.220 and 180.300.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. 2 CFR 180.300; 180.320, and 180.325. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. 2 CFR 180.335. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (<a href="https://www.sam.gov/">https://www.sam.gov/</a>). 2 CFR 180.300, 180.320, and 180.325.
- i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default. 2 CFR 180.325.

\* \* \* \* \*

# 2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

- a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:
- (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.335;.

- (2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property, 2 CFR 180.800;
- (3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification, 2 CFR 180.700 and 180.800; and
- (4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default. 2 CFR 180.335(d).
- (5) Are not a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and
- (6) Are not a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability (USDOT Order 4200.6 implementing appropriations act requirements).
- b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal. 2 CFR 180.335 and 180.340.

#### 3. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders, and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200). 2 CFR 180.220 and 1200.220.

- a. By signing and submitting this proposal, the prospective lower tier participant is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances. 2 CFR 180.365.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900 180.1020, and 1200. You may contact the person to which this proposal is

submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated. 2 CFR 1200.220 and 1200.332.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold. 2 CFR 180.220 and 1200.220.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (<a href="https://www.sam.gov/">https://www.sam.gov/</a>), which is compiled by the General Services Administration. 2 CFR 180.300, 180.320, 180.330, and 180.335.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment. 2 CFR 180.325.

\* \* \* \* \*

# Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals:

- (a) is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.355:
- (b) is a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and
- (c) is a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability. (USDOT Order 4200.6 implementing appropriations act requirements)
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal.

\* \* \* \* \*

# XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000. 49 CFR Part 20, App. A.

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
- a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier

subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

#### XII. USE OF UNITED STATES-FLAG VESSELS:

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, or any other covered transaction. 46 CFR Part 381.

This requirement applies to material or equipment that is acquired for a specific Federal-aid highway project. 46 CFR 381.7. It is not applicable to goods or materials that come into inventories independent of an FHWA funded-contract.

When oceanic shipments (or shipments across the Great Lakes) are necessary for materials or equipment acquired for a specific Federal-aid construction project, the bidder, proposer, contractor, subcontractor, or vendor agrees:

- 1. To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels. 46 CFR 381.7.
- 2. To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b)(1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Office of Cargo and Commercial Sealift (MAR-620), Maritime Administration, Washington, DC 20590. (MARAD requires copies of the ocean carrier's (master) bills of lading, certified onboard, dated, with rates and charges. These bills of lading may contain business sensitive information and therefore may be submitted directly to MARAD by the Ocean Transportation Intermediary on behalf of the contractor). 46 CFR 381.7.

ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS (23 CFR 633, Subpart B, Appendix B) This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

- 1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:
- a. To the extent that qualified persons regularly residing in the area are not available.
- b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.
- c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.
- 2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.
- 3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.
- 4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above
- 5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.
- 6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

#### REIMBURSABLE FEDERAL ON-THE-JOB and APPRENTICESHIP TRAINING

This Section for Reimbursable Federal On-the-Job Training and Apprenticeship Training supersedes subparagraph B(7-e) of the "On-Site Workforce Affirmative Action Requirements for Women and Minorities on Federal Aid Contracts," and is in implementation of 23 U.S.C. 140(a). All other provisions apply.

#### **SECTION 1: ABBREVIATIONS AND DEFINITIONS**

#### (a) Abbreviations

**BOLI** - Bureau of Labor and Industries for the State of Oregon

**EEO** - Equal Employment Opportunity

**OCR** - Office of Civil Rights

OJT - On-the-Job Training

#### (b) Definitions

**Affirmative Action** - Contractor's efforts exerted towards achieving equal opportunity through positive, aggressive, and continuous result-oriented measures to correct past and present discriminatory practices and their effects on the conditions and privileges of employment. These measures include, but are not limited to, recruiting, hiring, promotion, upgrading, demotion, transfer, termination, compensation, and training.

**Apprenticeship Training Program** - A specific Apprenticeship Training Program, approved by BOLI, which provides a combination of field and classroom trade specific experience under the supervision of journey level workers. For this Contract, this is a Race and Gender Neutral program.

**OJT Program** - A specific on-the-job training program, approved by the Agency and FHWA, which provides a combination of field, and limited classroom, trade specific experience under the supervision of journey level workers. This is an Affirmative Action program that targets women and minorities.

**Qualified Hours** - Specific On-Site training hours (may include some classroom hours) completed by a properly registered and enrolled trainee consistent with the Contractor's OJT Program or an apprentice consistent with the Apprenticeship Training Program. The Contractor reports these Qualified Hours to the Agency for the OJT and Apprenticeship Training Goal.

**Race and Gender Neutral** - Employment and contracting practices where the ethnicity and the sex of a person are not considered in the evaluation of candidates for employment or bids for the Contract.

**Training Goal** - A fixed quantity of Qualified Hours set by the Agency and included in the bid schedule.

#### **SECTION 2: POLICY STATEMENT**

In order to increase the number of trained and skilled workers in highway construction the Agency will set a Training Goal for the Project.

It is the policy of the Agency that the Contractor shall take all necessary and reasonable steps to ensure that trainees and apprentices have the opportunity to participate on highway construction projects and to develop as journey-level workers in the given trade or job classification employed, and to meet this Training Goal.

The Contractor shall adopt the following policy:

It shall be the policy of the Contractor to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, or national origin, age or disability. Such action shall include employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and on-the-job training.

The Training Goal is not intended, and shall not be used to discriminate against any applicant, whether members of a minority group or not.

#### **SECTION 3: APPRENTICESHIP TRAINING PROGRAM**

#### (a) General

Apprentices shall be paid the appropriate rates approved in connection with their stage in the Apprenticeship Training Program.

A valid certification by an appropriate apprenticeship committee that the Contractor is an approved training agent shall be prima facie proof of compliance.

#### (b) EEO Requirements

The Contractor shall ensure that, without discrimination, minorities and women have an equal employment opportunity to compete for and participate as apprentices while supporting a diverse workforce that is representative of the population.

Apprenticeship training is Race and Gender Neutral, however, the Contractor is still obligated to comply with all applicable EEO requirements.

#### (c) Reports

The Contractor and each Subcontractor with an Apprenticeship Training Program shall complete and submit the following reports to the Engineer, according to the instructions provided in the respective forms:

- The "Training Program Approval Request (TPAR)" (Form 734-2880) shall be submitted prior to or at the preconstruction conference.
- Before an apprentice begins work, an "Apprentice/Trainee Approval Request (ATAR)" (Form 734-2878) shall be submitted.
- Each month the Contractor shall submit the "Monthly Employment Utilization Report" (Form 731-0668). This report is required of the Contractor and Subcontractors who have contracts that require certified payrolls, regardless of their participation in the apprenticeship.
- Each month the Contractor shall submit an "Apprentice/Trainee Monthly Progress Report (MPR)" (Form 734-2879) for each apprentice. This Form is used to report Qualified Hours for apprentices and will be the source document for estimated monthly progress payments to the Contractor.

Forms are published on the ODOT OCR website at:

https://www.oregon.gov/ODOT/Business/OCR/Pages/Forms.aspx

#### **SECTION 4: OJT PROGRAM**

#### (a) EEO Requirements

The Contractor shall make every effort to enroll minority and women trainees by conducting systematic and direct, meaningful recruitment through public and private sources likely to yield minority and women trainees within a reasonable area of recruitment.

Whenever minorities or women are not placed in OJT positions, the Contractor shall provide documented evidence of Affirmative Action recruitment efforts. The Agency will review the documents of the Contractor's systematic and direct, meaningful recruitment efforts to determine whether the Contractor has complied with the criteria in "Required Contract Provisions Federal-Aid Construction Contracts" (FHWA Form 1273), Section II Nondiscrimination.

When filling OJT positions Contractors are encouraged to hire previously approved trainees who have not yet completed their training.

#### (b) Training Requirements

The intent of these provisions is to provide real and meaningful training in the construction crafts. Off-Site training is permissible only when it is an integral part of an approved training program and does not comprise a significant part of the overall training. In addition:

- A Contractor, not registered as a training agent, may choose to adopt a standardized OJT Program. Standardized OJT Programs are published at the OCR website at: https://www.oregon.gov/ODOT/Business/OCR/Pages/Workforce-Development.aspx
- Some job classifications such as flagger, bookkeeper, clerk/typist or secretary are prohibited from OJT Programs.
- OJT Programs shall always maintain the approved ratio of trainees to journey level workers On-Site.

- OJT Programs shall always maintain the approved types and numbers of equipment On-Site.
- No employee shall be registered as a trainee in any job classification the employee has completed leading to journey level status, or for any job classification in which the employee has been employed as a journey level worker. The Contractor shall keep records, and provide to the Agency, if requested, documents on each trainee.
- Trainees shall be pre-approved by the Agency.

OJT Program trainees shall be paid the journey level rate specified in the contract for the type of work performed.

#### (c) Reports

The Contractor and each Subcontractor with an OJT Program shall complete and submit the following reports to the Engineer according to the instructions on their respective forms:

- The training program forecast using the "Training Program Approval Request (TPAR)" (Form 734-2880) shall be submitted prior to or at the preconstruction conference.
- Before the trainee begins work, an "Apprentice/Trainee Approval Request (ATAR)" (Form 734-2878) shall be submitted. Attach a copy of the "Training Program Approval Request (TPAR)" (Form 734-2880) to the "Apprentice/Trainee Approval Request (ATAR)" (Form 734-2878). The Contractor and trainee must sign and return a copy of the training program that will be utilized. The Contractor shall provide certification to the trainee upon completion of the OJT Program and also submit a copy to OCR. Upon completion of the Contract, a certification shall be given to each trainee and to the Agency to document the number of hours and training completed by the individual.
- Each month the Contractor shall submit the "Monthly Employment Utilization Report" (Form 731-0668). This report is required of the Contractor and Subcontractors (for contracts that require certified payrolls), regardless of their participation in the Apprenticeship or On-the-Job Training programs.
- Each month the Contractor shall submit an "Apprentice/Trainee Monthly Progress Report (MPR)" (Form 734-2879) for each trainee. This form is used to report Qualified Hours for trainees and will be the source document for estimated monthly progress payments to the Contractor.

Forms are published on the ODOT OCR website at:

https://www.oregon.gov/ODOT/Business/OCR/Pages/Forms.aspx

#### **SECTION 5: MONITORING AND COMPLIANCE**

The Contractor has the primary responsibility to monitor compliance levels throughout the Contract and to ensure the Training Goal is met. If the Contractor decides any of the training hours are to be provided by a Subcontractor, the Contractor shall ensure that the Subcontract contains the appropriate training clauses that obligate the Subcontractor. This shall not relieve the Contractor of the Contractor's primary responsibility.

At the request of the Agency, the Contractor will meet with the Agency to review records related to training. The Agency, through meetings and progress records provided by the Contractor, will provide the Contractor with informational compliance and reimbursement data including:

- The Contractor's training forecasts compared with the actual Qualified Hours achieved.
- Total Qualified Hours and payment reimbursement summary.
- For information purposes only, consolidated summary reports by OJT craft and apprenticeship crafts.

The Agency will track training activities provided by Contractor for the OJT trainees and apprentices.

#### **SECTION 6: MEASUREMENT AND PAYMENT**

#### (a) General

The quantity of Qualified Hours will be paid for at the Contract unit price of \$20 per hour for the item "Training."

No separate or additional payment will be made for failure to achieve the Training Goal. See (b) below for Disincentive.

No separate or additional payment will be made for Qualified Hours achieved in excess of 150% of the Training Goal. No Disincentive applies.

If the Contractor achieves from 100% to 150% of the Training Goal, the Agency will reimburse the Contractor for Qualified Hours.

After the Second Notification, the Agency will review the final reports required and make adjustments. Any additional reimbursements will be paid on the next Contract payment voucher.

#### **Examples of achieving the Training Goal:**

Example A: Training Goal = 1,000 hours; Pay Item = 20/h; Contractor achieves 100% of the Qualified Hours (fulfilled the goal): therefore 1,000 hours x 20.00/h = 20.00/h reimbursed (during progress of the Contract).

Example B: Training Goal = 1,000 hours; Pay Item = 20/h; Contractor achieves 150% of the Qualified Hours or 1,500 hours (exceeded the goal): therefore 1,500 hours x 20.00/h = 30,000 reimbursed (during progress of the Contract).

Example C: Training Goal = 1,000 hours; Pay Item = 20/h; Contractor achieves an actual 1,525 Qualified Hours (exceeded even 150% of the goal): therefore 1,500 hours x 20.00/h = pay of 30,000 reimbursed (during progress of the Contract).

#### (b) Disincentive

If, at the Second Notification, the Contractor has not achieved the Training Goal there will be no payment (disincentive) to the Contractor and no Qualified Hours as follows:

Regardless of all prior partial payments for the Pay Item "Training," a correction equal to 100% of the Pay Item goal times the Pay Item price will be subtracted from the final payment due the Contractor on the next Contract payment voucher.

#### Examples of *not* achieving the Training Goal:

Example A: Training Goal = 1,000 hours; Pay Item = 20/h; Contractor achieves an actual 500 Qualified Hours (failed to meet the goal): A disincentive applies; therefore 1,000 hours x 20.00/h = line item deduction of 20.000/h will show on the next Contract payment voucher. The previously paid qualified hours (500/x) = 10.000/h00 under the pay item on vouchers will remain and the net impact in this example will be the 20.000/h00 deduction offset by the 10.000/h00 qualified and paid hours for a net reduction of 10.000/h00.

Example B: Training Goal = 1,000 hours; Pay Item = \$20/hr; Contractor achieves zero Qualified Hours (failed to meet the goal): A disincentive applies; therefore 1,000 hours x  $$20.00/hr = \underline{line item deduction}$  of \$20,000 will show on the next Contract payment voucher.

If, as a result of a line item deduction, a net amount is due the Agency, the Contractor shall pay the Agency within 45 Calendar Days of notice of such deficiency.



# INVITATION TO BID #2023-90 Jennings Ave: OR99E to Oatfield Rd Project ADDENDUM NUMBER 1 November 7, 2023

On October 19, 2023, Clackamas County ("County") published Invitation to Bid #2023-90 ("BID"). The County has found that it is in its interest to amend the BID through the issuance of this Addendum #1. Except as expressly amended below, all other terms and conditions of the original BID and subsequent Addenda shall remain unchanged.

1. The Bid Closing date is hereby changed from November 16, 2023 at 2:00PM to **November 30, 2023 at 2:00PM** 

V.M.



## INVITATION TO BID #2023-90 Jennings Ave: OR99E to Oatfield Rd Project ADDENDUM NUMBER 2 November 15, 2023

On October 19, 2023, Clackamas County ("County") published Invitation to Bid #2023-90 ("BID"). The County has found that it is in its interest to amend the BID through the issuance of this Addendum #2. Except as expressly amended below, all other terms and conditions of the original BID and subsequent Addenda shall remain unchanged.

This letter is to inform you of a change in the Bid Closing date for this Project and to make changes to the Bid Booklet, Special Provisions, Replies to Clarifying Questions Received and Reissuance of Plan Set.

The time and date of Bid Closing on this Project, previously scheduled for Bid Closing at 2:00:00 p.m. on November 30, 2023, has been changed to **December 6, 2023 at 2:00PM**.

## The following changes are made to the Project Bid Booklet:

In Section 13, replace the Required Contract Provisions Federal-Aid Construction Contracts with the Revised October 23, 2023 version.

## The following changes are made to the Project Special Provisions:

1. Subsection 00221.98 Payment, Method "B"- Add the following to this section 'This method is relevant to items in Section s 00222, 00223, 00224, 00225, 00226, 00227, and 00228. Any and all pay items under these listed sections; materials, equipment, labor etc. are paid as lump sum /incidental under this bid item.

## The following are clarifications to questions received:

- 1. Q: We are looking for the project CAD files. Typically we are looking for finish grade and existing grade.
  - A: CAD files will be provided to the successful bidder after award of contract.
- 2. *Q: I would also like to request a bid item be added for flagging. Currently there is a lot of risk for DBE companies to bid lump sum traffic control so they don't bid but if there was a bid item for flagging they would bid.* 
  - A: Flagging costs will be kept as incidental to BI 3 "Temporary Work Zone Traffic Control, Complete".

3. Q: What are the limits for placing embankment on the project? Spec. 00330.42(c)(3) states "Construct the outer 12 inches of embankments with suitable materials to establish slope stabilization through permanent seeding." but no quantities are defined. Can you please provide some insight as to where you expect placing embankment and your calculations for this quantity? Is the quantity for embankment included in the 2200 CY of General Excavation?

A: This outer 12 inches of embankment is part of the 1,970 cubic yards of calculated total amount of embankment material in place that is called out in Section 00330.03. In general these embankment areas would be on open slopes or fills found behind sidewalks, around driveways and biofiltration swale side banks. These areas would also have an application of compost erosion blanket (BI 11) for fine grading and seeding establishment.

#### The Following changes have been made to the Online Bid Documents:

1. File 1831-2234\_K19276\_15.4\_Plans\_Bid Set.pdf has been replaced on the OneDrive link and a new file containing a clear set of plans titled 22234 Jennings\_Plans\_Bid Set\_11-14-23.pdf.

No changes were made to the plans. However, the plans file that was placed on the OneDrive link was corrupt and had shading errors, incorrect limits, and other line errors on various plan sheets.

Plan Set 1831-2234\_K19276\_15.4\_Plans\_Bid Set.pdf is no longer part of these documents

### The following changes are made to the INVITATION TO BID:

1. INVITATION TO BID - The time and date of Bid Closing on this Project, previously scheduled for Bid Closing at 2:00:00 p.m. on November 30, 2023, has been postponed to 2:00:00 p.m. on December 6, 2023.

## The following changes are made to the INSTRUCTIONS TO BIDDERS:

1. INSTRUCTIONS TO BIDDERS, Article 8 Submission of Bid - The time and date of Bid Closing on this Project, previously scheduled for Bid Closing at 2:00:00 p.m. on November 30, 2023, has been postponed to 2:00:00 p.m. on December 6, 2023.

# The following changes are made to the SUPPLEMENTAL INSTRUCTIONS TO BIDDERS:

1. SUPPLEMENTAL INSTRUCTIONS TO BIDDERS, paragraph 2 - The time and date of Bid Closing on this Project, previously scheduled for Bid Closing at 2:00:00 p.m. on November 30, 2023, has been postponed to 2:00:00 p.m. on December 6, 2023.

#### The following changes are made to the BID PROPOSAL FORM:

1. BID PROPOSAL FORM, BID CLOSING/OPENING - The time and date of Bid Closing/Opening on this Project, previously scheduled for Bid Closing/Opening at 2:00:00 p.m. on November 30, 2023, has been postponed to 2:00:00 p.m. on December 6, 2023. See attached updated form with new bid date.

# The following changes are made to the FIRST-TIER SUBCONTRACTOR DISCLOSURE FORM:

1. FIRST-TIER SUBCONTRACTOR DISCLOSURE FORM - The time and date of Bid Opening on this Project, previously scheduled for Bid Opening at 2:00:00 p.m. on November 30, 2023, has been postponed to 2:00:00 p.m. on December 6, 2023. See attached updated form with new bid date.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

Attachments:

New Required Contract Provisions Federal-aid Construction Contracts

 $\sqrt{m}$ 

End of Addendum #2