To request translation or disability-related accommodations, please contact us at **DTDcompliance@clackamas.us** | **503-742-4400**.

Si quiere solicitar servicios de traducción o adaptaciones para la discapacidad, contáctenos en/al **DTDcompliance@clackamas.us** | **503-742-4400**.

Чтобы запросить перевод или приспособления, связанные с инвалидностью, пожалуйста, свяжитесь с нами по:
DTDcompliance@clackamas.us | **503-742-4400**.

Щоб попросити переклад або спеціальні послуги для осіб з особливими потребами, зверніться до нас, скориставшись такими контактними даними:
DTDcompliance@clackamas.us | **503-742-4400**.

如需翻译服务或残障相关的协助，请与我们联系：
DTDcompliance@clackamas.us | **503-742-4400**。

Để yêu cầu dịch vụ dịch thuật hoặc điều chỉnh liên quan đến tình trạng khuyết tật, vui lòng liên hệ với chúng tôi qua **DTDcompliance@clackamas.us** | **503-742-4400.**

Clackamas County
www.clackamas.us

Table 5-3a 20-Year Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description
1000	County-wide	ITS Plan Program	N/A	Develop a program to support the implementation of the County's ITS Plan and support the County's efforts to make improvements to traffic operations based on the ITS Plan. Deploy traffic responsive signal timing, ramp metering, traffic management equipment for better routing of traffic during incidents along the three key ODOT corridors - I-205, I-5, 99E. Install signal controller upgrades and update County ITS plan.
1001	County-wide	Transportation Safety Action Plan Program	N/A	Develop a program to support the implementation of the County's TSAP and support the County's efforts to make improvements based on the outcomes of the road safety audits and other safety studies.
1002	5-11a	122nd Ave	Eagle Glen Dr to Hubbard Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1003	5-11a	122nd Ave	Sunnyside Rd to Hubbard Rd	Fill gaps in pedestrian facilities, turn lanes at Mather Rd
1004	5-11a	122nd Ave	Sunnyside Rd to Timber Valley Dr	Add bikeways and turn lanes at major intersections
1005	5-11a	132nd Ave	Sunnyside Rd to OR 212	Add bikeways, pedestrian facilities, traffic calming and turn lanes at major intersections
1006	5-11a	142nd Ave	Sunnyside Rd to OR 212	Add bikeways and pedestrian facilities
1007	5-11a	72nd Ave Multi-Use Path Connection	Thompson Rd to Harmony Rd	Construct multi-use path
1008	5-11a	82nd Dr	OR 212 to Lawnfield Rd	Fill in bikeways and pedestrian facilities gaps
1009	5-11a	85th Ave	Causey Ave to Monterey Ave	Add sidewalks and bikeways. Perform Pedestrian Safety Audit to verify lighting, crosswalk striping and signing at Causey Ave.
1010	5-11a	92nd Ave	Johnson Creek Blvd to Emmert View Ct	Fill gaps in pedestrian facilities
1011	5-11a	97th Ave / Mather Rd	Lawnfield Rd to Summers Ln	Add bikeways, pedestrian facilities and eastbound left turn lanes at Mather Rd / Summers Ln
1012	5-11a	Boyer Dr	OR 213 to Fuller Rd	Construct new 2 lane roadway with turn lanes at OR 213 and Fuller Rd, bikeways and pedestrian facilities; install flashing yellow arrow for left turns on northbound and southbound approaches at OR 213 intersection.
1013	5-11a	Boyer Dr / 85th Ave / Spencer Dr	OR 213 to I-205 bike path	Add bikeways
1014	5-11a	Causey Ave	Fuller Rd to I-205	Add bikeways and shared facility markings in accordance with the Active Transportation Plan.
1015	5-11a	Clackamas Industrial area multi-modal improvements	N/A	Complete bike and pedestrian connections within the Clackamas Industrial area on Jennifer St., Evelyn St., 106th Ave, 122nd Ave, 130th Ave and 135th Ave.
1016	5-11a	Clackamas Regional Center Bike/Pedestrian Corridors	N/A	Construct pedestrian and bike improvements as described in the Clackamas Regional Center Pedestrian / Bicycle Plan
1017	5-11a	Clackamas Town Center Alternative Performance Standards Study	Clackamas Regional Center	Develop alternative performance standards for the intersections within the Clackamas Regional Center.
1018	5-11a	Clackamas Town Center Circulation Plan	West of the Town Center	Study area circulation and create plan
1019	5-11a	Flavel Dr	Alberta Ave to County boundary	Add bikeways in accordance with the Active Transportation Plan.
1020	5-11a	Fuller Rd	Otty St to Johnson Creek Blvd	Add pedestrian facilities, turn lanes, on-street parking, central median and landscaping.
1021	5-11a	Fuller Rd / King Rd Improvements	Fuller Rd / King Rd intersection	Restrict access to right-in/right-out only

Table 5-3a 20-Year Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description
1022	5-11a	Harmony Rd	OR 213 to OR 224	Construct bikeways and pedestrian facilities. Linwood Ave to Aquatic Center, construct in accordance with the Active Transportation Plan. Provide left turn movement for cyclists from Harmony Rd to CCC Harmony Campus and a pedestrian crossing.
1023	5-11a	Harmony Rd	Railroad Ave / Linwood Ave / Harmony Rd	Railroad crossing and intersection improvements based on further study of intersection operations including bikeways and pedestrian facilities to be undertake jointly by the City of Milwaukie and the County
1024	5-11a	Harmony Rd / Sunnyside Rd	Harmony Rd / Sunnyside Rd / OR 213 intersection	Extend queue storage and double left turn lanes on westbound approach and rebuild median, including pedestrian island; extend queue storage on eastbound approach and install median; convert to right-in-right-out accesses on frontage road.
1025	5-11a	I-205 Multi-Use Path Connection	Between Sunnyside Rd and Sunnybrook Blvd	Construct ADA compliant access to the commercial area from the I-205 Multi-Use Path
1026	5-11a	I-205 Multi-Use Path Gap	OR 224/OR 213 to OR 212	Study the I-205 multi-use path gap to create a plan for connection and path completion in accordance with the Active Transportation Plan
1027	5-11a	Johnson Creek Blvd	55th Ave to I-205	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1028	5-11a	Johnson Creek Blvd	Johnson Creek Blvd near 79th Pl	Add signal to either Johnson Creek Blvd and 79th Pl or 80th Ave
1029	5-11a	Johnson Creek Blvd	55th Ave to Bell Ave	Widen to 3 lanes with bikeways and pedestrian facilities
1030	5-11a	Johnson Creek Blvd	Johnson Creek Blvd / OR 213 intersection	Extend westbound left-turn lane and rebuild median; install dual northbound and southbound left-turn lanes
1031	5-11a	Johnson Creek Blvd	OR 213 to 92nd Ave	Add pedestrian facilities with a crossing near 77th Ct, restripe for bikeways. Analyze for turn lane improvements at 92nd Ave.
1032	5-11a	Johnson Rd	SE Lake Rd to North Clackamas Park Trail	Identify bike/pedestrian connections to fill gaps along 82nd Ave
1033	5-11a	Lake Rd	Lake Rd / International Way intersection	Add northbound right-turn lane
1034	5-11a	Linwood Ave	Monroe St to Johnson Creek Blvd	Add pedestrian facilities in accordance with the Active Transportation Plan.
1035	5-11a	Monroe St	72nd Ave to Fuller Rd	Add bikeways, pedestrian facilities and traffic calming in accordance with the Active Transportation Plan.
1036	5-11a	Monroe St / 72nd Ave / Thompson Rd / Fuller Rd	Linwood Ave to Causey Ave	Add bikeways and traffic calming in accordance with the Active Transportation Plan.
1037	5-11a	Monterey Ave	Stevens Rd to Bob Schumacher Rd	Construct collector roadway with bikeways and pedestrian facilities
1038	5-11a	Monterey Ave	OR 213 to Fuller Rd	Construct new 2 lane extension with pedestrian facilities and bikeways. Install flashing yellow arrow for left-turns on northbound and southbound approaches at OR 213 intersection.
1039	5-11a	North Clackamas Regional Park Trail	Linwood Ave to North Clackamas Park Complex	Construct multi-use path
1040	5-11a	North Clackamas Regional Parks Trail	OR 213 to Linwood Ave	Construct multi-use path
1041	5-11a	Otty Rd	OR 213 to 92nd Ave	Improve to minor arterial standard consistent with Fuller Road Station Plan; improve curb radius; add turn lanes, on-street parking, central median, landscaping, bikeways and pedestrian facilities. Install pedestrian crossings between Fuller Rd and I-205 and near 91st Ave.
1042	5-11a	Otty St	Otty St / OR 213 / Otty Rd	Realign Otty St with Otty Rd at OR 213; install dual westbound left-turn lanes; install flashing yellow arrow for left-turns on northbound and southbound approaches.

Table 5-3a 20-Year Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description
1043	5-11a	Southwest Connector Multi-Use Path	North Clackamas Aquatic Center access road to 82nd Ave	Construct multi-use path in accordance with the Active Transportation Plan.
1044	5-11a	Springwater Rd	OR 224 to Hattan Rd	Widen to 3 lanes with shoulders (in accordance with the Active Transportation Plan between Clackamas River Dr and Gronlund Rd) and pedestrian facilities; bridge remains two lanes
1045	5-11a	Sunnyside Rd	93rd Ave to 126th Ave	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1046	5-11a	Sunnyside Rd	Sunnyside Rd / Stevens Rd intersection	Intersection improvements, such as additional turn lanes, turn lane extensions, and/or signal timing modifications
1047	5-11a	Tolbert St Overcrossing	82nd Dr to Industrial Way	Construct new 2 lane overcrossing with bikeways and pedestrian facilities
1048	5-11b	282nd Ave	US 26 to OR 212	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1049	5-11b	Amisigger Rd / Kelso Rd	OR 224 to Kelso / Richey Rd	Add paved shoulders; turn lanes at Amisigger/OR 212 and Kelso/Richey; smooth curves.
1050	5-11b	Arrah Wanna Blvd	US 26 to Fairway Ave	Add paved shoulders. In the interim, add 4-foot paved shoulders.
1051	5-11b	Cazadero Multi-Use Trail	Community of Boring to City of Estacada	Construct multi-use path in accordance with the Active Transportation Plan.
1052	5-11b	Compton Rd	US 26 to 352nd Ave	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1053	5-11b	Dodge Park Rd Bridge	~192 feet south of Pipeline Rd	Replace bridge nearing the end of its useful life and include paved shoulders
1054	5-11b	Eagle Creek Rd	Firwood Rd to Duus Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1055	5-11b	Eagle Creek Rd	Currin Rd to Duus Rd	Remove horizontal curve, relocate intersection, add paved shoulders and turn lanes at major intersection; investigate speed zone south of Currin Rd
1056	5-11b	Fairway Ave	Arrah Wanna Blvd to Salmon River Rd	Add paved shoulders
1057	5-11b	OR 211	OR 211 / Judd Rd intersection	Realign roadway
1058	5-11b	Richey Rd	Kelso Rd to OR 212	Add paved shoulders and left turn lane at Richey Rd and OR 212
1059	5-11b	Welches Rd	US 26 to Birdie Ln	Add paved shoulders; add pedestrian facilities in Welches rural center; evaluate pedestrian crossing near Stage Stop Rd; add multi-use path. Improve pedestrian crossing near Fairway Ave with advance signs and split flashing beacons
1060	5-11c	Aldercrest Dr	Thiessen Rd to Oatfield Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1061	5-11c	Concord Rd	River Rd to Oatfield Rd	Fill gaps in pedestrian facilities
1062	5-11c	Concord Rd	River Rd to Oatfield Rd	Add turn lanes at major intersections
1063	5-11c	Courtney Ave	OR 99E to Oatfield Rd	Fill gaps in pedestrian facilities and bikeways
1064	5-11c	Courtney Ave	River Rd to OR 99E (McLoughlin Blvd)	Construct pedestrian facilities / complete gaps on the south side; add bikeways
1065	5-11c	Harold Ave	Concord Rd to Roethe Rd	Add pedestrian facilities and traffic calming
1066	5-11c	Hull Ave	Wilmot St to Tims View Ave	Fill gaps in pedestrian facilities
1067	5-11c	Jennings Ave	Webster Rd to OR 99E	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1068	5-11c	Jennings Ave	River Rd to Oatfield Rd	Widen to 2-lane urban minor arterial standard with bikeway and pedestrian facilities infill

Table 5-3a 20-Year Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description
1069	5-11c	Oak Grove Blvd	Oatfield Rd to River Rd	Fill gaps in pedestrian facilities and bikeways
1070	5-11c	Oatfield Rd	Jennings Ave to Lake Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1071	5-11c	Oatfield Rd	Oatfield Rd / Park Rd intersection	Install traffic signal and add turn lanes
1072	5-11c	Oatfield Rd	Oatfield Rd / McNary Rd intersection	Add southbound and eastbound left-turn lanes
1073	5-11c	Park Ave	River Rd to OR 99E (McLoughlin Blvd)	Add pedestrian facilities
1074	5-11c	River Rd	Lark St to Courtney Ave	Add pedestrian facilities
1075	5-11c	River Rd	Oak Grove Blvd to Risley Ave	Fill gaps in bikeways in accordance with the Active Transportation Plan and fill gaps in pedestrian facilities
1076	5-11c	School Pedways	Johnson Rd / Clackamas Rd / Webster Rd	Fill gaps in pedestrian facilities on Johnson Rd, Clackamas Rd and Webster Rd within 1/4 mile of schools
1077	5-11c	Thiessen Rd	Thiessen Rd / Aldercrest Rd intersection	Add turn lanes on Thiessen Rd; consider converting to two-way stop controlled
1078	5-11c	Torbank Rd	River Rd to Trolley Trail	Fill gaps in pedestrian facilities
1079	5-11d	65th Ave	65th Ave / Elligsen Rd / Stafford Rd intersection	Construct roundabout
1080	5-11d	Advance Rd	53rd Ave to 43rd Dr	Grade and sight distance improvements
1081	5-11d	Borland Rd	Tualatin city limits to Stafford Rd	Add paved shoulders in accordance with the Active Transportation Plan and turn lanes at major intersections
1082	5-11d	Borland Rd	Stafford Rd to West Linn city limits	Add paved shoulders in accordance with the Active Transportation Plan
1083	5-11d	Carman Dr	Lake Oswego city limits to Roosevelt Ave	Add bikeways and pedestrian facilities; analyze for turn lanes
1084	5-11d	Childs Rd	Sycamore Ave to 65th Ave	Transfer roadway to local jurisdiction
1085	5-11d	French Prairie Bridge	Willamette River near I-5	Construct a bridge in accordance with the Active Transportation Plan
1086	5-11d	Rosemont Rd	Stafford Rd to West Linn	Add paved shoulders and turn lanes at major intersections
1087	5-11d	Stafford Rd	I-205 to Boeckman Rd / Advance Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1088	5-11d	Stafford Rd	Rosemont Rd to I-205	Add paved shoulders in accordance with the Active Transportation Plan and turn lanes at major intersections
1089	5-11d	Stafford Rd	Stafford Rd / Childs Rd intersection	Install traffic signal and southbound and northbound turn lanes or roundabout
1090	5-11d	Stafford Rd	Rosemont Rd to I-205	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1091	5-11d	Tonquin Trail	Willamette River through Wilsonville	Construct bike / pedestrian facilities pursuant to the Tonquin Trail Master Plan
1092	5-11d	Wilsonville Rd / Ladd Hill Rd	Wilsonville Rd / Ladd Hill Rd	Install Collision Countermeasure System
1093	5-11e	Airport Rd	Airport Rd / Miley Rd intersection	Install traffic signal
1094	5-11e	Barlow Rd	Barlow Rd / OR 99E intersection	Add dual left-turn lanes on southbound Barlow Rd
1095	5-11e	Beavercreek Rd	Lower Highland Rd to Butte Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements

Table 5-3a 20-Year Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description
1096	5-11e	Beavercreek Rd	Ferguson Rd to Spangler Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1097	5-11e	Beavercreek Rd	Henrici Rd to Yeoman Rd/Steiner Rd	Add paved shoulders in accordance with the Active Transportation Plan and turn lanes at major intersections.
1098	5-11e	Beavercreek Rd	Beavercreek Rd / Leland Rd / Kamrath Rd intersection	Construct roundabout with additional analysis
1099	5-11e	Canby-Marquam Highway	Canby-Marquam Hwy / Lone Elder Rd intersection	Reconstruct intersection; install northbound left-turn lane and southbound right-turn lane
1100	5-11e	Canby-Marquam Highway	~1,900 ft south of Barnards Rd	Replace bridge nearing the end of its useful life with 2-lane structure including paved shoulders
1101	5-11e	Clarkes Four Corners Intersection	Beavercreek Rd / Unger Rd	Reconstruct intersection
1102	5-11e	Emerald Necklace Trail	To Canby Ferry	Extend Molalla Forest Rd to Locust St in accordance with the Active Transportation Plan.
1103	5-11e	Ferguson Multi-Use Path	Thayer Rd to Ferguson Rd	Multi-use path to connect Ferguson Rd to Thayer Rd
1104	5-11e	Fischers Mill Rd	Fischers Mill / Hattan Rd intersection	Install eastbound left-turn lane
1105	5-11e	Graves Rd / Passmore Rd / Mulino Rd / OR 213	Graves Rd / Passmore Rd/ Mulino Rd/ OR 213	Work in conjunction with the Molalla River School District, ODOT and community stake-holders to complete a safety audit to look at all options for the safe movement of Mulino Elementary School students in relation to the adjacent transportation system. Utilize the results from the audit to develop a list of projects and/or programs to maximize safety for all users.
1106	5-11e	Greater Arndt Rd/I-5/Canby Access Feasibility Study	Southwest County in the vicinity of Arndt Rd/I-5/Canby	Conduct an alternatives analysis and land use study to identify and consider roadway improvements to address access to I-5 within the Southwest County and address capacity deficiencies.
1107	5-11e	Hattan Rd	Hattan Rd/Gronlund Rd intersection	Install southbound right-turn lane
1108	5-11e	Henrici Rd	Beavercreek Rd to Ferguson Rd	Add paved shoulders and turn lanes at major intersections. Remove horizontal and vertical curves
1109	5-11e	Holly St	Territorial Rd to Canby Ferry	Add paved shoulders in accordance with the Active Transportation Plan.
1110	5-11e	Hult Rd	OR 211 to Unger Rd	Re-open and improve Hult Rd
1111	5-11e	Klang's Mill Bridge	~1,000 ft north of OR 211	Replace bridge nearing the end of its useful life
1112	5-11e	Lone Elder Rd Bridge	~5,800 feet east of Barlow Rd	Replace bridge (nearing the end of its useful life) and include paved shoulders
1113	5-11e	Maplelane Rd	Beavercreek Rd to Ferguson Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1115	5-11e	Molalla Ave Flooding	Just south of city of Molalla	Construct bridge to resolve flooding issues

Table 5-3a 20-Year Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description
1116	5-11e	Mulino Rd	Mulino Rd / 13th Ave	Relocate intersection to south away from railroad trestle
1117	5-11e	OR 170	OR 99E to Macksburg Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1118	5-11e	Redland Rd	OR 213 to Hattan Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1119	5-11e	Redland Rd	Redland Rd / Springwater Rd intersection	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1120	5-11e	Redland Rd	Redland Rd / Holly Rd intersection	Install traffic signal and westbound and northbound left-turn lanes or roundabout
1121	5-11e	Redland Rd	Redland Rd / Ferguson Rd intersection	Construct roundabout
1122	5-11e	Ridge Rd	~1 miles north of Lower Highland Rd	Fix sinkhole
1123	5-11e	Springwater Rd	Springwater Rd / Clackamas River Dr intersection	Install signal at Clackamas River Dr
1124	5-11e	Springwater Rd	400 ft east of Hattan Rd	Construct bridge to accommodate paved shoulders
1125	5-11e	Springwater Rd	Hattan Rd to Bakers Ferry Rd	Add paved shoulders in accordance with the Active Transportation Plan and turn lanes at major intersections
1126	5-11e	Township Rd	Central Point Rd to Canby City limit	Add paved shoulders and turn lanes at major intersections
1127	5-11e	Union Mills Rd	OR 213 to OR 211	Add turn lanes at major intersections
1128	5-11e	Union Mills Rd	OR 213 to OR 211	Construct a shoulder on the south side of the roadway
1129	5-11e	Upper Highland Rd	Beavercreek Rd to Lower Highland Rd	Perform road safety audit or transportation safety review to identify appropriate safety improvements
1130	5-11c	Oetkin Rd - Naef Rd	Thiessen Rd to River Rd	Construct bike boulevard consistent with the Active Transportation Plan
1131	5-11c	River Rd	Park Ave to Glen Echo Ave	Construct buffered bike lane in accordance with the Active Transportation Plan.
1132	5-11a	Bob Schumacher Rd	Otty Rd to Sunnyside Rd	Investigate improved striping including centerline rumble stripe.
1133	5-11a	97th Ave	Sunnybrook Blvd to Mather Rd	Investigate improved striping including outside fog lines and rumble striping. Verify lighting, drainage and surface friction.
1134	5-11a	92nd Ave	Phillips Pl	Install a pedestrian crossing near Phillips Pl

Table 5-3a 20-Year Capital Projects

Project ID	Map	Project Name / Street Name	Segment / Locations	Project Description
1135	5-11a	Otty St	80th Ave	Install a pedestrian crossing near 80th Ave
1136	5-11a	Fuller Rd	Boyer Dr to Sunnyside Dr	Install pedestrian crossings near Boyer Dr, Causey Ave, Stephanie Ct and Southgate St
1137	5-11b	Brightwood Loop Rd	US 26 to US 26	Add 4-foot paved shoulders
1138	5-11a	SE 242nd Avenue	SE 242nd Ave/SE Borges Road intersection	Extend SE Kingswood Way from SE Borges Road to SE 242nd Avenue. Close SE 242nd Avenue/SE Borges Road intersection to through traffic
1139	5-11a	SE 242nd Avenue	SE 242nd Ave/SE Bohna Park Road intersection	Access management on northwest corner; delineated shoulders on SE 242nd Avenue
1140	5-11a	SE Foster Road	Happy Valley boundary to OR 212	Widen shoulder based on operational and safety analysis during project Development
1141	5-11a	SE Sunnyside Road	SE 187th Avenue to OR 212	Widen shoulder based on operational and safety analysis during project Development
1142	5-11a	SE Sunshine Valley Road	SE 242nd Avenue to east edge of Damascus Mobility Plan area	Widen shoulder based on operational and safety analysis during project Development
1143	5-11a	SE Tillstrom Road	SE Foster Road to SE 242nd Avenue	Widen shoulder based on operational and safety analysis during project Development