



INVITATION TO BID #2018-35
SE Last Road Improvements
ADDENDUM NUMBER 1
May 21, 2018

On May 9, 2018, Clackamas County ("County") published Invitation to Bid #2018-35 ("BID"). The County has found that it is in its interest to amend the BID through the issuance of this Addendum #1. Except as expressly amended below, all other terms and conditions of the original BID shall remain unchanged.

1. Remove and replace Bid Schedule Bid Alternate #1 with the attached Bid Schedule Alternate #1, titled SE LAST ROAD PUBLIC IMPROVEMENTS Bid Schedule- Issued for Construction BID ALTERNATE #1, May 17, 2018 Addendum #1:

*Note the following added item:

<u>Number</u>	<u>Item</u>	<u>Unit</u>	<u>Quantity</u>
34	Aggregate Base	CY	250

2. The following is clarification to Bid Alternate #1:

In addition to the required storm water improvements, Bid Alternate #1 pertains only to the Proposed Sidewalk and Flat Bench areas described on Plan Sheet 7, Cross Section B/7. The new 6.0' sidewalk on SE Evelyn Street shown on plan sheet 8 is also included in Bid Alternate #1.

3. The following Changes are made to the Project Plans:

- a. **SHEETS 5 thru 7 and 10** – The plan sheets refer to a 2" Min. AC Overlay and grinding at the beginning and end of the project limits on Last Road. The AC overlay and grinding are eliminated from the project and are not included in the bid schedule of items.
- b. **SHEET 7** – In Cross Section B/7 – the 1 ½" – ¾" Granular Drain Backfill is not required to be placed underneath the Proposed Sidewalk and Flat Bench sections. The quantities listed in Special Provision Section 01012.80 for the "Water Quality Swale, Last Road" do not include quantities under the Proposed Sidewalk and Flat Bench sections and, therefore, do not need to be changed.
- c. **SHEET 9** – Delete reference to trees (Zelkova Serrata 'Schmidtflow') and groundcover plantings (Massachussetts Kinnikinnick). Delete reference to grind asphalt and AC overlay referenced in Pavement Sections Note #2.
- d. **SHEETS 11 thru 13** – The cross sections will be updated to eliminate the 2" AC overlay. As a result, the proposed curb height will drop 2". The back of walk elevations are expected to remain the same elevation.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

Attachments:

SE LAST ROAD PUBLIC IMPROVEMENTS Bid Schedule- Issued for Construction BID
ALTERNATE #1, May 17, 2018 Addendum #1

End of Addendum #1

SE LAST ROAD PUBLIC IMPROVEMENTS
Bid Schedule - Issued For Construction

BID ALTERNATE #1
MAY 17, 2018 - ADDENDUM #1

ITEM	SPEC	DESCRIPTION	UNIT	QUAN.	UNIT PRICE	TOTAL
Part 00100 - General Conditions						
1	00196	Extra Work as Authorized	FA	1	-	\$ 10,000.00
Part 00200 - Temporary Features and Appurtenances						
2	00210	Mobilization	LS	1		
3	00225	Temporary Protection and Direction of Traffic	LS	1		
4	00225	Temporary Signs - Business Access and Traffic Zone	SQFT	250		
5	00225	Temporary Barricades, Type 2	EACH	2		
6	00225	Temporary Delineators	EACH	50		
7	00225	Flaggers	HR	200		
8	00280	Temporary Erosion Control	LS	1		
11	00280	Construction Entrance, Type 1	EACH	1		
12	00280	Sediment Fence, Unsupported	LF	30		
13	00280	Inlet Protection, Type 3	EACH	7		
14	00280	Compost Filter Sock, 12 inch	FOOT	250		
15	00290	Pollution Control Plan	LS	1		
Part 00300 - Roadwork						
16	00305	Construction Survey Work	LS	1		
17	00310	Removal of Structures and Obstructions	LS	1		
18	00310	Asphalt Pavement Saw Cutting	LF	300		
19	00310	Concrete Pavement Saw Cutting	LF	195		
20	00320	Clearing and Grubbing	LS	1		
21	00330	General Excavation	CY	400		
22	00350	Riprap Geotextile, Type 1, woven	SQYD	35		
24	00390	Rip-Rap Basins, Class 50, 10' x 7' x 1.5'	EACH	1		
Part 00400 - Drainage and Sewers						
25	00415	Main Line Storm Video Inspection	FOOT	332		
26	00445	12 Inch Storm Pipe, 5 feet Depth	FOOT	282		
27	00445	12 Inch Storm Pipe, 10 feet Depth	FOOT	50		
29	00470	Concrete Manholes, 48 Inch Storm	EACH	1		
30	00470	Concrete GB-2 Inlet Catch Basin	EACH	1		
31	00490	Major Adjustment of Manholes	EACH	1		
32	00490	Adjusting Boxes and Valves	EACH	8		
33	00495	Trench Resurfacing (rock base and HMAC)	SQYD	150		
Part 00600 - Bases						
34	00641	Aggregate Base	CY	250		
Part 00700 - Wearing Surfaces						
36	00744	HMAC Level 2, 3/4 Inch Dense PG 64-22 ACP Mixture	TON	50		
41	00759	Concrete Walks	SF	7,060		
44	00759	Extra for New Sidewalk Ramps (Parallel)	EACH	1		
Part 00900 - Permanent Traffic Control and Illumination Systems						
49	00905	Remove and Replace Existing Signs (2)	LS	1		
50	00930	Perforated Steel Square Tube Anchor Sign Supports (2)	LS	1		
Part 01000 - Right of Way Development and Control						
53	01030	Lawn Seeding (Hydroseeding) disturbed soils	ACRE	0.20		
54	01030	Weed Control	ACRE	0.24		
55	01030	Seed Mobilization	EACH	2		
56	01030	Fertilizing	ACRE	0.07		
57	01030	Hydromulch	ACRE	0.07		
58	01030	Compost Blanket (nominal thickness of 3")	CY	70		
59	01040	Top Soil	CY	10		
Part 01100 - Water Supply Systems						
60	01120	Irrigation System Repair	LS	1		

Total Bid Price =

TOTAL BID PRICE: _____
(In Words)

CONTRACTOR: _____